



ATLANTIC GOLD

Appendix F.3

Field Activities Report Beaver Dam Mine Project



November 8, 2018

Reference No. 088664-20

James Millard
Manager Environment and Permitting
Atlantic Gold Corporation
6749 Moose River Road, RR#2
Middle Musquodoboit NS B0N 1X0

Via email: jmillard@atlanticgoldcorporation.com

Dear Mr. Millard:

Re: Field Activities Report - Beaver Dam Mine Project, Marinette, Nova Scotia

1. Introduction

GHD Limited (GHD) is pleased to provide this report on GHD's field activities completed for the proposed Beaver Dam Mine Project, Marinette, Nova Scotia (Site) during the period of March 29 and June 27, 2018. The monitoring well drilling, installation and associated groundwater investigation was undertaken to assist with data collection to support the ongoing Environmental Assessment (EA) process for the Site.

The monitoring well drilling and installation program consisted of drilling 49 nested monitoring wells. The following letter report details of the monitoring well drilling and installation program, the associated groundwater level monitoring, hydraulic conductivity (k) testing and groundwater quality sampling program. This data and data generated from the ongoing monitoring program will be used for impact assessment and input data for the groundwater and surface water modelling efforts.

2. Site Description

The Beaver Dam Mine Project is located on Beaver Dam Mines Rd. in Marinette, Halifax Regional Municipality (Halifax County), Nova Scotia. The Beaver Dam Mine site will be developed on approximately 145 hectares (ha) of land owned by the Northern Timber Nova Scotia Corporation (Northern Timber). Access to the land for mining purposes will likely be granted by a lease agreement between Northern Timber and Atlantic Gold. Project facilities will occupy approximately 150 ha of this property as shown on Figure 1.

The Beaver Dam Mine Project will consist of the following facilities, including the open pit mine, the waste rock storage area, the crusher site, and supporting buildings and infrastructure. The processing of ore from Beaver Dam gold deposit will occur at the existing Touquoy plant upon completion of mining ore from the Touquoy deposit.



3. Monitoring Well Installation

The drilling program was completed from March 29, 2018 to May 7, 2018 and consisted of drilling and installation of 49 nested monitoring wells as follows:

MW-01A/B/C

MW-02A/B

MW-03A/B/C

MW-04A/B

MW-05A/B/C/D

MW-07A/B/C/D

MW-09A/B/C/D

MW-11A/B/C

MW-12A/B

MW-14A/B/C

MW-16A/B

MW-17A/B/C

MW-18A/B/C

MW-19A/B/C

MW-20A/B

MW-21A/B/C

MW-22A/B/C

Alan Deal, P.Geo, supervised the monitoring well design and overall program. Richard Hollett, B.A, C.Tech provided oversight and direction in the field on behalf of GHD. The monitoring wells were installed by two drill rigs (CME 55 track mount and CME 75 track mount) operated by Logan Geotech Incorporated of Stewiacke, NS. Monitoring wells were installed in an HQ sized borehole. Monitoring well materials consisted of 50 mm diameter PVC threaded pipe and #20 slot PVC well screen. The pipe and screen arrived at the Site factory-wrapped in plastic. These materials were handled only with disposable nitrile gloves after being unwrapped. Silica sand was placed around the screen to a level approximately 0.3 metres above the screen. A bentonite seal was placed above the sand pack to prevent surface runoff from entering the monitoring wells and affecting groundwater conditions. Each monitoring well was capped with a locking J plug and protected with an aboveground protector.



At each nested location, one shallow monitoring well (A) was drilled to intercept the water table or the first saturated conditions encountered. A second, deeper monitoring well (B) was also installed at every monitoring well nest, typically in competent bedrock. A series of deeper wells were installed at a depth of approximately 30.0 m bgs at MW-01C, MW-03C, MW-05D, MW-07D, MW-09D, MW-11C, MW-14C, MW-17C, MW-18C, MW-19C, MW-21C, and MW-22C. These wells are designed to assess more regional groundwater flow patterns in the deeper bedrock and determine the relationship between shallow and deep groundwater. Finally, three additional wells were installed at depths of approximately 60 m bgs at MW-05C, MW-07C, and MW-09C in order to determine deep bedrock conditions in the immediate vicinity of the proposed open pit mine.

The location of the monitoring wells are presented on Figure 1. Table 1 is a summary of the well completion details including coordinates for northings and eastings, ground surface elevation and screen intervals. Monitoring well logs containing information on stratigraphy, rock quality designation (RQD), and monitoring well construction details are included in Attachment 1. Representative photos taken during the drilling program are attached as Attachment 2.

All monitoring locations were surveyed by WSP and supplied in UTM NAD83 CSRS coordinates with elevations provided in both CGVD28 and CGVD2013. Atlantic Mining has used the CGVD28 datum in the past and all elevations of monitoring location data are reported as such.

Biweekly synoptic monitoring of surface water and groundwater elevations began on July 5, 2018. Groundwater elevations were also measured during other investigation tasks (described below). Water levels measured in all available monitoring wells and surface water monitoring locations at the Site are provided in Attachment 3.

4. Well Development

Following installation of the monitoring wells, the newly drilled monitoring wells were developed using dedicated Waterra tubing and an attached foot valve. The purging procedure is intended to promote the collection of representative groundwater samples. Monitoring well development consisted of purging groundwater from the wells in order to remove any water introduced into the borehole during drilling. Well development also removed any silt or clay fines from the wells in order to minimize sediment inside the monitoring well's screen.

5. Hydraulic Conductivity Testing

GHD completed a series of test to determine the hydraulic conductivity of the overburden and bedrock encountered during the investigation.

From May 28, 2018 to June 21, 2018, GHD completed single well response tests or "slug" tests in the newly installed monitoring wells, with the exception of two 60 m deep monitoring wells (MW-07C and MW-09C), as they recovered too slowly.



The slug tests were completed by measuring the static water level in the well, installing a pressure transducer in the well to record changes in the water level and then introducing a solid “slug” of known volume into the well. This caused an instantaneous rise in the water level in the well, which then began to recover or “fall” back to the static water level. Once the recovery was at least 90 percent complete, GHD removed the slug. This caused an instantaneous drop in the water level in the well, which then began to recover or “rise” back to the static water level. Once recovery was complete, GHD removed the transducer and downloaded the data. Data were entered into AQTESOLV, which was used to estimate the hydraulic conductivity of the material surrounding the monitoring well screen.

Table 2 provides a summary of the results of the slug tests. The hydraulic conductivities calculated ranged from 1.1×10^{-6} m/sec (MW-18C) to 3.8×10^{-2} cm/sec (MW-19A).

Logan and GHD completed packer tests in the core holes drilled for MW-05C, MW-07C, and MW-09C from May 10 through May 17, 2018. A total of thirty (30) tests (10 per well) were carried out during this period. Table 3 provides a summary of the hydraulic conductivities values derived from the packer tests. The hydraulic conductivities calculated ranged from 7.2×10^{-8} cm/sec to 2.1×10^{-4} cm/sec.

The packer tests were carried out following the Lugeon test method, which consists of isolating a section of the previously drilled borehole using inflatable packers, and injecting water in the rock mass under five (5) steady pressure levels that each last for a period of 10 minutes. The pressure levels successively correspond to 33%, 66%, 100%, 66% and 33% of the maximum test pressure. The maximum test pressure was determined based on the depth of the test, the overburden pressure and the quality of the bedrock. Based on the measured water absorptions during each of the five periods, the type of water flow within the rock mass and its associated hydraulic conductivity were determined.

6. Groundwater and Surface Water Quality Monitoring Program

The groundwater monitoring and sampling program were completed to assess groundwater conditions at the Site prior to commencement of construction activities. All surface water and groundwater samples were submitted to Maxxam Analytics (Maxxam), in Bedford, Nova Scotia for laboratory analysis.. Laboratory certificates are included as Attachment 4.

Surface water samples were collected monthly from October 2014 to August 2015. Seven samples were collected (SW-1, SW-2A, SW-4A, SW-5, SW-6A, SW-9, and SW-10) for the Beaver Dam Mine Site to characterize surface water quality on Site. Prior to sample collection GHD measured the surface water temperature, conductivity, total dissolved solids, dissolved oxygen, and pH. Table 4 provides the surface water quality data.

Groundwater samples were collected from all the newly installed wells from June 18, 2018 to June 27, 2018. A second round of groundwater samples were collected September 12 and 21, 2018. Prior to sample collection, the depth to groundwater was measured using an electronic water level meter. GHD calculated the volume of standing water in each well. The wells were purged using an inertial pump. During purging, GHD measured stabilization parameters (temperature, pH, and conductivity) at 5 L



increments for the shallow wells (A), and 10 L increments for the intermediate/deep wells (B and D). Purgging was considered complete when the following stabilization criteria were achieved in three successive measurements:

Parameter	Units	Stabilization Criteria
pH	Standard units	+/- 1
Specific Conductivity	µS/cm	+/- 10%
Temperature	°C	+/- 10%

If the monitoring well went dry, it was allowed to recover until a sufficient volume of groundwater accumulated in the well to permit sample collection.

Prior to sample collection, GHD personnel donned a new pair of disposable nitrile gloves. Laboratory supplied sample bottles were filled directly from the inertial pump tubing. Samples collected for metals analysis were filtered in the field using a 45-micron in-line filter. One blind field duplicate sample was collected for approximately every ten investigative samples. Immediately after sample collection was complete the samples were placed on ice in a cooler.

Groundwater quality data are tabulated in Table 5. The results are not compared to any guidelines or other criteria as the data is baseline only and will be used for future comparisons to compliance values set out in the IA and later to Canada Council of the Ministers of Environment (CCME) and/or Metal Mining Effluent Regulations (MMER) values.

7. Closing

A monitoring well drilling, installation, and groundwater sampling program completed for the proposed Beaver Dam Mine Project in Marinette, Nova Scotia during the period of March 29 and June 27, 2018 to assist with data collection to support the ongoing EA process for the Site.

The drilling program was completed during the period of March 29 and May 7, 2018, GHD staff oversaw the drilling and installation of 49 nested monitoring wells on the proposed Beaver Dam Mine property. The drill rigs (CME 55 track mount and CME 75 track mount) were supplied and operated by Logan Geotech Incorporated of Stewiacke, Nova Scotia.

Fifty-one groundwater samples including five field duplicate samples were collected from the on-Site monitoring wells in June 2018. A second round of groundwater samples was collected in September 2018. The groundwater samples were submitted to the Maxxam for laboratory analysis based on analytical parameters/test requirements typically established by NSE for this type of industrial site.



We trust this report meets your requirements. Should any questions arise, please do not hesitate to contact the undersigned.

Sincerely,

GHD

<Original signed by>



Peter Oram, P.Geo.
Senior Environmental Specialist/Hydrogeologist

JR/tj/1


Encl.

<Original signed
by>

Alan Deal, P.Geo.
Senior Hydrogeologist



Source: GHD, Leading Edge Geomatics (Aerial 2015); Service Nova Scotia/ Service Layer Credits: © 2018 Microsoft Corporation © 2018 DigitalGlobe ©CNES (2018) Distribution Airbus DS



Coordinate System:
NAD 1983 CSRS UTM Zone 20N



ATLANTIC MINING NS CORP
BEAVER DAM MINE
GROUND WATER MONITORING PROGRAM

MONITORING LOCATIONS

088664-20
Nov 7, 2018

FIGURE 1

Table 1: Well Completion Details
Beaver Dam Mine Project Field Activities Report
Marinette, Nova Scotia

	UTM Zone 20 NAD83 CSRS		Installation Date	Unit	Well Depth		Ground Surface Elevation (m AMSL)	Stick-up (m ags)	Top of Casing Elevation (m AMSL)	Top of Screen Interval		Bottom of Screen Interval	
	Well_ID	Easting	Northing		(m bgs)	(m AMSL)				(m bgs)	(m AMSL)	(m bgs)	(m AMSL)
MW-01A	520942.252	4990095.110	1-May-18	Shallow	6.30	144.13	150.429	1.121	151.550	1.83	148.599	6.3	144.129
MW-01B	520943.031	4990093.660	4-May-18	Intermediate	15.30	135.31	150.610	0.994	151.604	12.24	138.370	15.3	135.310
MW-01C	520944.122	4990092.462	4-May-18	Deep	30.06	120.59	150.647	1.129	151.776	27.1	123.547	30.2	120.497
MW-02A	520728.778	4989595.501	7-May-18	Shallow	4.72	146.69	151.410	1.064	152.474	1.7	149.730	4.7	146.690
MW-02B	520730.397	4989594.708	7-May-18	Intermediate	15.60	135.84	151.441	1.093	152.534	12.5	138.941	15.6	135.891
MW-03A	521823.117	4989220.163	1-May-18	Shallow	6.32	160.10	166.421	1.015	167.436	3.3	163.141	6.3	160.101
MW-03B	521823.540	4989222.229	1-May-18	Intermediate	15.32	151.05	166.374	1.014	167.388	12.3	154.104	15.3	151.054
MW-03C	521824.051	4989223.934	2-May-18	Deep	30.30	136.03	166.334	1.007	167.341	27.3	139.084	30.3	136.034
MW-04A	522649.993	4989640.335	3-Apr-18	Shallow	5.96	158.70	164.655	0.853	165.508	2.9	161.735	6.0	158.695
MW-04B	522649.439	4989639.523	3-Apr-18	Intermediate	15.53	149.16	164.687	0.869	165.556	12.5	152.197	15.5	149.157
MW-05A	521746.140	4990210.163	25-Apr-18	Shallow	6.10	134.76	140.855	0.826	141.681	1.5	139.355	6.1	134.755
MW-05B	521747.858	4990208.591	24-Apr-18	Intermediate	15.57	125.32	140.894	0.944	141.838	12.5	128.374	15.6	125.324
MW-05C	521745.609	4990207.042	23-Apr-18	Intermediate	60.43	80.52	140.947	0.993	141.940	57.4	83.567	60.4	80.517
MW-05D	521742.062	4990206.839	1-May-18	Deep	30.48	110.87	141.346	1.012	142.358	27.4	113.916	30.5	110.866
MW-07A	522676.986	4990257.899	9-Apr-18	Shallow	7.49	122.97	130.461	0.928	131.389	4.4	126.021	7.5	122.971
MW-07B	522677.763	4990256.675	6-Apr-18	Intermediate	15.49	115.11	130.600	0.943	131.543	12.4	118.160	15.5	115.110
MW-07C	522676.908	4990255.360	19-Apr-18	Intermediate	60.96	69.63	130.588	0.989	131.577	57.9	72.678	61.0	69.628
MW-07D	522674.898	4990259.556	14-May-18		30.48		130.256	1.040	131.296	27.2	103.026	30.5	99.776
MW-09A	522024.415	4990682.566	13-Apr-18	Shallow	7.14	126.75	133.894	1.075	134.969	4.1	129.804	7.1	126.754
MW-09B	522022.788	4990682.720	13-Apr-18	Intermediate	15.39	118.36	133.748	1.040	134.788	12.3	121.408	15.4	118.358
MW-09C	522022.547	4990680.996	12-Apr-18	Intermediate	63.37	70.42	133.791	0.950	134.741	60.3	73.461	63.4	70.421
MW-09D	522023.739	4990684.215	2-May-18	Deep	30.48	103.23	133.705	1.046	134.751	27.43	106.275	30.48	103.225
MW-11A	522324.169	4990130.598	3-Apr-18	Shallow	6.09	141.75	147.844	0.933	148.777	3.04	144.804	6.09	141.754
MW-11B	522325.095	4990132.870	5-Apr-18	Intermediate	15.24	132.48	147.718	0.783	148.501	12.19	135.528	15.24	132.478
MW-11C	522323.713	4990132.377	4-Apr-18	Deep	26.01	121.79	147.795	0.744	148.539	22.96	124.835	26.01	121.785
MW-12A	521711.672	4991000.037	15-Apr-18	Shallow	6.10	141.80	147.903	0.652	148.555	0.91	146.993	6.1	141.803
MW-12B	521710.995	4990999.179	15-Apr-18	Deep	25.83	121.99	147.815	0.721	148.536	22.78	125.035	25.83	121.985
MW-14A	523253.265	4989830.507	26-Apr-18	Shallow	6.10	131.30	137.404	0.977	138.381	1.5	135.904	6.1	131.304
MW-14B	523253.939	4989828.780	26-Apr-18	Deep	26.04	111.40	137.442	1.049	138.491	22.99	114.452	26.04	111.402
MW-14C	523254.933	4989827.886	26-Apr-18	VERY Deep	41.15	96.34	137.486	0.819	138.305	38.1	99.386	41.15	96.336
MW-16A	522898.761	4990744.060	20-Apr-18	Shallow	7.14	146.60	153.744	1.068	154.812	3.5	150.244	7.14	146.604
MW-16B	522898.057	4990742.630	20-Apr-18	Intermediate	15.24	138.53	153.768	1.033	154.801	12.19	141.578	15.24	138.528
MW-17A	524121.346	4990324.445	26-Apr-18	Shallow	4.57	149.94	154.508	0.941	155.449	0.76	153.748	4.57	149.938
MW-17B	524123.059	4990323.426	25-Apr-18	Shallow	9.17	145.24	154.409	1.056	155.465	6.12	148.289	9.17	145.239
MW-17C	524124.712	4990324.229	25-Apr-18	Intermediate	15.44	138.92	154.355	0.894	155.249	12.45	141.905	15.44	138.915

Table 1: Well Completion Details
Beaver Dam Mine Project Field Activities Report
Marinette, Nova Scotia

	UTM Zone 20 NAD83 CSRS		Installation Date	Unit	Well Depth		Ground Surface Elevation (m AMSL)	Stick-up (m ags)	Top of Casing Elevation (m AMSL)	Top of Screen Interval		Bottom of Screen Interval	
	Well ID	Easting	Northing		(m bgs)	(m AMSL)				(m bgs)	(m AMSL)	(m bgs)	(m AMSL)
MW-18A	523118.888	4991142.236	20-Apr-18	Shallow	7.62	139.87	147.493	0.971	148.464	4.57	142.923	7.62	139.873
MW-18B	523120.436	4991141.883	24-Apr-18	Intermediate	15.77	131.73	147.496	0.835	148.331	12.72	134.776	15.77	131.726
MW-18C	523121.844	4991141.264	25-Apr-18	Shallow	35.05	112.26	147.313	1.146	148.459	1.5	145.813	35.05	112.263
MW-19A	520765.986	4991427.087	4-May-18	Shallow	4.72	128.87	133.590	0.971	134.561	0.61	132.980	4.72	128.870
MW-19B	520764.377	4991426.125	4-May-18	Intermediate	15.37	118.25	133.619	0.967	134.586	12.32	121.299	15.37	118.249
MW-19C	520762.233	4991425.291	7-May-18	Deep	30.30	103.39	133.692	0.881	134.573	27.25	106.442	30.3	103.392
MW-20A	520263.534	4990264.985	7-May-18	Shallow	7.62	144.49	152.106	1.165	153.271	4.57	147.536	7.62	144.486
MW-20B	520263.490	4990263.750	7-May-18	Intermediate	15.27	136.92	152.194	1.013	153.207	12.22	139.974	15.27	136.924
MW-21A	521749.236	4987642.034	7-May-18	Shallow	6.35	152.22	158.566	0.920	159.486	3.3	155.266	6.35	152.216
MW-21B	521747.935	4987641.733	3-May-18	Intermediate	15.42	143.10	158.518	0.988	159.506	12.37	146.148	15.42	143.098
MW-21C	521749.207	4987639.956	2-May-18	Deep	30.48	127.90	158.384	1.007	159.391	27.43	130.954	30.48	127.904
MW-22A	524377.001	4988520.078	25-Apr-18	Shallow	6.55	132.58	139.130	0.900	140.030	3.51	135.620	6.55	132.580
MW-22B	524377.199	4988521.744	27-Apr-18	Intermediate	15.55	123.60	139.148	0.987	140.135	12.5	126.648	15.55	123.598
MW-22C	524377.504	4988523.209	1-May-18	Deep	29.03	110.10	139.129	0.965	140.094	25.98	113.149	29.03	110.099
SW-1	523246.710	4990047.232					125.308	1.770	127.078				
SW-1A	523321.000	4989964.000											
SW-2A	521821.700	4991319.756					129.205	-0.236	128.969				
SW-4A	521343.751	4991071.233					129.343	-0.018	129.325				
SW-5	522696.387	4990229.101					130.874	-0.353	130.521				
SW-10	522176.584	4990321.015					134.168	-0.316	133.852				
SW-13	522769.824	4990261.347					129.170	-0.450	128.720				
SW-14	522677.366	4990219.104					131.709	-0.188	131.521				
SW-15	521434.000	4990457.000											
SW-16	521570.917	4990336.002					138.069	-0.253	137.816				
SW-17	521906.952	4990205.472					139.893	-0.253	139.640				
SW-18	521637.704	4990067.184					146.236	-0.582	145.654				
SW-19	520827.905	4991473.874					129.133	1.337	130.470				
SW-21	521811.000	4989584.000											
SW-22	521113.269	4989464.177					152.100	-0.886	151.214				
SW-23	522639.881	4989067.980					159.839	-0.170	159.669				

Table 2: Summary of Single-Well Response Test Results
Beaver Dam Mine Project
Marinette, Nova Scotia

Page 1 of 1

Well ID	Screened Material (overburden, weathered bedrock, bedrock)	Analytical Method ⁽¹⁾	Hydraulic Conductivity	
			Falling Head Tests (cm/sec)	Rising Head Tests (cm/sec)
Overburden Monitoring Wells				
MW-02A		Bouwer-Rice	1.8E-03	1.7E-03
MW-12A	overburden	Bouwer-Rice Dagan	invalid (water in screen) -	8.8E-05 8.9E-05
MW-14A	overburden	Bouwer-Rice Bouwer-Rice	9.7E-05 1.2E-04	6.1E-05 9.4E-05
MW-17A	overburden	Bouwer-Rice	6.7E-04	2.1E-04
MW-16A	overburden/weathered bedrock/bedrock - graywacke	Bouwer-Rice	7.2E-04	4.9E-04
MW-18C	overburden/weathered bedrock - graywacke	Bouwer-Rice	1.5E-06	1.1E-06
MW-19A	overburden	Bouwer-Rice Springer-Gelhar Dagan Bouwer-Rice Springer-Gelhar Dagan	invalid (water in screen) - - invalid (water in screen) - -	8.5E-03 1.7E-02 7.7E-03 1.1E-02 3.8E-02 9.3E-03
Weathered Bedrock Monitoring Wells				
MW-05A	weathered bedrock/bedrock - graywacke	Bouwer-Rice Dagan Bouwer-Rice Dagan	invalid (water in screen) - invalid (water in screen) -	2.6E-04 1.7E-04 3.8E-04 4.4E-04
MW-09A	weathered bedrock/bedrock - graywacke	Bouwer-Rice	9.8E-05	8.3E-05
MW-17B	weathered upper bedrock - greywacke	Bouwer-Rice Bouwer-Rice	5.0E-03 2.6E-03	3.5E-03 2.8E-03
MW-20A	weathered bedrock/bedrock - greywacke	Bouwer-Rice	3.7E-03	4.4E-03
Bedrock Monitoring Wells				
MW-01B	bedrock - greywacke	Bouwer-Rice	2.3E-05	2.5E-05
MW-02B	bedrock - granite	Bouwer-Rice	5.0E-05	4.2E-05
MW-03C	bedrock - greywacke	Bouwer-Rice	5.4E-04	3.6E-04
MW-04A	bedrock - greywacke	Bouwer-Rice Springer-Gelhar	1.0E-02 -	- 1.6E-02
MW-04B	bedrock - greywacke	Bouwer-Rice	2.0E-03	1.4E-03
MW-05B	bedrock - greywacke	Bouwer-Rice	9.6E-04	8.2E-04
MW-05C	bedrock - greywacke	Bouwer-Rice	bad test	3.4E-06
MW-05D	bedrock - greywacke	Bouwer-Rice	1.2E-05	1.0E-05
MW-07A	bedrock - greywacke	Bouwer-Rice	5.7E-05	3.0E-03
MW-07B	bedrock - greywacke	Bouwer-Rice	1.3E-05	1.2E-05
MW-07D	-	Bouwer-Rice	3.0E-05	2.9E-05
MW-09B	bedrock - greywacke	Bouwer-Rice	3.0E-06	2.3E-06
MW-09D	bedrock - greywacke	Bouwer-Rice	3.0E-06	2.4E-06
MW-11A	bedrock - greywacke	Bouwer-Rice	2.8E-04	4.6E-03
MW-11B	bedrock - greywacke	Bouwer-Rice	3.2E-05	2.4E-05
MW-11C ⁽⁴⁾	bedrock	-	<10-8	
MW-12B	bedrock - greywacke	Bouwer-Rice	8.2E-05	9.4E-05
MW-14B	bedrock - greywacke	Bouwer-Rice	7.7E-06	4.5E-06
MW-14C	bedrock - greywacke	Bouwer-Rice Bouwer-Rice	2.7E-05 5.0E-04	1.6E-05 2.3E-05
MW-16B	bedrock - greywacke	Bouwer-Rice	5.1E-05	4.1E-05
MW-17C	bedrock - greywacke	Bouwer-Rice	6.4E-04	4.6E-04
MW-18A	bedrock - greywacke	Bouwer-Rice	4.7E-03	3.6E-03
MW-18B	bedrock - greywacke	Bouwer-Rice	7.0E-05	3.7E-05
MW-19C	bedrock - greywacke	Bouwer-Rice	3.7E-04	3.3E-04
MW-21A	bedrock - greywacke	Bouwer-Rice	3.4E-04	3.9E-04
MW-21B	bedrock - greywacke	Bouwer-Rice	9.3E-05	4.5E-05
MW-22B	bedrock - greywacke	Bouwer-Rice	1.8E-04	1.3E-04
MW-22C	bedrock - greywacke	Bouwer-Rice	5.0E-05	4.2E-05

Notes:

(1) Bouwer, H., and R.C. Rice, 1976. A Slug Test Method for Determining Hydraulic Conductivity of Unconfined Aquifers with Completely or Partially Penetrating Wells, Water Resources Research, vol. 12, no. 3, pp. 423-428.

Dagan, G., 1978. A Note on Packer, Slug, and Recovery Tests in Unconfined Aquifers, Water Resources Research, vol. 14, no. 5, pp. 929-934.

Springer, R.K., and L.W. Gelhar, 1991. Characterization of Large-Scale Aquifer Heterogeneity in Glacial Outwash by Analysis of Slug Tests with Oscillatory Response, Cape Cod, Massachusetts, U.S.G.S. Water Resources Investigation Report 91-4034, pp. 36-40.

Falling head slug tests are considered invalid when the water level is within the screened interval.

(2) The Dagan (1978) analytical solution is typically used when the water level is within the screened interval.

(3) Data was not suitable for analysis or considered anomalous.

(4) Barometric effects were too large to determine hydraulic conductivity; however, recovery is on the order of several days to weeks (thus K<10-8 cm/sec)

Table 3: Summary of Packer Test Results
Beaver Dam Mine Project
Marinette, Nova Scotia

Page 1 of 1

MW-05C			MW-07C			MW-09C		
Depth of Packers (m)	Hydraulic Conductivit y (cm/s)	Type	Depth of Packers (m)	Hydraulic Conductivit y (cm/s)	Type	Depth of Packers (m)	Hydraulic Conductivity (cm/s)	Type
0.9 - 4	5.0E-05	laminar	4.3 - 7.3	2.1E-04	laminar	7 - 10.1	1.3E-05	laminar
4 - 7	8.3E-06	void-filling	7.3 - 10.4	1.3E-04	turbulent	10.1 - 13.1	2.7E-05	laminar
7 - 10.1	4.3E-05	wash-out	11.6 - 14.6	4.6E-05	turbulent	13.1 - 16.2	5.5E-07	dilation
10.1 - 13.1	3.8E-05	laminar	14.6 - 17.7	3.3E-07	turbulent	16.2 - 19.2	1.7E-07	turbulent
13.1 - 16.2	8.2E-05	turbulent	17.7 - 20.7	7.4E-06	turbulent	19.2 - 22.3	1.1E-06	turbulent
16.2 - 19.2	1.6E-05	wash-out	23.8 - 26.8	4.3E-06	turbulent	25.3 - 28.3	3.5E-07	laminar
37.5 - 40.5	6.8E-07	turbulent	29.9 - 32.9	4.4E-07	turbulent	31.4 - 34.4	4.5E-07	laminar
43.6 - 46.6	2.3E-07	laminar	42.1 - 45.1	2.2E-06	turbulent	40.5 - 43.6	7.2E-08	turbulent
46.6 - 49.7	7.9E-08	turbulent	45.1 - 48.2	2.8E-06	dilatation	49.7 - 52.7	1.2E-06	dilation
55.8 - 58.8	1.0E-06	turbulent	54.3 - 57.3	2.0E-05	turbulent	58.8 - 61.9	4.2E-07	dilation

Table 4: Surface Water Quality Data
Beaver Dam Mine Project
Marinette, Nova Scotia

TABLE 4A: SW-1 General Chemistry Results

		CCME FAL	MMER	SW-1									
Sampling Date				9-Oct-14	13-Nov-14	18-Dec-14	22-Jan-15	22-Jan-15	29-Apr-15	28-May-15	30-Jun-15	29-Jul-15	24-Aug-15
Calculated Parameters	Units							SW-1D (DUP)					
Anion Sum	me/L			0.140	0.170	0.100	0.120	0.120	0.060	0.0900	0.0800	0.0800	0.100
Bicarb. Alkalinity (calc. as CaCO ₃)	mg/L			<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Calculated TDS	mg/L			14	16	10	12	13	6	8.0	9.0	10	12
Carb. Alkalinity (calc. as CaCO ₃)	mg/L			<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Cation Sum	me/L			0.290	0.290	0.190	0.210	0.210	0.110	0.160	0.170	0.180	0.230
Hardness (CaCO ₃)	mg/L			5.5	5.0	3.3	3.5	3.5	1.6	2.6	2.9	3.3	4.0
Ion Balance (% Difference)	%			34.9	26.1	31.0	27.3	27.3	29.4	28.0	36.0	38.5	39.4
Langelier Index (@ 20C)	N/A			NC	NC	NC	NC	NC	NC	NC	NC	NC	NC
Langelier Index (@ 4C)	N/A			NC	NC	NC	NC	NC	NC	NC	NC	NC	NC
Nitrate (N)	mg/L	2.935		<0.050	0.061	<0.050	0.087	0.080	0.052	<0.050	0.062	0.051	<0.050
Saturation pH (@ 20C)	N/A			NC	NC	NC	NC	NC	NC	NC	NC	NC	NC
Saturation pH (@ 4C)	N/A			NC	NC	NC	NC	NC	NC	NC	NC	NC	NC
Inorganics													
Total Alkalinity (Total as CaCO ₃)	mg/L			<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0
Dissolved Chloride (Cl)	mg/L			5.1	5.8	3.4	4.0	4.2	1.9	3.1	2.6	2.8	3.7
Colour	TCU			150	160	99	83	100	85	110	170	160	230
Nitrate + Nitrite	mg/L			<0.050	0.061	<0.050	0.087	0.080	0.052	<0.050	0.062	0.051	<0.050
Nitrite (N)	mg/L	0.06		<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
Nitrogen (Ammonia Nitrogen)	mg/L	Varies ⁽¹⁾		<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	0.10	<0.050	<0.050	<0.050
Total Organic Carbon (C)	mg/L			13	18	8.2	7.0	7.5	6.3	7.5	12	12	11 (1)
Orthophosphate (P)	mg/L			<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
pH	pH	6.5-9	6-9.5	5.55	4.59	5.23	4.87	4.91	5.19	5.85	6.00	5.57	5.59
Reactive Silica (SiO ₂)	mg/L			2.5	3.9	2.7	3.8	4.0	1.9	1.1	2.1	2.6	3.2
Dissolved Sulphate (SO ₄)	mg/L			<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
Turbidity	NTU			1.1	0.64	0.59	0.62	0.69	0.76	1.1	1.2	1.1	1.2
Conductivity	uS/cm			30	33	25	27	27	14	16	17	18	21
Total Suspended Solids				-	-	-	-	-	-	-	-	-	-
Field Parameters													
Temperature	°C			15.57	8	4.2	0.16	-	3.62	19.14	19.69	19.90	-
Conductivity	µS/cm			39	36	26.7	25	-	16	22	24	-	-
Total Dissolved Solids	g/L			0.031	0.035	-	0.029	-	-	-	-	-	-
Dissolved Oxygen	mg/L	5.5-9.5 ⁽²⁾		9.99	14.31	13.32	37.9	-	14.97	10.63	9.6	-	-
pH		6.5-9	6-9.5	3.97	2.63	4.1	2.89	-	6.48	5.25	5.49	5.3	-

Notes

CCME FAL - Canadian Council of Ministers of the Environment Water Quality Guidelines for the Protection of Freshwater Aquatic Life (provided for reference)

MMER - Federal Metal Mining Effluent Regulations - guidelines shown represent maximum authorized concentrations in a grab sample (provided for reference)

(1) Ammonia guideline dependent on temperature and pH, e.g., if T = 10°C, guideline for total ammonia-N varies from 83.88 mg/L at pH = 6.0 to 0.02 mg/L at pH = 10 (see CCME Fact Sheet).

(2) Dissolved oxygen - lowest acceptable concentration ranges from 5.5 mg/L for warm water biota at other life stages to 9.5 mg/L for cold water biota at early life stages (see CCME Summary Table).

- denotes not analyzed

NC = not calculated

Table 4: Surface Water Quality Data
Beaver Dam Mine Project
Marinette, Nova Scotia

Table 4B: SW-1 Metals Results

		CCME FAL	MMER	SW-1										
				9-Oct-14	13-Nov-14	18-Dec-14	22-Jan-15	22-Jan-15	29-Apr-15	28-May-15	30-Jun-15	29-Jul-15	24-Aug-15	
Sampling Date	Metals	Units					SW-1D (DUP)							
Total Aluminum (Al)	ug/L	5 / 100 ⁽¹⁾		330	320	220	200	200	140	190	280	280	400	
Total Antimony (Sb)	ug/L			<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	
Total Arsenic (As)	ug/L	5.0	1000	2.7	1.5	1.3	<1.0	<1.0	<1.0	2.6	2.5	3.7	1.3	
Total Barium (Ba)	ug/L			5.8	5.6	3.1	3.3	3.4	1.7	2.4	3.0	3.2	4.6	
Total Beryllium (Be)	ug/L			<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	
Total Bismuth (Bi)	ug/L			<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	
Total Boron (B)	ug/L	1500		<50	<50	<50	<50	<50	<50	<50	<50	<50	<50	
Total Cadmium (Cd)	ug/L	0.04 - 0.37 ⁽²⁾		0.024	0.029	0.023	0.012	0.022	0.012	<0.010	0.028	0.014	0.022	
Total Calcium (Ca)	ug/L			1200	1100	780	720	740	350	630	690	790	770	
Total Chromium (Cr)	ug/L			<1.0	<1.0	<1.0	1.6	<1.0	<1.0	3.0	<1.0	<1.0	<1.0	
Total Cobalt (Co)	ug/L			0.51	0.52	<0.40	<0.40	<0.40	<0.40	<0.40	<0.40	<0.40	0.53	
Total Copper (Cu)	ug/L	2 - 4 ⁽³⁾	600	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	
Total Iron (Fe)	ug/L	300		670	630	330	350	340	240	360	580	750	1000	
Total Lead (Pb)	ug/L	1 - 7 ⁽⁴⁾	400	0.51	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	0.54	<0.50	0.57	
Total Magnesium (Mg)	ug/L			590	560	330	400	410	170	240	290	310	420	
Total Manganese (Mn)	ug/L			79	68	41	51	53	27	31	37	43	58	
Total Mercury (Hg)	ug/L	0.026		<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	0.015	<0.013	<0.013	0.032	
Total Molybdenum (Mo)	ug/L	73		<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	
Total Nickel (Ni)	ug/L	25 - 150 ⁽⁵⁾	1000	<2.0	<2.0	<2.0	<2.0	2.6	<2.0	<2.0	<2.0	<2.0	<2.0	
Total Phosphorus (P)	ug/L			<100	<100	<100	<100	<100	<100	<100	<100	150	170	
Total Potassium (K)	ug/L			570	550	380	380	370	330	340	170	210	170	
Total Selenium (Se)	ug/L	1		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	
Total Silver (Ag)	ug/L	0.1		<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	
Total Sodium (Na)	ug/L			3100	3000	2100	2300	2400	1200	1800	1900	1900	2300	
Total Strontium (Sr)	ug/L			11.0	10	5.8	6.3	6.6	2.9	4.6	5.9	6.3	7.4	
Total Thallium (Tl)	ug/L	0.8		<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	
Total Tin (Sn)	ug/L			<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	
Total Titanium (Ti)	ug/L			3.8	3.2	3.3	2.4	2.2	3.2	2.7	3.7	3.7	5.0	
Total Uranium (U)	ug/L	15		<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	
Total Vanadium (V)	ug/L			<2.0	2.3	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	
Total Zinc (Zn)	ug/L	30	1000	5.0	5.1	7.8	<5.0	<5.0	<5.0	6.8	<5.0	<5.0	<5.0	

Notes

CCME FAL - Canadian Council of Ministers of the Environment Water Quality Guidelines for the Protection of Freshwater Aquatic Life (provided for reference)

MMER - Federal Metal Mining Effluent Regulations - guidelines shown represent maximum authorized concentrations in a grab sample (provided for reference)

(1) Aluminum guideline dependent on pH. Guideline is 5 ug/L if pH <6.5 and 100 ug/L if pH ≥ 6.5 (see CCME Summary Table).

(2) Cadmium guideline (updated for 2014) ($\mu\text{g/L}$) = $10^{(0.83[\ln(\text{hardness})]-2.46)}$ for hardness between 17-280 mg/L CaCO_3 or a lower limit of 0.04 ug/L for hardness < 17mg/L or an upper limit of 0.37 ug/L for hardness >280 mg/L (see CCME Fact Sheet).

(3) Copper guideline based on sample hardness: copper guideline ($\mu\text{g/L}$) = $e^{0.8545[\ln(\text{hardness})]-1.465} * 0.2$ for hardness ≥82 to ≤180 mg/L, or a lower limit of 2 ug/L for hardness <82 mg/L and an upper limit of 4 ug/L for hardness >180 mg/L (see CCME Summary Table).

(4) Lead guideline based on sample hardness: lead guideline ($\mu\text{g/L}$) = $e^{1.273[\ln(\text{hardness})]-4.705}$ for hardness >60 to ≤180 mg/L, or a lower limit of 1 ug/L for hardness <60 mg/L and an upper limit of 7 ug/L for hardness >180 mg/L (see CCME Summary Table).

(5) Nickel guideline based on sample hardness: nickel guideline ($\mu\text{g/L}$) = $e^{0.76[\ln(\text{hardness})]+1.06}$ for hardness >60 to ≤180 mg/L, or a lower limit of 25 ug/L for hardness <60 mg/L and an upper limit of 150 ug/L for hardness >180 mg/L (see CCME Summary Table).

- denotes not analyzed

Table 4: Surface Water Quality Data
Beaver Dam Mine Project
Marinette, Nova Scotia

Table 4C: SW-2A General Chemistry Results

		CCME FAL	MMER	SW-2A												
Sampling Date				9-Oct-14	13-Nov-14	18-Dec-14	18-Dec-14	22-Jan-15	29-Apr-15	28-May-15	28-May-15	30-Jun-15	29-Jul-15	24-Aug-15		
Calculated Parameters	Units	SW-2AD (DUP)												SW-2AD (DUP)		
Anion Sum	me/L			0.150	0.180	0.100	0.110	0.130	0.0500	0.0900	0.0900	0.0800	0.0800	0.100		
Bicarb. Alkalinity (calc. as CaCO ₃)	mg/L			<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0		
Calculated TDS	mg/L			14	17	10	10	13	6.0	7.0	7.0	8.0	9.0	12		
Carb. Alkalinity (calc. as CaCO ₃)	mg/L			<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0		
Cation Sum	me/L			0.290	0.300	0.180	0.180	0.210	0.110	0.140	0.140	0.160	0.180	0.220		
Hardness (CaCO ₃)	mg/L			5.1	4.9	2.9	2.8	3.4	1.4	2.1	2.0	2.6	2.9	3.6		
Ion Balance (% Difference)	%			31.8	25.0	28.6	24.1	23.5	37.5	21.7	21.7	33.3	38.5	37.5		
Langelier Index (@ 20C)	N/A			NC	NC	NC	NC	NC	NC	NC	NC	NC	NC	NC		
Langelier Index (@ 4C)	N/A			NC	NC	NC	NC	NC	NC	NC	NC	NC	NC	NC		
Nitrate (N)	mg/L	2.935		0.11	0.065	<0.050	<0.050	0.079	<0.050	<0.050	<0.050	0.055	<0.050	<0.050		
Saturation pH (@ 20C)	N/A			NC	NC	NC	NC	NC	NC	NC	NC	NC	NC	NC		
Saturation pH (@ 4C)	N/A			NC	NC	NC	NC	NC	NC	NC	NC	NC	NC	NC		
Inorganics																
Total Alkalinity (Total as CaCO ₃)	mg/L			<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0		
Dissolved Chloride (Cl)	mg/L			5.0	6.3	3.6	3.8	4.2	1.6	3.1	3.1	2.8	2.8	3.7		
Colour	TCU			160	160	100	100	110	96	120	120	170	180	230		
Nitrate + Nitrite	mg/L			0.11	0.065	<0.050	<0.050	0.079	<0.050	<0.050	<0.050	0.055	<0.050	<0.050		
Nitrite (N)	mg/L	0.06		<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010		
Nitrogen (Ammonia Nitrogen)	mg/L	Varies ⁽¹⁾		<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	0.052	<0.050	<0.050	<0.050	0.084		
Total Organic Carbon (C)	mg/L			14	19	8.9	9.1	7.4	5.5	7.9	8.1	12	13	14 (1)		
Orthophosphate (P)	mg/L			<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010		
pH	pH	6.5-9	6-9.5	5.06	4.54	4.88	4.75	4.75	5.08	5.59	5.36	5.29	5.26	5.16		
Reactive Silica (SiO ₂)	mg/L			2.7	3.9	2.8	2.7	3.7	1.9	1.1	1.1	1.9	2.6	3.2		
Dissolved Sulphate (SO ₄)	mg/L			<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0		
Turbidity	NTU			1.1	0.50	0.59	0.23	0.70	0.29	1.5	1.4	0.99	0.97	1.9		
Conductivity	uS/cm			31	33	25	25	28	13	16	15	17	19	21		
Total Suspended Solids				-	-	-	-	-	-	-	-	-	-	-		
Field Parameters																
Temperature	°C			13.57	7.89	4.2	-	0.27	3.34	20.64	-	18.81	21.2	-		
Conductivity	µS/cm			38	37	27.4	-	25	16	23	-	24	-	-		
Total Dissolved Solids	g/L			0.031	0.036	-	-	0.03				-	-	-		
Dissolved Oxygen	mg/L	5.5-9.5 ⁽²⁾		8.97	13.07	12.88	-	36.14	15.35	9.91	-	9.18	-	-		
pH		6.5-9	6-9.5	4.09	3.08	3.75	-	3.56	6.53	4.63	-	4.00	4.94	-		

Notes

CCME FAL - Canadian Council of Ministers of the Environment Water Quality Guidelines for the Protection of Freshwater Aquatic Life (provided for reference)

MMER - Federal Metal Mining Effluent Regulations - guidelines shown represent maximum authorized concentrations in a grab sample (provided for reference)

(1) Ammonia guideline dependent on temperature and pH, e.g., if T = 10°C, guideline for total ammonia-N varies from 83.88 mg/L at pH = 6.0 to 0.02 mg/L at pH = 10 (see CCME Fact Sheet).

(2) Dissolved oxygen - lowest acceptable concentration ranges from 5.5 mg/L for warm water biota at other life stages to 9.5 mg/L for cold water biota at early life stages (see CCME Summary Table).

- denotes not analyzed

NC = not calculated

Table 4: Surface Water Quality Data
Beaver Dam Mine Project
Marinette, Nova Scotia

Table 4D: SW-2A Metals Results

		CCME FAL	MMER	SW-2A											
				9-Oct-14	13-Nov-14	18-Dec-14	18-Dec-14	22-Jan-15	29-Apr-15	28-May-15	28-May-15	30-Jun-15	29-Jul-15	24-Aug-15	
Sampling Date	Metals	Units				SW-2AD (DUP)	.		SW-2AD (DUP)						
Total Aluminum (Al)	ug/L	5 / 100 ⁽¹⁾		330	340	210	210	210	140	190	190	280	300	400	
Total Antimony (Sb)	ug/L			<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	
Total Arsenic (As)	ug/L	5.0	1000	1.1	<1.0	<1.0	<1.0	<1.0	<1.0	1.1	1.1	<1.0	1.5	1.3	
Total Barium (Ba)	ug/L			5.6	5.8	3.2	3.0	3.3	1.6	2.2	2.2	3.0	3.5	4.6	
Total Beryllium (Be)	ug/L			<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	
Total Bismuth (Bi)	ug/L			<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	
Total Boron (B)	ug/L	1500		<50	<50	<50	<50	<50	<50	<50	<50	<50	<50	<50	
Total Cadmium (Cd)	ug/L	0.04 - 0.37 ⁽²⁾		0.026	0.028	0.017	0.017	0.013	<0.010	0.013	0.013	0.012	0.017	0.022	
Total Calcium (Ca)	ug/L			1100	1000	640	590	680	290	470	460	580	620	770	
Total Chromium (Cr)	ug/L			1.4	1.6	<1.0	<1.0	<1.0	1.2	<1.0	<1.0	<1.0	<1.0	<1.0	
Total Cobalt (Co)	ug/L			0.49	0.58	<0.40	<0.40	<0.40	<0.40	<0.40	<0.40	<0.40	<0.40	0.53	
Total Copper (Cu)	ug/L	2 - 4 ⁽³⁾	600	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	
Total Iron (Fe)	ug/L	300		740	700	360	350	340	260	410	400	590	820	1000	
Total Lead (Pb)	ug/L	1 - 7 ⁽⁴⁾	400	0.78	0.55	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	0.55	0.62	0.57	
Total Magnesium (Mg)	ug/L			570	570	320	310	410	160	220	210	280	330	420	
Total Manganese (Mn)	ug/L			77	71	43	42	51	25	27	27	35	40	58	
Total Mercury (Hg)	ug/L	0.026		<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	0.013	0.013	<0.013	<0.013	0.035	
Total Molybdenum (Mo)	ug/L	73		<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	
Total Nickel (Ni)	ug/L	25 - 150 ⁽⁵⁾	1000	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	
Total Phosphorus (P)	ug/L			<100	110	<100	<100	<100	<100	<100	<100	<100	150	170	
Total Potassium (K)	ug/L			600	600	370	340	380	330	290	290	160	200	170	
Total Selenium (Se)	ug/L	1		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	
Total Silver (Ag)	ug/L	0.1		<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	
Total Sodium (Na)	ug/L			3100	3100	2100	2000	2400	1200	1600	1600	1900	1900	2300	
Total Strontium (Sr)	ug/L			11.0	9.5	5.6	5.2	6.6	3.0	4.1	3.9	5.0	6.3	7.4	
Total Thallium (Tl)	ug/L	0.8		<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	
Total Tin (Sn)	ug/L			<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	
Total Titanium (Ti)	ug/L			4.2	3.8	2.6	2.6	2.2	3.2	2.0	2.4	3.6	4.6	5.0	
Total Uranium (U)	ug/L	15		<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	
Total Vanadium (V)	ug/L			<2.0	2.5	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	
Total Zinc (Zn)	ug/L	30	1000	6.9	6.2	5.5	5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	

Notes

CCME FAL - Canadian Council of Ministers of the Environment Water Quality Guidelines for the Protection of Freshwater Aquatic Life (provided for reference)

MMER - Federal Metal Mining Effluent Regulations - guidelines shown represent maximum authorized concentrations in a grab sample (provided for reference)

(1) Aluminum guideline dependent on pH. Guideline is 5 ug/L if pH <6.5 and 100 ug/L if pH ≥ 6.5 (see CCME Summary Table).

(2) Cadmium guideline (updated for 2014) ($\mu\text{g/L}$) = $10^{(0.83[\log[\text{hardness}]]-2.46)}$ for hardness between 17-280 mg/L CaCO₃ or a lower limit of 0.04 ug/L for hardness < 17mg/L or an upper limit of 0.37 ug/L for hardness >280 mg/L (see CCME Fact Sheet).

(3) Copper guideline based on sample hardness: copper guideline ($\mu\text{g/L}$) = $e^{0.8545[\ln(\text{hardness})]-1.465} * 0.2$ for hardness ≥82 to ≤180 mg/L, or a lower limit of 2 ug/L for hardness <82 mg/L and an upper limit of 4 ug/L for hardness >180 mg/L (see CCME Summary Table).

(4) Lead guideline based on sample hardness: lead guideline ($\mu\text{g/L}$) = $e^{1.273[\ln(\text{hardness})]-4.705}$ for hardness >60 to ≤180 mg/L, or a lower limit of 1 ug/L for hardness <60 mg/L and an upper limit of 7 ug/L for hardness >180 mg/L (see CCME Summary Table).

(5) Nickel guideline based on sample hardness: nickel guideline ($\mu\text{g/L}$) = $e^{0.76[\ln(\text{hardness})]+1.06}$ for hardness >60 to ≤180 mg/L, or a lower limit of 25 ug/L for hardness <60 mg/L and an upper limit of 150 ug/L for hardness >180 mg/L (see CCME Summary Table).

- denotes not analyzed

Table 4: Surface Water Quality Data
Beaver Dam Mine Project
Marinette, Nova Scotia

Table 4E: SW-4A General Chemistry Results

		CCME FAL	MMER	SW-4A									
Sampling Date				9-Oct-14	13-Nov-14	13-Nov-14	18-Dec-14	22-Jan-15	29-Apr-15	28-May-15	30-Jun-15	29-Jul-15	24-Aug-15
Calculated Parameters	Units					SW-4AD (DUP)		No Sample					
Anion Sum	me/L			0.150	0.180	0.180	0.110		0.0400	0.110	0.0700	0.0700	0.110
Bicarb. Alkalinity (calc. as CaCO ₃)	mg/L			<1.0	<1.0	<1.0	<1.0		<1.0	<1.0	<1.0	<1.0	<1.0
Calculated TDS	mg/L			15	16	16	11		6.0	9.0	8.0	9.0	12
Carb. Alkalinity (calc. as CaCO ₃)	mg/L			<1.0	<1.0	<1.0	<1.0		<1.0	<1.0	<1.0	<1.0	<1.0
Cation Sum	me/L			0.300	0.300	0.300	0.200		0.120	0.180	0.170	0.190	0.230
Hardness (CaCO ₃)	mg/L			5.9	5.6	5.6	3.5		1.6	3.1	3.0	3.6	3.9
Ion Balance (% Difference)	%			33.3	25.0	25.0	29.0		50.0	24.1	41.7	46.2	35.3
Langelier Index (@ 20C)	N/A			NC	NC	NC	NC		NC	NC	NC	NC	NC
Langelier Index (@ 4C)	N/A			NC	NC	NC	NC		NC	NC	NC	NC	NC
Nitrate (N)	mg/L	2.935		0.093	0.062	<0.050	<0.050		<0.050	<0.050	0.064	<0.050	<0.050
Saturation pH (@ 20C)	N/A			NC	NC	NC	NC		NC	NC	NC	NC	NC
Saturation pH (@ 4C)	N/A			NC	NC	NC	NC		NC	NC	NC	NC	NC
Inorganics													
Total Alkalinity (Total as CaCO ₃)	mg/L			<5.0	<5.0	<5.0	<5.0		<5.0	<5.0	<5.0	<5.0	<5.0
Dissolved Chloride (Cl)	mg/L			5.0	6.2	6.4	3.9		1.3	3.8	2.2	2.6	3.7
Colour	TCU			120	130	130	88		100	130	160	170	260
Nitrate + Nitrite	mg/L			0.093	0.062	<0.050	<0.050		<0.050	<0.050	0.064	<0.050	<0.050
Nitrite (N)	mg/L	0.06		<0.010	<0.010	<0.010	<0.010		<0.010	<0.010	<0.010	<0.010	<0.010
Nitrogen (Ammonia Nitrogen)	mg/L	Varies ⁽¹⁾		<0.050	<0.050	<0.050	<0.050		0.073	0.092	<0.050	<0.050	<0.050
Total Organic Carbon (C)	mg/L			9.3	16	16	8.2		5.5	9.7	12	18	14 (1)
Orthophosphate (P)	mg/L			<0.010	<0.010	<0.010	<0.010		<0.010	<0.010	<0.010	<0.010	<0.010
pH	pH	6.5-9	6-9.5	5.57	4.76	4.71	4.96		5.14	5.74	5.42	5.09	4.93
Reactive Silica (SiO ₂)	mg/L			3.4	3.5	3.6	2.9		2.5	1.5	2.0	2.3	3.0
Dissolved Sulphate (SO ₄)	mg/L			<2.0	<2.0	<2.0	<2.0		<2.0	<2.0	<2.0	<2.0	<2.0
Turbidity	NTU			1.4	0.68	0.65	0.80		0.38	1.4	1.3	0.81	1.0
Conductivity	uS/cm			29	31	31	24		15	18	17	19	21
Total Suspended Solids				-	-	-	-		-	-	-	-	-
Field Parameters													
Temperature	°C			10.85	8.98	-	5.1		5.98	22.45	20.72	22.4	-
Conductivity	µS/cm			34	35	-	24.9		31	27	32	-	-
Total Dissolved Solids	g/L			0.03	0.033	-	-		-	-	-	-	-
Dissolved Oxygen	mg/L	5.5-9.5 ⁽²⁾		7.11	10.4	-	7.82		13.48	7.88	6.8	-	-
pH		6.5-9	6-9.5	4.27	3.71	-	3.75		6.56	5.34	5.34	4.92	-

Notes

CCME FAL - Canadian Council of Ministers of the Environment Water Quality Guidelines for the Protection of Freshwater Aquatic Life (provided for reference)

MMER - Federal Metal Mining Effluent Regulations - guidelines shown represent maximum authorized concentrations in a grab sample (provided for reference)

(1) Ammonia guideline dependent on temperature and pH, e.g., if T = 10°C, guideline for total ammonia-N varies from 83.88 mg/L at pH = 6.0 to 0.02 mg/L at pH = 10 (see CCME Fact Sheet).

(2) Dissolved oxygen - lowest acceptable concentration ranges from 5.5 mg/L for warm water biota at other life stages to 9.5 mg/L for cold water biota at early life stages (see CCME Summary Table).

- denotes not analyzed

NC = not calculated

Table 4F: SW-4A Metals Results

Table 4: Surface Water Quality Data
Beaver Dam Mine Project

		CCME FAL	MMER	SW-4A										
Sampling Date				9-Oct-14	13-Nov-14	13-Nov-14	18-Dec-14	22-Jan-15	29-Apr-15	28-May-15	30-Jun-15	29-Jul-15	24-Aug-15	
Metals	Units					SW-4AD (DUP)		No Sample						
Total Aluminum (Al)	ug/L	5 / 100 ⁽¹⁾		250	300	310	220		130	240	300	350		390
Total Antimony (Sb)	ug/L			<1.0	<1.0	<1.0	<1.0		<1.0	<1.0	<1.0	<1.0		<1.0
Total Arsenic (As)	ug/L	5.0	1000	5.8	2.9	2.8	2.0		1.1	7.3	5.4	5.6		5.6
Total Barium (Ba)	ug/L			3.4	4.6	4.4	3.2		1.7	2.8	2.8	3.7		3.4
Total Beryllium (Be)	ug/L			<1.0	<1.0	<1.0	<1.0		<1.0	<1.0	<1.0	<1.0		<1.0
Total Bismuth (Bi)	ug/L			<2.0	<2.0	<2.0	<2.0		<2.0	<2.0	<2.0	<2.0		<2.0
Total Boron (B)	ug/L	1500		<50	<50	<50	<50		<50	<50	<50	<50		<50
Total Cadmium (Cd)	ug/L	0.04 - 0.37 ⁽²⁾		0.015	0.024	0.025	0.044		0.012	0.013	0.016	0.014		0.021
Total Calcium (Ca)	ug/L			1500	1300	1300	810		350	780	710	860		930
Total Chromium (Cr)	ug/L			<1.0	<1.0	<1.0	<1.0		<1.0	<1.0	<1.0	<1.0		<1.0
Total Cobalt (Co)	ug/L			0.43	0.53	0.59	<0.40		<0.40	0.42	<0.40	0.63		0.48
Total Copper (Cu)	ug/L	2 - 4 ⁽³⁾	600	<2.0	<2.0	<2.0	<2.0		<2.0	<2.0	<2.0	<2.0		<2.0
Total Iron (Fe)	ug/L	300		690	540	540	320		160	580	650	840		1100
Total Lead (Pb)	ug/L	1 - 7 ⁽⁴⁾	400	0.54	<0.50	<0.50	<0.50		<0.50	<0.50	0.52	0.56		0.55
Total Magnesium (Mg)	ug/L			540	590	590	350		170	280	290	360		370
Total Manganese (Mn)	ug/L			53	58	58	41		20	37	32	42		51
Total Mercury (Hg)	ug/L	0.026		<0.013	<0.013	<0.013	<0.013		<0.013	0.015	<0.013	<0.013		0.028
Total Molybdenum (Mo)	ug/L	73		<2.0	<2.0	<2.0	<2.0		<2.0	<2.0	<2.0	<2.0		<2.0
Total Nickel (Ni)	ug/L	25 - 150 ⁽⁵⁾	1000	<2.0	<2.0	<2.0	<2.0		<2.0	<2.0	<2.0	<2.0		<2.0
Total Phosphorus (P)	ug/L			<100	100	100	<100		<100	<100	140	150		150
Total Potassium (K)	ug/L			450	500	520	480		290	280	140	180		200
Total Selenium (Se)	ug/L	1		<1.0	<1.0	<1.0	<1.0		<1.0	<1.0	<1.0	<1.0		<1.0
Total Silver (Ag)	ug/L	0.1		<0.10	<0.10	<0.10	<0.10		<0.10	<0.10	<0.10	<0.10		<0.10
Total Sodium (Na)	ug/L			3200	3100	3200	2300		1300	1900	1900	1700		2200
Total Strontium (Sr)	ug/L			10	9.1	9.2	5.7		2.8	5.1	5.0	6.4		7.2
Total Thallium (Tl)	ug/L	1		<0.10	<0.10	<0.10	<0.10		<0.10	<0.10	<0.10	<0.10		<0.10
Total Tin (Sn)	ug/L			<2.0	<2.0	<2.0	<2.0		<2.0	<2.0	<2.0	<2.0		<2.0
Total Titanium (Ti)	ug/L			5	3.7	3.9	2.3		2.4	4.7	3.8	3.8		4.9
Total Uranium (U)	ug/L	15		<0.10	<0.10	<0.10	<0.10		<0.10	<0.10	<0.10	<0.10		<0.10
Total Vanadium (V)	ug/L			<2.0	2.9	2.8	<2.0		<2.0	<2.0	<2.0	<2.0		<2.0
Total Zinc (Zn)	ug/L	30	1000	19	7.8	6.9	12		<5.0	7.5	<5.0	<5.0		6.0

Notes

CCME FAL - Canadian Council of Ministers of the Environment Water Quality Guidelines for the Protection of Freshwater Aquatic Life (provided for reference)

MMER - Federal Metal Mining Effluent Regulations - guidelines shown represent maximum authorized concentrations in a grab sample (provided for reference)

(1) Aluminum guideline dependent on pH. Guideline is 5 ug/L if pH <6.5 and 100 ug/L if pH ≥ 6.5 (see CCME Summary Table).

(2) Cadmium guideline (updated for 2014) ($\mu\text{g/L}$) = $10^{0.83(\log[\text{hardness}])-2.46}$ for hardness between 17-280 mg/L CaCO₃ or a lower limit of 0.04 ug/L

for hardness < 17mg/L or an upper limit of 0.37 ug/L for hardness >280 mg/L (see CCME Fact Sheet).

(3) Copper guideline based on sample hardness: copper guideline ($\mu\text{g/L}$) = $e^{0.8545[\ln(\text{hardness})]-1.465} * 0.2$ for hardness ≥82 to ≤180 mg/L, or a lower limit of 2 ug/L for hardness <82 mg/L and an upper limit of 4 ug/L for hardness >180 mg/L (see CCME Summary Table).(4) Lead guideline based on sample hardness: lead guideline ($\mu\text{g/L}$) = $e^{1.273[\ln(\text{hardness})]-4.705}$ for hardness >60 to ≤180 mg/L, or a lower limit of 1 ug/L for hardness <60 mg/L and an upper limit of 7 ug/L for hardness >180 mg/L (see CCME Summary Table).(5) Nickel guideline based on sample hardness: nickel guideline ($\mu\text{g/L}$) = $e^{0.76[\ln(\text{hardness})]+1.06}$ for hardness >60 to ≤180 mg/L, or a lower limit of 25 ug/L for hardness <60 mg/L and an upper limit of 150 ug/L for hardness >180 mg/L (see CCME Summary Table).

- denotes not analyzed

Table 4: Surface Water Quality Data
Beaver Dam Mine Project
Marinette, Nova Scotia

Table 4G: SW-5 General Chemistry Results

		CCME FAL	MMER	SW-5										
Sampling Date				9-Oct-14	9-Oct-14	13-Nov-14	18-Dec-14	22-Jan-15	29-Apr-15	28-May-15	30-Jun-15	29-Jul-15	24-Aug-15	
Calculated Parameters	Units				SW-5D (DUP)									
Anion Sum	me/L			0.480	0.480	0.520	0.340	0.400	0.100	0.360	0.350	0.360	0.410	
Bicarb. Alkalinity (calc. as CaCO ₃)	mg/L			14	14	11	6.1	8.0	<1.0	7.8	9.3	11	13	
Calculated TDS	mg/L			28	28	33	23	27	12	21	21	21	25	
Carb. Alkalinity (calc. as CaCO ₃)	mg/L			<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	
Cation Sum	me/L			0.480	0.470	0.510	0.340	0.430	0.240	0.350	0.350	0.340	0.420	
Hardness (CaCO ₃)	mg/L			16	16	17	10	14	7.3	11	12	12	15	
Ion Balance (% Difference)	%			0.00	1.05	0.970	0.00	3.61	41.2	1.41	0.00	2.86	1.20	
Langelier Index (@ 20C)	N/A			(2.56)	(2.54)	-2.74	-3.79	-3.17	NC	-3.22	-3.00	-2.84	-2.55	
Langelier Index (@ 4C)	N/A			(2.81)	(2.80)	-2.99	-4.04	-3.42	NC	-3.48	-3.26	-3.09	-2.80	
Nitrate (N)	mg/L	2.935		0.10	0.15	0.051	0.094	0.096	0.870	<0.050	0.063	<0.050	0.055	
Saturation pH (@ 20C)	N/A			9.43	9.46	9.52	10.0	9.77	NC	9.84	9.76	9.66	9.50	
Saturation pH (@ 4C)	N/A			9.69	9.71	9.77	10.3	10.0	NC	10.1	10.0	9.92	9.75	
Inorganics														
Total Alkalinity (Total as CaCO ₃)	mg/L			14	14	11	6.1	8.0	<5.0	7.8	9.3	11	13	
Dissolved Chloride (Cl)	mg/L			4.0	4.1	5.2	4.0	5.0	1.5	3.4	1.9	1.7	2.2	
Colour	TCU			22	23	26	30	23	28	27	23	24	37	
Nitrate + Nitrite	mg/L			0.10	0.15	0.051	0.094	0.096	0.087	<0.050	0.063	<0.050	0.055	
Nitrite (N)	mg/L	0.06		<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	
Nitrogen (Ammonia Nitrogen)	mg/L	Varies ⁽¹⁾		<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	0.052	<0.050	<0.050	
Total Organic Carbon (C)	mg/L			4.1	4.3	3.5	4.0	3.1	3.5	3.6	4.1	5.3	4.3	
Orthophosphate (P)	mg/L			<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	0.011	<0.010	<0.010	0.011	
pH	pH	6.5-9	6-9.5	6.88	6.92	6.78	6.23	6.60	6.14	6.62	6.76	6.83	6.95	
Reactive Silica (SiO ₂)	mg/L			1.8	1.8	3.1	3.0	3.1	2.3	<0.50	0.92	0.77	2.5	
Dissolved Sulphate (SO ₄)	mg/L			3.5	3.6	7.0	4.6	4.4	2.5	5.0	5.0	4.5	3.6	
Turbidity	NTU			0.44	0.81	1.4	6.2	2.4	0.69	1.2	0.83	0.91	1.2	
Conductivity	uS/cm			48	47	49	35	45	28	34	35	32	40	
Total Suspended Solids				-	-	-	-	-	-	-	-	-	-	
Field Parameters														
Temperature	°C			13.98	-	7.76	4.6	1.75	2.7	20.84	20.51	22.4	-	
Conductivity	µS/cm			53	-	49	35.7	36	27	40	40	-	-	
Total Dissolved Solids	g/L			0.044	-	0.048	-	0.041	-	-	-	-	-	
Dissolved Oxygen	mg/L	5.5-9.5 ⁽²⁾		8.26	-	15.04	13.08	39.05	14.95	8.59	9.13	-	-	
pH		6.5-9	6-9.5	5.46	-	4.61	5.94	4.8	6.67	6.56	6.34	6.39	-	

Notes

CCME FAL - Canadian Council of Ministers of the Environment Water Quality Guidelines for the Protection of Freshwater Aquatic Life (provided for reference)

MMER - Federal Metal Mining Effluent Regulations - guidelines shown represent maximum authorized concentrations in a grab sample (provided for reference)

(1) Ammonia guideline dependent on temperature and pH, e.g., if T = 10°C, guideline for total ammonia-N varies from 83.88 mg/L at pH = 6.0 to 0.02 mg/L at pH = 10 (see CCME Fact Sheet).

(2) Dissolved oxygen - lowest acceptable concentration ranges from 5.5 mg/L for warm water biota at other life stages to 9.5 mg/L for cold water biota at early life stages (see CCME Summary Table).

- denotes not analyzed

NC = not calculated

Table 4: Surface Water Quality Data
Beaver Dam Mine Project
Marinette, Nova Scotia

Table 4H: SW-5 Metals Results

		CCME FAL	MMER	SW-5										
				9-Oct-14	9-Oct-14	13-Nov-14	18-Dec-14	22-Jan-15	29-Apr-15	28-May-15	30-Jun-15	29-Jul-15	24-Aug-15	
Sampling Date	Metals	Units		SW-5D (DUP)										
Total Aluminum (Al)	ug/L	5 / 100 ⁽¹⁾		28	29	100	460	210	98	61	45	43	52	
Total Antimony (Sb)	ug/L			<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Total Arsenic (As)	ug/L	5.0	1000	29	30	15	17	22	15	41	32	20	47	
Total Barium (Ba)	ug/L			4.5	4.6	5.5	6.1	6.1	4.6	4.4	3.6	4.1	4.5	
Total Beryllium (Be)	ug/L			<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Total Bismuth (Bi)	ug/L			<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
Total Boron (B)	ug/L	1500		<50	<50	<50	<50	<50	<50	<50	<50	<50	<50	<50
Total Cadmium (Cd)	ug/L	0.04 - 0.37 ⁽²⁾		<0.010	0.016	<0.010	0.010	0.011	0.018	<0.010	<0.010	<0.010	<0.010	<0.010
Total Calcium (Ca)	ug/L			5000	4900	5300	3000	4100	2200	3500	3600	3800	4500	
Total Chromium (Cr)	ug/L			<1.0	<1.0	<1.0	1.1	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Total Cobalt (Co)	ug/L			<0.40	<0.40	<0.40	<0.40	0.44	0.61	<0.40	<0.40	<0.40	<0.40	<0.40
Total Copper (Cu)	ug/L	2 - 4 ⁽³⁾	600	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
Total Iron (Fe)	ug/L	300		400	400	470	730	680	560	880	530	610	750	
Total Lead (Pb)	ug/L	1 - 7 ⁽⁴⁾	400	<0.50	<0.50	<0.50	0.57	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
Total Magnesium (Mg)	ug/L			940	920	970	640	780	430	600	640	720	870	
Total Manganese (Mn)	ug/L			60	59	28	25	150	200	65	50	45	97	
Total Mercury (Hg)	ug/L	0.026		<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	0.015	<0.013	<0.013	0.027	
Total Molybdenum (Mo)	ug/L	73		<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
Total Nickel (Ni)	ug/L	25 - 150 ⁽⁵⁾	1000	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
Total Phosphorus (P)	ug/L			<100	<100	<100	<100	<100	<100	<100	<100	140	170	150
Total Potassium (K)	ug/L			730	710	1000	720	740	480	670	580	350	450	
Total Selenium (Se)	ug/L	1		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Total Silver (Ag)	ug/L	0.1		<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10
Total Sodium (Na)	ug/L			2700	2700	2900	2200	2700	1400	1700	1800	1500	2000	
Total Strontium (Sr)	ug/L			28.0	27	26	15	21	11	18	20	25	27	
Total Thallium (Tl)	ug/L	0.8		<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10
Total Tin (Sn)	ug/L			<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
Total Titanium (Ti)	ug/L			<2.0	<2.0	<2.0	3.2	14	4.2	<2.0	<2.0	<2.0	<2.0	<2.0
Total Uranium (U)	ug/L	15		<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10
Total Vanadium (V)	ug/L			<2.0	<2.0	3.1	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
Total Zinc (Zn)	ug/L	30	1000	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	5.4	<5.0	<5.0	<5.0	<5.0

Notes

CCME FAL - Canadian Council of Ministers of the Environment Water Quality Guidelines for the Protection of Freshwater Aquatic Life (provided for reference)

MMER - Federal Metal Mining Effluent Regulations - guidelines shown represent maximum authorized concentrations in a grab sample (provided for reference)

(1) Aluminum guideline dependent on pH. Guideline is 5 ug/L if pH <6.5 and 100 ug/L if pH ≥ 6.5 (see CCME Summary Table).

(2) Cadmium guideline (updated for 2014) (ug/L) = $10^{(0.83[\log[\text{hardness}]]-2.46)}$ for hardness between 17-280 mg/L CaCO₃ or a lower limit of 0.04 ug/L for hardness < 17mg/L or an upper limit of 0.37 ug/L for hardness >280 mg/L (see CCME Fact Sheet).

(3) Copper guideline based on sample hardness: copper guideline (ug/L) = $e^{0.8545[\ln(\text{hardness})]-1.465}$ * 0.2 for hardness ≥82 to ≤180 mg/L, or a lower limit of 2 ug/L for hardness <82 mg/L and an upper limit of 4 ug/L for hardness >180 mg/L (see CCME Summary Table).

(4) Lead guideline based on sample hardness: lead guideline (ug/L) = $e^{1.273[\ln(\text{hardness})]-4.705}$ for hardness >60 to ≤180 mg/L, or a lower limit of 1 ug/L for hardness <60 mg/L and an upper limit of 7 ug/L for hardness >180 mg/L (see CCME Summary Table).

Table 4: Surface Water Quality Data
Beaver Dam Mine Project
Marinette, Nova Scotia

Table 4I: SW-6A General Chemistry Results

		CCME FAL	MMER	SW-6A									
Sampling Date				9-Oct-14	13-Nov-14	18-Dec-14	22-Jan-15	29-Apr-15	28-May-15	30-Jun-15	30-Jun-15	29-Jul-15	24-Aug-15
Calculated Parameters	Units							No Sample			SW-6AD (DUP)		
Anion Sum	me/L			0.130	0.160	0.110	0.120		0.0700	0.0700	0.0700	0.0700	0.100
Bicarb. Alkalinity (calc. as CaCO ₃)	mg/L			<1.0	<1.0	<1.0	<1.0		<1.0	<1.0	<1.0	<1.0	<1.0
Calculated TDS	mg/L			13	15	11	12		7.0	7.0	7.0	8.0	12
Carb. Alkalinity (calc. as CaCO ₃)	mg/L			<1.0	<1.0	<1.0	<1.0		<1.0	<1.0	<1.0	<1.0	<1.0
Cation Sum	me/L			0.240	0.270	0.190	0.210		0.140	0.170	0.160	0.170	0.240
Hardness (CaCO ₃)	mg/L			4.5	5.0	3.5	3.9		2.5	2.8	2.8	3.2	4.4
Ion Balance (% Difference)	%			29.7	25.6	26.7	27.3		33.3	41.7	39.1	41.7	41.2
Langelier Index (@ 20C)	N/A			NC	NC	NC	NC		NC	NC	NC	NC	NC
Langelier Index (@ 4C)	N/A			NC	NC	NC	NC		NC	NC	NC	NC	NC
Nitrate (N)	mg/L	2.935		0.080	<0.050	<0.050	<0.050		<0.050	0.053	0.059	<0.050	<0.050
Saturation pH (@ 20C)	N/A			NC	NC	NC	NC		NC	NC	NC	NC	NC
Saturation pH (@ 4C)	N/A			NC	NC	NC	NC		NC	NC	NC	NC	NC
Inorganics													
Total Alkalinity (Total as CaCO ₃)	mg/L			<5.0	<5.0	<5.0	<5.0		<5.0	<5.0	<5.0	<5.0	<5.0
Dissolved Chloride (Cl)	mg/L			4.3	5.8	3.8	4.2		2.5	2.2	2.2	2.4	3.5
Colour	TCU			80	99	87	82		88	140	130	140	220
Nitrate + Nitrite	mg/L			0.080	<0.050	<0.050	<0.050		<0.050	0.053	0.059	<0.050	<0.050
Nitrite (N)	mg/L	0.06		<0.010	<0.010	<0.010	<0.010		<0.010	<0.010	<0.010	<0.010	<0.010
Nitrogen (Ammonia Nitrogen)	mg/L	Varies ⁽¹⁾		<0.050	<0.050	<0.050	<0.050		<0.050	0.22	<0.050	<0.050	<0.050
Total Organic Carbon (C)	mg/L			9.1	13	8.1	8.9		7.3	10	11	13	12 (1)
Orthophosphate (P)	mg/L			<0.010	<0.010	<0.010	<0.010		<0.010	<0.010	<0.010	<0.010	<0.010
pH	pH	6.5-9	6-9.5	5.73	5.05	5.13	5.09		5.76	5.79	5.64	5.50	5.37
Reactive Silica (SiO ₂)	mg/L			3.3	3.5	2.8	3.4		1.1	1.3	1.2	1.6	2.7
Dissolved Sulphate (SO ₄)	mg/L			<2.0	<2.0	<2.0	<2.0		<2.0	<2.0	<2.0	<2.0	<2.0
Turbidity	NTU			0.30	0.69	0.42	0.44		0.43	0.65	1.1	0.49	0.54
Conductivity	uS/cm			25	28	24	25		16	16	16	16	20
Total Suspended Solids				-	-	-	-		-	-	-	-	-
Field Parameters													
Temperature	°C			10.98	8.04	4.6	1.15		17.4	18.09	-	20.4	-
Conductivity	µS/cm			31	32	25.7	23		34	22	-	-	-
Total Dissolved Solids	g/L			0.028	0.032	-	0.027		-	-	-	-	-
Dissolved Oxygen	mg/L	5.5-9.5 ⁽²⁾		8.88	14.49	12.01	42.34		10.89	9.17	-	-	-
pH		6.5-9	6-9.5	3.56	3.43	4.49	3.98		5.72	8.73	-	5.02	-

Notes

CCME FAL - Canadian Council of Ministers of the Environment Water Quality Guidelines for the Protection of Freshwater Aquatic Life (provided for reference)

MMER - Federal Metal Mining Effluent Regulations - guidelines shown represent maximum authorized concentrations in a grab sample (provided for reference)

(1) Ammonia guideline dependent on temperature and pH, e.g., if T = 10°C, guideline for total ammonia-N varies from 83.88 mg/L at pH = 6.0 to 0.02 mg/L at pH = 10 (see CCME Fact Sheet).

(2) Dissolved oxygen - lowest acceptable concentration ranges from 5.5 mg/L for warm water biota at other life stages to 9.5 mg/L for cold water biota at early life stages (see CCME Summary Table).

- denotes not analyzed

NC = not calculated

Table 4: Surface Water Quality Data
Beaver Dam Mine Project
Marinette, Nova Scotia

Table 4J: SW-6A Metals Results

Sampling Date	Metals	Units	CCME FAL	MMER	SW-6A									
					9-Oct-14	13-Nov-14	18-Dec-14	22-Jan-15	28-May-15	30-Jun-15	30-Jun-15	29-Jul-15	24-Aug-15	SW-6AD (DUP)
Total Aluminum (Al)	ug/L	5 / 100 ⁽¹⁾			220	290	240	250	220	290	39	320	470	
Total Antimony (Sb)	ug/L				<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	
Total Arsenic (As)	ug/L	5.0	1000		4.0	1.9	1.1	1.0	3.2	3.0	130	2.8	7.6	
Total Barium (Ba)	ug/L				3.2	4.1	3.1	3.0	2.3	2.6	5.4	3.1	3.8	
Total Beryllium (Be)	ug/L				<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	
Total Bismuth (Bi)	ug/L				<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	
Total Boron (B)	ug/L	1500			<50	<50	<50	<50	<50	<50	<50	<50	<50	
Total Cadmium (Cd)	ug/L	0.04 - 0.37 ⁽²⁾			0.024	0.021	0.014	0.011	<0.010	0.016	0.061	0.012	0.031	
Total Calcium (Ca)	ug/L				1000	1200	790	880	620	670	4900	770	1000	
Total Chromium (Cr)	ug/L				<1.0	<1.0	1.3	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	
Total Cobalt (Co)	ug/L				<0.40	0.44	<0.40	<0.40	<0.40	<0.40	1.8	<0.40	1.0	
Total Copper (Cu)	ug/L	2 - 4 ⁽³⁾	600		<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	3.0	<2.0	<2.0	
Total Iron (Fe)	ug/L	300			500	480	330	380	370	550	1400	750	1500	
Total Lead (Pb)	ug/L	1 - 7 ⁽⁴⁾	400		<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	
Total Magnesium (Mg)	ug/L				470	510	360	410	230	270	660	310	430	
Total Manganese (Mn)	ug/L				50	51	39	46	29	33	110	38	100	
Total Mercury (Hg)	ug/L	0.026			<0.013	<0.013	<0.013	<0.013	0.017	<0.013	0.013	<0.013	0.035	
Total Molybdenum (Mo)	ug/L	73			<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	
Total Nickel (Ni)	ug/L	25 - 150 ⁽⁵⁾	1000		<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	7.2	<2.0	<2.0	
Total Phosphorus (P)	ug/L				<100	<100	<100	<100	<100	<100	140	140	160	150
Total Potassium (K)	ug/L				340	470	300	300	280	190	640	200	240	
Total Selenium (Se)	ug/L	1			<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	
Total Silver (Ag)	ug/L	0.1			<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	
Total Sodium (Na)	ug/L				2800	3000	2200	2300	1700	1800	1900	1700	2200	
Total Strontium (Sr)	ug/L				7.1	7.7	5.9	6.1	4.4	4.8	19	5.5	7.6	
Total Thallium (Tl)	ug/L	0.8			<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	
Total Tin (Sn)	ug/L				<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	
Total Titanium (Ti)	ug/L				2.7	3.1	2.8	2.6	2.8	3.4	<2.0	3.5	4.3	
Total Uranium (U)	ug/L	15			<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	
Total Vanadium (V)	ug/L				<2.0	2.2	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	
Total Zinc (Zn)	ug/L	30	1000		<5.0	5.5	<5.0	<5.0	<5.0	5.7	<5.0	13	<5.0	<5.0

Notes

CCME FAL - Canadian Council of Ministers of the Environment Water Quality Guidelines for the Protection of Freshwater Aquatic Life (provided for reference)

MMER - Federal Metal Mining Effluent Regulations - guidelines shown represent maximum authorized concentrations in a grab sample (provided for reference)

(1) Aluminum guideline dependent on pH. Guideline is 5 ug/L if pH <6.5 and 100 ug/L if pH ≥ 6.5 (see CCME Summary Table).

(2) Cadmium guideline (updated for 2014) ($\mu\text{g/L}$) = $10^{(0.83[\ln(\text{hardness})]-2.46)}$ for hardness between 17-280 mg/L CaCO₃ or a lower limit of 0.04 ug/L for hardness < 17mg/L or an upper limit of 0.37 ug/L for hardness >280 mg/L (see CCME Fact Sheet).

(3) Copper guideline based on sample hardness: copper guideline ($\mu\text{g/L}$) = $e^{0.8545[\ln(\text{hardness})]-1.465} * 0.2$ for hardness ≥82 to ≤180 mg/L, or a lower limit of 2 $\mu\text{g/L}$ for hardness <82 mg/L and an upper limit of 4 $\mu\text{g/L}$ for hardness >180 mg/L (see CCME Summary Table).

(4) Lead guideline based on sample hardness: lead guideline ($\mu\text{g/L}$) = $e^{1.273[\ln(\text{hardness})]-4.705}$ for hardness >60 to ≤180 mg/L, or a lower limit of 1 $\mu\text{g/L}$ for hardness <60 mg/L and an upper limit of 7 $\mu\text{g/L}$ for hardness >180 mg/L (see CCME Summary Table).

(5) Nickel guideline based on sample hardness: nickel guideline ($\mu\text{g/L}$) = $e^{0.76[\ln(\text{hardness})]+1.06}$ for hardness >60 to ≤180 mg/L, or a lower limit of 25 $\mu\text{g/L}$ for hardness <60 mg/L and an upper limit of 150 $\mu\text{g/L}$ for hardness >180 mg/L (see CCME Summary Table).

- denotes not analyzed

Table 4: Surface Water Quality Data
Beaver Dam Mine Project
Marinette, Nova Scotia

Table 4K: SW-9 General Chemistry Results

		CCME FAL	MMER	SW-9									
Sampling Date				9-Oct-14	13-Nov-14	18-Dec-14	22-Jan-15	29-Apr-15	28-May-15	30-Jun-15	29-Jul-15	29-Jul-15	24-Aug-15
Calculated Parameters	Units												SW-9 (DUP)
Anion Sum	me/L			0.310	0.200	0.140	0.180	0.100	0.170	0.130	0.250	0.250	0.150
Bicarb. Alkalinity (calc. as CaCO ₃)	mg/L			5.8	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	5.6	5.5	<1.0
Calculated TDS	mg/L			23	17	12	16	9	13	13	18	18	15
Carb. Alkalinity (calc. as CaCO ₃)	mg/L			<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Cation Sum	me/L			0.420	0.340	0.230	0.290	0.180	0.260	0.310	0.330	0.340	0.330
Hardness (CaCO ₃)	mg/L			10	6.4	4.1	5.0	2.8	4.7	7.4	8.0	8.2	7.5
Ion Balance (% Difference)	%			15.1	25.9	24.3	23.4	28.6	20.9	40.9	13.8	15.3	37.5
Langelier Index (@ 20C)	N/A			(4.22)	NC	NC	NC	NC	NC	NC	-3.90	-3.83	NC
Langelier Index (@ 4C)	N/A			(4.47)	NC	NC	NC	NC	NC	NC	-4.16	-4.08	NC
Nitrate (N)	mg/L	2.935		0.091	<0.050	<0.050	0.051	<0.050	<0.050	<0.050	0.064	<0.050	<0.050
Saturation pH (@ 20C)	N/A			10.2	NC	NC	NC	NC	NC	NC	10.3	10.3	NC
Saturation pH (@ 4C)	N/A			10.4	NC	NC	NC	NC	NC	NC	10.5	10.5	NC
Inorganics													
Total Alkalinity (Total as CaCO ₃)	mg/L			5.8	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	5.6	5.5	<5.0
Dissolved Chloride (Cl)	mg/L			6.7	7.2	4.8	6.2	3.4	6.1	4.8	4.8	4.9	5.4
Colour	TCU			160	140	110	73	82	80	150	130	130	180
Nitrate + Nitrite	mg/L			0.091	<0.050	<0.050	0.051	<0.050	<0.050	<0.050	0.064	<0.050	<0.050
Nitrite (N)	mg/L	0.06		<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
Nitrogen (Ammonia Nitrogen)	mg/L	Varies ⁽¹⁾		<0.050	<0.050	<0.050	<0.050	0.082	<0.050	0.14	<0.050	<0.050	<0.050
Total Organic Carbon (C)	mg/L			17	18	8.9	7.0	6.1	6.7	12	12	12	11 (1)
Orthophosphate (P)	mg/L			<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
pH	pH	6.5-9	6-9.5	5.94	4.96	5.06	5.44	5.77	6.17	6.33	6.36	6.43	6.05
Reactive Silica (SiO ₂)	mg/L			3.2	3.1	2.4	3.5	1.6	1.5	2.2	2.7	2.6	2.3
Dissolved Sulphate (SO ₄)	mg/L			<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
Turbidity	NTU			1.5	0.74	0.49	0.77	1.0	0.72	0.99	1.0	0.93	0.82
Conductivity	uS/cm			39	35	27	32	19	29	29	30	30	29
Total Suspended Solids				-	-	-	-	-	-	-	-	-	-
Field Parameters													
Temperature	°C			16.03	7.84	4	0.07	2.72	20.69	18.96	20.3	-	-
Conductivity	µS/cm			47	36	28.2	26	20	34	34	-	-	-
Total Dissolved Solids	g/L			0.037	0.037	-	0.033	-	-	-	-	-	-
Dissolved Oxygen	mg/L	5.5-9.5 ⁽²⁾		9.82	12.85	12.34	21.9	15.27	10.89	9.9	-	-	-
pH		6.5-9	6-9.5	4.90	3.17	4.66	3.68	6.6	5.72	8.04	6.14	-	-

Notes

CCME FAL - Canadian Council of Ministers of the Environment Water Quality Guidelines for the Protection of Freshwater Aquatic Life (provided for reference)

MMER - Federal Metal Mining Effluent Regulations - guidelines shown represent maximum authorized concentrations in a grab sample (provided for reference)

(1) Ammonia guideline dependent on temperature and pH, e.g., if T = 10°C, guideline for total ammonia-N varies from 83.88 mg/L at pH = 6.0 to 0.02 mg/L at pH = 10 (see CCME Fact Sheet).

(2) Dissolved oxygen - lowest acceptable concentration ranges from 5.5 mg/L for warm water biota at other life stages to 9.5 mg/L for cold water biota at early life stages (see CCME Summary Table).

- denotes not analyzed

NC = not calculated

Table 4: Surface Water Quality Data
Beaver Dam Mine Project
Marinette, Nova Scotia

Table 4L: SW-9 Metals Results

		CCME FAL	MMER	SW-9										
				9-Oct-14	13-Nov-14	18-Dec-14	22-Jan-15	29-Apr-15	28-May-15	30-Jun-15	29-Jul-15	29-Jul-15	24-Aug-15	SW-1 (DUP)
Sampling Date														
Metals	Units													
Total Aluminum (Al)	ug/L	5 / 100 ⁽¹⁾		410	330	310	210	160	170	280	260	270	320	
Total Antimony (Sb)	ug/L			<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	
Total Arsenic (As)	ug/L	5.0	1000	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	
Total Barium (Ba)	ug/L			6.6	5.7	3.5	3.4	2.1	2.4	3.3	3.4	3.3	4.2	
Total Beryllium (Be)	ug/L			<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	
Total Bismuth (Bi)	ug/L			<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	
Total Boron (B)	ug/L	1500		<50	<50	<50	<50	<50	<50	<50	<50	<50	<50	
Total Cadmium (Cd)	ug/L	0.04 - 0.37 ⁽²⁾		0.024	0.025	0.019	0.010	0.014	<0.010	0.014	<0.010	<0.010	0.015	
Total Calcium (Ca)	ug/L			2300	1400	890	1100	640	1100	1700	1800	1900	1700	
Total Chromium (Cr)	ug/L			<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.3	<1.0
Total Cobalt (Co)	ug/L			<0.40	<0.40	<0.40	<0.40	<0.40	<0.40	<0.40	<0.40	<0.40	<0.40	
Total Copper (Cu)	ug/L	2 - 4 ⁽³⁾	600	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	
Total Iron (Fe)	ug/L	300		620	500	280	290	220	210	440	490	510	580	
Total Lead (Pb)	ug/L	1 - 7 ⁽⁴⁾	400	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	
Total Magnesium (Mg)	ug/L			1100	700	450	530	300	480	740	830	840	810	
Total Manganese (Mn)	ug/L			140	75	51	51	36	34	57	56	60	76	
Total Mercury (Hg)	ug/L	0.026		<0.013	<0.013	<0.013	<0.013	<0.013	0.013	<0.013	<0.013	0.013	0.032	
Total Molybdenum (Mo)	ug/L	73		<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	
Total Nickel (Ni)	ug/L	25 - 150 ⁽⁵⁾	1000	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	
Total Phosphorus (P)	ug/L			<100	<100	<100	<100	<100	<100	<100	150	160	170	160
Total Potassium (K)	ug/L			640	530	340	350	300	270	200	210	240	180	
Total Selenium (Se)	ug/L	1		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	
Total Silver (Ag)	ug/L	0.1		<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	
Total Sodium (Na)	ug/L			4000	3900	2900	3900	2400	3500	3100	3300	3500	3500	
Total Strontium (Sr)	ug/L			10	7.7	5.0	5.6	2.8	4.2	5.9	6.5	5.9	6.6	
Total Thallium (Tl)	ug/L	0.8		<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	
Total Tin (Sn)	ug/L			<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	
Total Titanium (Ti)	ug/L			4.8	4.1	3.5	2.8	3.1	3.0	3.1	3.6	4.9	4.3	
Total Uranium (U)	ug/L	15		0.11	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	0.12	0.13	0.11
Total Vanadium (V)	ug/L			<2.0	2.3	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	
Total Zinc (Zn)	ug/L	30	1000	5.2	7.5	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	

Notes

CCME FAL - Canadian Council of Ministers of the Environment Water Quality Guidelines for the Protection of Freshwater Aquatic Life (provided for reference)

MMER - Federal Metal Mining Effluent Regulations - guidelines shown represent maximum authorized concentrations in a grab sample (provided for reference)

(1) Aluminum guideline dependent on pH. Guideline is 5 ug/L if pH <6.5 and 100 ug/L if pH ≥ 6.5 (see CCME Summary Table).

(2) Cadmium guideline (updated for 2014) ($\mu\text{g/L}$) = $10^{(0.83(\log(\text{hardness}))-2.46)}$ for hardness between 17-280 mg/L CaCO_3 or a lower limit of 0.04 ug/L for hardness < 17mg/L or an upper limit of 0.37 ug/L for hardness >280 mg/L (see CCME Fact Sheet).

(3) Copper guideline based on sample hardness: copper guideline ($\mu\text{g/L}$) = $e^{0.8545[\ln(\text{hardness})]-1.465} * 0.2$ for hardness ≥82 to ≤180 mg/L, or a lower limit of 2 ug/L for hardness <82 mg/L and an upper limit of 4 ug/L for hardness >180 mg/L (see CCME Summary Table).

(4) Lead guideline based on sample hardness: lead guideline ($\mu\text{g/L}$) = $e^{1.273[\ln(\text{hardness})]-4.705}$ for hardness >60 to ≤180 mg/L, or a lower limit of 1 ug/L for hardness <60 mg/L and an upper limit of 7 ug/L for hardness >180 mg/L (see CCME Summary Table).

(5) Nickel guideline based on sample hardness: nickel guideline ($\mu\text{g/L}$) = $e^{0.76[\ln(\text{hardness})]+1.06}$ for hardness >60 to ≤180 mg/L, or a lower limit of 25 ug/L for hardness <60 mg/L and an upper limit of 150 ug/L for hardness >180 mg/L (see CCME Summary Table).

- denotes not analyzed

Table 4: Surface Water Quality Data
Beaver Dam Mine Project
Marinette, Nova Scotia

Table 4M: SW-10 General Chemistry Results

		CCME FAL	MMER	SW-10			
Sampling Date				30-Jun-15	29-Jul-15	24-Aug-15	24-Aug-15
Calculated Parameters	Units						SW-10 (DUP)
Anion Sum	me/L			0.450	0.580	0.770	0.780
Bicarb. Alkalinity (calc. as CaCO ₃)	mg/L			8.0	11	25	25
Calculated TDS	mg/L			32	39	55	55
Carb. Alkalinity (calc. as CaCO ₃)	mg/L			<1.0	<1.0	<1.0	<1.0
Cation Sum	me/L			0.450	0.510	0.960	0.960
Hardness (CaCO ₃)	mg/L			15	20	30	30
Ion Balance (% Difference)	%			0.00	6.42	11.0	10.3
Langelier Index (@ 20C)	N/A			-3.05	-3.09	-2.67	-2.60
Langelier Index (@ 4C)	N/A			-3.31	-3.35	-2.92	-2.85
Nitrate (N)	mg/L	2.935		0.060	0.070	<0.050	<0.050
Saturation pH (@ 20C)	N/A			9.70	9.46	8.91	8.91
Saturation pH (@ 4C)	N/A			9.96	9.71	9.16	9.16
Inorganics							
Total Alkalinity (Total as CaCO ₃)	mg/L			8.0	11	25	25
Dissolved Chloride (Cl)	mg/L			2.9	2.2	2.9	3.1
Colour	TCU			9.4	<5.0	100	110
Nitrate + Nitrite	mg/L			0.060	0.070	<0.050	<0.050
Nitrite (N)	mg/L	0.06		<0.010	<0.010	<0.010	<0.010
Nitrogen (Ammonia Nitrogen)	mg/L	Varies ⁽¹⁾		<0.050	<0.050	0.10	0.19
Total Organic Carbon (C)	mg/L			2.1	1.8	7.6	7.4
Orthophosphate (P)	mg/L			<0.010	0.012	0.064	0.064
pH	pH	6.5-9	6-9.5	6.65	6.37	6.24	6.31
Reactive Silica (SiO ₂)	mg/L			4.7	6.0	7.0	7.0
Dissolved Sulphate (SO ₄)	mg/L			9.6	14	8.8	8.9
Turbidity	NTU			1.0	<0.10	10	8.3
Conductivity	uS/cm			46	54	75	76
Total Suspended Solids				-	-	-	-
Field Parameters							
Temperature	°C			14.14	17.6	-	-
Conductivity	μS/cm			51	-	-	-
Total Dissolved Solids	g/L			-	-	-	-
Dissolved Oxygen	mg/L	5.5-9.5 ⁽²⁾		11.8	-	-	-
pH		6.5-9	6-9.5	6.55	5.88	-	-

Notes

CCME FAL - Canadian Council of Ministers of the Environment Water Quality Guidelines for the Protection of Freshwater Aquatic Life (provided for reference)

MMER - Federal Metal Mining Effluent Regulations - guidelines shown represent maximum authorized

(1) Ammonia guideline dependent on temperature and pH, e.g., if T = 10°C, guideline for total ammonia-N varies from 83.88 mg/L at pH = 6.0 to 0.02 mg/L at pH = 10 (see CCME Fact Sheet).

(2) Dissolved oxygen - lowest acceptable concentration ranges from 5.5 mg/L for warm water biota at other life stages to 9.5 mg/L for cold water biota at early life stages (see CCME Summary Table).

- denotes not analyzed

NC = not calculated

(4) Lead guideline based on sample hardness: lead guideline (μg/L) = $e^{1.273[\ln(\text{hardness})]-4.705}$ for hardness >60 to ≤180 mg/L, or a lower limit of 1 μg/L for hardness <60 mg/L and an upper limit of 7 μg/L for hardness >180 mg/L (see CCME Summary Table).

(5) Nickel guideline based on sample hardness: nickel guideline (μg/L) = $e^{0.76[\ln(\text{hardness})]+1.06}$ for hardness >60 to ≤180 mg/L, or a lower limit of 25 μg/L for hardness <60 mg/L and an upper limit of 150 μg/L for hardness >180 mg/L (see CCME Summary Table).

- denotes not analyzed

Table 4: Surface Water Quality Data
Beaver Dam Mine Project
Marinette, Nova Scotia

Table 4N: SW-10 Metals Results

Sampling Date	Metals	Units	CCME FAL	MMER	SW-10			
					30-Jun-15	29-Jul-16	24-Aug-15	24-Aug-15 SW-10 (DUP)
Total Aluminum (Al)	ug/L	5 / 100 ⁽¹⁾			39	28	220	210
Total Antimony (Sb)	ug/L				<1.0	<1.0	<1.0	<1.0
Total Arsenic (As)	ug/L	5.0	1000		130	36	380	370
Total Barium (Ba)	ug/L				5.4	7.3	7.1	6.9
Total Beryllium (Be)	ug/L				<1.0	<1.0	<1.0	<1.0
Total Bismuth (Bi)	ug/L				<2.0	<2.0	<2.0	<2.0
Total Boron (B)	ug/L	1500			<50	<50	<50	<50
Total Cadmium (Cd)	ug/L	0.04 - 0.37 ⁽²⁾			0.061	0.10	0.011	<0.010
Total Calcium (Ca)	ug/L				4900	6400	10000	10000
Total Chromium (Cr)	ug/L				<1.0	<1.0	<1.0	<1.0
Total Cobalt (Co)	ug/L				1.8	1.4	2.2	2.3
Total Copper (Cu)	ug/L	2 - 4 ⁽³⁾	600		3.0	3.6	<2.0	<2.0
Total Iron (Fe)	ug/L	300			1400	78	6000	5900
Total Lead (Pb)	ug/L	1 - 7 ⁽⁴⁾	400		<0.50	<0.50	1.1	1.2
Total Magnesium (Mg)	ug/L				660	900	1200	1200
Total Manganese (Mn)	ug/L				110	78	290	280
Total Mercury (Hg)	ug/L	0.026			<0.013	<0.013	0.025	0.028
Total Molybdenum (Mo)	ug/L	73			<2.0	<2.0	<2.0	<2.0
Total Nickel (Ni)	ug/L	25 - 150 ⁽⁵⁾	1000		7.2	8.7	6.2	6.1
Total Phosphorus (P)	ug/L				140	170	140	140
Total Potassium (K)	ug/L				640	790	1000	1000
Total Selenium (Se)	ug/L	1			<1.0	<1.0	<1.0	<1.0
Total Silver (Ag)	ug/L	0.1			<0.10	<0.10	<0.10	<0.10
Total Sodium (Na)	ug/L				1900	2100	2500	2400
Total Strontium (Sr)	ug/L				19	26	33	33
Total Thallium (Tl)	ug/L	0.8			<0.10	<0.10	<0.10	<0.10
Total Tin (Sn)	ug/L				<2.0	<2.0	<2.0	<2.0
Total Titanium (Ti)	ug/L				<2.0	<2.0	2.8	2.9
Total Uranium (U)	ug/L	15			<0.10	<0.10	0.21	0.20
Total Vanadium (V)	ug/L				<2.0	<2.0	<2.0	<2.0
Total Zinc (Zn)	ug/L	30	1000		13	19	<5.0	<5.0

Notes

CCME FAL - Canadian Council of Ministers of the Environment Water Quality Guidelines for the Protection of Freshwater Aquatic Life (provided for reference)

MMER - Federal Metal Mining Effluent Regulations - guidelines shown represent maximum authorized concentrations in a grab sample (provided for reference)

(1) Aluminum guideline dependent on pH. Guideline is 5 ug/L if pH <6.5 and 100 ug/L if pH ≥ 6.5 (see CCME Summary Table).

(2) Cadmium guideline (updated for 2014) ($\mu\text{g/L}$) = $10^{0.83(\log[\text{hardness}])-2.46}$ for hardness between 17-280 mg/L CaCO₃ or a lower limit of 0.04 ug/L for hardness < 17mg/L or an upper limit of 0.37 ug/L for hardness >280 mg/L (see CCME Fact Sheet).

(3) Copper guideline based on sample hardness: copper guideline ($\mu\text{g/L}$) = $e^{0.8545[\ln(\text{hardness})]-1.465} * 0.2$ for hardness ≥82 to ≤180 mg/L, or a lower limit of 2 ug/L for hardness <82 mg/L and an upper limit of 4 ug/L for hardness >180 mg/L (see CCME Summary Table).

(4) Lead guideline based on sample hardness: lead guideline ($\mu\text{g/L}$) = $e^{1.273[\ln(\text{hardness})]-4.705}$ for hardness >60 to ≤180 mg/L, or a lower limit of 1 ug/L for hardness <60 mg/L and an upper limit of 7 ug/L for hardness >180 mg/L (see CCME Summary Table).

(5) Nickel guideline based on sample hardness: nickel guideline ($\mu\text{g/L}$) = $e^{0.76[\ln(\text{hardness})]+1.06}$ for hardness >60 to ≤180 mg/L, or a lower limit of 25 ug/L for hardness <60 mg/L and an upper limit of 150 ug/L for hardness >180 mg/L (see CCME Summary Table).

- denotes not analyzed

Table 5: Groundwater Quality Data
Beaver Dam Mine Project
Marinette, Nova Scotia

Sample		MW-01						MW-02				MW-03								MW-04						
		MW-01A		MW-01B		MW-01C		MW-02A		MW-02B		MW-03A		MW-03B		MW-03C			MW-04A		MW-04B					
Sampling Date		19-Jun-18	12-Sep-18	18-Jun-18	12-Sep-18	18-Jun-18	12-Sep-18	18-Jun-18	12-Sep-18	12-Sep-18	Field DUP 3)															
Parameters	Units																									
Anion Sum	me/L	0.560	0.460	1.56	1.50	1.35	0.930	0.330	0.280	0.480	0.480	0.280	0.420	0.980	1.05	1.87	1.77	1.97	0.440	0.420	1.16	1.03	0.390			
Bicarb. Alkalinity (calc. as CaCO ₃)	mg/L	18	14	60	58	52	34	6.0	6.2	17	16	6.2	9.9	37	39	83	77	86	11	9.8	41	36	11			
Calculated TDS	mg/L	37	34	91	89	79	57	21	25	40	41	20	31	62	65	110	100	110	32	31	71	67	30			
Carb. Alkalinity (calc. as CaCO ₃)	mg/L	<1.0	ND	ND																						
Cation Sum	me/L	0.510	0.440	1.47	1.46	1.26	0.940	0.260	0.270	0.440	0.450	0.260	0.390	0.930	0.970	1.79	1.76	1.91	0.510	0.390	1.08	1.06	0.330			
Hardness (CaCO ₃)	mg/L	2.2	7.4	54	58	40	33	4.9	5.6	10	9.6	5.9	9.5	35	36	67	66	75	17	11	44	41	8.0			
Ion Balance (% Difference)	%	4.67	2.22	2.97	1.35	3.45	0.530	11.9	1.82	4.35	3.23	3.70	3.70	2.62	3.96	2.19	0.280	1.55	7.37	3.70	3.57	1.44	8.33			
Langelier Index (@ 20C)	N/A	-3.54	-3.14	-0.512	-0.286	-1.03	-1.41	-4.58	-4.24	-3.20	-2.94	-4.37	-3.65	-2.01	-1.67	-0.247	-0.304	-0.0900	-3.26	-3.27	-1.26	-1.22	-3.78			
Langelier Index (@ 4C)	N/A	-3.79	-3.39	-0.763	-0.537	-1.28	-1.66	-4.83	-4.50	-3.45	-3.19	-4.63	-3.91	-2.26	-1.92	-0.498	-0.556	-0.341	-3.51	-3.53	-1.51	-1.47	-4.03			
Nitrate (N)	mg/L	<0.050	0.065	<0.050	ND	<0.050	ND	<0.050	ND	<0.050	0.052	0.31	0.44	0.10	0.11	<0.050	<0.050	0.074	<0.050	0.060	<0.050	0.054	0.28			
Saturation pH (@ 20C)	N/A	10.3	9.9	8.29	8.28	8.50	8.75	10.4	10.4	9.64	9.70	10.3	9.87	8.67	8.63	8.06	8.10	8.00	9.58	9.80	8.54	8.62	9.97			
Saturation pH (@ 4C)	N/A	10.5	10.1	8.55	8.53	8.75	9.00	10.7	10.6	9.89	9.95	10.6	10.1	8.93	8.89	8.31	8.36	8.25	9.83	10.1	8.79	8.88	10.2			
INORGANICS																										
Total Alkalinity (Total as CaCO ₃)	mg/L	18	14	61	59	52	34	6.0	6.2	17	16	6.2	9.9	37	39	84	77	87	11	9.9	41	36	11			
Dissolved Chloride (Cl)	mg/L	4.8	4.0	4.4	4.1	4.7	5.1	5.4	3.3	2.7	3.3	4.7	4.9	5.5	6.3	4.3	5.2	5.1	6.4	5.0	4.9	4.5	3.7			
Colour	TCU	<5.0	ND	<5.0	ND	6.5	ND	<5.0	ND	<5.0	ND	8.6	ND	5.4	ND	5.3	<5.0	ND	<5.0	ND	<5.0	ND	ND			
Nitrate + Nitrite (N)	mg/L	<0.050	0.065	<0.050	ND	<0.050	ND	<0.050	ND	<0.050	0.052	0.31	0.44	0.10	0.11	<0.050	<0.050	0.074	<0.050	0.060	<0.050	0.054	0.28			
Nitrite (N)	mg/L	<0.010	ND	<0.010	ND	<0.050	ND	<0.010	ND	ND																
Nitrogen (Ammonia Nitrogen)	mg/L	<0.050	ND	ND																						
Total Organic Carbon (C)	mg/L	1.3	ND (1)	2.6	ND	1.9	2.9	1.2	ND	1.9	ND	3.6	2.3	1.1	0.88	4.2	4.3	1.7	0.73	ND	1.1	1.6	ND			
Orthophosphate (P)	mg/L	<0.010	ND	<0.010	ND	<0.010	ND	<0.010	0.011	0.058	0.068	<0.010	ND	0.010												
pH	pH	6.75	6.74	7.78	8.00	7.47	7.34	5.83	6.12	6.44	6.76	5.93	6.21	6.66	6.97	7.81	7.80	7.91	6.32	6.53	7.28	7.41	6.19			
Reactive Silica (SiO ₂)	mg/L	6.3	8.4	9.4	10	7.5	7.1	3.2	9.2	15	15	4.1	7.4	10	11	9.6	9.4	11	6.4	8.4	9.6	10	9.3			
Dissolved Sulphate (SO ₄)	mg/L	3.0	3.2	11	10	8.7	5.1	2.6	2.8	2.7	3.2	<2.0	2.5	3.8	3.6	3.7	3.9	4.1	2.3	3.5	9.6	8.9	2.5			
Turbidity	NTU	29	75	7.1	13	17	10	22	1.7	4.6	4.6	0.39	15	0.26	1.7	1.7	1.5	2.3	0.79	130	5.9	2.0	15			
Conductivity	µS/cm	54	47	140	150	120	100	34	32	46	49	32	43	94	100	170	170	190	41	45	110	110	42			
METALS																										
Total Aluminum (Al)	ug/L	69	40	20	14	19	8.2	160	34	9.2	8.7	190	96	<5.0	ND	26	30	16	6.0	13	9.0	7.0	17			
Total Antimony (Sb)	ug/L																									

Table 5: Groundwater Quality Data
Beaver Dam Mine Project
Marinette, Nova Scotia

Sample		MW-05							MW-07							MW-09							
		MW-05A			MW-05B			MW-05D	MW-07A		MW-07B		MW-07D		MW-09A			MW-09B		MW-09D			
Sampling Date		27-Jun-18	(Field DUP 4) 27-Jun-18	12-Sep-18	27-Jun-18	12-Sep-18	12-Sep-18 (Field DUP 2)	27-Jun-18	12-Sep-18	27-Jun-18	12-Sep-18	27-Jun-18	12-Sep-18	18-Jun-18	18-Jun-18 (Field DUP 1)	12-Sep-18	18-Jun-18	12-Sep-18	18-Jun-18	12-Sep-18	18-Jun-18	12-Sep-18	
Parameters	Units																						
Anion Sum	me/L	0.41	0.420	0.450	0.990	1.84	1.78	1.73	1.70	2.47	2.46	7.02	6.93	2.59	2.91	0.340	0.320	0.930	2.46	2.75	2.97	4.21	
Bicarb. Alkalinity (calc. as CaCO3)	mg/L	11	11	15	37	73	72	66	66	100	100	320	310	110	120	9.2	8.8	37	71	74	65	79	
Calculated TDS	mg/L	27	28	30	60	100	100	100	100	150	150	380	370	150	170	30	29	56	150	170	190	260	
Carb. Alkalinity (calc. as CaCO3)	mg/L	<1.0	<1.0	ND	<1.0	ND	ND	<1.0	ND	<1.0	ND	2.2	2.0	1.1	1.3	<1.0	<1.0	ND	<1.0	ND	<1.0	ND	
Cation Sum	me/L	0.37	0.380	0.390	0.900	1.03	1.04	1.61	1.58	2.53	2.70	6.68	6.50	2.75	2.86	0.630	0.630	0.870	2.37	2.53	2.89	4.01	
Hardness (CaCO3)	mg/L	10	10	11	27	34	35	56	56	93	100	290	280	120	110	25	25	36	72	66	93	120	
Ion Balance (% Difference)	%	5.13	5.00	7.14	4.76	28.2	26.2	3.59	3.66	1.20	4.65	2.48	3.20	3.00	0.870	29.9	32.6	3.33	1.86	4.17	1.37	2.43	
Langelier Index (@ 20C)	N/A	-3.37	-3.46	-3.35	-1.33	-0.614	-0.780	-0.134	-0.184	-0.988	-0.642	0.935	0.874	0.288	0.346	-3.07	-2.95	-1.79	-0.174	-0.0840	-0.547	-0.0610	
Langelier Index (@ 4C)	N/A	-3.62	-3.71	-3.60	-1.58	-0.865	-1.03	-0.385	-0.435	-1.24	-0.892	0.686	0.625	0.0380	0.0960	-3.32	-3.20	-2.04	-0.424	-0.335	-0.798	-0.311	
Nitrate (N)	mg/L	0.051	<0.050	ND	0.061	ND	ND	<0.050	ND	<0.050	ND	<0.050	ND	<0.050	ND	<0.050	<0.050	0.051	<0.050	ND	<0.050	ND	
Saturation pH (@ 20C)	N/A	9.8	9.79	9.64	8.80	8.42	8.42	8.26	8.26	7.93	7.90	6.93	6.96	7.77	7.73	9.37	9.39	8.64	8.11	8.13	8.09	7.90	
Saturation pH (@ 4C)	N/A	10.1	10.0	9.89	9.05	8.68	8.67	8.51	8.51	8.18	8.15	7.18	7.21	8.02	7.98	9.62	9.64	8.89	8.36	8.38	8.34	8.15	
INORGANICS																							
Total Alkalinity (Total as CaCO3)	mg/L	11	11	15	37	74	72	66	66	100	100	320	310	110	120	9.2	8.8	37	72	75	65	80	
Dissolved Chloride (Cl)	mg/L	4.5	4.8	3.1	4.0	3.9	3.5	4.7	4.6	4.4	4.5	6.7	6.2	6.9	6.5	3.5	2.9	3.3	5.1	4.6	8.6	11	
Colour	TCU	<5.0	<5.0	ND	<5.0	ND	ND	<5.0	ND	8.0	70	<5.0	ND	<5.0	ND	<5.0	<5.0	ND	<5.0	ND	<5.0	ND	
Nitrate + Nitrite (N)	mg/L	0.051	<0.050	ND	0.061	ND	ND	<0.050	ND	<0.050	ND	<0.050	ND	<0.050	ND	<0.050	<0.050	0.051	<0.050	ND	<0.050	ND	
Nitrite (N)	mg/L	<0.010	<0.010	ND	<0.010	ND	ND	<0.010	ND	<0.010	ND	<0.010	ND	<0.010	ND	<0.010	0.021	ND	<0.010	ND	<0.010	ND	
Nitrogen (Ammonia Nitrogen)	mg/L	<0.050	<0.050	ND	<0.050	ND	ND	<0.050	ND	<0.050	ND	0.060	ND	<0.050	ND	<0.050	<0.050	ND	<0.050	ND	<0.050	ND	
Total Organic Carbon (C)	mg/L	1.5	1.5	0.61	2.0	7.6	8.0	1.3	ND	1.1	0.72	3.2	3.4	2.2	3.3	0.59	0.61	ND	2.5	5.4	9.1	17	
Orthophosphate (P)	mg/L	<0.010	<0.010	ND	<0.010	ND	ND	<0.010	ND	<0.010	ND	0.013	0.013	0.035	0.038	<0.010	<0.010	ND	0.027	0.016	0.012	0.013	
pH	pH	6.43	6.33	6.29	7.47	7.81	7.64	8.13	8.08	6.94	7.26	7.86	7.83	8.05	8.08	6.30	6.44	6.85	7.94	8.05	7.54	7.84	
Reactive Silica (SiO2)	mg/L	5.1	5.2	6.4	8.2	21	20	12	12	21	22	24	24	15	15	5.1	5.1	8.6	9.3	9.0	12	11	
Dissolved Sulphate (SO4)	mg/L	3	3.0	3.1	6.6	12	11	13	12	13	12	19	22	12	16	2.9	2.9	4.6	42	53	68	110	
Turbidity	NTU	1.5	0.77	1.8	11	20	24	2.2	0.40	30	31	4.6	8.7	9.5	5.1	0.29	0.33	2.9	6.1	36	2.4	14	
Conductivity	uS/cm	44	43	47	100	170	170	160	240	250	620	620	280	290	30	31	93	230	270	300	430		
METALS																							
Total Aluminum (Al)	ug/L	8.3	8.8	14	10	11	6.5	29	7.4	<5.0	ND	5.7	7.2	10	14	<5.0	81	36	61	11	8.9	ND	
Total Antimony (Sb)	ug/L	<1.0	<1.0	ND	<1.0	ND	ND	<1.0	ND	<1.0	ND	<1.0	ND	<1.0	ND	<1.0	<1.0	ND	<1.0	ND	<1.0	ND	
Total Arsenic (As)	ug/L	<1.0	<1.0	ND	1.0	1.4	1.3	<1.0	ND	12	14	39	36	170	170	1.0	<1.0	5.5	120	120	140	110	
Total Barium (Ba)	ug/L	5.9	5.7	9.9	5.8	6.6	6.3	3.4	2.2	11	9.9	13	15	5.5	8.2	6.1	5.7	3.8	12				

Table 5: Groundwater Quality Data
Beaver Dam Mine Project
Marinette, Nova Scotia

Sample		MW-11							MW-12				MW-14							MW-16					
		MW-11A		MW-11B		MW-11C			MW-12A		MW-12B		MW-14A		MW-14B			MW-14C		MW-16A		MW-16B			
Sampling Date		27-Jun-18	12-Sep-18	27-Jun-18	12-Sep-18	27-Jun-18	21-Sep-18	21-Sep-18 (Field Dup 5)	18-Jun-18	12-Sep-18	18-Jun-18	12-Sep-18	27-Jun-18	12-Sep-18	(Field DUP 5) 27-Jun-18	12-Sep-18	27-Jun-18	12-Sep-18	18-Jun-18	12-Sep-18	18-Jun-18	12-Sep-18	18-Jun-18	12-Sep-18	
Parameters	Units																								
Anion Sum	me/L	0.300	0.340	1.87	1.06	2.02	2.02	2.12	0.83	0.880	2.20	2.21	0.740	0.670	5.07	5.04	4.00	1.80	1.73	1.80	1.38	1.43	1.41		
Bicarb. Alkalinity (calc. as CaCO3)	mg/L	5.5	8.3	78	47	68	71	76	33	36	80	83	27	25	91	94	94	72	71	79	60	59	59		
Calculated TDS	mg/L	21	23	100	63	120	120	120	64	62	130	130	53	52	320	310	240	100	100	100	78	84	82		
Carb. Alkalinity (calc. as CaCO3)	mg/L	<1.0	ND	<1.0	ND	<1.0	<1.0	<1.0	<1.0	ND	<1.0	ND	<1.0	ND	1.3	1.5	1.1	1.3	ND	<1.0	ND	<1.0	ND		
Cation Sum	me/L	0.280	0.290	1.71	1.15	1.91	1.89	1.88	0.94	0.770	2.10	2.06	0.670	0.620	4.58	4.50	3.58	1.60	1.57	1.72	1.25	1.34	1.30		
Hardness (CaCO3)	mg/L	8.0	7.8	71	24	76	71	71	31	24	70	70	18	14	46	45	54	29	32	66	46	55	54		
Ion Balance (% Difference)	%	3.45	7.94	4.47	4.07	2.80	3.32	6.00	6.21	6.67	2.33	3.51	4.96	3.88	5.08	5.66	5.54	5.88	4.85	2.27	4.94	3.25	4.06		
Langelier Index (@ 20C)	N/A	-4.04	-3.63	0.0690	-1.41	-0.283	-0.250	-0.307	-2.42	-2.50	-0.212	-0.155	-2.64	-2.58	-0.123	-0.0470	-0.106	-0.227	-0.406	-0.291	-1.07	-0.510	-0.249		
Langelier Index (@ 4C)	N/A	-4.29	-3.88	-0.182	-1.66	-0.534	-0.501	-0.557	-2.67	-2.75	-0.462	-0.405	-2.89	-2.83	-0.371	-0.297	-0.356	-0.478	-0.657	-0.542	-1.33	-0.761	-0.501		
Nitrate (N)	mg/L	0.059	ND	0.19	ND	0.066	0.089	0.077	0.085	0.17	0.062	ND	0.11	0.084	<0.050	<0.050	ND	0.052	ND	0.092	ND	0.14	0.13		
Saturation pH (@ 20C)	N/A	10.2	10.0	8.05	8.75	8.10	8.10	8.08	8.9	8.95	8.08	8.07	9.19	9.31	8.29	8.29	8.20	8.52	8.48	8.08	8.34	8.27	8.27		
Saturation pH (@ 4C)	N/A	10.4	10.3	8.30	9.00	8.35	8.35	8.33	9.15	9.21	8.33	8.32	9.44	9.57	8.54	8.54	8.45	8.77	8.73	8.33	8.59	8.52	8.52		
INORGANICS																									
Total Alkalinity (Total as CaCO3)	mg/L	5.5	8.3	79	47	69	72	77	33	36	81	83	27	25	92	95	95	74	72	79	60	59	60		
Dissolved Chloride (Cl)	mg/L	4.8	3.9	3.5	4.1	4.4	3.7	3.8	2.4	2.8	4.6	3.3	3.6	3.2	13	13	8.5	3.9	3.0	4.0	3.2	4.1	3.3		
Colour	TCU	<5.0	ND	<5.0	ND	<5.0	<5.0	<5.0	<5.0	ND	<5.0	ND	<5.0	ND	5.7	ND	<5.0	ND	<5.0	ND	<5.0	<5.0	ND		
Nitrate + Nitrite (N)	mg/L	0.059	ND	0.19	ND	0.066	0.089	0.077	0.085	0.17	0.062	ND	0.11	0.084	<0.050	<0.050	ND	0.052	ND	0.092	ND	0.14	0.13		
Nitrite (N)	mg/L	<0.010	ND	<0.010	ND	<0.010	<0.010	<0.010	<0.010	ND	<0.010	ND	<0.010	ND	<0.010	<0.010	ND	<0.010	ND	<0.010	ND	<0.010	<0.010		
Nitrogen (Ammonia Nitrogen)	mg/L	<0.050	ND	<0.050	ND	<0.050	<0.050	<0.050	<0.050	ND	<0.050	ND	<0.050	ND	<0.050	<0.050	ND	<0.050	ND	<0.050	ND	<0.050	<0.050		
Total Organic Carbon (C)	mg/L	1.3	0.60	0.65	9.0	1.7	0.91	0.95	<0.50	ND	1.0	ND	0.62	ND	14	14	6.6	1.5	0.53	0.60	1.5	<0.50	ND		
Orthophosphate (P)	mg/L	<0.010	ND	0.018	ND	0.021	0.019	0.018	<0.010	ND	0.016	0.013	0.012	0.018	<0.010	<0.010	ND	<0.010	ND	<0.010	ND	<0.010	<0.010		
pH	pH	6.12	6.37	8.11	7.34	7.82	7.85	7.77	6.48	6.46	7.86	7.91	6.56	6.74	8.17	8.24	8.09	8.29	8.08	7.79	7.27	7.76	8.02		
Reactive Silica (SiO2)	mg/L	3.8	5.2	8.7	4.6	8.8	9.0	8.9	17	17	10	11	14	17	8.9	9.0	9.5	10	11	11	9.1	10	10		
Dissolved Sulphate (SO4)	mg/L	2.6	3.1	8.2	ND	25	23	23	4.0	3.0	21	22	4.3	4.0	140	130	90	11	10	4.5	3.8	6.0	5.4		
Turbidity	NTU	0.80	0.68	10	21	6.8	1.4	1.0	41	2.6	11	1.2	61	1.4	37	37	24	33	11	3.0	14	0.68	0.35		
Conductivity	uS/cm	35	35	170	120	200	190	200	80	86	200	210	74	68	540	540	400	170	160	160	130	130	130		
METALS																									
Total Aluminum (Al)	ug/L	31	78	14	5.6	18	6.2	7.6	5.0	5.0	5.5	ND	<5.0	ND	<5.0	<5.0	7.4	6.5	ND	<5.0	5.2	11	8.8		
Total Antimony (Sb)	ug/L	<1.0	ND	<1.0	ND	<1.0	<1.0	<1.0	<1.0	ND	<1.0	ND	<1.0	ND	1.6	1.6	1.3	<1.0	ND	<1.0	ND	<1.0	<1.0	ND	

Table 5: Groundwater Quality Data
Beaver Dam Mine Project
Marinette, Nova Scotia

Sample		MW-17							MW-18							MW-19					
		MW-17A		MW-17B			MW-17C		MW-18A			MW-18B		MW-18C		MW-19A		MW-19B		MW-19C	
Sampling Date		18-Jun-18	12-Sep-18	18-Jun-18	18-Jul-18 (Field DUP 2)	12-Sep-18	18-Jun-18	12-Sep-18	27-Jun-18	12-Sep-18	12-Sep-18 (Field DUP 1)	27-Jun-18	12-Sep-18	27-Jun-18	12-Sep-18	19-Jun-18	12-Sep-18	19-Jun-18	12-Sep-18	19-Jun-18	12-Sep-18
Parameters	Units																				
Anion Sum	me/L	0.510	0.640	0.300	0.300	0.330	0.420	0.450	0.310	0.320	0.330	1.34	1.39	2.02	2.52	0.210	0.240	1.49	1.65	1.24	1.30
Bicarb. Alkalinity (calc. as CaCO ₃)	mg/L	15	23	8.3	7.4	9.3	14	15	5.5	6.8	7.3	45	50	52	56	<1.0	5.3	60	67	37	39
Calculated TDS	mg/L	34	42	25	25	26	32	35	23	24	24	84	86	130	160	21	18	88	94	80	83
Carb. Alkalinity (calc. as CaCO ₃)	mg/L	<1.0	ND	<1.0	<1.0	ND	<1.0	ND	<1.0	ND	ND	<1.0	ND	<1.0	ND	<1.0	ND	<1.0	ND	<1.0	ND
Cation Sum	me/L	0.470	0.540	0.260	0.260	0.250	0.390	0.400	0.270	0.290	0.270	1.23	1.25	1.89	2.33	0.280	0.180	1.45	1.49	1.21	1.22
Hardness (CaCO ₃)	mg/L	15	18	6.6	6.7	6.1	12	12	6.8	7.6	7.3	41	30	45	58	5.4	4.1	59	60	36	36
Ion Balance (% Difference)	%	4.08	8.47	7.14	7.14	13.8	3.70	5.88	6.90	4.92	10.0	4.28	5.30	3.32	3.92	14.3	14.3	1.36	5.10	1.22	3.17
Langelier Index (@ 20C)	N/A	-3.14	-2.47	-4.06	-4.08	-3.80	-3.07	-2.93	-4.17	-3.82	-3.86	-0.820	-0.564	-0.636	-0.465	NC	-4.53	-0.330	-0.255	-1.53	-1.39
Langelier Index (@ 4C)	N/A	-3.40	-2.72	-4.31	-4.33	-4.06	-3.33	-3.18	-4.42	-4.07	-4.11	-1.07	-0.815	-0.886	-0.715	NC	-4.78	-0.581	-0.506	-1.78	-1.64
Nitrate (N)	mg/L	<0.050	ND	<0.050	<0.050	ND	<0.050	ND	0.062	ND	ND	<0.050	ND	<0.050	ND	0.25	0.15	0.066	ND	0.11	0.052
Saturation pH (@ 20C)	N/A	9.42	9.17	10.2	10.2	10.1	9.59	9.57	10.3	10.2	10.1	8.52	8.61	8.44	8.32	NC	10.6	8.23	8.18	8.68	8.64
Saturation pH (@ 4C)	N/A	9.67	9.42	10.4	10.4	10.4	9.84	9.82	10.6	10.4	10.4	8.77	8.86	8.69	8.57	NC	10.8	8.48	8.43	8.93	8.89
INORGANICS																					
Total Alkalinity (Total as CaCO ₃)	mg/L	15	23	8.3	7.4	9.3	14	15	5.5	6.8	7.3	45	50	52	56	<5.0	5.3	61	68	37	39
Dissolved Chloride (Cl)	mg/L	5.2	4.3	2.9	3.3	2.9	2.9	2.7	3.8	3.5	3.7	3.5	2.7	5.3	5.7	4.1	2.9	2.4	2.6	3.8	3.3
Colour	TCU	<5.0	ND	<5.0	5.3	ND	<5.0	ND	<5.0	ND	ND	<5.0	ND	<5.0	ND	<5.0	ND	<5.0	ND	<5.0	ND
Nitrate + Nitrite (N)	mg/L	<0.050	ND	<0.050	<0.050	ND	<0.050	ND	0.062	ND	ND	<0.050	ND	<0.050	ND	0.25	0.15	0.066	ND	0.15	0.063
Nitrite (N)	mg/L	<0.010	ND	<0.010	<0.010	ND	<0.010	ND	<0.010	ND	ND	<0.010	ND	<0.010	ND	<0.010	ND	<0.010	ND	0.041	0.010
Nitrogen (Ammonia Nitrogen)	mg/L	<0.050	ND	<0.050	<0.050	ND	<0.050	ND	<0.050	ND	ND	<0.050	ND	<0.050	ND	<0.050	ND	<0.050	ND	<0.050	ND
Total Organic Carbon (C)	mg/L	0.59	ND	0.56	0.51	ND	<0.50	ND	1.7	ND	ND	1.4	1.6	5.8	7.7	2.4	0.85	0.95	1.2	2.1	2.0
Orthophosphate (P)	mg/L	<0.010	ND	0.014	0.017	0.019	<0.010	0.016	<0.010	ND	0.011	0.054	0.046	<0.010	ND	<0.010	ND	<0.010	ND	<0.010	ND
pH	pH	6.28	6.70	6.10	6.12	6.34	6.51	6.64	6.18	6.34	6.28	7.70	8.04	7.81	7.86	5.85	6.06	7.90	7.93	7.15	7.26
Reactive Silica (SiO ₂)	mg/L	6.9	9.7	8.6	9.1	9.5	10	11	5.3	6.5	6.6	11	11	11	11	5.9	5.1	8.9	9.0	8.8	9.3
Dissolved Sulphate (SO ₄)	mg/L	2.6	2.9	2.7	2.6	2.8	2.9	3.2	4.3	3.9	3.8	17	15	40	59	3.5	2.2	9.8	11	18	20
Turbidity	NTU	1.6	3.3	0.49	0.90	2.1	0.74	1.0	1.1	0.23	0.45	20	43	18	9.3	1.3	14	2.7	8.9	7.0	10
Conductivity	uS/cm	46	64	29	29	31	40	45	35	36	36	130	140	210	260	34	26	140	160	130	140
METALS																					
Total Aluminum (Al)	ug/L	6.4	ND	12	11	8.7	<5.0	ND	23	27	23	13	20	16	11	110	50	15	15	37	ND
Total Antimony (Sb)	ug/L	<1.0	ND	<1.0	<1.0	ND	<1.0	ND	<1.0	ND	ND	<1.0	ND	<1.0	ND	<1.0	ND	<1.0	ND	<1.0	ND
Total Arsenic (As)	ug/L	<1.0	ND	<1.0	<1.0	ND	1.2	2.6	40	26	24	230	230	57	79	<1.0	ND	8.5	6.4	3.0	3.2
Total Barium (Ba)	ug/L	10	12	3.0	2.9	3.4	2.4	1.2	5.7	11	6.1	4.1	8.4	6.4	9.6	7.4	12	10	13	7.3	7.3
Total Beryllium (Be)	ug/L	<1.0	ND	<1.0	<1.0	ND	<1.0	ND	<1.0	ND	ND	<1.0	ND	<1.0	ND	<1.0	ND	<1.0	ND	<1.0	ND
Total Bismuth (Bi)	ug/L	<2.0	ND	<2.0	<2.0	ND	<2.0	ND	<2.0	ND	ND	<2.0	ND	<2.0	ND	<2.0	ND	<2.0	ND	<2.0	ND
Total Boron (B)	ug/L	<50	ND	<50	<50	ND	<														

Table 5: Groundwater Quality Data
Beaver Dam Mine Project
Marinette, Nova Scotia

Sample	MW-20						MW-21						MW-22					
	MW-20A			MW-20B			MW-21A		MW-21B		MW-21C		MW-22A		MW-22B		MW-22C	
	Sampling Date	26-Jun-18	12-Sep-18	12-Sep-18 (Field DUP 4)	26-Jun-18	12-Sep-18	18-Jun-18	12-Sep-18	18-Jun-18	12-Sep-18	18-Jun-18	12-Sep-18	26-Jun-18	12-Sep-18	26-Jun-18	12-Sep-18	26-Jun-18	12-Sep-18
Parameters	Units																	
Anion Sum	me/L	0.360	0.410	1.11	2.12	2.23	0.250	0.420	0.580	0.690	1.67	1.69	0.300	0.390	1.56	0.850	2.24	2.13
Bicarb. Alkalinity (calc. as CaCO ₃)	mg/L	7.9	12	41	90	96	6.5	13	21	26	54	61	5.8	11	59	31	94	95
Calculated TDS	mg/L	26	31	68	120	120	20	31	40	46	110	110	23	31	94	59	130	120
Carb. Alkalinity (calc. as CaCO ₃)	mg/L	<1.0	ND	ND	<1.0	ND	<1.0	ND	<1.0	ND	<1.0	ND	<1.0	ND	<1.0	ND	1.0	ND
Cation Sum	me/L	0.310	0.330	1.01	1.95	1.96	0.240	0.370	0.550	0.620	1.56	1.52	0.260	0.330	1.38	0.790	2.00	1.90
Hardness (CaCO ₃)	mg/L	7.6	8.1	40	72	74	7.0	7.5	18	20	38	43	5.5	7.4	48	14	52	56
Ion Balance (% Difference)	%	7.46	10.8	4.72	4.18	6.44	2.04	6.33	2.65	5.34	3.41	5.30	7.14	8.33	6.12	3.66	5.66	5.71
Langelier Index (@ 20C)	N/A	-4.03	-3.63	-1.40	-0.0410	-0.0810	-4.65	-4.08	-2.94	-2.91	-1.93	-1.55	-4.11	-3.83	-0.786	-2.36	-0.0890	-0.106
Langelier Index (@ 4C)	N/A	-4.28	-3.88	-1.66	-0.291	-0.332	-4.90	-4.34	-3.19	-3.16	-2.18	-1.81	-4.36	-4.08	-1.04	-2.62	-0.340	-0.357
Nitrate (N)	mg/L	0.21	0.27	ND	<0.050	ND	0.48	0.67	0.35	0.53	0.14	0.18	0.093	0.059	<0.050	ND	<0.050	ND
Saturation pH (@ 20C)	N/A	10.1	9.93	8.57	8.07	8.03	10.3	9.94	9.30	9.13	8.63	8.56	10.5	10.0	8.41	9.23	8.16	8.13
Saturation pH (@ 4C)	N/A	10.4	10.2	8.83	8.32	8.28	10.5	10.2	9.56	9.38	8.88	8.81	10.7	10.3	8.66	9.48	8.41	8.38
INORGANICS																		
Total Alkalinity (Total as CaCO ₃)	mg/L	7.9	12	41	91	97	6.5	13	21	26	54	61	5.8	11	60	31	95	96
Dissolved Chloride (Cl)	mg/L	4.8	3.6	3.7	3.6	3.1	3.1	2.6	3.1	2.6	5.2	4.5	4.0	3.5	4.2	3.7	4.2	3.2
Colour	TCU	5.5	ND	ND	<5.0	ND	8.0	5.6	<5.0	ND								
Nitrate + Nitrite (N)	mg/L	0.21	0.27	ND	<0.050	ND	0.48	0.67	0.35	0.53	0.14	0.18	0.093	0.059	<0.050	ND	<0.050	ND
Nitrite (N)	mg/L	<0.010	ND	ND	<0.010	ND	<0.010	ND	<0.010	ND	<0.010	0.010	<0.010	ND	<0.010	ND	<0.010	ND
Nitrogen (Ammonia Nitrogen)	mg/L	<0.050	ND	ND	0.054	ND	<0.050	ND										
Total Organic Carbon (C)	mg/L	1.3	ND	1.6	0.84	ND	2.1	2.0	1.0	1.3	4.2	2.5	1.0	0.93	1.8	2.6	1.6	0.93
Orthophosphate (P)	mg/L	<0.010	0.011	ND	<0.010	0.014	<0.010	ND	0.018	0.020	<0.010	ND	<0.010	ND	<0.010	ND	<0.010	ND
pH	pH	6.08	6.30	7.17	8.02	7.95	5.64	5.86	6.37	6.22	6.70	7.01	6.38	6.20	7.63	6.86	8.07	8.02
Reactive Silica (SiO ₂)	mg/L	6.7	9.2	10	12	12	5.6	6.8	8.9	10	15	19	6.5	10	14	13	12	12
Dissolved Sulphate (SO ₄)	mg/L	2.3	2.7	8.9	9.8	9.8	<2.0	2.3	2.2	2.7	21	16	3.3	3.3	12	5.6	10	6.1
Turbidity	NTU	4.9	7.9	1.0	4.7	2.5	1.1	1.7	23	17	7.6	1.8	2.2	2.7	1.8	2.3	6.8	1.0
Conductivity	uS/cm	38	41	110	200	200	33	48	61	71	160	170	33	41	150	89	210	200
METALS																		
Total Aluminum (Al)	ug/L	38	18	5.7	62	10	430	390	16	26	7.5	ND	22	19	23	8.6	12	7.6
Total Antimony (Sb)	ug/L	<1.0	ND	ND	<1.0	ND	<1.0	ND	<1.0	ND	<1.0	ND	<1.0	ND	<1.0	ND	<1.0	ND
Total Arsenic (As)	ug/L	<1.0	ND	ND	7.0	10	<1.0	ND	<1.0	ND	<1.0	ND	<1.0	ND	1.5	1.2	5.4	5.0
Total Barium (Ba)	ug/L	4.8	4.4	4.4	11	12	15	19	3.5	5.8	9.7	8.2	5.0	5.3	3.6	3.9	4.7	2.9
Total Beryllium (Be)	ug/L	<1.0	ND	ND	<1.0	ND	<1.0	ND	<1.0	ND	<1.0	ND	<1.0	ND	<1.0	ND	<1.0	ND
Total Bismuth (Bi)	ug/L	<2.0	ND	ND	<2.0	ND	<2.0	ND	<2.0	ND	<2.0	ND	<2.0	ND	<2.0	ND	<2.0	ND
Total Boron (B)	ug/L	<50	ND	ND	<50	ND	<50	ND	<50	ND	<50	ND	<50	ND	<50	ND	<50	ND
Total Cadmium (Cd)	ug/L	0.035	0.036	0.018	0.011	ND	0.049	0.066	0.015	0.025	0.019	ND	0.016	0.015	<0.010	ND	<0.010	ND
Total Calcium (Ca)	ug/L	1900	2000	14000	22000	22000	1500	1800	4700	5800	9700	10000	1000	1700	14000	3900	17000	18000
Total Chromium (Cr)	ug/L	<1.0	ND	ND	<1.0	ND	<1.0	ND	<1.0	ND	<1.0	ND	<1.0	ND	<1.0	ND	<1.0	ND
Total Cobalt (Co)	ug/L	2.8	ND	ND	<0.40	ND	3.7	4.2	<0.40	0.46	0.51	0.65	1.8	1.2	0.43	1.1	<0.40	ND
Total Copper (Cu)	ug/L	3.0	2.1	2.0	<2.0	ND	<2.0	ND	<2.0	ND	<2.0	ND	9.4	6.6	<2.0	ND	<2.0	ND
Total Iron (Fe)	ug/L	<50	ND	ND	<50	ND	65	ND										

Attachment 1

Stratigraphic Logs

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-01A		
LOCATION: Beaver Dam Mines Road					TPC ELEV.: 150.368	START DATE: May 1, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.: 149.247	COMPLETION DATE: May 1, 2018		
BENCHMARK:					PAGE 1 of 1			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION					SOIL VAPOUR CONCENTRATION					COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level	
									100	300	500	700	900	10	30	50	70	90				
-1	UTM Zone 20 NAD83 (CSRS) N:4990095.110 E:520942.252 Elev: CGVD 2013																			Stick-up		-3
0	Ground Surface																			Silica Sand		0
	ORGANIC - rootmat	██████																		PVC Riser		1
	SILTY SAND - brown, trace to some clay, numerous cobbles and boulders																			Bentonite Seal	████████	2
1	WEATHERED BEDROCK - grey greywacke, mechanical breaks, silt and clay in fractures, orange and black staining		1	CS	-	50	0															3
2	BEDROCK - grey greywacke, some fractures, orange and black staining		2	CS	-	86	40															4
3	BEDROCK - grey greywacke, mechanical breaks, numerous fractures, orange and black staining		3	CS	-	100	0															5
4	BEDROCK - grey greywacke, numerous fractures, no staining		4	CS	-	100	42															6
																				PVC Threaded Well Point	████████	20
																						21

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-01B		
LOCATION: Beaver Dam Mines Road					TPC ELEV.: 150.422	START DATE: May 4, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.: 149.428	COMPLETION DATE: May 4, 2018		
BENCHMARK:					PAGE 1 of 1			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)			SOIL VAPOUR CONCENTRATION (%LEL)			COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level	
									100	300	500	700	900	10	30	50	70	90
-1	UTM Zone 20 NAD83 (CSRS) N:4990093.660 E:520943.031 Elev: CGVD 2013																	
0	Ground Surface																	
0	ORGANIC - rootmat																	-4
0	SILTY SAND - brown, trace to some clay, some cobbles and boulders																	-3
0	WEATHERED BEDROCK - grey greywacke, mechanical break, silt and clay in fractures, orange and black staining																	-2
0	BEDROCK - grey greywacke, some fractures, orange and black staining																	-1
1																		0
1																		1
1	1 CS - 39 0																	2
2																		3
2																		4
2	2 CS - 60 9																	5
3																		6
3																		7
3	3 CS - 100 63																	8
4																		9
4																		10
4	4 CS - 100 78																	11
5																		12
5																		13
5	5 CS - 100 75																	14
6																		15
6																		16
6	6 CS - 100 88																	17
7																		18
7																		19
7	7 CS - 100 80																	20
8																		21
8																		22
8	8 CS - 100 56																	23
9																		24
9																		25
9	9 CS - 100 44																	26
10																		27
10																		28
10	10 CS - 100 69																	29
11																		30
12																		31
13																		32
14																		33
15																		34
																		35
																		36
																		37
																		38
																		39
																		40
																		41
																		42
																		43
																		44
																		45
																		46
																		47
																		48
																		49
																		50
																		51

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-01C		
LOCATION: Beaver Dam Mines Road					TPC ELEV.: 150.594	START DATE: May 4, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.: 149.465	COMPLETION DATE: May 4, 2018		
BENCHMARK:					PAGE 1 of 2			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)			SOIL VAPOUR CONCENTRATION (%LEL)			COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level	
									100	300	500	700	900	10	30	50	70	90
-1	UTM Zone 20 NAD83 (CSRS) N:4990092.462 E:520944.122 Elev: CGVD 2013 Ground Surface																	Stick-up
0	ORGANIC - rootmat	[Hatched]																Silica Sand
1	SILTY SAND - brown, trace to some clay, some cobbles and boulders	[Hatched]	1	CS	-	97	15											
2	BEDROCK - grey greywacke, mechanical breaks, silt and clay in fractures, orange and black staining	[Hatched]	2	CS	-	100	42											PVC Riser
3	BEDROCK - grey greywacke, some fractures, orange and black staining	[Hatched]	3	CS	-	100	41											
4																		
5	BEDROCK - grey greywacke, some fractures, no staining	[Hatched]	4	CS	-	100	75											Bentonite Seal
6																		
7																		
8																		
9																		
10																		
11																		
12																		
13																		
14																		

 <p>45 Akerley Blvd Dartmouth, NS B3B 1J7</p>	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-01C		
LOCATION: Beaver Dam Mines Road					TPC ELEV.: 150.594	START DATE: May 4, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.: 149.465	COMPLETION DATE: May 4, 2018		
BENCHMARK:					PAGE 2 of 2			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)					SOIL VAPOUR CONCENTRATION (%LEL)					COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level
								100	300	500	700	900	10	30	50	70	90			
15																				
16		11	CS	-	100	73														49
17		12	CS	-	100	59														50
18		13	CS	-	100	51														51
19		14	CS	-	100	51														52
20		15	CS	-	100	24														53
21	BEDROCK - grey greywacke, mechanical breaks, some fractures, no staining	16	CS	-	100	54														54
22		17	CS	-	100	68														55
23		18	CS	-	100	73														56
24	BEDROCK - grey greywacke, some fractures, no staining	19	CS	-	100	37														57
25		20	CS	-	100	63														58
26																				59
27																				60
28																				61
29																				62
30																				63
																				64
																				65
																				66
																				67
																				68
																				69
																				70
																				71
																				72
																				73
																				74
																				75
																				76
																				77
																				78
																				79
																				80
																				81
																				82
																				83
																				84
																				85
																				86
																				87
																				88
																				89
																				90
																				91
																				92
																				93
																				94
																				95
																				96
																				97
																				98
																				99
																				100

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling				REF. NO: 088664	BOREHOLE: MW-02A		
LOCATION: Beaver Dam Mines Road				TPC ELEV.: 151.292	START DATE: May 7, 2018		
CLIENT: Atlantic Gold Corporation				GRADE ELEV.: 150.228	COMPLETION DATE: May 7, 2018		
BENCHMARK:					PAGE 1 of 1		

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)				SOIL VAPOUR CONCENTRATION (%LEL)				COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level	
									100	300	500	700	900	10	30	50	70			
-1	UTM Zone 20 NAD83 (CSRS) N:4989595.501 E:520728.778 Elev: CGVD 2013																	Stick-up		-3
0	Ground Surface																			0
0	ORGANIC - rootmat	[Hatched]																Silica Sand		0
0	SILTY SAND - grey, some sand, some cobbles and boulders, wet at 0.6m	[Dotted]																PVC Riser	[Blue arrow]	1
1																		Bentonite Seal		2
2																				3
3																				4
4																				5
5																				6
6																				7
7																				8
8																				9
9																				10
10																				11
11																				12
12																				13
13																				14
14																				15
15																				16
16																				17

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-02B		
LOCATION: Beaver Dam Mines Road					TPC ELEV.: 151.352	START DATE: May 7, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.: 150.259	COMPLETION DATE: May 7, 2018		
BENCHMARK:					PAGE 1 of 1			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)			SOIL VAPOUR CONCENTRATION (%LEL)			COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level	
									100	300	500	700	900	10	30	50	70	90
-1	UTM Zone 20 NAD83 (CSRS) N:4989594.708 E:520730.397 Elev: CGVD 2013 Ground Surface																	Stick-up
0	ORGANIC - rootmat SILTY SAND - grey, some clay, some cobbles and boulders, wet at 2.03m	██████																Silica Sand
1																		PVC Riser
2																		Bentonite Seal
3																		
4																		
5	BEDROCK - grey granite, some fractures, silt and clay in fractures, orange and black staining	██████	1	CS	-	92	51											
6																		
7	BEDROCK - grey with some pinkish granite, highly fractured, orange and black staining	██████	2	CS	-	100	22											
8																		
9	BEDROCK - grey granite, numerous fractures, orange and black staining	██████	3	CS	-	100	44											
10																		
11	BEDROCK - grey granite, some fractures, no staining	██████	4	CS	-	100	41											
12																		
13																		
14																		
15																		
16																		

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-03A		
LOCATION: Beaver Dam Mines Road					TPC ELEV.: 166.256	START DATE: May 1, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.: 165.241	COMPLETION DATE: May 1, 2018		
BENCHMARK:					PAGE 1 of 1			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION					SOIL VAPOUR CONCENTRATION					COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level		
									100	300	500	700	900	10	30	50	70	90					
-1	UTM Zone 20 NAD83 (CSRS) N:4989220.163 E:521823.117 Elev: CGVD 2013																			Stick-up		-3	
0	Ground Surface																			Silica Sand		-2	
0	ORGANIC - rootmat																						0
0	SILTY SAND - brown, trace to some clay, some cobbles and boulders																						1
1	BEDROCK - grey greywacke, mechanical breaks, numerous fractures, silt and clay in fractures, orange and black staining, steeply dipping																			PVC Riser		2	
1			1	CS	-	70	0															3	
2			2	CS	-	97	20															4	
3			3	CS	-	98	31															5	
4			4	CS	-	100	78															6	
5																							
6																							

 <p>45 Akerley Blvd Dartmouth, NS B3B 1J7</p>	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling				REF. NO: 088664	BOREHOLE: MW-03B		
LOCATION: Beaver Dam Mines Road				TPC ELEV.: 166.208	START DATE: May 1, 2018		
CLIENT: Atlantic Gold Corporation				GRADE ELEV.: 165.194	COMPLETION DATE: May 1, 2018		
BENCHMARK:						PAGE 1 of 1	

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)				SOIL VAPOUR CONCENTRATION (%LEL)				COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level	
									100	300	500	700	900	10	30	50	70			
-1	UTM Zone 20 NAD83 (CSRS) N:4989222.229 E:521823.540 Elev: CGVD 2013																	Stick-up		-4
0	Ground Surface																	Silica Sand		-3
0	ORGANIC - rootmat																			0
0	SILTY SAND - brown, trace to some clay, some cobbles and boulders																			1
1	BEDROCK - grey greywacke, mechanical breaks, numerous fractures, silt and clay in fractures, orange and black staining, steeply dipping		1	CS	-	91	0													2
2			2	CS	-	95	0													3
3			3	CS	-	98	40													4
4	BEDROCK - grey greywacke, some fractures, orange and black staining, more competent, steeply dipping		4	CS	-	100	75													5
5	BEDROCK - grey greywacke, some fractures, no staining, more competent, steeply dipping		6	CS	-	100	27													6
6			7	CS	-	100	41													7
7			8	CS	-	100	61													8
8			9	CS	-	100	59													9
9			10	CS	-	100	59													10
10			11	CS	-	100	69													11
11																				12
12																				13
13																				14
14																				15
15																				16

 <p>45 Akerley Blvd Dartmouth, NS B3B 1J7</p>	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-03C		
LOCATION: Beaver Dam Mines Road					TPC ELEV.: 166.161	START DATE: May 2, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.: 165.154	COMPLETION DATE: May 2, 2018		
BENCHMARK:					PAGE 1 of 2			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)				SOIL VAPOUR CONCENTRATION (%LEL)				COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level	
									100	300	500	700	900	10	30	50	70			
-1	UTM Zone 20 NAD83 (CSRS) N:4989223.934 E:521824.051 Elev: CGVD 2013 Ground Surface																	Stick-up		-4 -3 -2 -1
0	ORGANIC - rootmat																	Silica Sand		0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15
1	SILTY SAND - brown, trace to some clay, some cobbles and boulders at 0.6m		1	CS	-	83	0													
2	WEATHERED BEDROCK - grey greywacke, mechanical breaks, highly fractured, silt and clay in fractures, orange and black staining		2	CS	-	92	53													
3	BEDROCK - grey greywacke, highly fractured, orange and black staining, primary bedding at 10°,		3	CS	-	100	37													
4																				
5	BEDROCK - grey greywacke, some fractures, no staining, primary bedding at 15°		4	CS	-	100	75											PVC Riser		16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48
6			5	CS	-	100	76													
7			6	CS	-	100	80													
8			7	CS	-	100	73													
9			8	CS	-	100	73													
10			9	CS	-	100	54											Bentonite Seal		
11			10	CS	-	100	81													
12																				
13																				
14																				

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling				REF. NO: 088664	BOREHOLE: MW-03C		
LOCATION: Beaver Dam Mines Road				TPC ELEV.: 166.161	START DATE: May 2, 2018		
CLIENT: Atlantic Gold Corporation				GRADE ELEV.: 165.154	COMPLETION DATE: May 2, 2018		
BENCHMARK:					PAGE 2 of 2		

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)					SOIL VAPOUR CONCENTRATION (%LEL)					COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level
								100	300	500	700	900	10	30	50	70	90			
10				-																
15																				
16		11	CS	-	100	90														
17		12	CS	-	100	90														
18		13	CS	-	100	58														
19		14	CS	-	100	63														
20		15	CS	-	100	97												Bentonite Seal		
21		16	CS	-	100	78														
22		17	CS	-	100	86												PVC Riser		
23		18	CS	-	100	83														
24		19	CS	-	100	54												Silica Sand		
25		20	CS	-	100	86												PVC "2-Slot" Screen		
26																		PVC Threaded Well Point		
27																				
28																				
29																				
30																				

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-04A		
LOCATION: Beaver Dam Mines Road					TPC ELEV.: 164.330	START DATE: April 3, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.: 163.477	COMPLETION DATE: April 3, 2018		
BENCHMARK:					PAGE 1 of 1			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)					SOIL VAPOUR CONCENTRATION (%LEL)					COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level	
									100	300	500	700	900	10	30	50	70	90				
-1	UTM Zone 20 NAD83 (CSRS) N:4989640.335 E:522649.993 Elev: CGVD 2013																			Stick-up		-3
0	Ground Surface																			Silica Sand		-2
0	ORGANIC - rootmat																			PVC Riser		-1
0	SILTY SAND - grey brown, trace to some clay, some cobbles and boulders																			Bentonite Seal		0
1																						1
2	WEATHERED BEDROCK - grey greywacke, highly fractured, orange and black staining		1	CS	-	47	0															2
2	BEDROCK - grey greywacke, with fractures, silt in some fractures, orange and black staining, steeply dipping		2	CS	-	85	0															3
3			3	CS	-	100	57															4
4			4	CS	-	100	76															5
5			5	CS	-	94	87															6
6																						7
7																						8
8																						9
9																						10
10																						11
11																						12
12																						13
13																						14
14																						15
15																						16
16																						17
17																						18
18																						19
19																						20
20																						21

 <p>45 Akerley Blvd Dartmouth, NS B3B 1J7</p>	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-04B		
LOCATION: Beaver Dam Mines Road					TPC ELEV.: 164.378	START DATE: April 2, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.: 163.509	COMPLETION DATE: April 3, 2018		
BENCHMARK:					PAGE 1 of 1			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)					SOIL VAPOUR CONCENTRATION (%LEL)					COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level
									100	300	500	700	900	10	30	50	70	90			
-1	UTM Zone 20 NAD83 (CSRS) N:4989639.523 E:522649.439 Elev: CGVD 2013 Ground Surface																		Stick-up		-4 -3 -2 -1
0	ORGANIC - rootmat SILTY SAND - grey brown, trace to some clay, some cobbles and boulders																		Silica Sand		0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16
2	BEDROCK - grey greywacke, highly fractured, orange and black staining, water bearing zones, slight dip		1	CS	-	93	0												Bentonite Seal		6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31
5	BEDROCK - grey greywacke, minor fractures, orange and black staining, slight dip		5	CS	-	94	82												PVC Riser		32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50
6			6	CS	-	100	100														
7			7	CS	-	100	96														
8			8	CS	-	96	75														
10	BEDROCK - grey greywacke, no fractures, quartz vein from 10.03 to 10.54m, slight dip		9	CS	-	100	100														
11			10		-																
12			11	CS	-	100	97														
13			12	CS	-	98	97														
15			13	CS	-	100	93														
16																					

 <p>45 Akerley Blvd Dartmouth, NS B3B 1J7</p>	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-05A		
LOCATION: Beaver Dam Mines Road					TPC ELEV.: 140.503	START DATE: April 25, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.: 139.677	COMPLETION DATE: April 25, 2018		
BENCHMARK:					PAGE 1 of 1			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)					SOIL VAPOUR CONCENTRATION (%LEL)					COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level	
									100	300	500	700	900	10	30	50	70	90				
-1	UTM Zone 20 NAD83 (CSRS) N:4990210.163 E:521746.140 Elev: CGVD 2013																			Stick-up		-3
0	Ground Surface																			Silica Sand		0
	ORGANIC - rootmat																			Bentonite Seal		1
	SILTY SAND - grey, trace to some clay, some cobbles and boulders at 0.6m																			PVC Riser		2
1	WEATHERED BEDROCK - grey greywacke, mechanical breaks, silt and clay in fractures, orange and black staining, steeply dipping																			Silica Sand		3
			1	CS	-	89	17												PVC "2-Slot" Screen		4	
			2	CS	-	62	0												PVC Threaded Well Point		5	
			3	CS	-	88	0														6	
			4	CS	-	78	0														7	
			5	CS	-	93	26														8	
5	BEDROCK - grey greywacke, some fractures, minor orange and black staining, steeply dipping																				9	
6																					10	
																					11	
																					12	
																					13	
																					14	
																					15	
																					16	
																					17	
																					18	
																					19	
																					20	
																					21	



45 Akerley Blvd
Dartmouth, NS
B3B 1J7

LOGGED BY: RH

DAYLIGHTING TO: n/a

GAS METER TYPE: n/a

REVIEWED BY:

EQUIPMENT: CME-75 Trackmount

DRAFTED BY: MG

METHOD: Case and Core

BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling						REF. NO: 088664	BOREHOLE: MW-05B					
LOCATION: Beaver Dam Mines Road						TPC ELEV.: 140.660	START DATE: April 24, 2018					
CLIENT: Atlantic Gold Corporation						GRADE ELEV.: 139.716	COMPLETION DATE: April 24, 2018					
BENCHMARK:						PAGE 1 of 1						
Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm) 100 300 500 700 900	SOIL VAPOUR CONCENTRATION (%LEL) 10 30 50 70 90	COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level
-1	UTM Zone 20 NAD83 (CSRS) N:4990208.591 E:521747.858 Elev: CGVD 2013 Ground Surface									Stick-up		-4 -3 -2 -1
0	ORGANIC - rootmat SILTY SAND - brown, trace to some clay, numerous cobbles and boulders, water at 0.68m	1	CS	-	89	31				Silica Sand		0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26
1	WEATHERED BEDROCK - grey greywacke, numerous fractures, silt and clay in fractures, orange and black staining	2	CS	-	83	17						
2		3	CS	-	76	0						
3		4	-									
4	BEDROCK - grey greywacke, mechanical breaks, highly fractured, orange and black staining, steeply dipping	5	CS	-	91	0				Bentonite Seal		14 15 16 17 18 19 20 21 22 23 24 25 26
5	BEDROCK - grey greywacke, numerous fractures, orange and black staining, steeply dipping	6	CS	-	98	42						
6		7	CS	-	100	80				PVC Riser		27 28 29 30 31 32 33 34 35 36
7	BEDROCK - grey greywacke, minor fractures, minor orange and black staining, steeply dipping	8	CS	-	100	88						
8		9	CS	-	100	100						
9	BEDROCK - grey greywacke, some fractures, no staining, steeply dipping	10	CS	-	100	91						
10		11	CS	-	100	85				Silica Sand		37 38 39 40 41 42 43 44 45 46 47 48 49 50
11	BEDROCK - grey greywacke, some fractures, some orange and black staining in fractures from 14.32 to 14.55m, steeply dipping	12	CS	-	100	59				PVC "2-Slot" Screen		51 52 53 54
12										PVC Threaded Well Point		
13												
14												
15												
16												
				LOGGED BY: RH			DAYLIGHTING TO: n/a		GAS METER TYPE: n/a			
45 Akerley Blvd Dartmouth, NS B3B 1J7				REVIEWED BY:			EQUIPMENT: CME-75 Trackmount					
DRAFTED BY: MG				METHOD: Case and Core			BOREHOLE DIA: 0.10m					

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-05C		
LOCATION: Beaver Dam Mines Road					TPC ELEV.: 140.762	START DATE: April 20, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.: 139.769	COMPLETION DATE: April 23, 2018		
BENCHMARK:					PAGE 1 of 4			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)			SOIL VAPOUR CONCENTRATION (%LEL)			COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level	
									100	300	500	700	900	10	30	50	70	90
-1	UTM Zone 20 NAD83 (CSRS) N:4990207.042 E:521745.609 Elev: CGVD 2013																	
0	Ground Surface																	
0	ORGANIC - rootmat	██████																-4
0	SILTY SAND - brown to grey brown, trace to some clay, some cobbles and boulders	██████																-3
1	WEATHERED BEDROCK - grey greywacke, some fractures, orange and black staining	██████	1	CS	-	58	19											-2
1	BEDROCK - grey greywacke, less weathered, no fractures, steeply dipping	██████	2	CS	-	92	0											-1
2	BEDROCK - grey greywacke, mechanical breaks, numerous fractures, some orange and black staining, steeply dipping	██████	3	CS	-	88	53											0
3		██████	4	CS	-	100	76											1
4		██████	5	CS	-	100	68											2
5		██████	6	CS	-	100	69											3
6		██████	7	CS	-	100	28											4
7		██████	8	CS	-	100	77											5
8	BEDROCK - grey greywacke, some fractures, no staining, steeply dipping	██████	9	CS	-	100	92											6
9		██████	10	CS	-	100	62											7
10		██████	11															8
11		██████	12	CS	-	100	96											9
12		██████																10
13		██████																11
14		██████																12

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-05C		
LOCATION: Beaver Dam Mines Road					TPC ELEV.: 140.762	START DATE: April 20, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.: 139.769	COMPLETION DATE: April 23, 2018		
BENCHMARK:					PAGE 2 of 4			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)					SOIL VAPOUR CONCENTRATION (%LEL)					COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level
									100	300	500	700	900	10	30	50	70	90			
15			13	CS	-	100	20														48
16			14	CS	-	100	0														49
17			15	CS	-	100	21														50
18			11	CS	-	100	100														51
			16	CS	-	100	26														52
			17	CS	-	100	41														53
19	BEDROCK - grey greywacke, some fractures, no staining, steeply dipping, quartz vein from 19.13 to 19.28m		18	CS	-	100	58														54
20			19	CS	-	100	47														55
21			20	CS	-	100	34														56
22			21	CS	-	100	66														57
23			22	CS	-	100	81														58
24			23	CS	-	100	91														59
25			24	CS	-	100	68														60
26			25	CS	-	100	91														61
27																					62
28																					63
29																					64
30																					65

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-05C		
LOCATION: Beaver Dam Mines Road					TPC ELEV.: 140.762	START DATE: April 20, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.: 139.769	COMPLETION DATE: April 23, 2018		
BENCHMARK:					PAGE 3 of 4			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)					SOIL VAPOUR CONCENTRATION (%LEL)					COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level
								100	300	500	700	900	10	30	50	70	90			
31		26	CS	-	100	56														101
32		27	CS	-	100	23														102
33		28	CS	-	100	0														103
34		29	CS	-	100	44														104
35		30	CS	-	100	79														105
36		32	CS	-	100	26														106
37		33	CS	-	100	84														107
38		34	CS	-	100	38														108
39		35	CS	-	100	32														109
40		36	CS	-	100	55														110
41		37	CS	-	100	83														111
42		38	CS	-	100	83														112
43		39	CS	-	100	39														113
44	BEDROCK - grey greywacke, mechanical breaks at 46.0m, numerous fractures, no staining, steeply dipping																			114
45																				115
46																				116

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling				REF. NO: 088664	BOREHOLE: MW-05C		
LOCATION: Beaver Dam Mines Road				TPC ELEV.: 140.762	START DATE: April 20, 2018		
CLIENT: Atlantic Gold Corporation				GRADE ELEV.: 139.769	COMPLETION DATE: April 23, 2018		
BENCHMARK:					PAGE 4 of 4		

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)				SOIL VAPOUR CONCENTRATION (%LEL)				COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level
								100	300	500	700	900	10	30	50	70	90	
47																		153
48		40	CS	-	100	52												154
49		41	CS	-	100	46												155
50		42	CS	-	100	58												156
51		43	CS	-	100	68												157
52		44	CS	-	100	83												158
53		45	CS	-	100	71												159
54		46	CS	-	100	44												160
55		47	CS	-	100	69												161
56		48	CS	-	100	54												162
57																		163
58																		164
59																		165
60																		166
61																		167
62																		168
																		169
																		170
																		171
																		172
																		173
																		174
																		175
																		176
																		177
																		178
																		179
																		180
																		181
																		182
																		183
																		184
																		185
																		186
																		187
																		188
																		189
																		190
																		191
																		192
																		193
																		194
																		195
																		196
																		197
																		198
																		199
																		200
																		201
																		202
																		203
																		204
																		205

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-05D		
LOCATION: Beaver Dam Mines Road					TPC ELEV.: 141.180	START DATE: April 30, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.: 140.168	COMPLETION DATE: May 1, 2018		
BENCHMARK:					PAGE 1 of 2			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)				SOIL VAPOUR CONCENTRATION (%LEL)				COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level		
									100	300	500	700	900	10	30	50	70				
-1	UTM Zone 20 NAD83 (CSRS) N:4990206.839 E:521742.062 Elev: CGVD 2013 Ground Surface																	Stick-up		-4 -3 -2 -1	
0	ORGANIC - rootmat	██████																Silica Sand	██████	0 1 2 3 4 5 6 7 8 9 10 11 12	
1	SILTY SAND - brown, trace to some clay, some cobbles and boulders, wet at 0.61m	██████																		██████	2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48
2	BEDROCK - grey greywacke, numerous fractures, silt and clay in the fractures, orange and black staining	██████	1	CS	-	60	0														
3		██████	2	CS	-	43	0														
4	BEDROCK - grey greywacke, some fractures, orange and black staining	██████	3	CS	-	67	39											PVC Riser	██████	13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48	
5		██████	4	CS	-	100	61														
6		██████	6	CS	-	100	75														
7		██████	7	CS	-	100	63														
8		██████	8	CS	-	100	49														
11	BEDROCK - grey greywacke, broken up and blocky, some fractures, no staining	██████	9	CS	-	78	0														
12	BEDROCK - grey greywacke, slightly broken up and blocky, numerous fractures, no staining	██████	10	CS	-	100	78														
13		██████	11	CS	-	100	10														
14		██████	12	CS	-	100	50														

 <p>45 Akerley Blvd Dartmouth, NS B3B 1J7</p>	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-05D		
LOCATION: Beaver Dam Mines Road					TPC ELEV.: 141.180	START DATE: April 30, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.: 140.168	COMPLETION DATE: May 1, 2018		
BENCHMARK:					PAGE 2 of 2			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)					SOIL VAPOUR CONCENTRATION (%LEL)					COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level
								100	300	500	700	900	10	30	50	70	90			
15		13	CS	-	100	54														49
16		14	CS	-	100	76														50
17		15	CS	-	100	58														51
18		16	CS	-	100	46														52
19		17	CS	-	100	39														53
20																			Bentonite Seal	54
21																				55
22	BEDROCK - grey greywacke, some fractures, no staining	18	CS	-	100	75														56
23		19	CS	-	100	66													PVC Riser	57
24		20	CS	-	100	83														58
25		21	CS	-	100	85														59
26		22	CS	-	98	18														60
27		23	CS	-	97	61														61
28		24	CS	-	100	61														62
29																			Silica Sand	63
30																			PVC "2- Slot" Screen	64
																			PVC Threaded Well Point	65
																				66
																				67
																				68
																				69
																				70
																				71
																				72
																				73
																				74
																				75
																				76
																				77
																				78
																				79
																				80
																				81
																				82
																				83
																				84
																				85
																				86
																				87
																				88
																				89
																				90
																				91
																				92
																				93
																				94
																				95
																				96
																				97
																				98
																				99
																				100

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-07A		
LOCATION: Beaver Dam Mines Road					TPC ELEV.:	START DATE: April 9, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.:	COMPLETION DATE: April 9, 2018		
BENCHMARK:					PAGE 1 of 1			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)			SOIL VAPOUR CONCENTRATION (%LEL)			COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level	
								100	300	500	700	900	10	30	50	70	90
-1	Ground Surface															Stick-up	-3 -2 -1
0	SILTY SAND - brown, trace to some clay, some cobbles and boulders, water at 1.85m															Silica Sand	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24
1																PVC Riser	6
2																Bentonite Seal	7
3																	8
4	WEATHERED BEDROCK - grey greywacke, numerous fractures, orange and black staining, steeply dipping	1	CS	-	100	0											9
4	BEDROCK - grey greywacke, numerous fractures, orange and black staining at 3.88m, steeply dipping	2	CS	-	100	69											10
4	BEDROCK - grey greywacke, numerous fractures, no staining, steeply dipping	3	CS	-	96	36											11
5		4	CS	-	100	62											12
6		5	CS	-	100	46											13
7		6	CS	-	97	62											14
																	15
																	16
																	17
																	18
																	19
																	20
																	21
																	22
																	23
																	24
																	25
																	26

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling						REF. NO: 088664	BOREHOLE: MW-07B					
LOCATION: Beaver Dam Mines Road						TPC ELEV.:	START DATE: April 6, 2018					
CLIENT: Atlantic Gold Corporation						GRADE ELEV.:	COMPLETION DATE: April 6, 2018					
BENCHMARK:						PAGE 1 of 1						
Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm) 100 300 500 700 900	SOIL VAPOUR CONCENTRATION (%LEL) 10 30 50 70 90	COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level
-1	Ground Surface									Stick-up		-4 -3 -2 -1
0	ORGANIC - rootmat SILTY SAND - brown, trace to some clay, numerous cobbles and boulders									Silica Sand		0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50
3	WEATHERED BEDROCK - grey greywacke, soft, numerous fractures containing silt and clay, orange and black staining, steeply dipping	1	CS	-	68	0				Bentonite Seal		10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50
4	BEDROCK - grey greywacke, numerous fractures containing silt and clay, orange and black staining, steeply dipping	2	CS	-	100	26				PVC Riser		10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50
5	BEDROCK - grey greywacke, numerous fractures, no staining, very soft at 5.48m, small quartz vein at 5.63m	3	CS	-	96	18				Bentonite Seal		10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50
6	BEDROCK - grey greywacke, numerous fractures, no staining, soft, steeply dipping	4	CS	-	100	36				PVC Riser		10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50
7		5	CS	-	100	25				Bentonite Seal		10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50
8		6	CS	-	100	33				PVC Riser		10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50
9		7	CS	-	97	67				Bentonite Seal		10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50
10		8	CS	-	100	30				PVC Riser		10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50
11		9	CS	-	100	65				Bentonite Seal		10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50
12		10	CS	-	96	48				PVC Riser		10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50
13		11	CS	-	97	41				Bentonite Seal		10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50
14		12	CS	-	100	34				Silica Sand		10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50
15		13	CS	-	100	50				PVC "2-Slot" Screen		10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50
16		14	CS	-	100	36				PVC Threaded Well Point		10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50
17		15	CS	-	100	85						51 52 53 54
18		16	CS	-	100	37						
19		17	CS	-	100	44						
20												
21												
22												
23												
24												
25												
26												
27												
28												
29												
30												
31												
32												
33												
34												
35												
36												
37												
38												
39												
40												
41												
42												
43												
44												
45												
46												
47												
48												
49												
50												



45 Akerley Blvd
Dartmouth, NS
B3B 1J7

LOGGED BY: RH

DAYLIGHTING TO: n/a

GAS METER TYPE: n/a

REVIEWED BY:

EQUIPMENT: CME-75 Trackmount

DRAFTED BY: MG

METHOD: Case and Core

BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-07C		
LOCATION: Beaver Dam Mines Road					TPC ELEV.:	START DATE: April 16, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.:	COMPLETION DATE: April 19, 2018		
BENCHMARK:					PAGE 1 of 4			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)					SOIL VAPOUR CONCENTRATION (%LEL)					COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level
									100	300	500	700	900	10	30	50	70	90			
-1	Ground Surface																		Stick-up		-4 -3 -2 -1
0	ORGANIC - rootmat																		Silica Sand		0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20
1	SILTY SAND - brown to grey brown, trace to some clay, some cobbles and boulders, water at 1.07m																		Bentonite Seal		2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20
2	WEATHERED BEDROCK - grey greywacke, soft, some silt and clay in fractures, orange and black staining, steeply dipping		1	CS	-	46	0												Bentonite Seal		21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47
3	BEDROCK - grey greywacke, less weathered, numerous fractures, orange and black staining, steeply dipping		2	CS	-	81	0												PVC Riser		21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47
4	BEDROCK - grey greywacke, some fractures, some orange and black staining, steeply dipping		3	CS	-	100	19														
5			4	CS	-	100	46														
6			5	CS	-	97	16														
7	BEDROCK - grey greywacke, some fractures, no staining, steeply dipping		6	CS	-	100	43														
8			7	CS	-	100	43														
9			8	CS	-	100	21														
10			9	CS	-	100	0														
11			10	CS	-	100	0														
12			11	CS	-	100	0														
13			12	CS	-	100	37														
14			13	CS	-	64	0														
15	BEDROCK - grey greywacke, no staining, steeply dipping, quartz vein at 13.44m		14	CS	-	100	0														
16			15	CS	-	100	44														
			16	CS	-	100	15														

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling				REF. NO: 088664	BOREHOLE: MW-07C		
LOCATION: Beaver Dam Mines Road				TPC ELEV.:	START DATE: April 16, 2018		
CLIENT: Atlantic Gold Corporation				GRADE ELEV.:	COMPLETION DATE: April 19, 2018		
BENCHMARK:				PAGE 2 of 4			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)					SOIL VAPOUR CONCENTRATION (%LEL)					COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level
								100	300	500	700	900	10	30	50	70	90			
15	BEDROCK - grey greywacke, some fractures, no staining, steeply dipping	10	-	-	-	-													48	
		17	CS	-	100	33													49	
		18	CS	-	98	0													50	
		19	CS	-	100	0													51	
		20	CS	-	100	0													52	
		21	CS	-	100	0													53	
		22	CS	-	100	0													54	
		23	CS	-	100	47													55	
		24	CS	-	100	34													56	
		25	CS	-	100	33													57	
		26	CS	-	100	0													58	
		27	CS	-	100	47													59	
		28	CS	-	97	36													60	
		29	CS	-	96	50													61	
		30	CS	-	100	0													62	
		31	CS	-	95	0													63	
		32	CS	-	88	0													64	
		33	CS	-	95	31													65	
		34	CS	-	100	14													66	
		35	CS	-	100	0													67	
		36	CS	-	100	46													68	

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling						REF. NO: 088664	BOREHOLE: MW-07C		
LOCATION: Beaver Dam Mines Road						TPC ELEV.:	START DATE: April 16, 2018		
CLIENT: Atlantic Gold Corporation						GRADE ELEV.:	COMPLETION DATE: April 19, 2018		
BENCHMARK:						PAGE 3 of 4			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE NUMBER	SAMPLE TYPE	SAMPLE NAME/ LAB ANALYSIS		SOIL VAPOUR CONCENTRATION (ppm)				SOIL VAPOUR CONCENTRATION (%LEL)				COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level	
						100	300	500	700	900	10	30	50	70	90		
BEDROCK - grey greywacke, some fractures, no staining, steeply dipping		37	CS	-	100	32											101
		38	CS	-	100	56											102
		39	CS	-	100	46											103
		40	CS	-	100	68											104
		41	CS	-	100	19											105
		42	CS	-	100	14											106
		43	CS	-	100	26											107
		44	CS	-	98	14											108
		45	CS	-	98	0											109
		46	CS	-	100	0											110
		47	CS	-	100	36											111
		48	CS	-	100	14											112
		49	CS	-	100	49											113
		50	CS	-	100	13											114
		51	CS	-	100	12											115

 <p>45 Akerley Blvd Dartmouth, NS B3B 1J7</p>	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-07C		
LOCATION: Beaver Dam Mines Road					TPC ELEV.:	START DATE: April 16, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.:	COMPLETION DATE: April 19, 2018		
BENCHMARK:					PAGE 4 of 4			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)				SOIL VAPOUR CONCENTRATION (%LEL)				COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level	
									100	300	500	700	900	10	30	50	70			
47	BEDROCK - grey greywacke, some fractures, no staining, steeply dipping		52	CS	-	100	31													153
48			53	CS	-	87	0													154
49			54	CS	-	98	18													155
50	BEDROCK - grey greywacke, some fractures, no staining, steeply dipping, quartz vein from 49.63 to 49.78m		55	CS	-	100	73													156
51			56	CS	-	100	80													157
52			57	CS	-	100	42													158
53	BEDROCK - grey greywacke, some fractures, steeply dipping, quartz vein throughout (vertical)		58	CS	-	100	52													159
54			59	CS	-	100	80													160
55	BEDROCK - grey greywacke, some fractures, no staining, steeply dipping		60	CS	-	100	23													161
56			61	CS	-	100	39													162
57			62	CS	-	100	36													163
58			63	CS	-	100	14													164
59																			165	
60																			166	
61																			167	
62																			168	
																			169	
																			170	
																			171	
																			172	
																			173	
																			174	
																			175	
																			176	
																			177	
																			178	
																			179	
																			180	
																			181	
																			182	
																			183	
																			184	
																			185	
																			186	
																			187	
																			188	
																			189	
																			190	
																			191	
																			192	
																			193	
																			194	
																			195	
																			196	
																			197	
																			198	
																			199	
																			200	
																			201	
																			202	
																			203	
																			204	
																			205	

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling						REF. NO: 088664			BOREHOLE: MW-07D			
LOCATION: Beaver Dam Mines Road						TPC ELEV.: 131.296			START DATE: May 14, 2018			
CLIENT: Atlantic Gold Corporation						GRADE ELEV.: 130.256			COMPLETION DATE: May 14, 2018			
BENCHMARK:						PAGE 1 of 2						
Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)	SOIL VAPOUR CONCENTRATION (%LEL)	COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level
-1	UTM Zone 20 NAD83 (CSRS) N:4990259.556 E:522674.898 Elev: CGVD 2013 Ground Surface							100 300 500 700 900	10 30 50 70 90			-4 -3 -2 -1
0	ORGANIC - rootmat SILTY SAND - brown to grey-brown, trace to some clay, some cobbles and boulders, wet at 1.24m									Stick-up		0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25
1												
2												
3	BEDROCK - grey greywacke, numerous fractures, silt and clay in the fractures, orange and black staining	1	CS	-	83	0						
4	BEDROCK - grey greywacke, numerous fractures, mechanical breaks, silt and clay in the fractures, orange and black staining	2	CS	-	98	0						
5	BEDROCK - grey greywacke, broken up, no staining	3	CS	-	97	21						
6	BEDROCK - grey greywacke, more competent, numerous fractures, no staining	4	CS	-	92	47						
7		5	CS	-	100	18						
8		6	CS	-	100	40						
9		7	CS	-	100	22						
10		8	CS	-	100	22						
11		9	CS	-	100	0						
12	BEDROCK - grey greywacke, more competent, numerous fractures noted, no staining	10	CS	-	100	11						
13		11	CS	-	100	42						
14		12	CS	-	100	36						
				LOGGED BY: RH			DAYLIGHTING TO: n/a			GAS METER TYPE: n/a		
45 Akerley Blvd Dartmouth, NS B3B 1J7				REVIEWED BY:			EQUIPMENT: CME-75 Trackmount					
DRAFTED BY: MG				METHOD: Case and Core			BOREHOLE DIA: 0.10m					

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling				REF. NO: 088664	BOREHOLE: MW-07D		
LOCATION: Beaver Dam Mines Road				TPC ELEV.: 131.296	START DATE: May 14, 2018		
CLIENT: Atlantic Gold Corporation				GRADE ELEV.: 130.256	COMPLETION DATE: May 14, 2018		
BENCHMARK:					PAGE 2 of 2		

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)					SOIL VAPOUR CONCENTRATION (%LEL)					COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level	
									100	300	500	700	900	10	30	50	70	90				
15																						49
16	BEDROCK - grey greywacke, not very competent, numerous fractures, no staining		13	CS	-	100	37															50
17			14	CS	-	100	22															51
18																						52
19	BEDROCK - grey greywacke, more competent, numerous fractures, no staining		15	CS	-	100	64															53
20			16	CS	-	100	34															54
21																						55
22	BEDROCK - grey greywacke, some fractures, no staining		17	CS	-	100	49															56
23			18	CS	-	100	25															57
24			19	CS	-	100	63															58
25			20	CS	-	100	47															59
26			21	CS	-	100	66															60
27			22	CS	-	100	52															61
28																						62
29																						63
30																						64

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-09A		
LOCATION: Beaver Dam Mines Road					TPC ELEV.:	START DATE: April 13, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.:	COMPLETION DATE: April 13, 2018		
BENCHMARK:					PAGE 1 of 1			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)					SOIL VAPOUR CONCENTRATION (%LEL)					COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level
									100	300	500	700	900	10	30	50	70	90			
-1	Ground Surface																		Stick-up		-3
0	ORGANIC - rootmat SILTY SAND - grey brown, trace to some clay, some cobbles and boulders	[Hatched]																	Silica Sand	[Hatched]	0
1	WEATHERED BEDROCK - grey greywacke, numerous fractures, silt and clay in fractures, orange and black staining, steeply	[Hatched]	1	CS	-	94	0												PVC Riser	[Solid Black]	2
2		[Hatched]	2	CS	-	76	0												Bentonite Seal	[Solid Black]	3
3		[Hatched]	3	CS	-	51	0														4
4		[Hatched]	4	CS	-	84	0														5
5		[Hatched]	5	CS	-	85	20														6
6		[Hatched]	6	CS	-	100	24														7
7	BEDROCK - grey greywacke, numerous fractures, no staining, steeply dipping	[Hatched]	7	CS	-	100	32												PVC "2-Slot" Screen	[Hatched]	8
8		[Hatched]	8	CS	-	100	69												PVC Threaded Well Point	[Hatched]	9
																					10
																					11
																					12
																					13
																					14
																					15
																					16
																					17
																					18
																					19
																					20
																					21
																					22
																					23
																					24

 <p>45 Akerley Blvd Dartmouth, NS B3B 1J7</p>	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling						REF. NO: 088664	BOREHOLE: MW-09B					
LOCATION: Beaver Dam Mines Road						TPC ELEV.:	START DATE: April 12, 2018					
CLIENT: Atlantic Gold Corporation						GRADE ELEV.:	COMPLETION DATE: April 13, 2018					
BENCHMARK:						PAGE 1 of 1						
Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm) 100 300 500 700 900	SOIL VAPOUR CONCENTRATION (%LEL) 10 30 50 70 90	COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level
-1	Ground Surface									Stick-up		-4
0	ORGANIC - rootmat SILTY SAND - grey brown, trace to some clay, some cobbles and boulders	1	CS	-	86	0				Silica Sand		-3
1	WEATHERED BEDROCK - grey greywacke, orange and black staining, clay and silt in fractures	2	CS	-	87	0						-2
2		3	CS	-	31	0						-1
3		4	CS	-	33	0						0
4		5	CS	-	58	0						1
5		6	CS	-	100	35						2
6	BEDROCK - grey greywacke, numerous fractures, orange and black staining, steeply dipping	7	CS	-	100	0				PVC Riser		3
7		8	CS	-	100	0						4
8		9	CS	-	100	25						5
9		10	CS	-	100	32						6
10	BEDROCK - grey greywacke, numerous fractures, mechanical breaks, no staining	11	CS	-	100	34						7
11		12	CS	-	100	0						8
12	BEDROCK - grey greywacke, numerous fractures, soft, no staining, steeply dipping	13	CS	-	100	11				Silica Sand		9
13		14	CS	-	100	33				PVC "2- Slot" Screen		10
14										PVC Threaded Well Point		11
15												12
16												13
 GHD				LOGGED BY: RH			DAYLIGHTING TO: n/a		GAS METER TYPE: n/a			51
45 Akerley Blvd Dartmouth, NS B3B 1J7				REVIEWED BY:			EQUIPMENT: CME-75 Trackmount					
DRAFTED BY: MG				METHOD: Case and Core			BOREHOLE DIA: 0.10m					

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-09C		
LOCATION: Beaver Dam Mines Road					TPC ELEV.:	START DATE: April 9, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.:	COMPLETION DATE: April 12, 2018		
BENCHMARK:					PAGE 1 of 4			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)					SOIL VAPOUR CONCENTRATION (%LEL)					COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level	
									100	300	500	700	900	10	30	50	70	90				
-1	Ground Surface																		Stick-up		-4 -3 -2 -1	
0	ORGANIC - rootmat																		Silica Sand		0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17	
1	SILTY SAND - brown, trace to some clay, numerous cobbles and boulders		1	CS	-	74	0															
2	WEATHERED BEDROCK - grey greywacke, numerous fractures, orange and black staining		2	CS	-	83	0															
3			3	CS	-	60	0															
4			4	CS	-	81	0															
5			5	CS	-	60	0															
6			6	CS	-	63	0															
7			7	CS	-	67	0															
8	BEDROCK - grey greywacke, some fractures, no staining, steeply dipping		8	CS	-	95	52												PVC Riser		18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51	
9			9	CS	-	100	59															
10			10	CS	-	97	59															
11			11	CS	-	96	52															
12			12	CS	-	100	56															
13			13	CS	-	100	0															
14			14	CS	-	100	100															
15			15	CS	-	91	0															
16			16	CS	-	100	0															
17			17	CS	-	96	21															
18			18	CS	-	97	0															
19			19	CS	-	97	0															
20			20	CS	-	100	24															

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-09C		
LOCATION: Beaver Dam Mines Road					TPC ELEV.:	START DATE: April 9, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.:	COMPLETION DATE: April 12, 2018		
BENCHMARK:					PAGE 2 of 4			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)					SOIL VAPOUR CONCENTRATION (%LEL)					COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level
								100	300	500	700	900	10	30	50	70	90			
16	BEDROCK - grey greywacke, highly fractured, no staining, steeply dipping	21	CS	-	95	0														52
17		22	CS	-	80	0														53
18		23	CS	-	80	0														54
19		24	CS	-	100	37														55
20	BEDROCK - grey greywacke, mechanical breaks, numerous fractures, no staining, steeply dipping	25	CS	-	100	40														56
21		26	CS	-	100	34														57
22		27	CS	-	100	54														58
23		28	CS	-	98	0														59
24		29	CS	-	100	47														60
25		30	CS	-	100	40														61
26		31	CS	-	96	42														62
27		32	CS	-	100	59														63
28		33	CS	-	100	37														64
29		34	CS	-	100	17														65
30		35	CS	-	100	85														66
31		36	CS	-	98	34														67
32		37	CS	-	100	68														68
		38	CS	-	100	37														69
		39	CS	-	100	50														70
		40	CS	-	100	41														71
		41																		72
																				73
																				74
																				75
																				76
																				77
																				78
																				79
																				80
																				81
																				82
																				83
																				84
																				85
																				86
																				87
																				88
																				89
																				90
																				91
																				92
																				93
																				94
																				95
																				96
																				97
																				98
																				99
																				100
																				101
																				102
																				103
																				104
																				105
																				106

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-09C		
LOCATION: Beaver Dam Mines Road					TPC ELEV.:	START DATE: April 9, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.:	COMPLETION DATE: April 12, 2018		
BENCHMARK:					PAGE 3 of 4			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)					SOIL VAPOUR CONCENTRATION (%LEL)					COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level
								100	300	500	700	900	10	30	50	70	90			
33		41	CS	-	100	61														107
34	BEDROCK - grey greywacke, numerous fractures, soft, no staining, steeply dipping	42	CS	-	96	27														108
35		43	CS	-	100	75														109
36		44	CS	-	100	0														110
37		45	CS	-	93	0														111
38		46	CS	-	100	80														112
39		47	CS	-	100	43														113
40	BEDROCK - grey greywacke, some fractures, mechanical breaks, no staining, steeply dipping	48	CS	-	100	19														114
41		49	CS	-	100	49														115
42		50	CS	-	100	61														116
43		51	CS	-	100	73														117
44		52	CS	-	91	0														118
45		53	CS	-	100	59														119
46		54	CS	-	100	56														120
47		55	CS	-	100	63														121
48		56	CS	-	100	66														122
49		57	CS	-	100	76														123

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-09C		
LOCATION: Beaver Dam Mines Road					TPC ELEV.:	START DATE: April 9, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.:	COMPLETION DATE: April 12, 2018		
BENCHMARK:					PAGE 4 of 4			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)					SOIL VAPOUR CONCENTRATION (%LEL)					COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level
									100	300	500	700	900	10	30	50	70	90			
50	BEDROCK - grey greywacke, minor fractures, no staining, slightly dipping, quartzite vein from 50.46 to 50.52m		58	CS	-	100	83														163
51			59	CS	-	100	68														164
52			60	CS	-	100	78														165
53			61	CS	-	100	86														166
54			62	CS	-	100	81														167
55			63	CS	-	100	56														168
56			64	CS	-	100	58														169
57			65	CS	-	100	20														170
58	BEDROCK - grey greywacke, some fractures, no staining, steeply dipping, light greywhite quartz vein from 58.72 to 58.75m		66	CS	-	100	41													Silica Sand	171
59																					172
60																					173
61																					174
62																					175
63																					176
64																					177
65																					178
66																					179
67																					180
68																					181
69																					182
70																					183
71																					184
72																					185
73																					186
74																					187
75																					188
76																					189
77																					190
78																					191
79																					192
80																					193
81																					194
82																					195
83																					196
84																					197
85																					198
86																					199
87																					200
88																					201
89																					202
90																					203
91																					204
92																					205
93																					206
94																					207
95																					208
96																					209
97																					210
98																					211
99																					212
100																					213
101																					214
102																					215
103																					216
104																					217
105																					218

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-09D		
LOCATION: Beaver Dam Mines Road					TPC ELEV.:	START DATE: May 2, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.:	COMPLETION DATE: May 2, 2018		
BENCHMARK:					PAGE 1 of 2			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)					SOIL VAPOUR CONCENTRATION (%LEL)					COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level	
								100	300	500	700	900	10	30	50	70	90				
-1	Ground Surface ORGANIC - rootmat SILTY SAND - brown, trace to some clay, some cobbles and boulders WEATHERED BEDROCK - grey greywacke, mechanical breaks, highly fractured, silt and clay in fractures, BEDROCK - grey greywacke, mechanical breaks, numerous fractures, no staining, primary bedding at 20°	11	CS	-	44	0												Stick-up Silica Sand PVC Riser Bentonite Seal		-3 -2 -1 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49	
0																					
1																					
2																					
3																					
4																					
5																					
6																					
7																					
8																					
9																					
10																					
11																					
12																					
13																					
14																					

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-09D		
LOCATION: Beaver Dam Mines Road					TPC ELEV.:	START DATE: May 2, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.:	COMPLETION DATE: May 2, 2018		
BENCHMARK:					PAGE 2 of 2			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)					SOIL VAPOUR CONCENTRATION (%LEL)					COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level
								100	300	500	700	900	10	30	50	70	90			
15	BEDROCK - grey greywacke, mechanical breaks, numerous fractures, no staining, primary bedding at 20°																			50
16		14	CS	-	100	51														51
17		15	CS	-	100	41														52
18		16	CS	-	100	20														53
19		17	CS	-	100	78														54
20		18	CS	-	100	0														55
21		19	CS	-	100	15														56
22		20	CS	-	100	0														57
23		21	CS	-	100	0														58
24		22	CS	-	100	16														59
25		23	CS	-	100	0														60
26		24	CS	-	100	0														61
27		25	CS	-	100	32														62
28		26	CS	-	100	0														63
29	BEDROCK - grey greywacke, numerous natural fractures, slightly more competent, primary bedding at 5	27	CS	-	100	32														64
30																				65
																				66
																				67
																				68
																				69
																				70
																				71
																				72
																				73
																				74
																				75
																				76
																				77
																				78
																				79
																				80
																				81
																				82
																				83
																				84
																				85
																				86
																				87
																				88
																				89
																				90
																				91
																				92
																				93
																				94
																				95
																				96
																				97
																				98
																				99
																				100
																				101

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH		DAYLIGHTING TO: n/a		GAS METER TYPE: n/a	
	REVIEWED BY:		EQUIPMENT: CME-75 Trackmount			
	DRAFTED BY: MG		METHOD: Case and Core		BOREHOLE DIA: 0.10m	

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-11A		
LOCATION: Beaver Dam Mines Road					TPC ELEV.: 147.599	START DATE: April 3, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.: 146.666	COMPLETION DATE: April 3, 2018		
BENCHMARK:					PAGE 1 of 1			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION					SOIL VAPOUR CONCENTRATION					COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level	
									100	300	500	700	900	10	30	50	70	90				
-1	UTM Zone 20 NAD83 (CSRS) N:4990130.598 E:522324.169 Elev: CGVD 2013																			Stick-up		-3
0	Ground Surface																			Silica Sand		0
1	ORGANIC - rootmat																			PVC Riser		1
2	SILTY SAND - grey brown, trace to some clay, some cobbles and boulders																			Bentonite Seal		2
3	BEDROCK - grey greywacke, some fractures and weathered rock, orange and black staining, some silt and clay in fractures		1	CS	-	92	53													Silica Sand		3
4			2	CS	-	93	59												PVC "2- Slot" Screen		4	
5			3	CS	-	86	43												PVC Threaded Well Point		5	
6	BEDROCK - grey greywacke, no fractures, shallow dip		4	CS	-	97	97															6
																						7
																						8
																						9
																						10
																						11
																						12
																						13
																						14
																						15
																						16
																						17
																						18
																						19
																						20
																						21

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling						REF. NO: 088664	BOREHOLE: MW-11B					
LOCATION: Beaver Dam Mines Road						TPC ELEV.: 147.323	START DATE: April 5, 2018					
CLIENT: Atlantic Gold Corporation						GRADE ELEV.: 146.540	COMPLETION DATE: April 5, 2018					
BENCHMARK:						PAGE 1 of 1						
Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm) 100 300 500 700 900	SOIL VAPOUR CONCENTRATION (%LEL) 10 30 50 70 90	COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level
-1	UTM Zone 20 NAD83 (CSRS) N:4990132.870 E:522325.095 Elev: CGVD 2013 Ground Surface									Stick-up		-4 -3 -2 -1
0	ORGANIC - rootmat SILTY SAND - brown, trace to some clay, numerous cobbles and boulders, water at 0.76m									Silica Sand		0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49
1	SILTY SAND - brown, some clay and boulders, wet	1	CS	-	81	0						
2	WEATHERED BEDROCK - grey greywacke, orange and black staining	2	CS	-	41	0						
3	BEDROCK - grey greywacke, some fractures containing clay and silt, orange and black staining, steeply dipping	3	CS	-	92	42						
4	BEDROCK - grey greywacke, mechanical breaks, very soft and fractured, orange and black staining	4	CS	-	85	33						
5	BEDROCK - grey greywacke, minor fractures, no staining, shallow dip	5	CS	-	76	0						
6		6	CS	-	92	66						
7		7	CS	-	100	68						
8		8	CS	-	89	50						
9	BEDROCK - grey greywacke, some fractures, mechanical breaks, some orange and black staining in fractures, steeply dipping	9	CS	-	94	46					PVC Riser	
10		10	CS	-	98	64						
11		11	CS	-	100	78						
12		12	CS	-	96	69						
13		13	CS	-	100	66						
14		14	CS	-	100	48						
15												
16												
 GHD				LOGGED BY: RH			DAYLIGHTING TO: n/a		GAS METER TYPE: n/a			
				REVIEWED BY:			EQUIPMENT: CME-75 Trackmount					
				DRAFTED BY: MG			METHOD: Case and Core		BOREHOLE DIA: 0.10m			

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-11C		
LOCATION: Beaver Dam Mines Road					TPC ELEV.: 147.361	START DATE: April 3, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.: 146.617	COMPLETION DATE: April 4, 2018		
BENCHMARK:					PAGE 1 of 2			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)					SOIL VAPOUR CONCENTRATION (%LEL)					COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level
									100	300	500	700	900	10	30	50	70	90			
-1	UTM Zone 20 NAD83 (CSRS) N:4990132.377 E:522323.713 Elev: CGVD 2013 Ground Surface																		Stick-up		-4 -3 -2 -1
0	ORGANIC - rootmat SILTY SAND - brown, trace to some clay, numerous cobbles and boulders	[Hatched]																	Silica Sand	[Hatched]	0 1 2 3 4 5 6 7 8 9
1	WEATHERED BEDROCK - grey greywacke, mechanical breaks BEDROCK - grey greywacke, highly fractured, silt and clay in fractures	[Hatched]																	Bentonite Seal	[Solid Black]	10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44
2			1	CS	-	71	0														
3			2	CS	-	87	0														
4			3	CS	-	97	29														
5			4	CS	-	100	65														
6			5	CS	-	96	61													PVC Riser	
7			6	CS	-	96	88														
8			7	CS	-	96	76														
9			8	CS	-	96	86														
10			9	CS	-	98	80														
11			10	CS	-	98	91														
12																					
13	BEDROCK - grey greywacke, trace quartz veins, minor fractures, steeply dipping	[Hatched]																			

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-11C		
LOCATION: Beaver Dam Mines Road					TPC ELEV.: 147.361	START DATE: April 3, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.: 146.617	COMPLETION DATE: April 4, 2018		
BENCHMARK:					PAGE 2 of 2			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)					SOIL VAPOUR CONCENTRATION (%LEL)					COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level	
									100	300	500	700	900	10	30	50	70	90				
14																						45
14	BEDROCK - grey greywacke, minor fractures, steeply dipping, mechanical breaks 14.40 to 15.47m		11	CS	-	94	47															46
15																						47
16	BEDROCK - grey greywacke, mechanical breaks, steeply dipping		12	CS	-	95	15															48
17	BEDROCK - grey greywacke, quartzite vein from 16.79 to 16.91 m, steeply dipping, no staining		13	CS	-	90	0														PVC Riser	49
18	BEDROCK - grey greywacke, minor fractures, steeply dipping		14	CS	-	97	43															50
19			15	CS	-	100	35															51
20			16	CS	-	93	19															52
21			17	CS	-	100	59															53
22			18	CS	-	100	57															54
23			19	CS	-	98	83															55
24	BEDROCK - grey greywacke, mechanical breaks, steeply dipping		20	CS	-	94	0															56
24	BEDROCK - grey greywacke, minor fractures, steeply dipping		21	CS	-	96	84															57
25	BEDROCK - grey greywacke, some fractures, steeply dipping, water bearing fracture making water		22	CS	-	96	46														Silica Sand	58
26																					PVC "2-Slot" Screen	59
27																					PVC Threaded Well Point	60
28																						61

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a		
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount			
	DRAFTED BY: MG	METHOD: Case and Core		BOREHOLE DIA: 0.10m	

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling				REF. NO: 088664	BOREHOLE: MW-12A		
LOCATION: Beaver Dam Mines Road				TPC ELEV.: 147.377	START DATE: April 15, 2018		
CLIENT: Atlantic Gold Corporation				GRADE ELEV.: 146.725	COMPLETION DATE: April 15, 2018		
BENCHMARK:					PAGE 1 of 1		

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)					SOIL VAPOUR CONCENTRATION (%LEL)					COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level
									100	300	500	700	900	10	30	50	70	90			
-1	UTM Zone 20 NAD83 (CSRS) N:4991000.037 E:521711.672 Elev: CGVD 2013																		Stick-up		-3
0	Ground Surface																		Silica Sand		-2
	ORGANIC - rootmat																		Bentonite Seal		-1
	SILTY SAND - grey brown, trace sand, some clay, numerous cobbles and boulders, wet at 1.07m																		PVC Riser		0
1																					1
2																					2
3																					3
4																					4
5																					5
6																					6
																					7
																					8
																					9
																					10
																					11
																					12
																					13
																					14
																					15
																					16
																					17
																					18
																					19
																					20
																					21

 <p>45 Akerley Blvd Dartmouth, NS B3B 1J7</p>	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling			REF. NO: 088664	BOREHOLE: MW-12B		
LOCATION: Beaver Dam Mines Road			TPC ELEV.: 147.358	START DATE: April 14, 2018		
CLIENT: Atlantic Gold Corporation			GRADE ELEV.: 146.637	COMPLETION DATE: April 15, 2018		
BENCHMARK:				PAGE 1 of 2		

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)			SOIL VAPOUR CONCENTRATION (%LEL)			COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level			
									100	300	500	700	900	10	30	50	70	90		
-1	UTM Zone 20 NAD83 (CSRS) N:4990999.179 E:521710.995 Elev: CGVD 2013 Ground Surface																	Stick-up		-4 -3 -2 -1
0	ORGANIC - rootmat SILTY SAND - grey, trace sand, some clay, numerous greywacke boulders/fragments, some boulders, wet at 1.22m	██████████	██████████	██████████	██████████	██████████	██████████	██████████										Silica Sand	██████████	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44
1																		Bentonite Seal	██████████	10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44
2																		PVC Riser	██████████	10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44
3																				
4																				
5																				
6																				
7																				
8																				
9																				
10																				
11																				
12																				
13																				

 GHD	45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
		REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
		DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-12B		
LOCATION: Beaver Dam Mines Road					TPC ELEV.: 147.358	START DATE: April 14, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.: 146.637	COMPLETION DATE: April 15, 2018		
BENCHMARK:					PAGE 2 of 2			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)					SOIL VAPOUR CONCENTRATION (%LEL)					COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level		
									100	300	500	700	900	10	30	50	70	90					
14																						45	
15																						46	
16																						47	
17																						48	
18																						49	
19																						50	
20																						51	
21	BEDROCK - grey greywacke, mechanical breaks, some fractures, no staining, steeply dipping		1	CS	-	100	0													PVC Riser		52	
22	BEDROCK - grey greywacke, some fractures, some black staining, steeply dipping		2	CS	-	100	36													Bentonite Seal		53	
23			3	CS	-	100	0													Silica Sand		54	
24			4	CS	-	100	22													PVC "2- Slot" Screen		55	
25																					PVC Threaded Well Point		56
26																						57	
27																						58	
28																						59	

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling				REF. NO: 088664	BOREHOLE: MW-14A		
LOCATION: Beaver Dam Mines Road				TPC ELEV.: 137.203	START DATE: April 26, 2018		
CLIENT: Atlantic Gold Corporation				GRADE ELEV.: 136.226	COMPLETION DATE: April 26, 2018		
BENCHMARK:					PAGE 1 of 1		

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)				SOIL VAPOUR CONCENTRATION (%LEL)				COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level	
									100	300	500	700	900	10	30	50	70			
-1	UTM Zone 20 NAD83 (CSRS) N:4989830.507 E:523253.265 Elev: CGVD 2013																	Stick-up		-3
0	Ground Surface																	Silica Sand		0
	ORGANIC - rootmat	██████																PVC Riser		1
	SILTY SAND - grey, trace to some clay, some cobbles and boulders, wet at 1.91m																	Bentonite Seal	██████████	2
1																				3
2																				4
3																				5
4																				6
5																				7
6																				8
																				9
																				10
																				11
																				12
																				13
																				14
																				15
																				16
																				17
																				18
																				19
																				20
																				21

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling			REF. NO: 088664	BOREHOLE: MW-14B		
LOCATION: Beaver Dam Mines Road			TPC ELEV.: 137.313	START DATE: April 25, 2018		
CLIENT: Atlantic Gold Corporation			GRADE ELEV.: 136.264	COMPLETION DATE: April 26, 2018		
BENCHMARK:					PAGE 1 of 2	

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)			SOIL VAPOUR CONCENTRATION (%LEL)			COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level	
									100	300	500	700	900	10	30	50	70	90
-1	UTM Zone 20 NAD83 (CSRS) N:4989828.780 E:523253.939 Elev: CGVD 2013																	Stick-up
0	Ground Surface																	Silica Sand
0	ORGANIC - rootmat																	
0	SILTY SAND - grey, trace to some clay, some cobbles and boulders, wet at 1.45m																	
1																		
2																		
3																		
4																		
5																		
6																		
7																		
8																		
9																		
10																		
11																		
12																		

 <p>45 Akerley Blvd Dartmouth, NS B3B 1J7</p>	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-14B		
LOCATION: Beaver Dam Mines Road					TPC ELEV.: 137.313	START DATE: April 25, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.: 136.264	COMPLETION DATE: April 26, 2018		
BENCHMARK:					PAGE 2 of 2			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)					SOIL VAPOUR CONCENTRATION (%LEL)					COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level	
									100	300	500	700	900	10	30	50	70	90				
13																						42
14																						43
15																						44
16																						45
17																						46
18	BEDROCK - grey greywacke, some fractures, no staining, steeply dipping		1	CS	-	100	43															47
19			2	CS	-	100	39															48
20	BEDROCK - grey greywacke, mechanical breaks, numerous fractures, no staining, steeply dipping		3	CS	-	97	34															49
21			4	CS	-	100	87															50
22			5	CS	-	100	64															51
23			6	CS	-	97	10															52
24			7	CS	-	100	69															53
25																						54
26																						55
																						56
																						57
																						58
																						59
																						60
																						61
																						62
																						63
																						64
																						65
																						66
																						67
																						68
																						69
																						70
																						71
																						72
																						73
																						74
																						75
																						76
																						77
																						78
																						79
																						80
																						81
																						82
																						83
																						84
																						85
																						86
																						87

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling			REF. NO: 088664	BOREHOLE: MW-14C		
LOCATION: Beaver Dam Mines Road			TPC ELEV.: 137.127	START DATE: April 24, 2018		
CLIENT: Atlantic Gold Corporation			GRADE ELEV.: 136.308	COMPLETION DATE: April 26, 2018		
BENCHMARK:					PAGE 1 of 3	

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)					SOIL VAPOUR CONCENTRATION (%LEL)					COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level
									100	300	500	700	900	10	30	50	70	90			
-1	UTM Zone 20 NAD83 (CSRS) N:4989827.886 E:523254.933 Elev: CGVD 2013 Ground Surface																		Stick-up		-4 -3 -2 -1
0	ORGANIC - rootmat SILTY SAND - grey, trace to some clay, some cobbles and boulders	██████	██████	██████	██████	██████	██████	██████											Silica Sand	██████	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44
1																			PVC Riser		
2																			Bentonite Seal		
3																					
4																					
5																					
6																					
7																					
8																					
9																					
10																					
11																					
12																					
13																					

 <p>45 Akerley Blvd Dartmouth, NS B3B 1J7</p>	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling				REF. NO: 088664	BOREHOLE: MW-14C		
LOCATION: Beaver Dam Mines Road				TPC ELEV.: 137.127	START DATE: April 24, 2018		
CLIENT: Atlantic Gold Corporation				GRADE ELEV.: 136.308	COMPLETION DATE: April 26, 2018		
BENCHMARK:					PAGE 2 of 3		

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)					SOIL VAPOUR CONCENTRATION (%LEL)					COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level	
									100	300	500	700	900	10	30	50	70	90				
14																						45
15																						46
16																						47
17																						48
18																						49
19	WEATHERED BEDROCK - grey greywacke, highly fractured, no staining, steeply dipping		1	CS	-	100	28													Bentonite Seal		50
20			2	CS	-	100	38															51
21	BEDROCK - grey greywacke, some fractures, no staining, steeply dipping		3	CS	-	100	54															52
22			4	CS	-	100	49															53
23			5	CS	-	100	80															54
24			6	SS		100	56															55
25			7	SS		100	80															56
26			8	SS		100	85															57
27			9	SS		100	56															58
28																						59
																						60
																						61
																						62
																						63
																						64
																						65
																						66
																						67
																						68
																						69
																						70
																						71
																						72
																						73
																						74
																						75
																						76
																						77
																						78
																						79
																						80
																						81
																						82
																						83
																						84
																						85
																						86
																						87
																						88
																						89
																						90
																						91
																						92
																						93
																						94

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-14C		
LOCATION: Beaver Dam Mines Road					TPC ELEV.: 137.127	START DATE: April 24, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.: 136.308	COMPLETION DATE: April 26, 2018		
BENCHMARK:					PAGE 3 of 3			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)				SOIL VAPOUR CONCENTRATION (%LEL)				COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level	
								100	300	500	700	900	10	30	50	70	90		
29	BEDROCK - grey greywacke, numerous fractures, no staining, steeply dipping	 10	SS	100	42	100											Bentonite Seal		95
30																			
31																			
32																			
33																			
34																			
35																			
36																			
37																			
38																			
39																			
40																			
41																			
42																			
43																			

	45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
		REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
		DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-16A		
LOCATION: Beaver Dam Mines Road					TPC ELEV.: 153.636	START DATE: April 20, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.: 152.568	COMPLETION DATE: April 20, 2018		
BENCHMARK:					PAGE 1 of 1			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)			SOIL VAPOUR CONCENTRATION (%LEL)			COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level	
									100	300	500	700	900	10	30	50	70	90
-1	UTM Zone 20 NAD83 (CSRS) N:4990744.060 E:522898.761 Elev: CGVD 2013 Ground Surface																	Stick-up
0	ORGANIC - rootmat SILTY SAND - grey, trace to some clay, some cobbles and boulders, water at 2.36m	██████	1	CS	-	100	0											Silica Sand
1																		PVC Riser
2																		Bentonite Seal
3																		
4	WEATHERED BEDROCK - grey greywacke, mechanical breaks, orange and black staining BEDROCK - grey greywacke, mechanical breaks, numerous fractures, orange and black staining,	██████████	1	CS	-	100	0											Silica Sand
5			2	CS	-	83	0											PVC "2-Slot" Screen
6			3	CS	-	100	0											
7			4	CS	-	100	24											PVC Threaded Well Point



45 Akerley Blvd
Dartmouth, NS
B3B 1J7

LOGGED BY: RH DAYLIGHTING TO: n/a GAS METER TYPE: n/a

REVIEWED BY: EQUIPMENT: CME-75 Trackmount

DRAFTED BY: MG METHOD: Case and Core BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-16B		
LOCATION: Beaver Dam Mines Road					TPC ELEV.: 153.625	START DATE: April 19, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.: 152.592	COMPLETION DATE: April 20, 2018		
BENCHMARK:					PAGE 1 of 1			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)			SOIL VAPOUR CONCENTRATION (%LEL)			COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level			
									100	300	500	700	900	10	30	50	70	90		
-1	UTM Zone 20 NAD83 (CSRS) N:4990742.630 E:522898.057 Elev: CGVD 2013 Ground Surface																	Stick-up		-4 -3 -2 -1
0	ORGANIC - rootmat SILTY SAND - grey, trace to some clay, numerous cobbles and boulders, wet at 2.36m																	Silica Sand		0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15
1	BEDROCK - grey greywacke, mechanical breaks, numerous fractures, orange and black staining, steeply dipping																	Bentonite Seal		8 9 10 11 12 13 14 15
2																		PVC Riser		16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49
3																		Silica Sand		50 51 52 53 54
4																		PVC "2-Slot" Screen		
5																		PVC Threaded Well Point		
6																				
7																				
8																				
9																				
10																				
11																				
12																				
13																				
14																				
15																				
16																				

 <p>45 Akerley Blvd Dartmouth, NS B3B 1J7</p>	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling				REF. NO: 088664	BOREHOLE: MW-17A		
LOCATION: Beaver Dam Mines Road				TPC ELEV.: 154.269	START DATE: April 26, 2018		
CLIENT: Atlantic Gold Corporation				GRADE ELEV.: 153.328	COMPLETION DATE: April 26, 2018		
BENCHMARK:					PAGE 1 of 1		

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)					SOIL VAPOUR CONCENTRATION (%LEL)					COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level		
									100	300	500	700	900	10	30	50	70	90					
-1	UTM Zone 20 NAD83 (CSRS) N:4990324.445 E:524121.346 Elev: CGVD 2013																			Stick-up		-3	
0	Ground Surface																			Silica Sand		-2	
	ORGANIC - rootmat	██████																		PVC Riser Bentonite Seal	██████	-1	
	SILTY SAND - brown to grey, trace to some clay, some cobbles and boulders, wet at 3.25m																				██████	0	
1																				Silica Sand		1	
2																				PVC "2-Slot" Screen		2	
3																						██████	3
4																				PVC Threaded Well Point		4	
5																							5
6																							6
7																							7
8																							8
9																							9
10																							10
11																							11
12																							12
13																							13
14																							14
15																							15
16																							16
17																							17
18																							18
19																							19
20																							20
21																							21

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-17B		
LOCATION: Beaver Dam Mines Road					TPC ELEV.: 154.285	START DATE: April 25, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.: 153.229	COMPLETION DATE: April 25, 2018		
BENCHMARK:					PAGE 1 of 1			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)			SOIL VAPOUR CONCENTRATION (%LEL)			COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level	
									100	300	500	700	900	10	30	50	70	90
-1	UTM Zone 20 NAD83 (CSRS) N:4990323.426 E:524123.059 Elev: CGVD 2013 Ground Surface																	Stick-up
0	ORGANIC - rootmat SILTY SAND - brown to grey, trace to some clay, some cobbles and boulders, wet at 3.25m	[Hatched]																Silica Sand
1																		PVC Riser
2																		Bentonite Seal
3																		
4																		
5	BEDROCK - grey greywacke, mechanical breaks, numerous fractures, silt and clay in fractures, orange and black staining	[Hatched]	1	CS	-	97	10											
6	BEDROCK - grey greywacke, slightly blocky, more competent, orange and black staining, shallow dip	[Hatched]	2	CS	-	100	17											
7			3	CS	-	100	25											
8																		
9																		

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling						REF. NO: 088664	BOREHOLE: MW-17C					
LOCATION: Beaver Dam Mines Road						TPC ELEV.: 154.069	START DATE: April 25, 2018					
CLIENT: Atlantic Gold Corporation						GRADE ELEV.: 153.175	COMPLETION DATE: April 25, 2018					
BENCHMARK:						PAGE 1 of 1						
Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm) 100 300 500 700 900	SOIL VAPOUR CONCENTRATION (%LEL) 10 30 50 70 90	COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level
-1	UTM Zone 20 NAD83 (CSRS) N:4990324.229 E:524124.712 Elev: CGVD 2013 Ground Surface									Stick-up		-4 -3 -2 -1
0	ORGANIC - rootmat SILTY SAND - brown to grey, trace to some clay, numerous cobbles and boulders, water at 3.15m									Silica Sand		0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50
5	BEDROCK - grey greywacke, numerous fractures, orange and black staining, shallow dip	1	CS	-	100	33				Bentonite Seal		
6		2	CS	-	100	23				PVC Riser		
7		3	CS	-	100	32						
8		4	CS	-	100	49						
9		5	CS	-	100	65						
10		6	CS	-	100	51						
11		7	CS	-	98	10						
12												
13												
14												
15												
16												
 45 Akerley Blvd Dartmouth, NS B3B 1J7			LOGGED BY: RH			DAYLIGHTING TO: n/a		GAS METER TYPE: n/a				
			REVIEWED BY:			EQUIPMENT: CME-75 Trackmount						
			DRAFTED BY: MG			METHOD: Case and Core			BOREHOLE DIA: 0.10m			

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-18A		
LOCATION: Beaver Dam Mines Road					TPC ELEV.: 147.288	START DATE: April 20, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.: 146.317	COMPLETION DATE: April 20, 2018		
BENCHMARK:					PAGE 1 of 1			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)				SOIL VAPOUR CONCENTRATION (%LEL)				COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level	
									100	300	500	700	900	10	30	50	70			
-1	UTM Zone 20 NAD83 (CSRS) N:4991142.236 E:523118.888 Elev: CGVD 2013																	Stick-up		-3
0	Ground Surface																	Silica Sand		-2
0	ORGANIC - rootmat																			0
0	SILTY SAND - grey brown, trace to some clay, some cobbles and boulders, wet at 1.29m																			1
1																				2
2																				3
3																				4
4	BEDROCK - grey greywacke, mechanical breaks, numerous fractures, orange and black staining, steeply dipping		1	CS	-	100	13											PVC Riser		5
5			2	CS	-	100	0											Bentonite Seal		6
6			3	CS	-	100	0													7
7	BEDROCK - grey greywacke, some fractures, orange and black staining, steeply dipping		4	CS	-	100	19											PVC Threaded Well Point		8
																				9
																				10
																				11
																				12
																				13
																				14
																				15
																				16
																				17
																				18
																				19
																				20
																				21
																				22
																				23
																				24
																				25

 <p>45 Akerley Blvd Dartmouth, NS B3B 1J7</p>	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-18B		
LOCATION: Beaver Dam Mines Road					TPC ELEV.: 147.155	START DATE: April 24, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.: 146.320	COMPLETION DATE: April 24, 2018		
BENCHMARK:					PAGE 1 of 1			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)			SOIL VAPOUR CONCENTRATION (%LEL)			COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level		
									100	300	500	700	900	10	30	50	70	90	
-1	UTM Zone 20 NAD83 (CSRS) N:4991141.883 E:523120.436 Elev: CGVD 2013 Ground Surface																Stick-up		
0	ORGANIC - rootmat SILTY SAND - brown, trace to some clay, numerous cobbles and boulders, water at 2.01m																Silica Sand		
1	BEDROCK - grey greywacke, mechanical breaks, numerous fractures, orange and black staining, steeply dipping		1	CS	-	89	0											Bentonite Seal	
2			2	CS	-	97	0												
3			3	CS	-	98	0												
4			4	CS	-	100	32											PVC Riser	
5			5	CS	-	100	37												
6			6	CS	-	100	22												
7			7	CS	-	100	33												
8			8	CS	-	100	32											Silica Sand	
9			9	CS	-	100	0											PVC "2-Slot" Screen	
10																			
11																			
12																			
13																			
14																			
15																			
16																			

 <p>45 Akerley Blvd Dartmouth, NS B3B 1J7</p>	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-18C		
LOCATION: Beaver Dam Mines Road					TPC ELEV.: 147.207	START DATE: April 25, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.: 146.137	COMPLETION DATE: April 25, 2018		
BENCHMARK:					PAGE 1 of 2			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)			SOIL VAPOUR CONCENTRATION (%LEL)			COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level	
									100	300	500	700	900	10	30	50	70	90
-1	UTM Zone 20 NAD83 (CSRS) N:4991141.264 E:523121.844 Elev: CGVD 2013 Ground Surface																	Stick-up
0	ORGANIC - rootmat SILTY SAND - brown, trace to some clay, some cobbles and boulders	██████																Silica Sand
1		██████																PVC Riser
2		██████																Bentonite Seal
3		██████																
4	BEDROCK - grey greywacke, mechanical breaks, highly fractured, orange and black staining in fractures, steeply dipping	██████	1	CS	-	100	0											
5		██████	2	CS	-	100	0											
6		██████	3	CS	-	100	0											
7		██████	4	CS	-	100	57											
8		██████	5	CS	-	100	57											
9	BEDROCK - grey greywacke, mechanical breaks, some fractures, no staining, steeply dipping	██████	6	CS	-	100	14											
10		██████	7	CS	-	100	10											
11		██████	8	CS	-	100	13											
12		██████	9	CS	-	98	13											
13		██████	10	CS	-	100	26											
14		██████	11	CS	-	100	15											
15		██████	12	CS	-	100	23											
16																		
17																		

 <p>45 Akerley Blvd Dartmouth, NS B3B 1J7</p>	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-18C		
LOCATION: Beaver Dam Mines Road					TPC ELEV.: 147.207	START DATE: April 25, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.: 146.137	COMPLETION DATE: April 25, 2018		
BENCHMARK:					PAGE 2 of 2			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)					SOIL VAPOUR CONCENTRATION (%LEL)					COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level
									100	300	500	700	900	10	30	50	70	90			
18	BEDROCK - grey greywacke, mechanical breaks, some fractures, no staining		13	CS	-	100	64														58
19			14	CS	-	100	67														59
20			15	CS	-	100	34														60
21			16	CS	-	100	75														61
22			17	CS	-	100	10														62
23			18	CS	-	100	25														63
24			19	CS	-	100	44														64
25			20	CS	-	100	47														65
26			21	CS	-	100	39														66
27			22	CS	-	100	17														67
28			23	CS	-	100	20														68
29			24	CS	-	100	0														69
30			25	CS	-	100	15														70
31																					71
32																					72
33																					73
34																					74
35																					75
36																					76

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling				REF. NO: 088664	BOREHOLE: MW-19A		
LOCATION: Beaver Dam Mines Road				TPC ELEV.: 133.385	START DATE: May 4, 2018		
CLIENT: Atlantic Gold Corporation				GRADE ELEV.: 132.414	COMPLETION DATE: May 4, 2018		
BENCHMARK:					PAGE 1 of 1		

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)					SOIL VAPOUR CONCENTRATION (%LEL)					COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level
									100	300	500	700	900	10	30	50	70	90			
-1	UTM Zone 20 NAD83 (CSRS) N:4991427.087 E:520765.986 Elev: CGVD 2013																		Stick-up		-3
0	Ground Surface																		Silica Sand PVC Riser Bentonite Seal		-2
0	ORGANIC - rootmat	██████																			0
0	SILTY SAND - brown, trace to some clay, numerous cobbles and boulders, wet at 0.64m																				1
1																					2
2																					3
3																					4
4																					5
5																					6
6																					7
7																					8
8																					9
9																					10
10																					11
11																					12
12																					13
13																					14
14																					15
15																					16
16																					17
17																					18
18																					19
19																					20
20																					21

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling				REF. NO: 088664	BOREHOLE: MW-19B		
LOCATION: Beaver Dam Mines Road				TPC ELEV.: 133.410	START DATE: May 4, 2018		
CLIENT: Atlantic Gold Corporation				GRADE ELEV.: 132.443	COMPLETION DATE: May 4, 2018		
BENCHMARK:					PAGE 1 of 1		

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)				SOIL VAPOUR CONCENTRATION (%LEL)				COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level	
									100	300	500	700	900	10	30	50	70			
-1	UTM Zone 20 NAD83 (CSRS) N:4991426.125 E:520764.377 Elev: CGVD 2013																	Stick-up		-4
0	Ground Surface																	Silica Sand		-3
0	ORGANIC - rootmat																			0
0	SILTY SAND - brown, trace to some clay, some cobbles and boulders, wet at 0.71m																			1
1																				2
2																				3
3																				4
4																				5
5	BEDROCK - grey greywacke, some fractures, some silt and clay in fractures, orange and black staining		1	CS	-	100	41											PVC Riser		15
5	BEDROCK - grey greywacke, some fractures, orange and black staining		2	CS	-	100	68													16
6			3	CS	-	100	85													17
7			4	CS	-	100	61													18
8			5	CS	-	100	80													19
9			6	CS	-	100	83													20
10			7	CS	-	100	44													21
11			8	CS	-	100	76													22
12																				23
13																				24
14																				25
15																				26
																				27
																				28
																				29
																				30
																				31
																				32
																				33
																				34
																				35
																				36
																				37
																				38
																				39
																				40
																				41
																				42
																				43
																				44
																				45
																				46
																				47
																				48
																				49
																				50
																				51

 <p>45 Akerley Blvd Dartmouth, NS B3B 1J7</p>	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-19C		
LOCATION: Beaver Dam Mines Road					TPC ELEV.: 133.397	START DATE: May 7, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.: 132.516	COMPLETION DATE: May 7, 2018		
BENCHMARK:					PAGE 1 of 2			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)					SOIL VAPOUR CONCENTRATION (%LEL)					COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level
									100	300	500	700	900	10	30	50	70	90			
-1	UTM Zone 20 NAD83 (CSRS) N:4991425.291 E:520762.233 Elev: CGVD 2013 Ground Surface																		Stick-up		-4 -3 -2 -1
0	ORGANIC - rootmat SILTY SAND - grey brown, some clay, some cobbles and boulders	██████																	Silica Sand	██████	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25
1		██████																	PVC Riser	██████	26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48
2		██████																	Bentonite Seal	██████	
3		██████																			
4		██████	1	CS	-	63	0														
5	WEATHERED BEDROCK - grey greywacke, mechanical breaks, highly fractured, orange and black staining	██████	2	CS	-	85	37														
6	BEDROCK - grey greywacke, some fractures, silt and clay in fractures, orange and black staining	██████	3	SS	-	100	76														
7	BEDROCK - grey greywacke, some fractures, orange and black staining	██████	4	CS	-	100	64														
8		██████	5	CS	-	100	63														
9		██████	6	CS	-	100	93														
10		██████	7	CS	-	100	78														
11		██████	8	CS	-	100	80														
12		██████																			
13		██████																			
14		██████																			

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling				REF. NO: 088664	BOREHOLE: MW-19C		
LOCATION: Beaver Dam Mines Road				TPC ELEV.: 133.397	START DATE: May 7, 2018		
CLIENT: Atlantic Gold Corporation				GRADE ELEV.: 132.516	COMPLETION DATE: May 7, 2018		
BENCHMARK:					PAGE 2 of 2		

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)					SOIL VAPOUR CONCENTRATION (%LEL)					COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level
								100	300	500	700	900	10	30	50	70	90			
15	BEDROCK - grey greywacke, mechanical breaks, some fractures, no staining	8	-	-	-	-														49
16		9	CS	-	100	68														50
17		10	CS	-	100	75														51
18		11	CS	-	100	58														52
19		12	CS	-	100	51														53
20		13	CS	-	100	54														54
21		14	CS	-	100	75														55
22		15	CS	-	100	69														56
23		16	CS	-	100	64														57
24		17	CS	-	100	95														58
25		18	CS	-	100	81														59
26																				60
27																				61
28																				62
29																				63
30																				64

 <p>45 Akerley Blvd Dartmouth, NS B3B 1J7</p>	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-20A		
LOCATION: Beaver Dam Mines Road					TPC ELEV.: 152.089	START DATE: May 7, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.: 150.924	COMPLETION DATE: May 7, 2018		
BENCHMARK:					PAGE 1 of 1			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)					SOIL VAPOUR CONCENTRATION (%LEL)					COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level	
									100	300	500	700	900	10	30	50	70	90				
-1	UTM Zone 20 NAD83 (CSRS) N:4990264.985 E:520263.534 Elev: CGVD 2013																			Stick-up		-3
0	Ground Surface ORGANIC - rootmat SILTY SAND - grey to , trace to some clay, some cobbles and boulders, wet at 1.37m	[Hatched]		[Hatched]																Silica Sand	[Hatched]	0
1																				PVC Riser		1
2																				Bentonite Seal		2
3																						3
4	WEATHERED BEDROCK - grey greywacke, mechanical breaks, numerous fractures, silt and clay in fractures, orange and black staining	[Hatched]	1	CS	-	75	0															4
5		[Hatched]	2	CS	-	74	0															5
6		[Hatched]	3	CS	-	73	0															6
7	BEDROCK - grey greywacke, some fractures, orange and black staining, primary bedding at 30°	[Hatched]	4	CS	-	100	73													Silica Sand		7
		[Hatched]	5	CS	-	100	70												PVC "2- Slot" Screen		8	
	BEDROCK - grey greywacke, trace fractures, no staining, primary bedding 30°	[Hatched]																	PVC Threaded Well Point		9	
		[Hatched]																				10
		[Hatched]																				11
		[Hatched]																				12
		[Hatched]																				13
		[Hatched]																				14
		[Hatched]																				15
		[Hatched]																				16
		[Hatched]																				17
		[Hatched]																				18
		[Hatched]																				19
		[Hatched]																				20
		[Hatched]																				21
		[Hatched]																				22
		[Hatched]																				23
		[Hatched]																				24
		[Hatched]																				25
		[Hatched]																				26

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling				REF. NO: 088664	BOREHOLE: MW-20B		
LOCATION: Beaver Dam Mines Road				TPC ELEV.: 152.025	START DATE: May 7, 2018		
CLIENT: Atlantic Gold Corporation				GRADE ELEV.: 151.012	COMPLETION DATE: May 7, 2018		
BENCHMARK:						PAGE 1 of 1	

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)				SOIL VAPOUR CONCENTRATION (%LEL)				COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level	
									100	300	500	700	900	10	30	50	70			
-1	UTM Zone 20 NAD83 (CSRS) N:4990263.750 E:520263.490 Elev: CGVD 2013 Ground Surface																	Stick-up		-4 -3 -2 -1
0	ORGANIC - rootmat SILTY SAND - grey brown, trace to some clay, some cobbles and boulders, wet at 0.97m																	Silica Sand		0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15
4	BEDROCK - grey greywacke, some mechanical breaks, numerous fractures, silt and clay in fractures, orange and black staining		1	CS	-	97	12											PVC Riser		16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49
5	BEDROCK - grey greywacke, some fractures, no staining		2	CS	-	100	85											Bentonite Seal		50 51 52 53 54
6			3	CS	-	100	71													
7			4	CS	-	100	80													
8			5	CS	-	100	64													
9			6	CS	-	100	66													
10			7	CS	-	100	66													
11			8	CS	-	100	64													
12																				
13																				
14																				
15																				
16																				

 <p>45 Akerley Blvd Dartmouth, NS B3B 1J7</p>	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-21A		
LOCATION: Beaver Dam Mines Road					TPC ELEV.: 158.304	START DATE: May 7, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.: 157.384	COMPLETION DATE: May 7, 2018		
BENCHMARK:					PAGE 1 of 1			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)					SOIL VAPOUR CONCENTRATION (%LEL)					COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level
									100	300	500	700	900	10	30	50	70	90			
-1	UTM Zone 20 NAD83 (CSRS) N:4987642.034 E:521749.236 Elev: CGVD 2013																		Stick-up		-3
0	Ground Surface																		Silica Sand		0
0	ORGANIC - rootmat																		PVC Riser		1
0	SILTY SAND - grey brown, trace to some clay, some cobbles and boulders, wet at 1.5m																		Bentonite Seal		2
2	BEDROCK - grey greywacke, some fractures, orange and black staining		1	CS	-	88	37												Silica Sand		3
4	BEDROCK - grey greywacke, some fractures, silt and clay in fractures, orange and black staining, primary bedding at 25°		2	CS	-	100	69												PVC "2- Slot" Screen		4
6			3	CS	-	100	58											PVC Threaded Well Point		5	
																					21
																					22

 <p>45 Akerley Blvd Dartmouth, NS B3B 1J7</p>	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-21B		
LOCATION: Beaver Dam Mines Road					TPC ELEV.: 158.324	START DATE: May 2, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.: 157.336	COMPLETION DATE: May 3, 2018		
BENCHMARK:					PAGE 1 of 1			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)			SOIL VAPOUR CONCENTRATION (%LEL)			COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level	
									100	300	500	700	900	10	30	50	70	90
-1	UTM Zone 20 NAD83 (CSRS) N:4987641.733 E:521747.935 Elev: CGVD 2013																	
0	Ground Surface																	
0	ORGANIC - rootmat																	
0	SILTY SAND - grey brown, trace to some clay, some cobbles and boulders																	
2	BEDROCK - grey greywacke, some fractures, orange and black staining		1	CS	-	96	14											
2			2	CS	-	100	59											
2			3	CS	-	100	69											
2			4	CS	-	100	78											
2			5	CS	-	100	80											
10	BEDROCK - grey greywacke, some fractures, no staining		6	CS	-	100	93											
10			7	CS	-	100	98											
10			8	CS	-	100	76											
14	BEDROCK - grey greywacke, trace fractures, no staining		9	CS	-	100	78											
15																		

 <p>45 Akerley Blvd Dartmouth, NS B3B 1J7</p>	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-21C		
LOCATION: Beaver Dam Mines Road					TPC ELEV.: 158.209	START DATE: May 16, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.: 157.202	COMPLETION DATE: May 16, 2018		
BENCHMARK:					PAGE 1 of 2			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)					SOIL VAPOUR CONCENTRATION (%LEL)					COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level
									100	300	500	700	900	10	30	50	70	90			
-1	Ground Surface																		Stick-up		-3 -2 -1
0	ORGANIC - rootmat																		Silica Sand		0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49
1	SILTY SAND - grey brown, trace clay, some cobbles, some boulders																				
2	WEATHERED BEDROCK - grey greywacke, mechanical breaks, some fractures, silt and clay in fractures, orange and black staining		1	CS		95	25												PVC Riser		0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49
3			2	CS		100	49														
4			3	CS		100	58														
5			4	CS		100	90														
6			5	CS		100	71												Bentonite Seal		0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49
7			6	CS		100	81														
8			7	CS		100	73														
9			8	CS		100	80														
10			9	CS		100	73														

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-21C		
LOCATION: Beaver Dam Mines Road					TPC ELEV.: 158.209	START DATE: May 16, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.: 157.202	COMPLETION DATE: May 16, 2018		
BENCHMARK:					PAGE 2 of 2			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)					SOIL VAPOUR CONCENTRATION (%LEL)					COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level
									100	300	500	700	900	10	30	50	70	90			
15																					
16	BEDROCK - grey greywacke, some fractures, no staining 40mm fracture @ 16.967 filled with grey clay and silt		10	CS		100	85														50
17	BEDROCK - grey greywacke, some fractures, orange staining		11	CS		100	86														51
18																					52
19																					53
20																					54
21																					55
22																					56
23																					57
24																					58
25																					59
26																					60
27																					61
28																					62
29																					63
30																					64
																					65
																					66
																					67
																					68
																					69
																					70
																					71
																					72
																					73
																					74
																					75
																					76
																					77
																					78
																					79
																					80
																					81
																					82
																					83
																					84
																					85
																					86
																					87
																					88
																					89
																					90
																					91
																					92
																					93
																					94
																					95
																					96
																					97
																					98
																					99
																					100
																					101

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-22A		
LOCATION: Beaver Dam Mines Road					TPC ELEV.: 138.850	START DATE: April 25, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.: 137.955	COMPLETION DATE: April 25, 2018		
BENCHMARK:					PAGE 1 of 1			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)			SOIL VAPOUR CONCENTRATION (%LEL)			COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level	
									100	300	500	700	900	10	30	50	70	90
-1	UTM Zone 20 NAD83 (CSRS) N:4988520.078 E:524377.001 Elev: CGVD 2013																	
0	Ground Surface																	
0	ORGANIC - rootmat	[Hatched]																0
0	SILTY SAND - grey, trace to some clay, some cobbles and boulders, wet at 0.81m	[Hatched]																0
1																		1
2	WEATHERED BEDROCK - grey greywacke, mechanical breaks, highly fractured, silt and clay in fractures, orange and black staining	[Hatched]	1	CS	-	95	16											2
3	BEDROCK - grey greywacke, some fractures, orange and black staining, steeply dipping	[Hatched]	2	CS	-	91	32											3
4	BEDROCK - grey greywacke, mechanical breaks, highly fractured, orange and black staining, steeply dipping	[Hatched]	3	CS	-	68	0											4
5																		5
6	BEDROCK - grey greywacke, some fractures, orange and black staining noted in fractures, steeply dipping	[Hatched]	4	CS	-	73	36											6
7																		7
8																		8
9																		9
10																		10
11																		11
12																		12
13																		13
14																		14
15																		15
16																		16
17																		17
18																		18
19																		19
20																		20
21																		21
22																		22

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-22B		
LOCATION: Beaver Dam Mines Road					TPC ELEV.: 138.955	START DATE: April 27, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.: 137.968	COMPLETION DATE: April 27, 2018		
BENCHMARK:					PAGE 1 of 1			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)				SOIL VAPOUR CONCENTRATION (%LEL)				COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level	
									100	300	500	700	900	10	30	50	70			
-1	UTM Zone 20 NAD83 (CSRS) N:4988521.744 E:524377.199 Elev: CGVD 2013 Ground Surface																	Stick-up		-4 -3 -2 -1
0	ORGANIC - rootmat SILTY SAND - brown, trace to some clay, some cobbles and boulders, wet at 0.76m																	Silica Sand		0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50
1	BEDROCK - grey greywacke, some fractures, orange and black staining, steeply dipping		1	CS	-	100	18											PVC Riser		
2			2	CS	-	100	15													
3			3	CS	-	100	56													
4			4	CS	-	100	85													
5			5	CS	-	100	76													
6			6	CS	-	100	70													
7			7	CS	-	100	45													
8			8	CS	-	100	54													
9			9	CS	-	100	46													
10			10	CS	-	100	0													
11			11	CS	-	100	76													
12			12	CS	-	100	81													
13																				
14																				
15																				
16																				

 <p>45 Akerley Blvd Dartmouth, NS B3B 1J7</p>	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-22C		
LOCATION: Beaver Dam Mines Road					TPC ELEV.: 138.914	START DATE: April 28, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.: 137.949	COMPLETION DATE: May 1, 2018		
BENCHMARK:					PAGE 1 of 2			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)				SOIL VAPOUR CONCENTRATION (%LEL)				COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level	
									100	300	500	700	900	10	30	50	70			
-1	UTM Zone 20 NAD83 (CSRS) N:4988523.209 E:524377.504 Elev: CGVD 2013 Ground Surface																			-4
0	ORGANIC - rootmat	[Hatched]																	Flushmount Silica Sand	0
1	SILTY SAND - brown, trace to some clay, some cobbles and boulders, wet at 0.71m	[Hatched]																		1
2	BEDROCK - grey greywacke, some fractures, orange and black staining, steeply dipping	[Hatched]	1	CS	-	100	25												PVC Riser	2
3		[Hatched]	2	CS	-	100	46													3
4		[Hatched]	3	CS	-	95	60													4
5		[Hatched]	4	CS	-	100	50													5
6		[Hatched]	5	CS	-	100	88													6
7	BEDROCK - grey greywacke, mechanical breaks, some fractures, no staining, steeply dipping	[Hatched]	6	CS	-	100	41												Bentonite Seal	7
8	BEDROCK - grey greywacke, slightly fractured, no staining, steeply dipping	[Hatched]	7	CS	-	100	88													8
9		[Hatched]	8	CS	-	100	69													9
10		[Hatched]	9	CS	-	100	88													10
11		[Hatched]	10	CS	-	100	41													11
12		[Hatched]																		12
13	BEDROCK - grey greywacke, some fractures, no staining, steeply dipping	[Hatched]																		13
14		[Hatched]																		14

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

MONITORING WELL LOG

PROJECT: EIS - Hydrogeologic Assessment and Modelling					REF. NO: 088664	BOREHOLE: MW-22C		
LOCATION: Beaver Dam Mines Road					TPC ELEV.: 138.914	START DATE: April 28, 2018		
CLIENT: Atlantic Gold Corporation					GRADE ELEV.: 137.949	COMPLETION DATE: May 1, 2018		
BENCHMARK:					PAGE 2 of 2			

Depth (m) Water Level	STRATIGRAPHY DESCRIPTION	MATERIAL TYPE	NUMBER	SAMPLE TYPE	"N" VALUE	RECOVERY %	RQD (%)	SAMPLE NAME/ LAB ANALYSIS	SOIL VAPOUR CONCENTRATION (ppm)					SOIL VAPOUR CONCENTRATION (%LEL)					COMMENTS AND MONITORING WELL NOTES	SLOTTED PIEZOMETER	Depth (ft) Water Level	
									100	300	500	700	900	10	30	50	70	90				
15			11	CS	-	100	42															49
16	BEDROCK - grey greywacke, some fratures, no staining, steeply dipping, quartz vein at 16.23		12	CS	-	100	58															50
17			13	CS	-	100	73															51
18			14	CS	-	100	81															52
19			15	CS	-	100	86															53
20	BEDROCK - grey greywacke, trace natural fractures, no staining, steeply dippingd		16	CS	-	100	88															54
21			17	CS	-	100	97															55
22			18	CS	-	100	98															56
23	BEDROCK - grey greywacke, some natural fractures, no staining, steeply dipping		19	CS	-	100	93															57
24			20	CS	-	100	100															58
25	BEDROCK - grey greywacke, minor fractures,no staining, steeply dipping, quartz veins at 24.74m and 25.15m																					59
26																						60
27																						61
28	BEDROCK - grey greywacke, no fractures, steeply dipping																					62
29																						63
30																						64

 45 Akerley Blvd Dartmouth, NS B3B 1J7	LOGGED BY: RH	DAYLIGHTING TO: n/a	GAS METER TYPE: n/a
	REVIEWED BY:	EQUIPMENT: CME-75 Trackmount	
	DRAFTED BY: MG	METHOD: Case and Core	BOREHOLE DIA: 0.10m

Attachment 2

Photographic Log of Drilling Activities



PHOTO 1 - DRILLING ACTIVITIES FOR BEAVER DAM MINE PROJECT



PHOTO 2 - DRILL RIG DURING MOBILIZATION TO "MW16"



ATLANTIC GOLD CORPORATION
MARINETTE, NOVA SCOTIA
BEAVER DAMN MINE PROJECT

PHOTOGRAPHIC LOG

088664-20
Nov 7, 2018

FIGURE 1



PHOTO 3 - ROCK CORES TAKEN FROM MONITORING WELL "MW02B"



PHOTO 4 - ROCK CORES TAKEN FROM MONITORING WELL "MW18B"



ATLANTIC GOLD CORPORATION
MARINETTE, NOVA SCOTIA
BEAVER DAMN MINE PROJECT

PHOTOGRAPHIC LOG

088664-20
Nov 7, 2018

FIGURE 2



PHOTO 5 - VIEW OF STICKUP CASING FOR COMPLETED MONITORING WELLS "MW02"



PHOTO 6 - VIEW OF STICKUP CASING FOR COMPLETED MONITORING WELLS "MW18"



ATLANTIC GOLD CORPORATION
MARINETTE, NOVA SCOTIA
BEAVER DAMN MINE PROJECT

PHOTOGRAPHIC LOG

088664-20
Nov 7, 2018

FIGURE 3

Attachment 3

Surface Water and Groundwater Elevation Data

Attachment 3
Surface Water and Groundwater Elevation Data
Beaver Dam Mine Project
Marinette, Nova Scotia

	UTM Zone 20 NAD83 CSRS		Installation Date	Unit	Well Depth		Ground Surface Elevation	Stick-up	Top of Casing Elevation	Top of Screen Interval		Bottom of Screen Interval	
					(m bgs)	(m AMSL)	(m AMSL)	(m ags)	(m AMSL)	(m bgs)	(m AMSL)	(m bgs)	(m AMSL)
Well_ID	Easting	Northing											
MW-1A	520942.252	4990095.110	1-May-18	Shallow	6.30	144.13	150.429	1.121	151.550	1.83	148.599	6.3	144.129
MW-1B	520943.031	4990093.660	4-May-18	Intermediate	15.30	135.31	150.610	0.994	151.604	12.24	138.370	15.3	135.310
MW-1C	520944.122	4990092.462	4-May-18	Deep	30.06	120.59	150.647	1.129	151.776	27.1	123.547	30.2	120.497
MW-2A	520728.778	4989595.501	7-May-18	Shallow	4.72	146.69	151.410	1.064	152.474	1.7	149.730	4.7	146.690
MW-2B	520730.397	4989594.708	7-May-18	Intermediate	15.60	135.84	151.441	1.093	152.534	12.5	138.941	15.6	135.891
MW-03A	521823.117	4989220.163	1-May-18	Shallow	6.32	160.10	166.421	1.015	167.436	3.3	163.141	6.3	160.101
MW-03B	521823.540	4989222.229	1-May-18	Intermediate	15.32	151.05	166.374	1.014	167.388	12.3	154.104	15.3	151.054
MW-03C	521824.051	4989223.934	2-May-18	Deep	30.30	136.03	166.334	1.007	167.341	27.3	139.084	30.3	136.034
MW-04A	522649.993	4989640.335	3-Apr-18	Shallow	5.96	158.70	164.655	0.853	165.508	2.9	161.735	6.0	158.695
MW-04B	522649.439	4989639.523	3-Apr-18	Intermediate	15.53	149.16	164.687	0.869	165.556	12.5	152.197	15.5	149.157
MW-05A	521746.140	4990210.163	25-Apr-18	Shallow	6.10	134.76	140.855	0.826	141.681	1.5	139.355	6.1	134.755
MW-05B	521747.858	4990208.591	24-Apr-18	Intermediate	15.57	125.32	140.894	0.944	141.838	12.5	128.374	15.6	125.324
MW-05C	521745.609	4990207.042	23-Apr-18	Intermediate	15.49	125.46	140.947	0.993	141.940	12.4	128.507	15.5	125.457
MW-05D	521742.062	4990206.839	1-May-18	Deep	30.48	110.87	141.346	1.012	142.358	27.4	113.916	30.5	110.866
MW-07A	522676.986	4990257.899	9-Apr-18	Shallow	7.49	122.97	130.461	0.928	131.389	4.4	126.021	7.5	122.971
MW-07B	522677.763	4990256.675	6-Apr-18	Intermediate	15.49	115.11	130.600	0.943	131.543	12.4	118.160	15.5	115.110
MW-07C	522676.908	4990255.360	19-Apr-18	Intermediate	15.49	115.10	130.588	0.989	131.577	12.4	118.148	15.5	115.098
MW-07D	522674.898	4990259.556					130.256	1.040	131.296				130.256
MW-09A	522024.415	4990682.566	13-Apr-18	Shallow	7.14	126.75	133.894	1.075	134.969	4.1	129.804	7.1	126.754
MW-09B	522022.788	4990682.720	13-Apr-18	Intermediate	15.39	118.36	133.748	1.040	134.788	12.3	121.408	15.4	118.358
MW-09C	522022.547	4990680.996	12-Apr-18	Intermediate	15.49	118.30	133.791	0.950	134.741	12.4	121.351	15.5	118.301
MW-09D	522023.739	4990684.215	2-May-18	Deep	30.48	103.23	133.705	1.046	134.751	27.43	106.275	30.48	103.225
MW-11A	522324.169	4990130.598	3-Apr-18	Shallow	6.09	141.75	147.844	0.933	148.777	3.04	144.804	6.09	141.754
MW-11B	522325.095	4990132.870	5-Apr-18	Intermediate	15.24	132.48	147.718	0.783	148.501	12.19	135.528	15.24	132.478
MW-11C	522323.713	4990132.377	4-Apr-18	Deep	26.01	121.79	147.795	0.744	148.539	22.96	124.835	26.01	121.785
MW-12A	521711.672	4991000.037	15-Apr-18	Shallow	6.10	141.80	147.903	0.652	148.555	0.91	146.993	6.1	141.803
MW-12B	521710.995	4990999.179	15-Apr-18	Deep	25.83	121.99	147.815	0.721	148.536	22.78	125.035	25.83	121.985
MW-14A	523253.265	4989830.507	26-Apr-18	Shallow	6.10	131.30	137.404	0.977	138.381	1.5	135.904	6.1	131.304
MW-14B	523253.939	4989828.780	26-Apr-18	Deep	26.04	111.40	137.442	1.049	138.491	22.99	114.452	26.04	111.402
MW-14C	523254.933	4989827.886	26-Apr-18	VERY Deep	41.15	96.34	137.486	0.819	138.305	38.1	99.386	41.15	96.336
MW-16A	522898.761	4990744.060	20-Apr-18	Shallow	7.14	146.60	153.744	1.068	154.812	3.5	150.244	7.14	146.604
MW-16B	522898.057	4990742.630	20-Apr-18	Intermediate	15.24	138.53	153.768	1.033	154.801	12.19	141.578	15.24	138.528
MW-17A	524121.346	4990324.445	26-Apr-18	Shallow	4.57	149.94	154.508	0.941	155.449	0.76	153.748	4.57	149.938
MW-17B	524123.059	4990323.426	25-Apr-18	Shallow	9.17	145.24	154.409	1.056	155.465	6.12	148.289	9.17	145.239
MW-17C	524124.712	4990324.229	25-Apr-18	Intermediate	15.44	138.92	154.355	0.894	155.249	12.45	141.905	15.44	138.915
MW-18A	523118.888	4991142.236	20-Apr-18	Shallow	7.62	139.87	147.493	0.971	148.464	4.57	142.923	7.62	139.873
MW-18B	523120.436	4991141.883	24-Apr-18	Intermediate	15.77	131.73	147.496	0.835	148.331	12.72	134.776	15.77	131.726

Attachment 3
Surface Water and Groundwater Elevation Data
Beaver Dam Mine Project
Marinette, Nova Scotia

	UTM Zone 20 NAD83 CSRS		Installation Date	Unit	Well Depth		Ground Surface Elevation	Stick-up	Top of Casing Elevation	Top of Screen Interval		Bottom of Screen Interval	
					(m bgs)	(m AMSL)				(m bgs)	(m AMSL)	(m bgs)	(m AMSL)
Well_ID	Easting	Northing											
MW-18C	523121.844	4991141.264	25-Apr-18	Shallow	6.10	141.21	147.313	1.146	148.459	1.5	145.813	6.1	141.213
MW-19A	520765.986	4991427.087	4-May-18	Shallow	4.72	128.87	133.590	0.971	134.561	0.61	132.980	4.72	128.870
MW-19B	520764.377	4991426.125	4-May-18	Intermediate	15.37	118.25	133.619	0.967	134.586	12.32	121.299	15.37	118.249
MW-19C	520762.233	4991425.291	7-May-18	Deep	30.30	103.39	133.692	0.881	134.573	27.25	106.442	30.3	103.392
MW-20A	520263.534	4990264.985	7-May-18	Shallow	7.62	144.49	152.106	1.165	153.271	4.57	147.536	7.62	144.486
MW-20B	520263.490	4990263.750	7-May-18	Intermediate	15.27	136.92	152.194	1.013	153.207	12.22	139.974	15.27	136.924
MW-21A	521749.236	4987642.034	7-May-18	Shallow	6.35	152.22	158.566	0.920	159.486	3.3	155.266	6.35	152.216
MW-21B	521747.935	4987641.733	3-May-18	Intermediate	15.42	143.10	158.518	0.988	159.506	12.37	146.148	15.42	143.098
MW-21C	521749.207	4987639.956	2-May-18	Deep	30.48	127.90	158.384	1.007	159.391	27.43	130.954	30.48	127.904
MW-22A	524377.001	4988520.078	25-Apr-18	Shallow	6.55	132.58	139.130	0.900	140.030	3.51	135.620	6.55	132.580
MW-22B	524377.199	4988521.744	27-Apr-18	Intermediate	15.55	123.60	139.148	0.987	140.135	12.5	126.648	15.55	123.598
MW-22C	524377.504	4988523.209	1-May-18	Deep	29.03	110.10	139.129	0.965	140.094	25.98	113.149	29.03	110.099
SW-1	523246.783	4990047.378					127.711	-1.170	126.541				
SW-2A	521821.700	4991319.756					129.205	-0.236	128.969				
SW-4A	521343.751	4991071.233					129.343	-0.018	129.325				
SW-5	522696.387	4990229.101					130.874	-0.353	130.521				
SW-10	522176.584	4990321.015					134.168	-0.316	133.852				
SW13	522769.824	4990261.347					129.170	-0.450	128.720				
SW-14	522677.366	4990219.104					131.709	-0.188	131.521				
SW-15	521434.975	4990457.303					133.055						
SW-16	521570.917	4990336.002					138.069	-0.253	137.816				
SW-17	521906.952	4990205.472					139.893	-0.253	139.640				
SW-18	521637.704	4990067.184					146.236	-0.582	145.654				
SW-21	521809.216	4989583.858					159.224						
SW-22	521113.269	4989464.177					152.100	-0.886	151.214				
SW-23	522639.881	4989067.980					159.839	-0.170	159.669				
SW-24													

Attachment 4

Laboratory Certificates

Your Project #: 088664
 Site Location: BEAVER DAM
 Your C.O.C. #: B 171028

Attention:Peter Oram

Conestoga-Rovers and Associates Ltd
 45 Akerley Blvd
 Dartmouth , NS
 B3B 1J7

Report Date: 2014/10/21
 Report #: R3195176
 Version: 1 - Final

CERTIFICATE OF ANALYSIS

MAXXAM JOB #: B4J1118

Received: 2014/10/14, 14:21

Sample Matrix: Water
 # Samples Received: 7

Analyses	Quantity	Date Extracted	Date Analyzed	Laboratory Method	Reference
Carbonate, Bicarbonate and Hydroxide	7	N/A	2014/10/21	N/A	SM 22 4500-CO2 D
Alkalinity	7	N/A	2014/10/17	ATL SOP 00013	EPA 310.2 R1974 m
Chloride	7	N/A	2014/10/20	ATL SOP 00014	SM 22 4500-Cl- E m
Colour	7	N/A	2014/10/20	ATL SOP 00020	SM 22 2120C m
Conductance - water	7	N/A	2014/10/21	ATL SOP 00004	SM 22 2510B m
Hardness (calculated as CaCO ₃)	7	N/A	2014/10/17	ATL SOP 00048	SM 22 2340 B
Mercury - Total (CVAA,LL)	7	2014/10/17	2014/10/17	ATL SOP 00026	EPA 245.1 R3 m
Metals Water Total MS (1)	7	2014/10/16	2014/10/16	ATL SOP 00058	EPA 6020A R1 m
Ion Balance (% Difference)	7	N/A	2014/10/21		Auto Calc.
Anion and Cation Sum	7	N/A	2014/10/21		Auto Calc.
Nitrogen Ammonia - water	7	N/A	2014/10/20	ATL SOP 00015	EPA 350.1 R2 m
Nitrogen - Nitrate + Nitrite	7	N/A	2014/10/20	ATL SOP 00016	USGS SOPINCF0452.2 m
Nitrogen - Nitrite	7	N/A	2014/10/20	ATL SOP 00017	SM 22 4500-NO2- B m
Nitrogen - Nitrate (as N)	7	N/A	2014/10/20	ATL SOP 00018	ASTM D3867
pH (2)	7	N/A	2014/10/21	ATL SOP 00003	SM 22 4500-H+ B m
Phosphorus - ortho	7	N/A	2014/10/17	ATL SOP 00021	EPA 365.2 m
Sat. pH and Langelier Index (@ 20C)	7	N/A	2014/10/21	ATL SOP 00049	Auto Calc.
Sat. pH and Langelier Index (@ 4C)	7	N/A	2014/10/21	ATL SOP 00049	Auto Calc.
Reactive Silica	7	N/A	2014/10/16	ATL SOP 00022	EPA 366.0 m
Sulphate	7	N/A	2014/10/20	ATL SOP 00023	EPA 375.4 R1978 m
Total Dissolved Solids (TDS calc)	7	N/A	2014/10/21		Auto Calc.
Organic carbon - Total (TOC) (3)	7	N/A	2014/10/17	ATL SOP 00037	SM 22 5310C m
Turbidity	7	N/A	2014/10/20	ATL SOP 00011	EPA 180.1 R2 m

This report shall not be reproduced except in full, without the written approval of the laboratory.

Results relate only to the items tested.

* RPDs calculated using raw data. The rounding of final results may result in the apparent difference.

(1) New RDLs in effect due to release of NS Contaminated Sites Regulations. Reduced RDL based on MDL study performance. Low level analytical run checks being implemented.

(2) The APHA Standard Method require pH to be analyzed within 15 minutes of sampling and therefore field analysis is required for compliance. All Laboratory pH analyses in this report are reported past the APHA Standard Method holding time.

(3) TOC / DOC present in the sample should be considered as non-purgeable TOC / DOC.

Your Project #: 088664
Site Location: BEAVER DAM
Your C.O.C. #: B 171028

Attention:Peter Oram

Conestoga-Rovers and Associates Ltd
45 Akerley Blvd
Dartmouth , NS
B3B 1J7

Report Date: 2014/10/21
Report #: R3195176
Version: 1 - Final

CERTIFICATE OF ANALYSIS

MAXXAM JOB #: B4J1118

Received: 2014/10/14, 14:21

Encryption Key  Katie Campbell
21 Oct 2014 16:55:16 -03:00

Please direct all questions regarding this Certificate of Analysis to your Project Manager.

Michelle Hill, Project Manager

Email: MHill@maxxam.ca

Phone# (902)420-0203 Ext:289

=====

Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(E), signing the reports. For Service Group specific validation please refer to the Validation Signature Page.

Maxxam Job #: B4J1118
Report Date: 2014/10/21

Conestoga-Rovers and Associates Ltd
Client Project #: 088664
Site Location: BEAVER DAM
Sampler Initials: JP

RESULTS OF ANALYSES OF WATER

Maxxam ID		XZ3577		XZ3578	XZ3579		XZ3580	XZ3580		
Sampling Date		2014/10/10		2014/10/10	2014/10/10		2014/10/10	2014/10/10		
COC Number		B 171028		B 171028	B 171028		B 171028	B 171028		
	Units	SW-1	QC Batch	SW-2A	SW-4A	RDL	SW-5	SW-5 Lab-Dup	RDL	QC Batch

Calculated Parameters

Anion Sum	me/L	0.140	3784855	0.150	0.150	N/A	0.480		N/A	3784855
Bicarb. Alkalinity (calc. as CaCO3)	mg/L	<1.0	3784852	<1.0	<1.0	1.0	14		1.0	3784852
Calculated TDS	mg/L	14	3784860	14	15	1.0	28		1.0	3784860
Carb. Alkalinity (calc. as CaCO3)	mg/L	<1.0	3784852	<1.0	<1.0	1.0	<1.0		1.0	3784852
Cation Sum	me/L	0.290	3784855	0.290	0.300	N/A	0.480		N/A	3784855
Hardness (CaCO3)	mg/L	5.5	3784853	5.1	5.9	1.0	16		1.0	3784853
Ion Balance (% Difference)	%	34.9	3784854	31.8	33.3	N/A	0.00		N/A	3784854
Langelier Index (@ 20C)	N/A	NC	3784858	NC	NC		-2.56			3784858
Langelier Index (@ 4C)	N/A	NC	3784859	NC	NC		-2.81			3784859
Nitrate (N)	mg/L	<0.050	3784856	0.11	0.093	0.050	0.10		0.050	3784856
Saturation pH (@ 20C)	N/A	NC	3784858	NC	NC		9.43			3784858
Saturation pH (@ 4C)	N/A	NC	3784859	NC	NC		9.69			3784859

Inorganics

Total Alkalinity (Total as CaCO3)	mg/L	<5.0	3786534	<5.0	<5.0	5.0	14		5.0	3786534
Dissolved Chloride (Cl)	mg/L	5.1	3786536	5.0	5.0	1.0	4.0		1.0	3786536
Colour	TCU	150	3786543	160	120	25	22		5.0	3786543
Nitrate + Nitrite	mg/L	<0.050	3786546	0.11	0.093	0.050	0.10		0.050	3786546
Nitrite (N)	mg/L	<0.010	3786547	<0.010	<0.010	0.010	<0.010		0.010	3786547
Nitrogen (Ammonia Nitrogen)	mg/L	<0.050	3788334	<0.050	<0.050	0.050	<0.050	<0.050	0.050	3788334
Total Organic Carbon (C)	mg/L	13 (1)	3788537	14 (1)	9.3 (1)	5.0	4.1		0.50	3788537
Orthophosphate (P)	mg/L	<0.010	3786544	<0.010	<0.010	0.010	<0.010		0.010	3786544
pH	pH	5.55	3792031	5.06	5.57	N/A	6.88		N/A	3792034
Reactive Silica (SiO2)	mg/L	2.5	3786541	2.7	3.4	0.50	1.8		0.50	3786541
Dissolved Sulphate (SO4)	mg/L	<2.0	3786538	<2.0	<2.0	2.0	3.5		2.0	3786538
Turbidity	NTU	1.1	3790888	1.1	1.4	0.10	0.44		0.10	3790888
Conductivity	uS/cm	30	3792033	31	29	1.0	48		1.0	3792035

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Lab-Dup = Laboratory Initiated Duplicate

N/A = Not Applicable

(1) Elevated reporting limit due to sample matrix.

Maxxam Job #: B4J1118
Report Date: 2014/10/21

Conestoga-Rovers and Associates Ltd
Client Project #: 088664
Site Location: BEAVER DAM
Sampler Initials: JP

RESULTS OF ANALYSES OF WATER

Maxxam ID		XZ3581		XZ3582		XZ3583		
Sampling Date		2014/10/10		2014/10/10		2014/10/10		
COC Number		B 171028		B 171028		B 171028		
	Units	SW-5D	RDL	SW-6A	RDL	SW-9	RDL	QC Batch
Calculated Parameters								
Anion Sum	me/L	0.480	N/A	0.130	N/A	0.310	N/A	3784855
Bicarb. Alkalinity (calc. as CaCO3)	mg/L	14	1.0	<1.0	1.0	5.8	1.0	3784852
Calculated TDS	mg/L	28	1.0	13	1.0	23	1.0	3784860
Carb. Alkalinity (calc. as CaCO3)	mg/L	<1.0	1.0	<1.0	1.0	<1.0	1.0	3784852
Cation Sum	me/L	0.470	N/A	0.240	N/A	0.420	N/A	3784855
Hardness (CaCO3)	mg/L	16	1.0	4.5	1.0	10	1.0	3784853
Ion Balance (% Difference)	%	1.05	N/A	29.7	N/A	15.1	N/A	3784854
Langelier Index (@ 20C)	N/A	-2.54		NC		-4.22		3784858
Langelier Index (@ 4C)	N/A	-2.80		NC		-4.47		3784859
Nitrate (N)	mg/L	0.15	0.050	0.080	0.050	0.091	0.050	3784856
Saturation pH (@ 20C)	N/A	9.46		NC		10.2		3784858
Saturation pH (@ 4C)	N/A	9.71		NC		10.4		3784859
Inorganics								
Total Alkalinity (Total as CaCO3)	mg/L	14	5.0	<5.0	5.0	5.8	5.0	3786534
Dissolved Chloride (Cl)	mg/L	4.1	1.0	4.3	1.0	6.7	1.0	3786536
Colour	TCU	23	5.0	80	25	160	25	3786543
Nitrate + Nitrite	mg/L	0.15	0.050	0.080	0.050	0.091	0.050	3786546
Nitrite (N)	mg/L	<0.010	0.010	<0.010	0.010	<0.010	0.010	3786547
Nitrogen (Ammonia Nitrogen)	mg/L	<0.050	0.050	<0.050	0.050	<0.050	0.050	3788334
Total Organic Carbon (C)	mg/L	4.3	0.50	9.1	0.50	17 (1)	5.0	3788537
Orthophosphate (P)	mg/L	<0.010	0.010	<0.010	0.010	<0.010	0.010	3786544
pH	pH	6.92	N/A	5.73	N/A	5.94	N/A	3792034
Reactive Silica (SiO2)	mg/L	1.8	0.50	3.3	0.50	3.2	0.50	3786541
Dissolved Sulphate (SO4)	mg/L	3.6	2.0	<2.0	2.0	<2.0	2.0	3786538
Turbidity	NTU	0.81	0.10	0.30	0.10	1.5	0.10	3790888
Conductivity	uS/cm	47	1.0	25	1.0	39	1.0	3792035

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

N/A = Not Applicable

(1) Elevated reporting limit due to sample matrix.

Maxxam Job #: B4J1118
 Report Date: 2014/10/21

Conestoga-Rovers and Associates Ltd
 Client Project #: 088664
 Site Location: BEAVER DAM
 Sampler Initials: JP

MERCURY BY COLD VAPOUR AA (WATER)

Maxxam ID		XZ3577	XZ3578	XZ3579	XZ3580	XZ3581	XZ3582	XZ3583		
Sampling Date		2014/10/10	2014/10/10	2014/10/10	2014/10/10	2014/10/10	2014/10/10	2014/10/10		
COC Number		B 171028								
	Units	SW-1	SW-2A	SW-4A	SW-5	SW-5D	SW-6A	SW-9	RDL	QC Batch

Metals

Total Mercury (Hg)	ug/L	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	0.013	3788512
--------------------	------	--------	--------	--------	--------	--------	--------	--------	-------	---------

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Maxxam Job #: B4J1118
Report Date: 2014/10/21

Conestoga-Rovers and Associates Ltd
Client Project #: 088664
Site Location: BEAVER DAM
Sampler Initials: JP

ELEMENTS BY ICP/MS (WATER)

Maxxam ID		XZ3577	XZ3578	XZ3579	XZ3580	XZ3580	XZ3581	XZ3582		
Sampling Date		2014/10/10	2014/10/10	2014/10/10	2014/10/10	2014/10/10	2014/10/10	2014/10/10		
COC Number		B 171028	B 171028	B 171028						
	Units	SW-1	SW-2A	SW-4A	SW-5	SW-5 Lab-Dup	SW-5D	SW-6A	RDL	QC Batch

Metals

Total Aluminum (Al)	ug/L	330	330	250	28	27	29	220	5.0	3785198
Total Antimony (Sb)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	3785198
Total Arsenic (As)	ug/L	2.7	1.1	5.8	29	30	30	4.0	1.0	3785198
Total Barium (Ba)	ug/L	5.8	5.6	3.4	4.5	4.6	4.6	3.2	1.0	3785198
Total Beryllium (Be)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	3785198
Total Bismuth (Bi)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	3785198
Total Boron (B)	ug/L	<50	<50	<50	<50	<50	<50	<50	50	3785198
Total Cadmium (Cd)	ug/L	0.024	0.026	0.015	<0.010	<0.010	0.016	0.024	0.010	3785198
Total Calcium (Ca)	ug/L	1200	1100	1500	5000	5000	4900	1000	100	3785198
Total Chromium (Cr)	ug/L	<1.0	1.4	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	3785198
Total Cobalt (Co)	ug/L	0.51	0.49	0.43	<0.40	<0.40	<0.40	<0.40	0.40	3785198
Total Copper (Cu)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	3785198
Total Iron (Fe)	ug/L	670	740	690	400	400	400	500	50	3785198
Total Lead (Pb)	ug/L	0.51	0.78	0.54	<0.50	<0.50	<0.50	<0.50	0.50	3785198
Total Magnesium (Mg)	ug/L	590	570	540	940	930	920	470	100	3785198
Total Manganese (Mn)	ug/L	79	77	53	60	59	59	50	2.0	3785198
Total Molybdenum (Mo)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	3785198
Total Nickel (Ni)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	3785198
Total Phosphorus (P)	ug/L	<100	<100	<100	<100	<100	<100	<100	100	3785198
Total Potassium (K)	ug/L	570	600	450	730	730	710	340	100	3785198
Total Selenium (Se)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	3785198
Total Silver (Ag)	ug/L	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	0.10	3785198
Total Sodium (Na)	ug/L	3100	3100	3200	2700	2700	2700	2800	100	3785198
Total Strontium (Sr)	ug/L	11	11	9.9	28	27	27	7.1	2.0	3785198
Total Thallium (Tl)	ug/L	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	0.10	3785198
Total Tin (Sn)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	3785198
Total Titanium (Ti)	ug/L	3.8	4.2	5.1	<2.0	<2.0	<2.0	2.7	2.0	3785198
Total Uranium (U)	ug/L	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	0.10	3785198
Total Vanadium (V)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	3785198
Total Zinc (Zn)	ug/L	5.0	6.9	19	<5.0	<5.0	<5.0	<5.0	5.0	3785198

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Lab-Dup = Laboratory Initiated Duplicate

Maxxam Job #: B4J1118
 Report Date: 2014/10/21

Conestoga-Rovers and Associates Ltd
 Client Project #: 088664
 Site Location: BEAVER DAM
 Sampler Initials: JP

ELEMENTS BY ICP/MS (WATER)

Maxxam ID		XZ3583		
Sampling Date		2014/10/10		
COC Number		B 171028		
	Units	SW-9	RDL	QC Batch
Metals				
Total Aluminum (Al)	ug/L	410	5.0	3785198
Total Antimony (Sb)	ug/L	<1.0	1.0	3785198
Total Arsenic (As)	ug/L	<1.0	1.0	3785198
Total Barium (Ba)	ug/L	6.6	1.0	3785198
Total Beryllium (Be)	ug/L	<1.0	1.0	3785198
Total Bismuth (Bi)	ug/L	<2.0	2.0	3785198
Total Boron (B)	ug/L	<50	50	3785198
Total Cadmium (Cd)	ug/L	0.024	0.010	3785198
Total Calcium (Ca)	ug/L	2300	100	3785198
Total Chromium (Cr)	ug/L	<1.0	1.0	3785198
Total Cobalt (Co)	ug/L	<0.40	0.40	3785198
Total Copper (Cu)	ug/L	<2.0	2.0	3785198
Total Iron (Fe)	ug/L	620	50	3785198
Total Lead (Pb)	ug/L	<0.50	0.50	3785198
Total Magnesium (Mg)	ug/L	1100	100	3785198
Total Manganese (Mn)	ug/L	140	2.0	3785198
Total Molybdenum (Mo)	ug/L	<2.0	2.0	3785198
Total Nickel (Ni)	ug/L	<2.0	2.0	3785198
Total Phosphorus (P)	ug/L	<100	100	3785198
Total Potassium (K)	ug/L	640	100	3785198
Total Selenium (Se)	ug/L	<1.0	1.0	3785198
Total Silver (Ag)	ug/L	<0.10	0.10	3785198
Total Sodium (Na)	ug/L	4000	100	3785198
Total Strontium (Sr)	ug/L	10	2.0	3785198
Total Thallium (Tl)	ug/L	<0.10	0.10	3785198
Total Tin (Sn)	ug/L	<2.0	2.0	3785198
Total Titanium (Ti)	ug/L	4.8	2.0	3785198
Total Uranium (U)	ug/L	0.11	0.10	3785198
Total Vanadium (V)	ug/L	<2.0	2.0	3785198
Total Zinc (Zn)	ug/L	5.2	5.0	3785198
RDL = Reportable Detection Limit				
QC Batch = Quality Control Batch				

Maxxam Job #: B4J1118
Report Date: 2014/10/21

Conestoga-Rovers and Associates Ltd
Client Project #: 088664
Site Location: BEAVER DAM
Sampler Initials: JP

GENERAL COMMENTS

Each temperature is the average of up to three cooler temperatures taken at receipt

Package 1	1.3°C
-----------	-------

Sample XZ3577-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample XZ3578-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample XZ3579-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample XZ3582-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample XZ3583-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Results relate only to the items tested.

QUALITY ASSURANCE REPORT

Conestoga-Rovers and Associates Ltd
Client Project #: 088664
Site Location: BEAVER DAM
Sampler Initials: JP

QC Batch	Parameter	Date	Matrix Spike		Spiked Blank		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	Units	Value (%)	QC Limits	% Recovery	QC Limits
3785198	Total Aluminum (Al)	2014/10/16	103 (1)	80 - 120	102	80 - 120	<5.0	ug/L	2.5 (2)	20		
3785198	Total Antimony (Sb)	2014/10/16	99 (1)	80 - 120	99	80 - 120	<1.0	ug/L	NC (2)	20		
3785198	Total Arsenic (As)	2014/10/16	99 (1)	80 - 120	99	80 - 120	<1.0	ug/L	0.50 (2)	20		
3785198	Total Barium (Ba)	2014/10/16	100 (1)	80 - 120	97	80 - 120	<1.0	ug/L	NC (2)	20		
3785198	Total Beryllium (Be)	2014/10/16	99 (1)	80 - 120	100	80 - 120	<1.0	ug/L	NC (2)	20		
3785198	Total Bismuth (Bi)	2014/10/16	100 (1)	80 - 120	98	80 - 120	<2.0	ug/L	NC (2)	20		
3785198	Total Boron (B)	2014/10/16	97 (1)	80 - 120	102	80 - 120	<50	ug/L	NC (2)	20		
3785198	Total Cadmium (Cd)	2014/10/16	100 (1)	80 - 120	98	80 - 120	<0.010	ug/L	NC (2)	20		
3785198	Total Calcium (Ca)	2014/10/16	102 (1)	80 - 120	102	80 - 120	<100	ug/L	0.17 (2)	20		
3785198	Total Chromium (Cr)	2014/10/16	98 (1)	80 - 120	98	80 - 120	<1.0	ug/L	NC (2)	20		
3785198	Total Cobalt (Co)	2014/10/16	98 (1)	80 - 120	98	80 - 120	<0.40	ug/L	NC (2)	20		
3785198	Total Copper (Cu)	2014/10/16	96 (1)	80 - 120	97	80 - 120	<2.0	ug/L	NC (2)	20		
3785198	Total Iron (Fe)	2014/10/16	104 (1)	80 - 120	103	80 - 120	<50	ug/L	0.74 (2)	20		
3785198	Total Lead (Pb)	2014/10/16	102 (1)	80 - 120	102	80 - 120	<0.50	ug/L	NC (2)	20		
3785198	Total Magnesium (Mg)	2014/10/16	107 (1)	80 - 120	105	80 - 120	<100	ug/L	1.1 (2)	20		
3785198	Total Manganese (Mn)	2014/10/16	NC (1)	80 - 120	101	80 - 120	<2.0	ug/L	2.3 (2)	20		
3785198	Total Molybdenum (Mo)	2014/10/16	100 (1)	80 - 120	100	80 - 120	<2.0	ug/L	NC (2)	20		
3785198	Total Nickel (Ni)	2014/10/16	99 (1)	80 - 120	100	80 - 120	<2.0	ug/L	NC (2)	20		
3785198	Total Phosphorus (P)	2014/10/16	106 (1)	80 - 120	104	80 - 120	<100	ug/L	NC (2)	20		
3785198	Total Potassium (K)	2014/10/16	104 (1)	80 - 120	101	80 - 120	<100	ug/L	0.012 (2)	20		
3785198	Total Selenium (Se)	2014/10/16	98 (1)	80 - 120	97	80 - 120	<1.0	ug/L	NC (2)	20		
3785198	Total Silver (Ag)	2014/10/16	98 (1)	80 - 120	98	80 - 120	<0.10	ug/L	NC (2)	20		
3785198	Total Sodium (Na)	2014/10/16	102 (1)	80 - 120	102	80 - 120	<100	ug/L	0.062 (2)	20		
3785198	Total Strontium (Sr)	2014/10/16	100 (1)	80 - 120	100	80 - 120	<2.0	ug/L	1.2 (2)	20		
3785198	Total Thallium (Tl)	2014/10/16	98 (1)	80 - 120	98	80 - 120	<0.10	ug/L	NC (2)	20		
3785198	Total Tin (Sn)	2014/10/16	102 (1)	80 - 120	100	80 - 120	<2.0	ug/L	NC (2)	20		
3785198	Total Titanium (Ti)	2014/10/16	105 (1)	80 - 120	104	80 - 120	<2.0	ug/L	NC (2)	20		
3785198	Total Uranium (U)	2014/10/16	103 (1)	80 - 120	101	80 - 120	<0.10	ug/L	NC (2)	20		
3785198	Total Vanadium (V)	2014/10/16	99 (1)	80 - 120	101	80 - 120	<2.0	ug/L	NC (2)	20		
3785198	Total Zinc (Zn)	2014/10/16	97 (1)	80 - 120	98	80 - 120	<5.0	ug/L	NC (2)	20		
3786534	Total Alkalinity (Total as CaCO3)	2014/10/17	106	80 - 120	108	80 - 120	<5.0	mg/L	NC (3)	25		
3786536	Dissolved Chloride (Cl)	2014/10/20	NC	80 - 120	103	80 - 120	<1.0	mg/L	0.49 (3)	25	111	80 - 120

QUALITY ASSURANCE REPORT(CONT'D)

Conestoga-Rovers and Associates Ltd
Client Project #: 088664
Site Location: BEAVER DAM
Sampler Initials: JP

QC Batch	Parameter	Date	Matrix Spike		Spiked Blank		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	Units	Value (%)	QC Limits	% Recovery	QC Limits
3786538	Dissolved Sulphate (SO4)	2014/10/20	98	80 - 120	105	80 - 120	<2.0	mg/L	NC (3)	25		
3786541	Reactive Silica (SiO2)	2014/10/16	NC	80 - 120	100	80 - 120	<0.50	mg/L	0.56 (3)	25		
3786543	Colour	2014/10/20			105	80 - 120	<5.0	TCU	9.8 (3)	25		
3786544	Orthophosphate (P)	2014/10/17	103	80 - 120	99	80 - 120	<0.010	mg/L	NC (3)	25		
3786546	Nitrate + Nitrite	2014/10/20	102	80 - 120	102	80 - 120	0.091 ,RDL=0.050	mg/L	NC (3)	25		
3786547	Nitrite (N)	2014/10/20	90	80 - 120	97	80 - 120	<0.010	mg/L	NC (3)	25		
3788334	Nitrogen (Ammonia Nitrogen)	2014/10/20	96 (4)	80 - 120	99	80 - 120	<0.050	mg/L	NC (5)	25		
3788512	Total Mercury (Hg)	2014/10/17	84	80 - 120	94	80 - 120	<0.013	ug/L	NC (3)	20		
3788537	Total Organic Carbon (C)	2014/10/17	99	80 - 120	104	80 - 120	<0.50	mg/L	NC (3)	20		
3790888	Turbidity	2014/10/20					<0.10	NTU	NC (3)	25	96	80 - 120
3792031	pH	2014/10/21							1.3 (3)	N/A	101	97 - 103
3792033	Conductivity	2014/10/21			100	80 - 120	1.1 ,RDL=1.0	uS/cm	0.36 (3)	25		
3792034	pH	2014/10/21							0.67 (3)	N/A	101	97 - 103
3792035	Conductivity	2014/10/21			99	80 - 120	<1.0	uS/cm	0.35 (3)	25		

N/A = Not Applicable

Duplicate: Paired analysis of a separate portion of the same sample. Used to evaluate the variance in the measurement.

Matrix Spike: A sample to which a known amount of the analyte of interest has been added. Used to evaluate sample matrix interference.

QC Standard: A sample of known concentration prepared by an external agency under stringent conditions. Used as an independent check of method accuracy.

Spiked Blank: A blank matrix sample to which a known amount of the analyte, usually from a second source, has been added. Used to evaluate method accuracy.

Method Blank: A blank matrix containing all reagents used in the analytical procedure. Used to identify laboratory contamination.

NC (Matrix Spike): The recovery in the matrix spike was not calculated. The relative difference between the concentration in the parent sample and the spiked amount was too small to permit a reliable recovery calculation (matrix spike concentration was less than 2x that of the native sample concentration).

NC (Duplicate RPD): The duplicate RPD was not calculated. The concentration in the sample and/or duplicate was too low to permit a reliable RPD calculation (one or both samples < 5x RDL).

- (1) Matrix Spike Parent ID [XZ3581-03]
- (2) Duplicate Parent ID [XZ3580-03]
- (3) Duplicate Parent ID
- (4) Matrix Spike Parent ID [XZ3580-01]
- (5) Duplicate Parent ID [XZ3580-01]

Maxxam Job #: B4J1118
Report Date: 2014/10/21

Conestoga-Rovers and Associates Ltd
Client Project #: 088664
Site Location: BEAVER DAM
Sampler Initials: JP

VALIDATION SIGNATURE PAGE

The analytical data and all QC contained in this report were reviewed and validated by the following individual(s).

<Original signed by>

Kevin MacDonald, Inorganics Supervisor

Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(E), signing the reports. For Service Group specific validation please refer to the Validation Signature Page.



200 Bluewater Road, Suite 105, Bedford, Nova Scotia B4B 1G9
 Tel: 902-420-0203 Fax: 902-420-8612 Toll Free: 1-800-565-7227
 49 Elizabeth Ave., St John's, NL A1A 1W9 Tel: 709-754-0203 Fax: 709-754-8612 Toll Free: 1-888-492-7227
 90 Esplanade Sydney, NS B1P 1A1 Tel: 902-567-1255 Fax: 902-539-6504 Toll Free: 1-888-535-7770
www.maxxamanalytics.com E-mail: Clientservicesbedford@maxxamanalytics.com

MAXXAM Chain of Custody Record

COC #: B 171028

Page 1 of 1

This column for lab use only:				INVOICE INFORMATION:			REPORT INFORMATION (if differs from invoice):			PO #		TURNAROUND TIME Standard <input checked="" type="checkbox"/> 10 day <input type="checkbox"/> If RUSH Specify Date: <u>N/A</u> Pre-schedule rush work Charge for # Jars used but not submitted <u>0</u>		
Client Code				Company Name: <u>CRA</u>			Company Name:			Project # / Phase # <u>088664</u>				
Maxxam Job #				Contact Name: <u>PETER CRAM</u>			Contact Name:			Project Name / Site Location <u>BEAVER DAM</u>				
<u>B4J1118</u>				Address: <u>45 AKERLEY BLVD.</u> <u>DARTMOUTH, NS B3B 1J7</u>			Address:			Quote <u>14-161KG</u>				
Cooler ID	Seal Present	Seal Intact	Average Temp	Temp 1	Temp 2	Temp 3	Postal Code							
				1	3	0								
Integrity	Integrity / Checklist by	YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	<u>4/16</u>	Guideline Requirements / Detection Limits / Special Instructions <u>CCME FRESHWATER AQUATIC LIFE</u> <u>cc: jparks@craworld.com</u>			Email:			Task Order #				
Labelled by	Location / Bin #	Specify Matrix: Surface/Salt/Ground/Tapwater/Sewage/Effluent/Potable/NonPotable/Tissue/Soil/Sludge/Metal/Seawater			Ph:	Fax:	Ph:			Sampled by <u>JEFF PARKS/AMANDA FALEY</u>				
				Field Sample Identification	Matrix*	Date/Time Sampled	# & type of bottles	Field Filtered & Preserved	Lab Filtration Required	Choose Total or Diss Metals	Choose Total or Diss Metals	Metals Water	Metals Soil	Hydrocarbons
				1 SW-1	SURFACE WATER	10-OCT-14	1x50 1x200 1x100		X					
				2 SW-2A	SURFACE WATER	10-OCT-14	1x50 1x200 1x100		X		X			
				3 SW-4A	SURFACE WATER	10-OCT-14	1x50 1x200 1x100		X		X			
				4 SW-5	SURFACE WATER	10-OCT-14	1x50 1x200 1x100		X		X			
				5 SW-5D	SURFACE WATER	10-OCT-14	1x50 1x200 1x100		X		X			
				6 SW-6A	SURFACE WATER	10-OCT-14	1x50 1x200 1x100		X		X			
				7 SW-9	SURFACE WATER	10-OCT-14	1x50 1x200 1x100		X		X			
				8										
				9										
<u>14 OCT 14 14:21</u>														
 B4J1118				RELINQUISHED BY: (Signature/Print) <u><Original signed</u> / <u>RAYNA HART</u> 14-OCT-14 14:20			RECEIVED BY: (Signature/Print) <u><Original signed by></u> <u>RAYNA HART</u> <u>Karen Burilkault TCSHA PARTBAULT</u>							

Your Project #: 088664
 Site Location: BEAVER DAM
 Your C.O.C. #: B 171028

Attention:Peter Oram

Conestoga-Rovers and Associates Ltd
 45 Akerley Blvd
 Dartmouth , NS
 B3B 1J7

Report Date: 2014/10/24
 Report #: R3199243
 Version: 2 - Revision

CERTIFICATE OF ANALYSIS – REVISED REPORT

MAXXAM JOB #: B4J1118

Received: 2014/10/14, 14:21

Sample Matrix: Water
 # Samples Received: 7

Analyses	Quantity	Date Extracted	Date Analyzed	Laboratory Method	Reference
Carbonate, Bicarbonate and Hydroxide	7	N/A	2014/10/21	N/A	SM 22 4500-CO2 D
Alkalinity	7	N/A	2014/10/17	ATL SOP 00013	EPA 310.2 R1974 m
Chloride	7	N/A	2014/10/20	ATL SOP 00014	SM 22 4500-Cl- E m
Colour	7	N/A	2014/10/20	ATL SOP 00020	SM 22 2120C m
Conductance - water	7	N/A	2014/10/21	ATL SOP 00004	SM 22 2510B m
Hardness (calculated as CaCO ₃)	7	N/A	2014/10/17	ATL SOP 00048	SM 22 2340 B
Mercury - Total (CVAA,LL)	7	2014/10/17	2014/10/17	ATL SOP 00026	EPA 245.1 R3 m
Metals Water Total MS (1)	7	2014/10/16	2014/10/16	ATL SOP 00058	EPA 6020A R1 m
Ion Balance (% Difference)	7	N/A	2014/10/21		Auto Calc.
Anion and Cation Sum	7	N/A	2014/10/21		Auto Calc.
Nitrogen Ammonia - water	7	N/A	2014/10/20	ATL SOP 00015	EPA 350.1 R2 m
Nitrogen - Nitrate + Nitrite	7	N/A	2014/10/20	ATL SOP 00016	USGS SOPINCF0452.2 m
Nitrogen - Nitrite	7	N/A	2014/10/20	ATL SOP 00017	SM 22 4500-NO2- B m
Nitrogen - Nitrate (as N)	7	N/A	2014/10/20	ATL SOP 00018	ASTM D3867
pH (2)	7	N/A	2014/10/21	ATL SOP 00003	SM 22 4500-H+ B m
Phosphorus - ortho	7	N/A	2014/10/17	ATL SOP 00021	EPA 365.2 m
Sat. pH and Langelier Index (@ 20C)	7	N/A	2014/10/21	ATL SOP 00049	Auto Calc.
Sat. pH and Langelier Index (@ 4C)	7	N/A	2014/10/21	ATL SOP 00049	Auto Calc.
Reactive Silica	7	N/A	2014/10/16	ATL SOP 00022	EPA 366.0 m
Sulphate	7	N/A	2014/10/20	ATL SOP 00023	EPA 375.4 R1978 m
Total Dissolved Solids (TDS calc)	7	N/A	2014/10/21		Auto Calc.
Organic carbon - Total (TOC) (3)	7	N/A	2014/10/17	ATL SOP 00037	SM 22 5310C m
Turbidity	7	N/A	2014/10/20	ATL SOP 00011	EPA 180.1 R2 m

This report shall not be reproduced except in full, without the written approval of the laboratory.

Results relate only to the items tested.

* RPDs calculated using raw data. The rounding of final results may result in the apparent difference.

(1) New RDLs in effect due to release of NS Contaminated Sites Regulations. Reduced RDL based on MDL study performance. Low level analytical run checks being implemented.

(2) The APHA Standard Method require pH to be analyzed within 15 minutes of sampling and therefore field analysis is required for compliance. All Laboratory pH analyses in this report are reported past the APHA Standard Method holding time.

(3) TOC / DOC present in the sample should be considered as non-purgeable TOC / DOC.

Your Project #: 088664
Site Location: BEAVER DAM
Your C.O.C. #: B 171028

Attention:Peter Oram

Conestoga-Rovers and Associates Ltd
45 Akerley Blvd
Dartmouth , NS
B3B 1J7

Report Date: 2014/10/24
Report #: R3199243
Version: 2 - Revision

CERTIFICATE OF ANALYSIS – REVISED REPORT

MAXXAM JOB #: B4J1118

Received: 2014/10/14, 14:21

Encryption Key <Original signed by> Mari Kenny
24 Oct 2014 1

24 Oct 2014 15:44:11 -03:00

Please direct all questions regarding this Certificate of Analysis to your Project Manager.
Michelle Hill, Project Manager
Email: mhill@williams.com

Email: M^Hill@maxxam.ca

Phone# (902)420-0203 Ext:289

Maxxam has procedures in place

signing the reports. For Service

Fig. 1. The effect of the number of iterations on the convergence of the proposed algorithm.

Total Cover Pages : 2
Page 2 of 12

Maxxam Job #: B4J1118
Report Date: 2014/10/24

Conestoga-Rovers and Associates Ltd
Client Project #: 088664
Site Location: BEAVER DAM
Sampler Initials: JP

RESULTS OF ANALYSES OF WATER

Maxxam ID		XZ3577		XZ3578	XZ3579		XZ3580	XZ3580		
Sampling Date		2014/10/10		2014/10/10	2014/10/10		2014/10/10	2014/10/10		
COC Number		B 171028		B 171028	B 171028		B 171028	B 171028		
	Units	SW-1	QC Batch	SW-2A	SW-4A	RDL	SW-5	SW-5 Lab-Dup	RDL	QC Batch

Calculated Parameters

Anion Sum	me/L	0.140	3784855	0.150	0.150	N/A	0.480		N/A	3784855
Bicarb. Alkalinity (calc. as CaCO3)	mg/L	<1.0	3784852	<1.0	<1.0	1.0	14		1.0	3784852
Calculated TDS	mg/L	14	3784860	14	15	1.0	28		1.0	3784860
Carb. Alkalinity (calc. as CaCO3)	mg/L	<1.0	3784852	<1.0	<1.0	1.0	<1.0		1.0	3784852
Cation Sum	me/L	0.290	3784855	0.290	0.300	N/A	0.480		N/A	3784855
Hardness (CaCO3)	mg/L	5.5	3784853	5.1	5.9	1.0	16		1.0	3784853
Ion Balance (% Difference)	%	34.9	3784854	31.8	33.3	N/A	0.00		N/A	3784854
Langelier Index (@ 20C)	N/A	NC	3784858	NC	NC		-2.56			3784858
Langelier Index (@ 4C)	N/A	NC	3784859	NC	NC		-2.81			3784859
Nitrate (N)	mg/L	<0.050	3784856	0.11	0.093	0.050	0.10		0.050	3784856
Saturation pH (@ 20C)	N/A	NC	3784858	NC	NC		9.43			3784858
Saturation pH (@ 4C)	N/A	NC	3784859	NC	NC		9.69			3784859

Inorganics

Total Alkalinity (Total as CaCO3)	mg/L	<5.0	3786534	<5.0	<5.0	5.0	14		5.0	3786534
Dissolved Chloride (Cl)	mg/L	5.1	3786536	5.0	5.0	1.0	4.0		1.0	3786536
Colour	TCU	150	3786543	160	120	25	22		5.0	3786543
Nitrate + Nitrite	mg/L	<0.050	3786546	0.11	0.093	0.050	0.10		0.050	3786546
Nitrite (N)	mg/L	<0.010	3786547	<0.010	<0.010	0.010	<0.010		0.010	3786547
Nitrogen (Ammonia Nitrogen)	mg/L	<0.050	3788334	<0.050	<0.050	0.050	<0.050	<0.050	0.050	3788334
Total Organic Carbon (C)	mg/L	13 (1)	3788537	14 (1)	9.3 (1)	5.0	4.1		0.50	3788537
Orthophosphate (P)	mg/L	<0.010	3786544	<0.010	<0.010	0.010	<0.010		0.010	3786544
pH	pH	5.55	3792031	5.06	5.57	N/A	6.88		N/A	3792034
Reactive Silica (SiO2)	mg/L	2.5	3786541	2.7	3.4	0.50	1.8		0.50	3786541
Dissolved Sulphate (SO4)	mg/L	<2.0	3786538	<2.0	<2.0	2.0	3.5		2.0	3786538
Turbidity	NTU	1.1	3790888	1.1	1.4	0.10	0.44		0.10	3790888
Conductivity	uS/cm	30	3792033	31	29	1.0	48		1.0	3792035

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Lab-Dup = Laboratory Initiated Duplicate

N/A = Not Applicable

(1) Elevated reporting limit due to sample matrix.

Maxxam Job #: B4J1118
Report Date: 2014/10/24

Conestoga-Rovers and Associates Ltd
Client Project #: 088664
Site Location: BEAVER DAM
Sampler Initials: JP

RESULTS OF ANALYSES OF WATER

Maxxam ID		XZ3581		XZ3582		XZ3583		
Sampling Date		2014/10/10		2014/10/10		2014/10/10		
COC Number		B 171028		B 171028		B 171028		
	Units	SW-5D	RDL	SW-6A	RDL	SW-9	RDL	QC Batch
Calculated Parameters								
Anion Sum	me/L	0.480	N/A	0.130	N/A	0.310	N/A	3784855
Bicarb. Alkalinity (calc. as CaCO3)	mg/L	14	1.0	<1.0	1.0	5.8	1.0	3784852
Calculated TDS	mg/L	28	1.0	13	1.0	23	1.0	3784860
Carb. Alkalinity (calc. as CaCO3)	mg/L	<1.0	1.0	<1.0	1.0	<1.0	1.0	3784852
Cation Sum	me/L	0.470	N/A	0.240	N/A	0.420	N/A	3784855
Hardness (CaCO3)	mg/L	16	1.0	4.5	1.0	10	1.0	3784853
Ion Balance (% Difference)	%	1.05	N/A	29.7	N/A	15.1	N/A	3784854
Langelier Index (@ 20C)	N/A	-2.54		NC		-4.22		3784858
Langelier Index (@ 4C)	N/A	-2.80		NC		-4.47		3784859
Nitrate (N)	mg/L	0.15	0.050	0.080	0.050	0.091	0.050	3784856
Saturation pH (@ 20C)	N/A	9.46		NC		10.2		3784858
Saturation pH (@ 4C)	N/A	9.71		NC		10.4		3784859
Inorganics								
Total Alkalinity (Total as CaCO3)	mg/L	14	5.0	<5.0	5.0	5.8	5.0	3786534
Dissolved Chloride (Cl)	mg/L	4.1	1.0	4.3	1.0	6.7	1.0	3786536
Colour	TCU	23	5.0	80	25	160	25	3786543
Nitrate + Nitrite	mg/L	0.15	0.050	0.080	0.050	0.091	0.050	3786546
Nitrite (N)	mg/L	<0.010	0.010	<0.010	0.010	<0.010	0.010	3786547
Nitrogen (Ammonia Nitrogen)	mg/L	<0.050	0.050	<0.050	0.050	<0.050	0.050	3788334
Total Organic Carbon (C)	mg/L	4.3	0.50	9.1	0.50	17 (1)	5.0	3788537
Orthophosphate (P)	mg/L	<0.010	0.010	<0.010	0.010	<0.010	0.010	3786544
pH	pH	6.92	N/A	5.73	N/A	5.94	N/A	3792034
Reactive Silica (SiO2)	mg/L	1.8	0.50	3.3	0.50	3.2	0.50	3786541
Dissolved Sulphate (SO4)	mg/L	3.6	2.0	<2.0	2.0	<2.0	2.0	3786538
Turbidity	NTU	0.81	0.10	0.30	0.10	1.5	0.10	3790888
Conductivity	uS/cm	47	1.0	25	1.0	39	1.0	3792035

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

N/A = Not Applicable

(1) Elevated reporting limit due to sample matrix.

Maxxam Job #: B4J1118
 Report Date: 2014/10/24

Conestoga-Rovers and Associates Ltd
 Client Project #: 088664
 Site Location: BEAVER DAM
 Sampler Initials: JP

MERCURY BY COLD VAPOUR AA (WATER)

Maxxam ID		XZ3577	XZ3578	XZ3579	XZ3580	XZ3581	XZ3582	XZ3583		
Sampling Date		2014/10/10	2014/10/10	2014/10/10	2014/10/10	2014/10/10	2014/10/10	2014/10/10		
COC Number		B 171028								
	Units	SW-1	SW-2A	SW-4A	SW-5	SW-5D	SW-6A	SW-9	RDL	QC Batch

Metals

Total Mercury (Hg)	ug/L	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	0.013	3788512
--------------------	------	--------	--------	--------	--------	--------	--------	--------	-------	---------

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Maxxam Job #: B4J1118
Report Date: 2014/10/24

Conestoga-Rovers and Associates Ltd
Client Project #: 088664
Site Location: BEAVER DAM
Sampler Initials: JP

ELEMENTS BY ICP/MS (WATER)

Maxxam ID		XZ3577	XZ3578	XZ3579	XZ3580	XZ3580	XZ3581	XZ3582		
Sampling Date		2014/10/10	2014/10/10	2014/10/10	2014/10/10	2014/10/10	2014/10/10	2014/10/10		
COC Number		B 171028	B 171028	B 171028						
	Units	SW-1	SW-2A	SW-4A	SW-5	SW-5 Lab-Dup	SW-5D	SW-6A	RDL	QC Batch

Metals

Total Aluminum (Al)	ug/L	330	330	250	28	27	29	220	5.0	3785198
Total Antimony (Sb)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	3785198
Total Arsenic (As)	ug/L	2.7	1.1	5.8	29	30	30	4.0	1.0	3785198
Total Barium (Ba)	ug/L	5.8	5.6	3.4	4.5	4.6	4.6	3.2	1.0	3785198
Total Beryllium (Be)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	3785198
Total Bismuth (Bi)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	3785198
Total Boron (B)	ug/L	<50	<50	<50	<50	<50	<50	<50	50	3785198
Total Cadmium (Cd)	ug/L	0.024	0.026	0.015	<0.010	<0.010	0.016	0.024	0.010	3785198
Total Calcium (Ca)	ug/L	1200	1100	1500	5000	5000	4900	1000	100	3785198
Total Chromium (Cr)	ug/L	<1.0	1.4	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	3785198
Total Cobalt (Co)	ug/L	0.51	0.49	0.43	<0.40	<0.40	<0.40	<0.40	0.40	3785198
Total Copper (Cu)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	3785198
Total Iron (Fe)	ug/L	670	740	690	400	400	400	500	50	3785198
Total Lead (Pb)	ug/L	0.51	0.78	0.54	<0.50	<0.50	<0.50	<0.50	0.50	3785198
Total Magnesium (Mg)	ug/L	590	570	540	940	930	920	470	100	3785198
Total Manganese (Mn)	ug/L	79	77	53	60	59	59	50	2.0	3785198
Total Molybdenum (Mo)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	3785198
Total Nickel (Ni)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	3785198
Total Phosphorus (P)	ug/L	<100	<100	<100	<100	<100	<100	<100	100	3785198
Total Potassium (K)	ug/L	570	600	450	730	730	710	340	100	3785198
Total Selenium (Se)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	3785198
Total Silver (Ag)	ug/L	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	0.10	3785198
Total Sodium (Na)	ug/L	3100	3100	3200	2700	2700	2700	2800	100	3785198
Total Strontium (Sr)	ug/L	11	11	9.9	28	27	27	7.1	2.0	3785198
Total Thallium (Tl)	ug/L	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	0.10	3785198
Total Tin (Sn)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	3785198
Total Titanium (Ti)	ug/L	3.8	4.2	5.1	<2.0	<2.0	<2.0	2.7	2.0	3785198
Total Uranium (U)	ug/L	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	0.10	3785198
Total Vanadium (V)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	3785198
Total Zinc (Zn)	ug/L	5.0	6.9	19	<5.0	<5.0	<5.0	<5.0	5.0	3785198

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Lab-Dup = Laboratory Initiated Duplicate

Maxxam Job #: B4J1118
Report Date: 2014/10/24

Conestoga-Rovers and Associates Ltd
Client Project #: 088664
Site Location: BEAVER DAM
Sampler Initials: JP

ELEMENTS BY ICP/MS (WATER)

Maxxam ID		XZ3583		
Sampling Date		2014/10/10		
COC Number		B 171028		
	Units	SW-9	RDL	QC Batch
Metals				
Total Aluminum (Al)	ug/L	410	5.0	3785198
Total Antimony (Sb)	ug/L	<1.0	1.0	3785198
Total Arsenic (As)	ug/L	<1.0	1.0	3785198
Total Barium (Ba)	ug/L	6.6	1.0	3785198
Total Beryllium (Be)	ug/L	<1.0	1.0	3785198
Total Bismuth (Bi)	ug/L	<2.0	2.0	3785198
Total Boron (B)	ug/L	<50	50	3785198
Total Cadmium (Cd)	ug/L	0.024	0.010	3785198
Total Calcium (Ca)	ug/L	2300	100	3785198
Total Chromium (Cr)	ug/L	<1.0	1.0	3785198
Total Cobalt (Co)	ug/L	<0.40	0.40	3785198
Total Copper (Cu)	ug/L	<2.0	2.0	3785198
Total Iron (Fe)	ug/L	620	50	3785198
Total Lead (Pb)	ug/L	<0.50	0.50	3785198
Total Magnesium (Mg)	ug/L	1100	100	3785198
Total Manganese (Mn)	ug/L	140	2.0	3785198
Total Molybdenum (Mo)	ug/L	<2.0	2.0	3785198
Total Nickel (Ni)	ug/L	<2.0	2.0	3785198
Total Phosphorus (P)	ug/L	<100	100	3785198
Total Potassium (K)	ug/L	640	100	3785198
Total Selenium (Se)	ug/L	<1.0	1.0	3785198
Total Silver (Ag)	ug/L	<0.10	0.10	3785198
Total Sodium (Na)	ug/L	4000	100	3785198
Total Strontium (Sr)	ug/L	10	2.0	3785198
Total Thallium (Tl)	ug/L	<0.10	0.10	3785198
Total Tin (Sn)	ug/L	<2.0	2.0	3785198
Total Titanium (Ti)	ug/L	4.8	2.0	3785198
Total Uranium (U)	ug/L	0.11	0.10	3785198
Total Vanadium (V)	ug/L	<2.0	2.0	3785198
Total Zinc (Zn)	ug/L	5.2	5.0	3785198
RDL = Reportable Detection Limit				
QC Batch = Quality Control Batch				

Maxxam Job #: B4J1118
Report Date: 2014/10/24

Conestoga-Rovers and Associates Ltd
Client Project #: 088664
Site Location: BEAVER DAM
Sampler Initials: JP

GENERAL COMMENTS

Each temperature is the average of up to three cooler temperatures taken at receipt

Package 1	1.3°C
-----------	-------

Report re-issued to include the National Excel EDD - 2014/10/24 MK

Sample XZ3577-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample XZ3578-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample XZ3579-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample XZ3582-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample XZ3583-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Results relate only to the items tested.

QUALITY ASSURANCE REPORT

Conestoga-Rovers and Associates Ltd
Client Project #: 088664
Site Location: BEAVER DAM
Sampler Initials: JP

QC Batch	Parameter	Date	Matrix Spike		Spiked Blank		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	Units	Value (%)	QC Limits	% Recovery	QC Limits
3785198	Total Aluminum (Al)	2014/10/16	103 (1)	80 - 120	102	80 - 120	<5.0	ug/L	2.5 (2)	20		
3785198	Total Antimony (Sb)	2014/10/16	99 (1)	80 - 120	99	80 - 120	<1.0	ug/L	NC (2)	20		
3785198	Total Arsenic (As)	2014/10/16	99 (1)	80 - 120	99	80 - 120	<1.0	ug/L	0.50 (2)	20		
3785198	Total Barium (Ba)	2014/10/16	100 (1)	80 - 120	97	80 - 120	<1.0	ug/L	NC (2)	20		
3785198	Total Beryllium (Be)	2014/10/16	99 (1)	80 - 120	100	80 - 120	<1.0	ug/L	NC (2)	20		
3785198	Total Bismuth (Bi)	2014/10/16	100 (1)	80 - 120	98	80 - 120	<2.0	ug/L	NC (2)	20		
3785198	Total Boron (B)	2014/10/16	97 (1)	80 - 120	102	80 - 120	<50	ug/L	NC (2)	20		
3785198	Total Cadmium (Cd)	2014/10/16	100 (1)	80 - 120	98	80 - 120	<0.010	ug/L	NC (2)	20		
3785198	Total Calcium (Ca)	2014/10/16	102 (1)	80 - 120	102	80 - 120	<100	ug/L	0.17 (2)	20		
3785198	Total Chromium (Cr)	2014/10/16	98 (1)	80 - 120	98	80 - 120	<1.0	ug/L	NC (2)	20		
3785198	Total Cobalt (Co)	2014/10/16	98 (1)	80 - 120	98	80 - 120	<0.40	ug/L	NC (2)	20		
3785198	Total Copper (Cu)	2014/10/16	96 (1)	80 - 120	97	80 - 120	<2.0	ug/L	NC (2)	20		
3785198	Total Iron (Fe)	2014/10/16	104 (1)	80 - 120	103	80 - 120	<50	ug/L	0.74 (2)	20		
3785198	Total Lead (Pb)	2014/10/16	102 (1)	80 - 120	102	80 - 120	<0.50	ug/L	NC (2)	20		
3785198	Total Magnesium (Mg)	2014/10/16	107 (1)	80 - 120	105	80 - 120	<100	ug/L	1.1 (2)	20		
3785198	Total Manganese (Mn)	2014/10/16	NC (1)	80 - 120	101	80 - 120	<2.0	ug/L	2.3 (2)	20		
3785198	Total Molybdenum (Mo)	2014/10/16	100 (1)	80 - 120	100	80 - 120	<2.0	ug/L	NC (2)	20		
3785198	Total Nickel (Ni)	2014/10/16	99 (1)	80 - 120	100	80 - 120	<2.0	ug/L	NC (2)	20		
3785198	Total Phosphorus (P)	2014/10/16	106 (1)	80 - 120	104	80 - 120	<100	ug/L	NC (2)	20		
3785198	Total Potassium (K)	2014/10/16	104 (1)	80 - 120	101	80 - 120	<100	ug/L	0.012 (2)	20		
3785198	Total Selenium (Se)	2014/10/16	98 (1)	80 - 120	97	80 - 120	<1.0	ug/L	NC (2)	20		
3785198	Total Silver (Ag)	2014/10/16	98 (1)	80 - 120	98	80 - 120	<0.10	ug/L	NC (2)	20		
3785198	Total Sodium (Na)	2014/10/16	102 (1)	80 - 120	102	80 - 120	<100	ug/L	0.062 (2)	20		
3785198	Total Strontium (Sr)	2014/10/16	100 (1)	80 - 120	100	80 - 120	<2.0	ug/L	1.2 (2)	20		
3785198	Total Thallium (Tl)	2014/10/16	98 (1)	80 - 120	98	80 - 120	<0.10	ug/L	NC (2)	20		
3785198	Total Tin (Sn)	2014/10/16	102 (1)	80 - 120	100	80 - 120	<2.0	ug/L	NC (2)	20		
3785198	Total Titanium (Ti)	2014/10/16	105 (1)	80 - 120	104	80 - 120	<2.0	ug/L	NC (2)	20		
3785198	Total Uranium (U)	2014/10/16	103 (1)	80 - 120	101	80 - 120	<0.10	ug/L	NC (2)	20		
3785198	Total Vanadium (V)	2014/10/16	99 (1)	80 - 120	101	80 - 120	<2.0	ug/L	NC (2)	20		
3785198	Total Zinc (Zn)	2014/10/16	97 (1)	80 - 120	98	80 - 120	<5.0	ug/L	NC (2)	20		
3786534	Total Alkalinity (Total as CaCO3)	2014/10/17	106	80 - 120	108	80 - 120	<5.0	mg/L	NC (3)	25		
3786536	Dissolved Chloride (Cl)	2014/10/20	NC	80 - 120	103	80 - 120	<1.0	mg/L	0.49 (3)	25	111	80 - 120

QUALITY ASSURANCE REPORT(CONT'D)

Conestoga-Rovers and Associates Ltd
Client Project #: 088664
Site Location: BEAVER DAM
Sampler Initials: JP

QC Batch	Parameter	Date	Matrix Spike		Spiked Blank		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	Units	Value (%)	QC Limits	% Recovery	QC Limits
3786538	Dissolved Sulphate (SO4)	2014/10/20	98	80 - 120	105	80 - 120	<2.0	mg/L	NC (3)	25		
3786541	Reactive Silica (SiO2)	2014/10/16	NC	80 - 120	100	80 - 120	<0.50	mg/L	0.56 (3)	25		
3786543	Colour	2014/10/20			105	80 - 120	<5.0	TCU	9.8 (3)	25		
3786544	Orthophosphate (P)	2014/10/17	103	80 - 120	99	80 - 120	<0.010	mg/L	NC (3)	25		
3786546	Nitrate + Nitrite	2014/10/20	102	80 - 120	102	80 - 120	0.091 ,RDL=0.050	mg/L	NC (3)	25		
3786547	Nitrite (N)	2014/10/20	90	80 - 120	97	80 - 120	<0.010	mg/L	NC (3)	25		
3788334	Nitrogen (Ammonia Nitrogen)	2014/10/20	96 (4)	80 - 120	99	80 - 120	<0.050	mg/L	NC (5)	25		
3788512	Total Mercury (Hg)	2014/10/17	84	80 - 120	94	80 - 120	<0.013	ug/L	NC (3)	20		
3788537	Total Organic Carbon (C)	2014/10/17	99	80 - 120	104	80 - 120	<0.50	mg/L	NC (3)	20		
3790888	Turbidity	2014/10/20					<0.10	NTU	NC (3)	25	96	80 - 120
3792031	pH	2014/10/21							1.3 (3)	N/A	101	97 - 103
3792033	Conductivity	2014/10/21			100	80 - 120	1.1 ,RDL=1.0	uS/cm	0.36 (3)	25		
3792034	pH	2014/10/21							0.67 (3)	N/A	101	97 - 103
3792035	Conductivity	2014/10/21			99	80 - 120	<1.0	uS/cm	0.35 (3)	25		

N/A = Not Applicable

Duplicate: Paired analysis of a separate portion of the same sample. Used to evaluate the variance in the measurement.

Matrix Spike: A sample to which a known amount of the analyte of interest has been added. Used to evaluate sample matrix interference.

QC Standard: A sample of known concentration prepared by an external agency under stringent conditions. Used as an independent check of method accuracy.

Spiked Blank: A blank matrix sample to which a known amount of the analyte, usually from a second source, has been added. Used to evaluate method accuracy.

Method Blank: A blank matrix containing all reagents used in the analytical procedure. Used to identify laboratory contamination.

NC (Matrix Spike): The recovery in the matrix spike was not calculated. The relative difference between the concentration in the parent sample and the spiked amount was too small to permit a reliable recovery calculation (matrix spike concentration was less than 2x that of the native sample concentration).

NC (Duplicate RPD): The duplicate RPD was not calculated. The concentration in the sample and/or duplicate was too low to permit a reliable RPD calculation (one or both samples < 5x RDL).

- (1) Matrix Spike Parent ID [XZ3581-03]
- (2) Duplicate Parent ID [XZ3580-03]
- (3) Duplicate Parent ID
- (4) Matrix Spike Parent ID [XZ3580-01]
- (5) Duplicate Parent ID [XZ3580-01]

Maxxam Job #: B4J1118
Report Date: 2014/10/24

Conestoga-Rovers and Associates Ltd
Client Project #: 088664
Site Location: BEAVER DAM
Sampler Initials: JP

VALIDATION SIGNATURE PAGE

The analytical data and all QC contained in this report were reviewed and validated by the following individual(s).

<Original signed by>

Kevin MacDonald, Inorganics Supervisor

Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(E), signing the reports. For Service Group specific validation please refer to the Validation Signature Page.




200 Bluewater Road, Suite 105, Bedford, Nova Scotia B4B 1G9
 Tel: 902-420-0203 Fax: 902-420-8612 Toll Free: 1-800-565-7227
 49 Elizabeth Ave., St John's, NL A1A 1W9 Tel: 709-754-0203 Fax: 709-754-8612 Toll Free: 1-888-492-7227
 90 Esplanade Sydney, NS B1P 1A1 Tel: 902-567-1255 Fax: 902-539-6504 Toll Free: 1-888-535-7770
www.maxxamanalytics.com E-mail: Clientservicesbedford@maxxamanalytics.com

MAXXAM Chain of Custody Record

COC #: **B 171028**

Page 1 of 1

This column for lab use only:					INVOICE INFORMATION:			REPORT INFORMATION (if differs from invoice):			PO #		TURNAROUND TIME Standard <input checked="" type="checkbox"/> 10 day <input type="checkbox"/> If RUSH Specify Date: <u>N/A</u> Pre-schedule rush work Charge for # Jars used but not submitted <u>0</u>
Client Code					Company Name: <u>CRA</u>			Company Name:			Project # / Phase # <u>088664</u>		
Maxxam Job #					Contact Name: <u>PETER CRAM</u>			Contact Name:			Project Name / Site Location <u>BEAVER DAM</u>		
B4J1118					Address: <u>45 AKERLEY BLVD.</u> <u>DARTMOUTH, NS B3B 1J7</u>			Address:			Quote <u>14-161KG</u>		
Cooler ID	Seal Present	Seal Intact	Temp 1	Temp 2	Temp 3	Average Temp	Postal Code	Email:	Ph:	Task Order #	Sampled by <u>JEFF PARKS/AMANDA FALEY</u>		
Guideline Requirements / Detection Limits / Special Instructions CCME FRESHWATER AQUATIC LIFE cc: <u>j.parks@craworld.com</u>													
Integrity <u>YES</u> <u>NO</u>		Integrity / Checklist by <u>4/16</u>											
Labelled by		Location / Bin #											
*Specify Matrix: Surface/Salt/Ground/Tapwater/Sewage/Effluent/Potable/NonPotable/Tissue/Soil/Sludge/Metal/Seawater													
Field Sample Identification		Matrix*	Date/Time Sampled	# & type of bottles	Field Filtered & Preserved	Lab Filtration Required	Choose Total or Diss Metals	RCAP-30 Choose Total or Diss Metals	RCAP-MS Choose Total or Diss Metals	Fax:	Metals & Mercury	Metals Soil	Hydrocarbons
1 SW-1		SURFACE WATER	10-OCT-14	1x50 1x200 1x100		X					Metals Total Digest - for Ocean sediments (HNO3/HF/HClO4)		
2 SW-2A		SURFACE WATER	10-OCT-14	1x50 1x200 1x100		X		X			Mercury		
3 SW-4A		SURFACE WATER	10-OCT-14	1x50 1x200 1x100		X		X			Selenium (low level) Req'd for CCME Residential, Parklands, Agricultural (required for CCME Agriculture)		
4 SW-5		SURFACE WATER	10-OCT-14	1x50 1x200 1x100		X		X			RBCA Hydrocarbons (BTEX, C6-C22)		
5 SW-5D		SURFACE WATER	10-OCT-14	1x50 1x200 1x100		X		X			Hydrocarbons Soil (Portable), NS Fuel Oil Spill Recy Low Level BTEX, C6-C22		
6 SW-6A		SURFACE WATER	10-OCT-14	1x50 1x200 1x100		X		X			NB Possible Water BTEX, VPH, Low level T.E.H.		
7 SW-9		SURFACE WATER	10-OCT-14	1x50 1x200 1x100		X		X			TPH Fractionation		
8											PAH's		
9											PAH's with Acridine, Quinoline		
14 OCT 14 14:21													
RELINQUISHED BY: (Signature/Print) <u><Original signed</u>				Date <u>14-OCT-14</u>			Time <u>14:20</u>			RECEIVED BY (Signature/Print) <u><Original signed by></u>			
										<u>ANSON WATERS</u>			
										<u>Karen Burilkault TESHA PARTIAULT</u>			
White: Maxxam Yellow: Mail													



B4J1118

Your P.O. #: 20-019340
 Your Project #: 088664-05
 Site Location: ATLANTIC GOLD-BEAVER DAM
 Your C.O.C. #: B 66223

Attention:Jeff Parks

Conestoga-Rovers and Associates Ltd
 45 Akerley Blvd
 Dartmouth , NS
 B3B 1J7

Report Date: 2014/11/24
 Report #: R3231882
 Version: 1 - Final

CERTIFICATE OF ANALYSIS

MAXXAM JOB #: B4L5339

Received: 2014/11/14, 10:45

Sample Matrix: Water
 # Samples Received: 7

Analyses	Quantity	Date Extracted	Date Analyzed	Laboratory Method	Reference
Carbonate, Bicarbonate and Hydroxide	7	N/A	2014/11/21	N/A	SM 22 4500-CO2 D
Alkalinity	7	N/A	2014/11/24	ATL SOP 00013	EPA 310.2 R1974 m
Chloride	7	N/A	2014/11/21	ATL SOP 00014	SM 22 4500-Cl- E m
Colour	6	N/A	2014/11/20	ATL SOP 00020	SM 22 2120C m
Colour	1	N/A	2014/11/21	ATL SOP 00020	SM 22 2120C m
Conductance - water	7	N/A	2014/11/20	ATL SOP 00004	SM 22 2510B m
Hardness (calculated as CaCO ₃)	7	N/A	2014/11/20	ATL SOP 00048	SM 22 2340 B
Mercury - Total (CVAA,LL)	7	2014/11/20	2014/11/21	ATL SOP 00026	EPA 245.1 R3 m
Metals Water Total MS (1)	7	2014/11/19	2014/11/20	ATL SOP 00058	EPA 6020A R1 m
Ion Balance (% Difference)	7	N/A	2014/11/24		Auto Calc.
Anion and Cation Sum	7	N/A	2014/11/21		Auto Calc.
Nitrogen Ammonia - water	7	N/A	2014/11/20	ATL SOP 00015	EPA 350.1 R2 m
Nitrogen - Nitrate + Nitrite	7	N/A	2014/11/21	ATL SOP 00016	USGS SOPINCF0452.2 m
Nitrogen - Nitrite	7	N/A	2014/11/21	ATL SOP 00017	SM 22 4500-NO2- B m
Nitrogen - Nitrate (as N)	7	N/A	2014/11/21	ATL SOP 00018	ASTM D3867
pH (2)	7	N/A	2014/11/20	ATL SOP 00003	SM 22 4500-H+ B m
Phosphorus - ortho	7	N/A	2014/11/20	ATL SOP 00021	EPA 365.2 m
Sat. pH and Langelier Index (@ 20C)	7	N/A	2014/11/24	ATL SOP 00049	Auto Calc.
Sat. pH and Langelier Index (@ 4C)	7	N/A	2014/11/24	ATL SOP 00049	Auto Calc.
Reactive Silica	1	N/A	2014/11/19	ATL SOP 00022	EPA 366.0 m
Reactive Silica	6	N/A	2014/11/20	ATL SOP 00022	EPA 366.0 m
Sulphate	7	N/A	2014/11/21	ATL SOP 00023	EPA 375.4 R1978 m
Total Dissolved Solids (TDS calc)	7	N/A	2014/11/24		Auto Calc.
Organic carbon - Total (TOC) (3)	7	N/A	2014/11/19	ATL SOP 00037	SM 22 5310C m
Turbidity	7	N/A	2014/11/21	ATL SOP 00011	EPA 180.1 R2 m

* RPDs calculated using raw data. The rounding of final results may result in the apparent difference.

(1) New RDLs in effect due to release of NS Contaminated Sites Regulations. Reduced RDL based on MDL study performance. Low level analytical run checks being implemented.

(2) The APHA Standard Method require pH to be analyzed within 15 minutes of sampling and therefore field analysis is required for compliance. All Laboratory pH analyses in this report are reported past the APHA Standard Method holding time.

(3) TOC / DOC present in the sample should be considered as non-purgeable TOC / DOC.

Your P.O. #: 20-019340
Your Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your C.O.C. #: B 66223

Attention:Jeff Parks

Conestoga-Rovers and Associates Ltd
45 Akerley Blvd
Dartmouth , NS
B3B 1J7

Report Date: 2014/11/24
Report #: R3231882
Version: 1 - Final

CERTIFICATE OF ANALYSIS

MAXXAM JOB #: B4L5339

Received: 2014/11/14, 10:45

Encryption Key <Original signed by>

Rachael Mansfield
24 Nov 2014 15:35:38 -04:00

Please direct all questions regarding this Certificate of Analysis to your Project Manager.

Michelle Hill, Project Manager

Email: MHill@maxxam.ca

Phone# (902)420-0203 Ext:289

=====

Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(E), signing the reports. For Service Group specific validation please refer to the Validation Signature Page.

Maxxam Job #: B4L5339
Report Date: 2014/11/24

Conestoga-Rovers and Associates Ltd
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340
Sampler Initials: AF

RESULTS OF ANALYSES OF WATER

Maxxam ID		YL6603	YL6604	YL6605	YL6605		YL6606		
Sampling Date		2014/11/13	2014/11/13	2014/11/13	2014/11/13		2014/11/13		
COC Number		B 66223	B 66223	B 66223	B 66223		B 66223		
	Units	SW-1	SW-2A	SW-4A	SW-4A Lab-Dup	QC Batch	SW-4AD	RDL	QC Batch

Calculated Parameters

Anion Sum	me/L	0.170	0.180	0.180		3824136	0.180	N/A	3824136
Bicarb. Alkalinity (calc. as CaCO3)	mg/L	<1.0	<1.0	<1.0		3824131	<1.0	1.0	3824131
Calculated TDS	mg/L	16	17	16		3824140	16	1.0	3824140
Carb. Alkalinity (calc. as CaCO3)	mg/L	<1.0	<1.0	<1.0		3824131	<1.0	1.0	3824131
Cation Sum	me/L	0.290	0.300	0.300		3824136	0.300	N/A	3824136
Hardness (CaCO3)	mg/L	5.0	4.9	5.6		3824134	5.6	1.0	3824134
Ion Balance (% Difference)	%	26.1	25.0	25.0		3824135	25.0	N/A	3824135
Langelier Index (@ 20C)	N/A	NC	NC	NC		3824138	NC		3824138
Langelier Index (@ 4C)	N/A	NC	NC	NC		3824139	NC		3824139
Nitrate (N)	mg/L	0.061	0.065	0.062		3824137	<0.050	0.050	3824137
Saturation pH (@ 20C)	N/A	NC	NC	NC		3824138	NC		3824138
Saturation pH (@ 4C)	N/A	NC	NC	NC		3824139	NC		3824139

Inorganics

Total Alkalinity (Total as CaCO3)	mg/L	<5.0	<5.0	<5.0	<5.0	3827629	<5.0	5.0	3827629
Dissolved Chloride (Cl)	mg/L	5.8	6.3	6.2	5.8	3827631	6.4	1.0	3827631
Colour	TCU	160	160	130	130	3827648	130	25	3827648
Nitrate + Nitrite	mg/L	0.061	0.065	0.062	0.066	3827662	<0.050	0.050	3827662
Nitrite (N)	mg/L	<0.010	<0.010	<0.010	<0.010	3827664	<0.010	0.010	3827664
Nitrogen (Ammonia Nitrogen)	mg/L	<0.050	<0.050	<0.050		3829220	<0.050	0.050	3829221
Total Organic Carbon (C)	mg/L	18	19	16		3828950	16	0.50	3828950
Orthophosphate (P)	mg/L	<0.010	<0.010	<0.010	<0.010	3827660	<0.010	0.010	3827660
pH	pH	4.59	4.54	4.76		3830316	4.71	N/A	3830316
Reactive Silica (SiO2)	mg/L	3.9	3.9	3.5	3.6	3827642	3.6	0.50	3827642
Dissolved Sulphate (SO4)	mg/L	<2.0	<2.0	<2.0	<2.0	3827633	<2.0	2.0	3827633
Turbidity	NTU	0.64	0.50	0.68		3832636	0.65	0.10	3832636
Conductivity	uS/cm	33	33	31		3830317	31	1.0	3830317

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Lab-Dup = Laboratory Initiated Duplicate

N/A = Not Applicable

Maxxam Job #: B4L5339
Report Date: 2014/11/24

Conestoga-Rovers and Associates Ltd
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340
Sampler Initials: AF

RESULTS OF ANALYSES OF WATER

Maxxam ID		YL6607		YL6608	YL6609		
Sampling Date		2014/11/13		2014/11/13	2014/11/13		
COC Number		B 66223		B 66223	B 66223		
	Units	SW-5	RDL	SW-6A	SW-9	RDL	QC Batch
Calculated Parameters							
Anion Sum	me/L	0.520	N/A	0.160	0.200	N/A	3824136
Bicarb. Alkalinity (calc. as CaCO ₃)	mg/L	11	1.0	<1.0	<1.0	1.0	3824131
Calculated TDS	mg/L	33	1.0	15	17	1.0	3824140
Carb. Alkalinity (calc. as CaCO ₃)	mg/L	<1.0	1.0	<1.0	<1.0	1.0	3824131
Cation Sum	me/L	0.510	N/A	0.270	0.340	N/A	3824136
Hardness (CaCO ₃)	mg/L	17	1.0	5.0	6.4	1.0	3824134
Ion Balance (% Difference)	%	0.970	N/A	25.6	25.9	N/A	3824135
Langelier Index (@ 20C)	N/A	-2.74		NC	NC		3824138
Langelier Index (@ 4C)	N/A	-2.99		NC	NC		3824139
Nitrate (N)	mg/L	0.051	0.050	<0.050	<0.050	0.050	3824137
Saturation pH (@ 20C)	N/A	9.52		NC	NC		3824138
Saturation pH (@ 4C)	N/A	9.77		NC	NC		3824139
Inorganics							
Total Alkalinity (Total as CaCO ₃)	mg/L	11	5.0	<5.0	<5.0	5.0	3827629
Dissolved Chloride (Cl)	mg/L	5.2	1.0	5.8	7.2	1.0	3827631
Colour	TCU	26	5.0	99	140	25	3827648
Nitrate + Nitrite	mg/L	0.051	0.050	<0.050	<0.050	0.050	3827662
Nitrite (N)	mg/L	<0.010	0.010	<0.010	<0.010	0.010	3827664
Nitrogen (Ammonia Nitrogen)	mg/L	<0.050	0.050	<0.050	<0.050	0.050	3829221
Total Organic Carbon (C)	mg/L	3.5	0.50	13	18	0.50	3828950
Orthophosphate (P)	mg/L	<0.010	0.010	<0.010	<0.010	0.010	3827660
pH	pH	6.78	N/A	5.05	4.96	N/A	3830316
Reactive Silica (SiO ₂)	mg/L	3.1	0.50	3.5	3.1	0.50	3827642
Dissolved Sulphate (SO ₄)	mg/L	7.0	2.0	<2.0	<2.0	2.0	3827633
Turbidity	NTU	1.4	0.10	0.69	0.74	0.10	3832636
Conductivity	uS/cm	49	1.0	28	35	1.0	3830317

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

N/A = Not Applicable

Maxxam Job #: B4L5339
 Report Date: 2014/11/24

Conestoga-Rovers and Associates Ltd
 Client Project #: 088664-05
 Site Location: ATLANTIC GOLD-BEAVER DAM
 Your P.O. #: 20-019340
 Sampler Initials: AF

MERCURY BY COLD VAPOUR AA (WATER)

Maxxam ID		YL6603	YL6604	YL6605	YL6606	YL6607	YL6608	YL6609		
Sampling Date		2014/11/13	2014/11/13	2014/11/13	2014/11/13	2014/11/13	2014/11/13	2014/11/13		
COC Number		B 66223								
	Units	SW-1	SW-2A	SW-4A	SW-4AD	SW-5	SW-6A	SW-9	RDL	QC Batch

Metals

Total Mercury (Hg)	ug/L	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	0.013	3831012
--------------------	------	--------	--------	--------	--------	--------	--------	--------	-------	---------

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Maxxam Job #: B4L5339
Report Date: 2014/11/24

Conestoga-Rovers and Associates Ltd
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340
Sampler Initials: AF

ELEMENTS BY ICP/MS (WATER)

Maxxam ID		YL6603	YL6604	YL6605	YL6606	YL6607	YL6608	YL6609		
Sampling Date		2014/11/13	2014/11/13	2014/11/13	2014/11/13	2014/11/13	2014/11/13	2014/11/13		
COC Number		B 66223								
	Units	SW-1	SW-2A	SW-4A	SW-4AD	SW-5	SW-6A	SW-9	RDL	QC Batch
Metals										
Total Aluminum (Al)	ug/L	320	340	300	310	100	290	330	5.0	3827227
Total Antimony (Sb)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	3827227
Total Arsenic (As)	ug/L	1.5	<1.0	2.9	2.8	15	1.9	<1.0	1.0	3827227
Total Barium (Ba)	ug/L	5.6	5.8	4.6	4.4	5.5	4.1	5.7	1.0	3827227
Total Beryllium (Be)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	3827227
Total Bismuth (Bi)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	3827227
Total Boron (B)	ug/L	<50	<50	<50	<50	<50	<50	<50	50	3827227
Total Cadmium (Cd)	ug/L	0.029	0.028	0.024	0.025	<0.010	0.021	0.025	0.010	3827227
Total Calcium (Ca)	ug/L	1100	1000	1300	1300	5300	1200	1400	100	3827227
Total Chromium (Cr)	ug/L	<1.0	1.6	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	3827227
Total Cobalt (Co)	ug/L	0.52	0.58	0.53	0.59	<0.40	0.44	<0.40	0.40	3827227
Total Copper (Cu)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	3827227
Total Iron (Fe)	ug/L	630	700	540	540	470	480	500	50	3827227
Total Lead (Pb)	ug/L	<0.50	0.55	<0.50	<0.50	<0.50	<0.50	<0.50	0.50	3827227
Total Magnesium (Mg)	ug/L	560	570	590	590	970	510	700	100	3827227
Total Manganese (Mn)	ug/L	68	71	58	58	28	51	75	2.0	3827227
Total Molybdenum (Mo)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	3827227
Total Nickel (Ni)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	3827227
Total Phosphorus (P)	ug/L	<100	110	100	100	<100	<100	<100	100	3827227
Total Potassium (K)	ug/L	550	600	500	520	1000	470	530	100	3827227
Total Selenium (Se)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	3827227
Total Silver (Ag)	ug/L	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	0.10	3827227
Total Sodium (Na)	ug/L	3000	3100	3100	3200	2900	3000	3900	100	3827227
Total Strontium (Sr)	ug/L	10	9.5	9.1	9.2	26	7.7	7.7	2.0	3827227
Total Thallium (Tl)	ug/L	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	0.10	3827227
Total Tin (Sn)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	3827227
Total Titanium (Ti)	ug/L	3.2	3.8	3.7	3.9	3.2	3.1	4.1	2.0	3827227
Total Uranium (U)	ug/L	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	0.10	3827227
Total Vanadium (V)	ug/L	2.3	2.5	2.9	2.8	3.1	2.2	2.3	2.0	3827227
Total Zinc (Zn)	ug/L	5.1	6.2	7.8	6.9	<5.0	5.5	7.5	5.0	3827227

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Maxxam Job #: B4L5339
Report Date: 2014/11/24

Conestoga-Rovers and Associates Ltd
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340
Sampler Initials: AF

GENERAL COMMENTS

Each temperature is the average of up to three cooler temperatures taken at receipt

Package 1	3.3°C
-----------	-------

Sample YL6603-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample YL6604-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample YL6605-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample YL6606-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample YL6608-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample YL6609-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Results relate only to the items tested.

QUALITY ASSURANCE REPORT

Conestoga-Rovers and Associates Ltd

Client Project #: 088664-05

Site Location: ATLANTIC GOLD-BEAVER DAM

Your P.O. #: 20-019340

Sampler Initials: AF

QC Batch	Parameter	Date	Matrix Spike		Spiked Blank		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	Units	Value (%)	QC Limits	% Recovery	QC Limits
3827227	Total Aluminum (Al)	2014/11/20	98	80 - 120	100	80 - 120	<5.0	ug/L	NC (1)	20		
3827227	Total Antimony (Sb)	2014/11/20	108	80 - 120	104	80 - 120	<1.0	ug/L				
3827227	Total Arsenic (As)	2014/11/20	99	80 - 120	97	80 - 120	<1.0	ug/L	NC (1)	20		
3827227	Total Barium (Ba)	2014/11/20	NC	80 - 120	103	80 - 120	<1.0	ug/L				
3827227	Total Beryllium (Be)	2014/11/20	104	80 - 120	103	80 - 120	<1.0	ug/L				
3827227	Total Bismuth (Bi)	2014/11/20	101	80 - 120	103	80 - 120	<2.0	ug/L				
3827227	Total Boron (B)	2014/11/20	99	80 - 120	98	80 - 120	<50	ug/L				
3827227	Total Cadmium (Cd)	2014/11/20	99	80 - 120	98	80 - 120	<0.010	ug/L	NC (1)	20		
3827227	Total Calcium (Ca)	2014/11/20	NC	80 - 120	92	80 - 120	<100	ug/L				
3827227	Total Chromium (Cr)	2014/11/20	96	80 - 120	96	80 - 120	<1.0	ug/L	NC (1)	20		
3827227	Total Cobalt (Co)	2014/11/20	95	80 - 120	95	80 - 120	<0.40	ug/L				
3827227	Total Copper (Cu)	2014/11/20	94	80 - 120	94	80 - 120	<2.0	ug/L	NC (1)	20		
3827227	Total Iron (Fe)	2014/11/20	101	80 - 120	102	80 - 120	<50	ug/L	NC (1)	20		
3827227	Total Lead (Pb)	2014/11/20	97	80 - 120	98	80 - 120	<0.50	ug/L	NC (1)	20		
3827227	Total Magnesium (Mg)	2014/11/20	NC	80 - 120	105	80 - 120	<100	ug/L				
3827227	Total Manganese (Mn)	2014/11/20	93	80 - 120	100	80 - 120	<2.0	ug/L				
3827227	Total Molybdenum (Mo)	2014/11/20	104	80 - 120	103	80 - 120	<2.0	ug/L	NC (1)	20		
3827227	Total Nickel (Ni)	2014/11/20	97	80 - 120	98	80 - 120	<2.0	ug/L	NC (1)	20		
3827227	Total Phosphorus (P)	2014/11/20	109	80 - 120	109	80 - 120	<100	ug/L				
3827227	Total Potassium (K)	2014/11/20	106	80 - 120	109	80 - 120	<100	ug/L				
3827227	Total Selenium (Se)	2014/11/20	96	80 - 120	94	80 - 120	<1.0	ug/L	NC (1)	20		
3827227	Total Silver (Ag)	2014/11/20	101	80 - 120	100	80 - 120	<0.10	ug/L	NC (1)	20		
3827227	Total Sodium (Na)	2014/11/20	NC	80 - 120	103	80 - 120	<100	ug/L				
3827227	Total Strontium (Sr)	2014/11/20	NC	80 - 120	100	80 - 120	<2.0	ug/L				
3827227	Total Thallium (Tl)	2014/11/20	100	80 - 120	101	80 - 120	<0.10	ug/L				
3827227	Total Tin (Sn)	2014/11/20	105	80 - 120	101	80 - 120	<2.0	ug/L				
3827227	Total Titanium (Ti)	2014/11/20	101	80 - 120	101	80 - 120	<2.0	ug/L				
3827227	Total Uranium (U)	2014/11/20	108	80 - 120	105	80 - 120	<0.10	ug/L				
3827227	Total Vanadium (V)	2014/11/20	98	80 - 120	101	80 - 120	3.5, RDL=2.0	ug/L				
3827227	Total Zinc (Zn)	2014/11/20	99	80 - 120	100	80 - 120	<5.0	ug/L	1.7 (1)	20		
3827629	Total Alkalinity (Total as CaCO3)	2014/11/24	102 (2)	80 - 120	109	80 - 120	<5.0	mg/L	NC (3)	25		

QUALITY ASSURANCE REPORT(CONT'D)

Conestoga-Rovers and Associates Ltd

Client Project #: 088664-05

Site Location: ATLANTIC GOLD-BEAVER DAM

Your P.O. #: 20-019340

Sampler Initials: AF

QC Batch	Parameter	Date	Matrix Spike		Spiked Blank		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	Units	Value (%)	QC Limits	% Recovery	QC Limits
3827631	Dissolved Chloride (Cl)	2014/11/21	100 (2)	80 - 120	103	80 - 120	<1.0	mg/L	7.3 (3)	25	107	80 - 120
3827633	Dissolved Sulphate (SO4)	2014/11/21	105 (2)	80 - 120	96	80 - 120	<2.0	mg/L	NC (3)	25		
3827642	Reactive Silica (SiO2)	2014/11/19	99 (2)	80 - 120	103	80 - 120	<0.50	mg/L	0.58 (3)	25		
3827648	Colour	2014/11/21			104	80 - 120	<5.0	TCU	3.2 (3)	25		
3827660	Orthophosphate (P)	2014/11/20	90 (2)	80 - 120	97	80 - 120	<0.010	mg/L	NC (3)	25		
3827662	Nitrate + Nitrite	2014/11/21	103 (2)	80 - 120	103	80 - 120	<0.050	mg/L	NC (3)	25		
3827664	Nitrite (N)	2014/11/21	91 (2)	80 - 120	101	80 - 120	<0.010	mg/L	NC (3)	25		
3828950	Total Organic Carbon (C)	2014/11/19	101	80 - 120	107	80 - 120	<0.50	mg/L	NC (1)	20		
3829220	Nitrogen (Ammonia Nitrogen)	2014/11/20	96	80 - 120	100	80 - 120	<0.050	mg/L	NC (1)	25		
3829221	Nitrogen (Ammonia Nitrogen)	2014/11/21	98	80 - 120	102	80 - 120	<0.050	mg/L	14 (1)	25		
3830316	pH	2014/11/20							0.45 (1)	N/A	100	97 - 103
3830317	Conductivity	2014/11/20			99	80 - 120	1.3, RDL=1.0	uS/cm	0 (1)	25		
3831012	Total Mercury (Hg)	2014/11/21	91	80 - 120	101	80 - 120	<0.013	ug/L	NC (1)	20		
3832636	Turbidity	2014/11/21					<0.10	NTU	5.6 (1)	25	106	80 - 120

N/A = Not Applicable

Duplicate: Paired analysis of a separate portion of the same sample. Used to evaluate the variance in the measurement.

Matrix Spike: A sample to which a known amount of the analyte of interest has been added. Used to evaluate sample matrix interference.

QC Standard: A sample of known concentration prepared by an external agency under stringent conditions. Used as an independent check of method accuracy.

Spiked Blank: A blank matrix sample to which a known amount of the analyte, usually from a second source, has been added. Used to evaluate method accuracy.

Method Blank: A blank matrix containing all reagents used in the analytical procedure. Used to identify laboratory contamination.

NC (Matrix Spike): The recovery in the matrix spike was not calculated. The relative difference between the concentration in the parent sample and the spiked amount was too small to permit a reliable recovery calculation (matrix spike concentration was less than 2x that of the native sample concentration).

NC (Duplicate RPD): The duplicate RPD was not calculated. The concentration in the sample and/or duplicate was too low to permit a reliable RPD calculation (one or both samples < 5x RDL).

(1) Duplicate Parent ID

(2) Matrix Spike Parent ID [YL6605-01]

(3) Duplicate Parent ID [YL6605-01]

Maxxam Job #: B4L5339
Report Date: 2014/11/24

Conestoga-Rovers and Associates Ltd
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340
Sampler Initials: AF

VALIDATION SIGNATURE PAGE

The analytical data and all QC contained in this report were reviewed and validated by the following individual(s).

<Original signed by>

Mike MacGillivray, Scientific Specialist (Inorganics)

Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(E), signing the reports. For Service Group specific validation please refer to the Validation Signature Page.



200 Bluewater Road, Suite 105, Bedford, Nova Scotia B4B 1G9 Tel: 902-420-0203 Fax: 902-420-8612 Toll Free: 1-800-585-7227
90 Esplanade Sydney, NS B1P 1A1 Tel: 902-567-1255 Fax: 902-539-6504 Toll Free: 888-535-7770
www.maxxamalytics.com E-mail: Clientservicesbedford@maxxamalytics.com

MAXXAM Chain of Custody Record

coc #: B 66223

Page 1 of 1

This column for lab use only:				INVOICE INFORMATION:				REPORT INFORMATION (if differs from invoice):				PO # 20-019340		TURNAROUND TIME		
Client Code				Company Name: CRA				Company Name:				Project # / Phase # 088664-05		Standard <input checked="" type="checkbox"/>		
Maxxam Job # B4L5339				Contact Name: Jeff Parks				Contact Name:				Project Name / Site Location Atlantic Gold-Beaver Dam		10 day <input type="checkbox"/>		
				Address: Dartmouth, NS				Address:				Quote 14-161KG		If RUSH Specify Date:		
Cooler ID	Seal Present	Seal Intact	Temp 1	Temp 2	Temp 3	Average Temp				Postal Code			Site #		Pre-schedule rush work	
								Email:				Task Order #		Charge for # Jars used but not submitted		
								Ph:				Sampled by AF		/		
Guideline Requirements / Detection Limits / Special Instructions CCME FWAL																
Integrity YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>		Integrity Checklist by SB														
Labelled by		Location / Bin # 50														
*Specify Matrix: Surface/Salt/Ground/Tapwater/Sewage/Effluent/Potable/NonPotable/Tissue/Soil/Sludge/Metal/Seawater																
Field Sample Identification			Matrix*	Date/Time Sampled	# & type of bottles	Field Filtered & Preserved	Lab Filtration Required	RCAP-30	Total or Diss Metals	RCAP-MS	Total or Diss Metals	Metals Water	Metals Soil	Hydrocarbons		
1	SW-1	SW	13 Nov 14	1X50 1X100 1X200	X		X		X							
2	SW-2A					X		X		X						
3	SW-4A					X		X		X						
4	SW-4AD					X		X		X						
5	SW-5					X		X		X						
6	SW-6A					X		X		X						
7	SW-9														2014 NOV 14 11:25	
8																
9																
10																
RELINQUISHED BY: (Signature/Print) <Original signed by> AFacey 14 Nov 14								RECEIVED BY: (Signature/Print) <Original signed by> See Doyle 14 NOV 14 10:45 <<Original signed by> SARA MARON								
 B4L5339																

White: Maxxim

Yellow : Mai

Pink: Client

ATL FCD 00149 / Revision 8 11/08

Your P.O. #: 20-019340
 Your Project #: 088664-05
 Site Location: ATLANTIC GOLD-BEAVER DAM
 Your C.O.C. #: B 100254

Attention:Jeff Parks

Conestoga-Rovers and Associates Ltd
 45 Akerley Blvd
 Dartmouth , NS
 B3B 1J7

Report Date: 2014/12/31
 Report #: R3275281
 Version: 1 - Final

CERTIFICATE OF ANALYSIS

MAXXAM JOB #: B4O0693

Received: 2014/12/19, 10:13

Sample Matrix: Water
 # Samples Received: 7

Analyses	Quantity	Date Extracted	Date Analyzed	Laboratory Method	Reference
Carbonate, Bicarbonate and Hydroxide	7	N/A	2014/12/30	N/A	SM 22 4500-CO2 D
Alkalinity	7	N/A	2014/12/29	ATL SOP 00013	EPA 310.2 R1974 m
Chloride	7	N/A	2014/12/30	ATL SOP 00014	SM 22 4500-Cl- E m
Colour	7	N/A	2014/12/30	ATL SOP 00020	SM 22 2120C m
Conductance - water	7	N/A	2014/12/30	ATL SOP 00004	SM 22 2510B m
Hardness (calculated as CaCO ₃)	7	N/A	2014/12/24	ATL SOP 00048	SM 22 2340 B
Mercury - Total (CVAA,LL)	7	2014/12/22	2014/12/22	ATL SOP 00026	EPA 245.1 R3 m
Metals Water Total MS (1)	7	2014/12/23	2014/12/23	ATL SOP 00058	EPA 6020A R1 m
Ion Balance (% Difference)	7	N/A	2014/12/31		Auto Calc.
Anion and Cation Sum	7	N/A	2014/12/30		Auto Calc.
Nitrogen Ammonia - water	7	N/A	2014/12/29	ATL SOP 00015	EPA 350.1 R2 m
Nitrogen - Nitrate + Nitrite	7	N/A	2014/12/30	ATL SOP 00016	USGS SOPINCF0452.2 m
Nitrogen - Nitrite	7	N/A	2014/12/30	ATL SOP 00017	SM 22 4500-NO2- B m
Nitrogen - Nitrate (as N)	7	N/A	2014/12/31	ATL SOP 00018	ASTM D3867
pH (2)	7	N/A	2014/12/30	ATL SOP 00003	SM 22 4500-H+ B m
Phosphorus - ortho	7	N/A	2014/12/31	ATL SOP 00021	EPA 365.2 m
Sat. pH and Langelier Index (@ 20C)	6	N/A	2014/12/30	ATL SOP 00049	Auto Calc.
Sat. pH and Langelier Index (@ 20C)	1	N/A	2014/12/31	ATL SOP 00049	Auto Calc.
Sat. pH and Langelier Index (@ 4C)	6	N/A	2014/12/30	ATL SOP 00049	Auto Calc.
Sat. pH and Langelier Index (@ 4C)	1	N/A	2014/12/31	ATL SOP 00049	Auto Calc.
Reactive Silica	7	N/A	2014/12/29	ATL SOP 00022	EPA 366.0 m
Sulphate	7	N/A	2014/12/30	ATL SOP 00023	EPA 375.4 R1978 m
Total Dissolved Solids (TDS calc)	7	N/A	2014/12/31		Auto Calc.
Organic carbon - Total (TOC) (3)	7	N/A	2014/12/30	ATL SOP 00037	SM 22 5310C m
Turbidity	7	N/A	2014/12/30	ATL SOP 00011	EPA 180.1 R2 m

* RPDs calculated using raw data. The rounding of final results may result in the apparent difference.

(1) New RDLs in effect due to release of NS Contaminated Sites Regulations. Reduced RDL based on MDL study performance. Low level analytical run checks being implemented.

(2) The APHA Standard Method require pH to be analyzed within 15 minutes of sampling and therefore field analysis is required for compliance. All Laboratory pH analyses in this report are reported past the APHA Standard Method holding time.

(3) TOC / DOC present in the sample should be considered as non-purgeable TOC / DOC.

Your P.O. #: 20-019340
Your Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your C.O.C. #: B 100254

Attention:Jeff Parks

Conestoga-Rovers and Associates Ltd
45 Akerley Blvd
Dartmouth , NS
B3B 1J7

Report Date: 2014/12/31
Report #: R3275281
Version: 1 - Final

CERTIFICATE OF ANALYSIS

MAXXAM JOB #: B4O0693

Received: 2014/12/19, 10:13

Encryption Key <Original
signed by>

Rachael Mansfield
31 Dec 2014 12:23:06 -04:00

Please direct all questions regarding this Certificate of Analysis to your Project Manager.

Michelle Hill, Project Manager

Email: M.Hill@maxxam.ca

Phone# (902)420-0203 Ex

Maxxam has procedures in place to guard against improper use of the electronic sign.

Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(L), signing the reports. For Service Group specific validation please refer to the Validation Signature Page.

Maxxam Job #: B4O0693
Report Date: 2014/12/31

Conestoga-Rovers and Associates Ltd
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340

RESULTS OF ANALYSES OF WATER

Maxxam ID		YX9103	YX9103	YX9104	YX9105			YX9106		
Sampling Date		2014/12/18	2014/12/18	2014/12/18	2014/12/18			2014/12/18		
COC Number		B 100254	B 100254	B 100254	B 100254			B 100254		
	Units	SW-1	SW-1 Lab-Dup	SW-2A	SW-4A	RDL	QC Batch	SW-5	RDL	QC Batch

Calculated Parameters

Anion Sum	me/L	0.100		0.100	0.110	N/A	3865872	0.340	N/A	3865872
Bicarb. Alkalinity (calc. as CaCO3)	mg/L	<1.0		<1.0	<1.0	1.0	3865868	6.1	1.0	3865868
Calculated TDS	mg/L	10		10	11	1.0	3865865	23	1.0	3865865
Carb. Alkalinity (calc. as CaCO3)	mg/L	<1.0		<1.0	<1.0	1.0	3865868	<1.0	1.0	3865868
Cation Sum	me/L	0.190		0.180	0.200	N/A	3865872	0.340	N/A	3865872
Hardness (CaCO3)	mg/L	3.3		2.9	3.5	1.0	3865870	10	1.0	3865870
Ion Balance (% Difference)	%	31.0		28.6	29.0	N/A	3865871	0.00	N/A	3865871
Langelier Index (@ 20C)	N/A	NC		NC	NC		3865863	-3.79		3865863
Langelier Index (@ 4C)	N/A	NC		NC	NC		3865864	-4.04		3865864
Nitrate (N)	mg/L	<0.050		<0.050	<0.050	0.050	3865873	0.094	0.050	3865873
Saturation pH (@ 20C)	N/A	NC		NC	NC		3865863	10.0		3865863
Saturation pH (@ 4C)	N/A	NC		NC	NC		3865864	10.3		3865864

Inorganics

Total Alkalinity (Total as CaCO3)	mg/L	<5.0	<5.0	<5.0	<5.0	5.0	3872171	6.1	5.0	3872171
Dissolved Chloride (Cl)	mg/L	3.4	3.8	3.6	3.9	1.0	3872174	4.0	1.0	3872174
Colour	TCU	99	96	100	88	25	3872177	30	5.0	3872177
Nitrate + Nitrite	mg/L	<0.050	0.066	<0.050	<0.050	0.050	3872180	0.094	0.050	3872180
Nitrite (N)	mg/L	<0.010	<0.010	<0.010	<0.010	0.010	3872181	<0.010	0.010	3872181
Nitrogen (Ammonia Nitrogen)	mg/L	<0.050		<0.050	<0.050	0.050	3872510	<0.050	0.050	3872510
Total Organic Carbon (C)	mg/L	8.2		8.9	8.2	0.50	3873222	4.0	0.50	3873222
Orthophosphate (P)	mg/L	<0.010	<0.010	<0.010	<0.010	0.010	3872178	<0.010	0.010	3872178
pH	pH	5.23		4.88	4.96	N/A	3872971	6.23	N/A	3872971
Reactive Silica (SiO2)	mg/L	2.7	2.8	2.8	2.9	0.50	3872176	3.0	0.50	3872176
Dissolved Sulphate (SO4)	mg/L	<2.0	<2.0	<2.0	<2.0	2.0	3872175	4.6	2.0	3872175
Turbidity	NTU	0.59		0.59	0.80	0.10	3873221	6.2	0.10	3873217
Conductivity	uS/cm	25		25	24	1.0	3872972	35	1.0	3872972

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Lab-Dup = Laboratory Initiated Duplicate

N/A = Not Applicable

Maxxam Job #: B4O0693
Report Date: 2014/12/31

Conestoga-Rovers and Associates Ltd
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340

RESULTS OF ANALYSES OF WATER

Maxxam ID		YX9106			YX9107	YX9107	YX9108	YX9109		
Sampling Date		2014/12/18			2014/12/18	2014/12/18	2014/12/18	2014/12/18		
COC Number		B 100254			B 100254	B 100254	B 100254	B 100254		
	Units	SW-5 Lab-Dup	RDL	QC Batch	SW-6A	SW-6A Lab-Dup	SW-9	SW-2AD	RDL	QC Batch

Calculated Parameters

Anion Sum	me/L		N/A	3865872	0.110		0.140	0.110	N/A	3865872
Bicarb. Alkalinity (calc. as CaCO3)	mg/L		1.0	3865868	<1.0		<1.0	<1.0	1.0	3865868
Calculated TDS	mg/L		1.0	3865865	11		12	10	1.0	3865865
Carb. Alkalinity (calc. as CaCO3)	mg/L		1.0	3865868	<1.0		<1.0	<1.0	1.0	3865868
Cation Sum	me/L		N/A	3865872	0.190		0.230	0.180	N/A	3865872
Hardness (CaCO3)	mg/L		1.0	3865870	3.5		4.1	2.8	1.0	3865870
Ion Balance (% Difference)	%		N/A	3865871	26.7		24.3	24.1	N/A	3865871
Langelier Index (@ 20C)	N/A			3865863	NC		NC	NC		3865863
Langelier Index (@ 4C)	N/A			3865864	NC		NC	NC		3865864
Nitrate (N)	mg/L	0.050	3865873	<0.050			<0.050	<0.050	0.050	3865873
Saturation pH (@ 20C)	N/A		3865863	NC			NC	NC		3865863
Saturation pH (@ 4C)	N/A		3865864	NC			NC	NC		3865864

Inorganics

Total Alkalinity (Total as CaCO3)	mg/L	5.0	3872171	<5.0		<5.0	<5.0	5.0	3872171	
Dissolved Chloride (Cl)	mg/L	1.0	3872174	3.8		4.8	3.8	1.0	3872174	
Colour	TCU	5.0	3872177	87		110	100	25	3872177	
Nitrate + Nitrite	mg/L	0.050	3872180	<0.050		<0.050	<0.050	0.050	3872180	
Nitrite (N)	mg/L	0.010	3872181	<0.010		<0.010	<0.010	0.010	3872181	
Nitrogen (Ammonia Nitrogen)	mg/L	0.050	3872510	<0.050	<0.050	<0.050	<0.050	0.050	3872510	
Total Organic Carbon (C)	mg/L	0.50	3873222	8.1		8.9	9.1	0.50	3873222	
Orthophosphate (P)	mg/L	0.010	3872178	<0.010		<0.010	<0.010	0.010	3872178	
pH	pH	N/A	3872971	5.13	4.97	5.06	4.75	N/A	3872971	
Reactive Silica (SiO2)	mg/L	0.50	3872176	2.8		2.4	2.7	0.50	3872176	
Dissolved Sulphate (SO4)	mg/L	2.0	3872175	<2.0		<2.0	<2.0	2.0	3872175	
Turbidity	NTU	6.1	0.10	3873217	0.42		0.49	0.23	0.10	3873221
Conductivity	uS/cm		1.0	3872972	24	24	27	25	1.0	3872972

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Lab-Dup = Laboratory Initiated Duplicate

N/A = Not Applicable

Maxxam Job #: B4O0693
 Report Date: 2014/12/31

Conestoga-Rovers and Associates Ltd
 Client Project #: 088664-05
 Site Location: ATLANTIC GOLD-BEAVER DAM
 Your P.O. #: 20-019340

MERCURY BY COLD VAPOUR AA (WATER)

Maxxam ID		YX9103	YX9104	YX9105	YX9106	YX9107	YX9108	YX9109		
Sampling Date		2014/12/18	2014/12/18	2014/12/18	2014/12/18	2014/12/18	2014/12/18	2014/12/18		
COC Number		B 100254								
	Units	SW-1	SW-2A	SW-4A	SW-5	SW-6A	SW-9	SW-2AD	RDL	QC Batch
Metals										
Total Mercury (Hg)	ug/L	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	0.013	3868558
RDL = Reportable Detection Limit										
QC Batch = Quality Control Batch										

Maxxam Job #: B4O0693
Report Date: 2014/12/31

Conestoga-Rovers and Associates Ltd
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340

ELEMENTS BY ICP/MS (WATER)

Maxxam ID		YX9103	YX9104	YX9105	YX9106	YX9107	YX9108	YX9109		
Sampling Date		2014/12/18	2014/12/18	2014/12/18	2014/12/18	2014/12/18	2014/12/18	2014/12/18		
COC Number		B 100254								
Units	SW-1	SW-2A	SW-4A	SW-5	SW-6A	SW-9	SW-2AD	RDL	QC Batch	
Metals										
Total Aluminum (Al)	ug/L	220	210	220	460	240	310	210	5.0	3868017
Total Antimony (Sb)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	3868017
Total Arsenic (As)	ug/L	1.3	<1.0	2.0	17	1.1	<1.0	<1.0	1.0	3868017
Total Barium (Ba)	ug/L	3.1	3.2	3.2	6.1	3.1	3.5	3.0	1.0	3868017
Total Beryllium (Be)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	3868017
Total Bismuth (Bi)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	3868017
Total Boron (B)	ug/L	<50	<50	<50	<50	<50	<50	<50	50	3868017
Total Cadmium (Cd)	ug/L	0.023	0.017	0.044	0.010	0.014	0.019	0.017	0.010	3868017
Total Calcium (Ca)	ug/L	780	640	810	3000	790	890	590	100	3868017
Total Chromium (Cr)	ug/L	<1.0	<1.0	<1.0	1.1	1.3	<1.0	<1.0	1.0	3868017
Total Cobalt (Co)	ug/L	<0.40	<0.40	<0.40	<0.40	<0.40	<0.40	<0.40	0.40	3868017
Total Copper (Cu)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	3868017
Total Iron (Fe)	ug/L	330	360	320	730	330	280	350	50	3868017
Total Lead (Pb)	ug/L	<0.50	<0.50	<0.50	0.57	<0.50	<0.50	<0.50	0.50	3868017
Total Magnesium (Mg)	ug/L	330	320	350	640	360	450	310	100	3868017
Total Manganese (Mn)	ug/L	41	43	41	25	39	51	42	2.0	3868017
Total Molybdenum (Mo)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	3868017
Total Nickel (Ni)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	3868017
Total Phosphorus (P)	ug/L	<100	<100	<100	<100	<100	<100	<100	100	3868017
Total Potassium (K)	ug/L	380	370	480	720	300	340	340	100	3868017
Total Selenium (Se)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	3868017
Total Silver (Ag)	ug/L	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	0.10	3868017
Total Sodium (Na)	ug/L	2100	2100	2300	2200	2200	2900	2000	100	3868017
Total Strontium (Sr)	ug/L	5.8	5.6	5.7	15	5.9	5.0	5.2	2.0	3868017
Total Thallium (Tl)	ug/L	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	0.10	3868017
Total Tin (Sn)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	3868017
Total Titanium (Ti)	ug/L	3.3	2.6	2.3	14	2.8	3.5	2.6	2.0	3868017
Total Uranium (U)	ug/L	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	0.10	3868017
Total Vanadium (V)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	3868017
Total Zinc (Zn)	ug/L	7.8	5.5	12	<5.0	<5.0	<5.0	5.0	5.0	3868017

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Maxxam Job #: B4O0693
Report Date: 2014/12/31

Conestoga-Rovers and Associates Ltd
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340

GENERAL COMMENTS

Each temperature is the average of up to three cooler temperatures taken at receipt

Package 1	5.0°C
-----------	-------

Sample YX9103-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample YX9104-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample YX9105-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample YX9107-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample YX9108-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample YX9109-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Results relate only to the items tested.

QUALITY ASSURANCE REPORT

QC Batch	Parameter	Date	Matrix Spike		Spiked Blank		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	Units	Value (%)	QC Limits	% Recovery	QC Limits
3868017	Total Aluminum (Al)	2014/12/23	103	80 - 120	103	80 - 120	<5.0	ug/L	0.22 (1)	20		
3868017	Total Antimony (Sb)	2014/12/23	106	80 - 120	105	80 - 120	<1.0	ug/L	NC (1)	20		
3868017	Total Arsenic (As)	2014/12/23	99	80 - 120	99	80 - 120	<1.0	ug/L	NC (1)	20		
3868017	Total Barium (Ba)	2014/12/23	97	80 - 120	98	80 - 120	<1.0	ug/L	NC (1)	20		
3868017	Total Beryllium (Be)	2014/12/23	102	80 - 120	102	80 - 120	<1.0	ug/L	NC (1)	20		
3868017	Total Bismuth (Bi)	2014/12/23	104	80 - 120	105	80 - 120	<2.0	ug/L	NC (1)	20		
3868017	Total Boron (B)	2014/12/23	100	80 - 120	101	80 - 120	<50	ug/L	NC (1)	20		
3868017	Total Cadmium (Cd)	2014/12/23	99	80 - 120	99	80 - 120	<0.010	ug/L	NC (1)	20		
3868017	Total Calcium (Ca)	2014/12/23	NC	80 - 120	95	80 - 120	<100	ug/L	3.3 (1)	20		
3868017	Total Chromium (Cr)	2014/12/23	96	80 - 120	98	80 - 120	<1.0	ug/L	3.5 (1)	20		
3868017	Total Cobalt (Co)	2014/12/23	97	80 - 120	98	80 - 120	<0.40	ug/L	NC (1)	20		
3868017	Total Copper (Cu)	2014/12/23	95	80 - 120	97	80 - 120	<2.0	ug/L	NC (1)	20		
3868017	Total Iron (Fe)	2014/12/23	104	80 - 120	106	80 - 120	<50	ug/L	0.82 (1)	20		
3868017	Total Lead (Pb)	2014/12/23	98	80 - 120	99	80 - 120	<0.50	ug/L	23 (2,1)	20		
3868017	Total Magnesium (Mg)	2014/12/23	103	80 - 120	105	80 - 120	<100	ug/L	2.0 (1)	20		
3868017	Total Manganese (Mn)	2014/12/23	102	80 - 120	104	80 - 120	<2.0	ug/L	NC (1)	20		
3868017	Total Molybdenum (Mo)	2014/12/23	NC	80 - 120	103	80 - 120	<2.0	ug/L	NC (1)	20		
3868017	Total Nickel (Ni)	2014/12/23	98	80 - 120	101	80 - 120	<2.0	ug/L	NC (1)	20		
3868017	Total Phosphorus (P)	2014/12/23	108	80 - 120	107	80 - 120	<100	ug/L	NC (1)	20		
3868017	Total Potassium (K)	2014/12/23	103	80 - 120	105	80 - 120	<100	ug/L	1.2 (1)	20		
3868017	Total Selenium (Se)	2014/12/23	97	80 - 120	95	80 - 120	<1.0	ug/L	NC (1)	20		
3868017	Total Silver (Ag)	2014/12/23	100	80 - 120	100	80 - 120	<0.10	ug/L	NC (1)	20		
3868017	Total Sodium (Na)	2014/12/23	99	80 - 120	103	80 - 120	<100	ug/L	2.9 (1)	20		
3868017	Total Strontium (Sr)	2014/12/23	96	80 - 120	102	80 - 120	<2.0	ug/L	7.0 (1)	20		
3868017	Total Thallium (Tl)	2014/12/23	104	80 - 120	104	80 - 120	<0.10	ug/L	NC (1)	20		
3868017	Total Tin (Sn)	2014/12/23	105	80 - 120	105	80 - 120	<2.0	ug/L	NC (1)	20		
3868017	Total Titanium (Ti)	2014/12/23	101	80 - 120	102	80 - 120	<2.0	ug/L	NC (1)	20		
3868017	Total Uranium (U)	2014/12/23	107	80 - 120	105	80 - 120	<0.10	ug/L	NC (1)	20		
3868017	Total Vanadium (V)	2014/12/23	98	80 - 120	99	80 - 120	<2.0	ug/L	NC (1)	20		
3868017	Total Zinc (Zn)	2014/12/23	99	80 - 120	100	80 - 120	<5.0	ug/L	2.8 (1)	20		
3868017	Total Mercury (Hg)	2014/12/22	100	80 - 120	99	80 - 120	<0.013	ug/L	NC (1)	20		
3872171	Total Alkalinity (Total as CaCO ₃)	2014/12/29	102 (3)	80 - 120	105	80 - 120	<5.0	mg/L	NC (4)	25		

QUALITY ASSURANCE REPORT(CONT'D)

Conestoga-Rovers and Associates Ltd

Client Project #: 088664-05

Site Location: ATLANTIC GOLD-BEAVER DAM

Your P.O. #: 20-019340

QC Batch	Parameter	Date	Matrix Spike		Spiked Blank		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	Units	Value (%)	QC Limits	% Recovery	QC Limits
3872174	Dissolved Chloride (Cl)	2014/12/30	100 (3)	80 - 120	98	80 - 120	<1.0	mg/L	NC (4)	25	103	80 - 120
3872175	Dissolved Sulphate (SO4)	2014/12/30	86 (3)	80 - 120	92	80 - 120	<2.0	mg/L	NC (4)	25		
3872176	Reactive Silica (SiO2)	2014/12/29	104 (3)	80 - 120	104	80 - 120	<0.50	mg/L	1.1 (4)	25		
3872177	Colour	2014/12/30			97	80 - 120	<5.0	TCU	NC (4)	25		
3872178	Orthophosphate (P)	2014/12/31	96 (3)	80 - 120	99	80 - 120	<0.010	mg/L	NC (4)	25		
3872180	Nitrate + Nitrite	2014/12/30	99 (3)	80 - 120	95	80 - 120	0.051, RDL=0.050	mg/L	NC (4)	25		
3872181	Nitrite (N)	2014/12/30	91 (3)	80 - 120	113	80 - 120	<0.010	mg/L	NC (4)	25		
3872510	Nitrogen (Ammonia Nitrogen)	2014/12/29	96 (5)	80 - 120	100	80 - 120	<0.050	mg/L	NC (6)	25		
3872971	pH	2014/12/30							3.3 (6)	N/A	100	97 - 103
3872972	Conductivity	2014/12/30			100	80 - 120	1.5, RDL=1.0	uS/cm	0.40 (6)	25		
3873217	Turbidity	2014/12/30					<0.10	NTU	2.4 (7)	25	96	80 - 120
3873221	Turbidity	2014/12/30					<0.10	NTU	NC (1)	25	95	80 - 120
3873222	Total Organic Carbon (C)	2014/12/30	100	80 - 120	99	80 - 120	<0.50	mg/L	NC (1)	20		

N/A = Not Applicable

Duplicate: Paired analysis of a separate portion of the same sample. Used to evaluate the variance in the measurement.

Matrix Spike: A sample to which a known amount of the analyte of interest has been added. Used to evaluate sample matrix interference.

QC Standard: A sample of known concentration prepared by an external agency under stringent conditions. Used as an independent check of method accuracy.

Spiked Blank: A blank matrix sample to which a known amount of the analyte, usually from a second source, has been added. Used to evaluate method accuracy.

Method Blank: A blank matrix containing all reagents used in the analytical procedure. Used to identify laboratory contamination.

NC (Matrix Spike): The recovery in the matrix spike was not calculated. The relative difference between the concentration in the parent sample and the spiked amount was too small to permit a reliable recovery calculation (matrix spike concentration was less than 2x that of the native sample concentration).

NC (Duplicate RPD): The duplicate RPD was not calculated. The concentration in the sample and/or duplicate was too low to permit a reliable RPD calculation (one or both samples < 5x RDL).

(1) Duplicate Parent ID

(2) Poor RPD due to sample inhomogeneity. < 10 % of compounds in multi-component analysis in violation.

(3) Matrix Spike Parent ID [YX9103-01]

(4) Duplicate Parent ID [YX9103-01]

(5) Matrix Spike Parent ID [YX9107-01]

(6) Duplicate Parent ID [YX9107-01]

(7) Duplicate Parent ID [YX9106-01]

Maxxam Job #: B4O0693
Report Date: 2014/12/31

Conestoga-Rovers and Associates Ltd
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340

VALIDATION SIGNATURE PAGE

The analytical data and all QC contained in this report were reviewed and validated by the following individual(s).

<Original signed by>

Mike MacGillivray, Scientific Specialist (Inorganics)

Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(E), signing the reports. For Service Group specific validation please refer to the Validation Signature Page.



200 Bluewater Road, Suite 105, Bedford, Nova Scotia B4B 1G9
 49 Elizabeth Ave., St John's, NL A1A 1W9
 90 Esplanade Sydney, NS B1P 1A1
www.maxxamanalytics.com E-mail: Clientservicesbedford@maxxamanalytics.com

MAXXAM Chain of Custody Record

COC #: B 100254

Page 1 of 1

This column for lab use only:

Client Code 16276

Maxxam Job #

B400693

Cooler ID	Seal Present	Seal Intact	Temp 1	Temp 2	Temp 3	Average Temp
-----------	--------------	-------------	--------	--------	--------	--------------

456

Integrity YES NO Integrity / Checklist by SM

Labelled by Location / Bin # 4



B400693

INVOICE INFORMATION:

Company Name: CRA

Contact Name: Jeff Parks

Address: Dartmouth, NS
Postal Code B3B 1J7

Email: jparks@crawford.com

Ph: 468-1248 Fax: 468-2207

Guideline Requirements / Detection Limits / Special Instructions

CCME FWAL

*Specify Matrix: Surface/Salt/Ground/Tapwater/Sewage/Effluent/
Potable/NonPotable/Tissue/Soil/Sludge/Metal/Seawater

Field Sample Identification	Matrix*	Date/Time Sampled	# & type of bottles	Field Filtered & Preserved	Lab Filtration Required	RCAP-30	Choose Total or Diss Metals	RCAP-MS	Choose Total or Diss Metals	Fax:	Metals Water	Metals Soil	Hydrocarbons
						XSD	X100	X200	X	Total Digest Method (for well water, surface water) for ground water	Mercury Dissolved	Mercury	Metals & Mercury Default Available Digest Method (for Ocean sediments) (HNO3/HF/HClO4)
1 SW -1	SW	18 Dec 14	1 XSD 1 X100 1 X200	X		X			X				Selenium (Low level) Residential Parklands, Agricultural Hot Water soluble Boron (required for CCME Agricultural)
2 SW -2A						X		X	X				RBCA Hydrocarbons (BTEX, C6-C32)
3 SW -4A						X		X	X				Hydrocarbons Soil (Portable) NS Fuel Oil Spill Policy Low Level BTEX, C6-C32
4 SW -5						X		X	X				NB Portable Water BTEX, VPH, Low level T.E.H.
5 SW -6A						X		X	X				TPH Fractionation
6 SW -9						X		X	X				PAHs
7 SW -2AD						X		X	X				PAHs with Acridine, Quinoline
8													
9													
10													

RELINQUISHED BY: (Signature/Print)

<Original signed by>

A Facey 19 Dec 14

RECEIVED BY: (Signature/Print)

<Original signed by>

Joe S. 19 Dec 19 10:18
SARA LUNSON

White: Maxxam

Yellow : Mail

Pink: Client

ATL FCD 00149 / Revision 10

Your P.O. #: 20-019340
 Your Project #: 088664-05
 Site Location: ATLANTIC GOLD-BEAVER DAM
 Your C.O.C. #: B 100261

Attention:Jeff Parks

Conestoga-Rovers and Associates Ltd
 45 Akerley Blvd
 Dartmouth , NS
 B3B 1J7

Report Date: 2015/01/30
 Report #: R3317426
 Version: 1 - Final

CERTIFICATE OF ANALYSIS

MAXXAM JOB #: B513234

Received: 2015/01/23, 09:47

Sample Matrix: Water
 # Samples Received: 6

Analyses	Quantity	Date Extracted	Date Analyzed	Laboratory Method	Reference
Carbonate, Bicarbonate and Hydroxide	6	N/A	2015/01/29	N/A	SM 22 4500-CO2 D
Alkalinity	6	N/A	2015/01/28	ATL SOP 00013	EPA 310.2 R1974 m
Chloride	6	N/A	2015/01/29	ATL SOP 00014	SM 22 4500-Cl- E m
Colour	6	N/A	2015/01/28	ATL SOP 00020	SM 22 2120C m
Conductance - water	6	N/A	2015/01/28	ATL SOP 00004	SM 22 2510B m
Hardness (calculated as CaCO ₃)	6	N/A	2015/01/29	ATL SOP 00048	SM 22 2340 B
Mercury - Total (CVAA,LL)	6	2015/01/30	2015/01/30	ATL SOP 00026	EPA 245.1 R3 m
Metals Water Total MS (1)	6	2015/01/28	2015/01/28	ATL SOP 00058	EPA 6020A R1 m
Ion Balance (% Difference)	6	N/A	2015/01/29		Auto Calc.
Anion and Cation Sum	6	N/A	2015/01/29		Auto Calc.
Nitrogen Ammonia - water	6	N/A	2015/01/28	ATL SOP 00015	EPA 350.1 R2 m
Nitrogen - Nitrate + Nitrite	6	N/A	2015/01/29	ATL SOP 00016	USGS SOPINCF0452.2 m
Nitrogen - Nitrite	6	N/A	2015/01/28	ATL SOP 00017	SM 22 4500-NO2- B m
Nitrogen - Nitrate (as N)	6	N/A	2015/01/29	ATL SOP 00018	ASTM D3867
pH (2)	6	N/A	2015/01/28	ATL SOP 00003	SM 22 4500-H+ B m
Phosphorus - ortho	6	N/A	2015/01/28	ATL SOP 00021	EPA 365.2 m
Sat. pH and Langelier Index (@ 20C)	6	N/A	2015/01/29	ATL SOP 00049	Auto Calc.
Sat. pH and Langelier Index (@ 4C)	6	N/A	2015/01/29	ATL SOP 00049	Auto Calc.
Reactive Silica	6	N/A	2015/01/28	ATL SOP 00022	EPA 366.0 m
Sulphate	6	N/A	2015/01/28	ATL SOP 00023	EPA 375.4 R1978 m
Total Dissolved Solids (TDS calc)	6	N/A	2015/01/29		Auto Calc.
Organic carbon - Total (TOC) (3)	6	N/A	2015/01/28	ATL SOP 00037	SM 22 5310C m
Turbidity	6	N/A	2015/01/29	ATL SOP 00011	EPA 180.1 R2 m

* RPDs calculated using raw data. The rounding of final results may result in the apparent difference.

(1) New RDLs in effect due to release of NS Contaminated Sites Regulations. Reduced RDL based on MDL study performance. Low level analytical run checks being implemented.

(2) The APHA Standard Method require pH to be analyzed within 15 minutes of sampling and therefore field analysis is required for compliance. All Laboratory pH analyses in this report are reported past the APHA Standard Method holding time.

(3) TOC / DOC present in the sample should be considered as non-purgeable TOC / DOC.

Your P.O. #: 20-019340
Your Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your C.O.C. #: B 100261

Attention:Jeff Parks

Conestoga-Rovers and Associates Ltd
45 Akerley Blvd
Dartmouth , NS
B3B 1J7

Report Date: 2015/01/30
Report #: R3317426
Version: 1 - Final

CERTIFICATE OF ANALYSIS

MAXXAM JOB #: B513234

Received: 2015/01/23, 09:47

Encryption Key *<Original
signed bv>* Rachael Mansfield
 30 Jan 2015 17:01:58 -04:00

Please direct all questions regarding this Certificate of Analysis to your Project Manager.

Michelle Hill, Project Manager

Email: MHill@maxxam.ca

Phone# (902)420-0203 Ext:289

=====

Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(E), signing the reports. For Service Group specific validation please refer to the Validation Signature Page.

Maxxam Job #: B513234
Report Date: 2015/01/30

Conestoga-Rovers and Associates Ltd
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340
Sampler Initials: AF

RESULTS OF ANALYSES OF WATER

Maxxam ID		ZG7131	ZG7132		ZG7133		ZG7134	ZG7135		
Sampling Date		2015/01/22	2015/01/22		2015/01/22		2015/01/22	2015/01/22		
COC Number		B 100261	B 100261		B 100261		B 100261	B 100261		
	Units	SW-1	SW-2A	RDL	QC Batch	SW-5	RDL	SW-6A	SW-9	RDL QC Batch

Calculated Parameters											
Anion Sum	me/L	0.120	0.130	N/A	3895941	0.400	N/A	0.120	0.180	N/A	3895941
Bicarb. Alkalinity (calc. as CaCO ₃)	mg/L	<1.0	<1.0	1.0	3895938	8.0	1.0	<1.0	<1.0	1.0	3895938
Calculated TDS	mg/L	12	13	1.0	3895946	27	1.0	12	16	1.0	3895946
Carb. Alkalinity (calc. as CaCO ₃)	mg/L	<1.0	<1.0	1.0	3895938	<1.0	1.0	<1.0	<1.0	1.0	3895938
Cation Sum	me/L	0.210	0.210	N/A	3895941	0.430	N/A	0.210	0.290	N/A	3895941
Hardness (CaCO ₃)	mg/L	3.5	3.4	1.0	3895939	14	1.0	3.9	5.0	1.0	3895939
Ion Balance (% Difference)	%	27.3	23.5	N/A	3895940	3.61	N/A	27.3	23.4	N/A	3895940
Langelier Index (@ 20C)	N/A	NC	NC		3895944	-3.17		NC	NC		3895944
Langelier Index (@ 4C)	N/A	NC	NC		3895945	-3.42		NC	NC		3895945
Nitrate (N)	mg/L	0.087	0.079	0.050	3895942	0.096	0.050	<0.050	0.051	0.050	3895942
Saturation pH (@ 20C)	N/A	NC	NC		3895944	9.77		NC	NC		3895944
Saturation pH (@ 4C)	N/A	NC	NC		3895945	10.0		NC	NC		3895945
Inorganics											
Total Alkalinity (Total as CaCO ₃)	mg/L	<5.0	<5.0	5.0	3898008	8.0	5.0	<5.0	<5.0	5.0	3898008
Dissolved Chloride (Cl)	mg/L	4.0	4.2	1.0	3898009	5.0	1.0	4.2	6.2	1.0	3898009
Colour	TCU	83	110	25	3898012	23	5.0	82	73	25	3898012
Nitrate + Nitrite	mg/L	0.087	0.079	0.050	3898014	0.096	0.050	<0.050	0.051	0.050	3898014
Nitrite (N)	mg/L	<0.010	<0.010	0.010	3898015	<0.010	0.010	<0.010	<0.010	0.010	3898015
Nitrogen (Ammonia Nitrogen)	mg/L	<0.050	<0.050	0.050	3898401	<0.050	0.050	<0.050	<0.050	0.050	3898402
Total Organic Carbon (C)	mg/L	7.0	7.4	0.50	3900707	3.1	0.50	8.9	7.0	0.50	3900707
Orthophosphate (P)	mg/L	<0.010	<0.010	0.010	3898013	<0.010	0.010	<0.010	<0.010	0.010	3898013
pH	pH	4.87	4.75	N/A	3900512	6.60	N/A	5.09	5.44	N/A	3900512
Reactive Silica (SiO ₂)	mg/L	3.8	3.7	0.50	3898011	3.1	0.50	3.4	3.5	0.50	3898011
Dissolved Sulphate (SO ₄)	mg/L	<2.0	<2.0	2.0	3898010	4.4	2.0	<2.0	<2.0	2.0	3898010
Turbidity	NTU	0.62	0.70	0.10	3902044	2.4	0.10	0.44	0.77	0.10	3902044
Conductivity	uS/cm	27	28	1.0	3900514	45	1.0	25	32	1.0	3900514

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

N/A = Not Applicable

Maxxam Job #: B513234
Report Date: 2015/01/30

Conestoga-Rovers and Associates Ltd
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340
Sampler Initials: AF

RESULTS OF ANALYSES OF WATER

Maxxam ID		ZG7135	ZG7136		
Sampling Date		2015/01/22	2015/01/22		
COC Number		B 100261	B 100261		
	Units	SW-9 Lab-Dup	SW-1D	RDL	QC Batch
Calculated Parameters					
Anion Sum	me/L		0.120	N/A	3895941
Bicarb. Alkalinity (calc. as CaCO ₃)	mg/L		<1.0	1.0	3895938
Calculated TDS	mg/L		13	1.0	3895946
Carb. Alkalinity (calc. as CaCO ₃)	mg/L		<1.0	1.0	3895938
Cation Sum	me/L		0.210	N/A	3895941
Hardness (CaCO ₃)	mg/L		3.5	1.0	3895939
Ion Balance (% Difference)	%		27.3	N/A	3895940
Langelier Index (@ 20C)	N/A		NC		3895944
Langelier Index (@ 4C)	N/A		NC		3895945
Nitrate (N)	mg/L		0.080	0.050	3895942
Saturation pH (@ 20C)	N/A		NC		3895944
Saturation pH (@ 4C)	N/A		NC		3895945
Inorganics					
Total Alkalinity (Total as CaCO ₃)	mg/L		<5.0	5.0	3898008
Dissolved Chloride (Cl)	mg/L		4.2	1.0	3898009
Colour	TCU		100	25	3898012
Nitrate + Nitrite	mg/L		0.080	0.050	3898014
Nitrite (N)	mg/L		<0.010	0.010	3898015
Nitrogen (Ammonia Nitrogen)	mg/L		<0.050	0.050	3898402
Total Organic Carbon (C)	mg/L	7.3	7.5	0.50	3900707
Orthophosphate (P)	mg/L		<0.010	0.010	3898013
pH	pH		4.91	N/A	3900512
Reactive Silica (SiO ₂)	mg/L		4.0	0.50	3898011
Dissolved Sulphate (SO ₄)	mg/L		<2.0	2.0	3898010
Turbidity	NTU	0.80	0.69	0.10	3902044
Conductivity	uS/cm		27	1.0	3900514
RDL = Reportable Detection Limit					
QC Batch = Quality Control Batch					
Lab-Dup = Laboratory Initiated Duplicate					
N/A = Not Applicable					

Maxxam Job #: B513234
Report Date: 2015/01/30

Conestoga-Rovers and Associates Ltd
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340
Sampler Initials: AF

MERCURY BY COLD VAPOUR AA (WATER)

Maxxam ID	ZG7131	ZG7132	ZG7133	ZG7134	ZG7135	ZG7136			
Sampling Date	2015/01/22	2015/01/22	2015/01/22	2015/01/22	2015/01/22	2015/01/22			
COC Number	B 100261	B 100261	B 100261	B 100261	B 100261	B 100261			
	Units	SW-1	SW-2A	SW-5	SW-6A	SW-9	SW-1D	RDL	
Metals									
Total Mercury (Hg)	ug/L	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	0.013	3903361
RDL = Reportable Detection Limit									
QC Batch = Quality Control Batch									

Maxxam Job #: B513234
Report Date: 2015/01/30

Conestoga-Rovers and Associates Ltd
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340
Sampler Initials: AF

ELEMENTS BY ICP/MS (WATER)

Maxxam ID		ZG7131	ZG7132	ZG7133	ZG7134	ZG7135	ZG7136		
Sampling Date		2015/01/22	2015/01/22	2015/01/22	2015/01/22	2015/01/22	2015/01/22		
COC Number		B 100261							
	Units	SW-1	SW-2A	SW-5	SW-6A	SW-9	SW-1D	RDL	QC Batch
Metals									
Total Aluminum (Al)	ug/L	200	210	210	250	210	200	5.0	3898143
Total Antimony (Sb)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	3898143
Total Arsenic (As)	ug/L	<1.0	<1.0	22	1.0	<1.0	<1.0	1.0	3898143
Total Barium (Ba)	ug/L	3.3	3.3	6.1	3.0	3.4	3.4	1.0	3898143
Total Beryllium (Be)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	3898143
Total Bismuth (Bi)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	3898143
Total Boron (B)	ug/L	<50	<50	<50	<50	<50	<50	50	3898143
Total Cadmium (Cd)	ug/L	0.012	0.013	0.011	0.011	0.010	0.022	0.010	3898143
Total Calcium (Ca)	ug/L	720	680	4100	880	1100	740	100	3898143
Total Chromium (Cr)	ug/L	1.6	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	3898143
Total Cobalt (Co)	ug/L	<0.40	<0.40	0.44	<0.40	<0.40	<0.40	0.40	3898143
Total Copper (Cu)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	3898143
Total Iron (Fe)	ug/L	350	340	680	380	290	340	50	3898143
Total Lead (Pb)	ug/L	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	0.50	3898143
Total Magnesium (Mg)	ug/L	400	410	780	410	530	410	100	3898143
Total Manganese (Mn)	ug/L	51	51	150	46	51	53	2.0	3898143
Total Molybdenum (Mo)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	3898143
Total Nickel (Ni)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	2.6	2.0	3898143
Total Phosphorus (P)	ug/L	<100	<100	<100	<100	<100	<100	100	3898143
Total Potassium (K)	ug/L	380	380	740	300	350	370	100	3898143
Total Selenium (Se)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	3898143
Total Silver (Ag)	ug/L	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	0.10	3898143
Total Sodium (Na)	ug/L	2300	2400	2700	2300	3900	2400	100	3898143
Total Strontium (Sr)	ug/L	6.3	6.6	21	6.1	5.6	6.6	2.0	3898143
Total Thallium (Tl)	ug/L	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	0.10	3898143
Total Tin (Sn)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	3898143
Total Titanium (Ti)	ug/L	2.4	2.2	4.2	2.6	2.8	2.2	2.0	3898143
Total Uranium (U)	ug/L	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	0.10	3898143
Total Vanadium (V)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	3898143
Total Zinc (Zn)	ug/L	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	5.0	3898143

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Maxxam Job #: B513234
Report Date: 2015/01/30

Conestoga-Rovers and Associates Ltd
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340
Sampler Initials: AF

GENERAL COMMENTS

Each temperature is the average of up to three cooler temperatures taken at receipt

Package 1	4.3°C
-----------	-------

Sample SW-4A was not received.

Sample ZG7131-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample ZG7132-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample ZG7133-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample ZG7134-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample ZG7135-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample ZG7136-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Results relate only to the items tested.

QUALITY ASSURANCE REPORT

Conestoga-Rovers and Associates Ltd

Client Project #: 088664-05

Site Location: ATLANTIC GOLD-BEAVER DAM

Your P.O. #: 20-019340

Sampler Initials: AF

QC Batch	Parameter	Date	Matrix Spike		Spiked Blank		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	Units	Value (%)	QC Limits	% Recovery	QC Limits
3898008	Total Alkalinity (Total as CaCO ₃)	2015/01/28	NC	80 - 120	102	80 - 120	<5.0	mg/L	0.10 (1)	25		
3898009	Dissolved Chloride (Cl)	2015/01/29	NC	80 - 120	99	80 - 120	<1.0	mg/L	0.51 (1)	25	106	80 - 120
3898010	Dissolved Sulphate (SO ₄)	2015/01/28	89	80 - 120	89	80 - 120	<2.0	mg/L	NC (1)	25		
3898011	Reactive Silica (SiO ₂)	2015/01/28	NC	80 - 120	105	80 - 120	<0.50	mg/L	1.5 (1)	25		
3898012	Colour	2015/01/28			99	80 - 120	<5.0	TCU	NC (1)	25		
3898013	Orthophosphate (P)	2015/01/28	95	80 - 120	99	80 - 120	<0.010	mg/L	NC (1)	25		
3898014	Nitrate + Nitrite	2015/01/29	93	80 - 120	96	80 - 120	<0.050	mg/L	NC (1)	25		
3898015	Nitrite (N)	2015/01/28	95	80 - 120	92	80 - 120	<0.010	mg/L	NC (1)	25		
3898143	Total Aluminum (Al)	2015/01/28	107	80 - 120	106	80 - 120	<5.0	ug/L	2.8 (1)	20		
3898143	Total Antimony (Sb)	2015/01/28	112	80 - 120	108	80 - 120	<1.0	ug/L				
3898143	Total Arsenic (As)	2015/01/28	101	80 - 120	101	80 - 120	<1.0	ug/L				
3898143	Total Barium (Ba)	2015/01/28	NC	80 - 120	100	80 - 120	<1.0	ug/L				
3898143	Total Beryllium (Be)	2015/01/28	100	80 - 120	99	80 - 120	<1.0	ug/L				
3898143	Total Bismuth (Bi)	2015/01/28	105	80 - 120	104	80 - 120	<2.0	ug/L				
3898143	Total Boron (B)	2015/01/28	98	80 - 120	96	80 - 120	<50	ug/L				
3898143	Total Cadmium (Cd)	2015/01/28	102	80 - 120	101	80 - 120	<0.010	ug/L				
3898143	Total Calcium (Ca)	2015/01/28	NC	80 - 120	98	80 - 120	<100	ug/L				
3898143	Total Chromium (Cr)	2015/01/28	99	80 - 120	100	80 - 120	<1.0	ug/L				
3898143	Total Cobalt (Co)	2015/01/28	99	80 - 120	100	80 - 120	<0.40	ug/L				
3898143	Total Copper (Cu)	2015/01/28	99	80 - 120	102	80 - 120	<2.0	ug/L				
3898143	Total Iron (Fe)	2015/01/28	NC	80 - 120	109	80 - 120	<50	ug/L				
3898143	Total Lead (Pb)	2015/01/28	102	80 - 120	101	80 - 120	<0.50	ug/L				
3898143	Total Magnesium (Mg)	2015/01/28	NC	80 - 120	109	80 - 120	<100	ug/L				
3898143	Total Manganese (Mn)	2015/01/28	102	80 - 120	103	80 - 120	<2.0	ug/L				
3898143	Total Molybdenum (Mo)	2015/01/28	112	80 - 120	110	80 - 120	<2.0	ug/L				
3898143	Total Nickel (Ni)	2015/01/28	101	80 - 120	103	80 - 120	<2.0	ug/L				
3898143	Total Phosphorus (P)	2015/01/28	114	80 - 120	113	80 - 120	<100	ug/L				
3898143	Total Potassium (K)	2015/01/28	112	80 - 120	112	80 - 120	<100	ug/L				
3898143	Total Selenium (Se)	2015/01/28	100	80 - 120	100	80 - 120	<1.0	ug/L				
3898143	Total Silver (Ag)	2015/01/28	107	80 - 120	104	80 - 120	<0.10	ug/L				
3898143	Total Sodium (Na)	2015/01/28	NC	80 - 120	107	80 - 120	<100	ug/L				

QUALITY ASSURANCE REPORT(CONT'D)

Conestoga-Rovers and Associates Ltd

Client Project #: 088664-05

Site Location: ATLANTIC GOLD-BEAVER DAM

Your P.O. #: 20-019340

Sampler Initials: AF

QC Batch	Parameter	Date	Matrix Spike		Spiked Blank		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	Units	Value (%)	QC Limits	% Recovery	QC Limits
3898143	Total Strontium (Sr)	2015/01/28	NC	80 - 120	103	80 - 120	<2.0	ug/L				
3898143	Total Thallium (Tl)	2015/01/28	106	80 - 120	104	80 - 120	<0.10	ug/L				
3898143	Total Tin (Sn)	2015/01/28	112	80 - 120	107	80 - 120	<2.0	ug/L				
3898143	Total Titanium (Ti)	2015/01/28	105	80 - 120	105	80 - 120	<2.0	ug/L				
3898143	Total Uranium (U)	2015/01/28	113	80 - 120	110	80 - 120	<0.10	ug/L				
3898143	Total Vanadium (V)	2015/01/28	100	80 - 120	102	80 - 120	<2.0	ug/L				
3898143	Total Zinc (Zn)	2015/01/28	100	80 - 120	102	80 - 120	<5.0	ug/L				
3898401	Nitrogen (Ammonia Nitrogen)	2015/01/28	100	80 - 120	102	80 - 120	<0.050	mg/L	NC (2,1)	25		
3898402	Nitrogen (Ammonia Nitrogen)	2015/01/28	99	80 - 120	99	80 - 120	<0.050	mg/L	NC (1)	25		
3900512	pH	2015/01/28							0 (1)	N/A	100	97 - 103
3900514	Conductivity	2015/01/28			99	80 - 120	1.2, RDL=1.0	uS/cm	0.84 (1)	25		
3900707	Total Organic Carbon (C)	2015/01/28	NC (3)	80 - 120	103	80 - 120	<0.50	mg/L	3.7 (4)	20		
3902044	Turbidity	2015/01/29					<0.10	NTU	3.8 (4)	25	101	80 - 120
3903361	Total Mercury (Hg)	2015/01/30	96	80 - 120	101	80 - 120	<0.013	ug/L	NC (1)	20		

N/A = Not Applicable

Duplicate: Paired analysis of a separate portion of the same sample. Used to evaluate the variance in the measurement.

Matrix Spike: A sample to which a known amount of the analyte of interest has been added. Used to evaluate sample matrix interference.

QC Standard: A sample of known concentration prepared by an external agency under stringent conditions. Used as an independent check of method accuracy.

Spiked Blank: A blank matrix sample to which a known amount of the analyte, usually from a second source, has been added. Used to evaluate method accuracy.

Method Blank: A blank matrix containing all reagents used in the analytical procedure. Used to identify laboratory contamination.

NC (Matrix Spike): The recovery in the matrix spike was not calculated. The relative difference between the concentration in the parent sample and the spiked amount was too small to permit a reliable recovery calculation (matrix spike concentration was less than 2x that of the native sample concentration).

NC (Duplicate RPD): The duplicate RPD was not calculated. The concentration in the sample and/or duplicate was too low to permit a reliable RPD calculation (one or both samples < 5x RDL).

(1) Duplicate Parent ID

(2) Duplicate results exceeded low level duplicate acceptance criteria. This may be due to sample heterogeneity.

(3) Matrix Spike Parent ID [ZG7135-01]

(4) Duplicate Parent ID [ZG7135-01]

Maxxam Job #: B513234
Report Date: 2015/01/30

Conestoga-Rovers and Associates Ltd
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340
Sampler Initials: AF

VALIDATION SIGNATURE PAGE

The analytical data and all QC contained in this report were reviewed and validated by the following individual(s).

<Original signed by>

Mike MacGillivray, Scientific Specialist (Inorganics)

Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(E), signing the reports. For Service Group specific validation please refer to the Validation Signature Page.

This column for lab use only:

Client Code **162776**

Maxxam Job #

B513234

Cooler ID	Seal Present	Seal Intact	Temp 1	Temp 2	Temp 3	Average Temp
						44.5

Integrity **YES** NO **SM**

Labelled by **8** Location / Bin #

INVOICE INFORMATION:

Company Name: **CRA**

Contact Name: **Jeff Parks**

Address: **Dartmouth, NS**

Postal Code **B3B 1J7**

Email: **j.parks@craworld.com**

Ph: **468-1248** Fax: **468-2207**

Guideline Requirements / Detection Limits / Special Instructions



*Specify N **B513234**

REPORT INFORMATION (if differs from invoice):

Company Name:

Contact Name:

Address:

Email:

Ph:

Postal Code

Fax:

Task Order #

Sampled by

AF + AD

MAXXAM Chain of Custody Record

COC #: **B 100261**

Page **1** of **1**

TURNAROUND TIME

Standard

10 day

If RUSH Specify Date:

Pre-schedule rush work

Charge for # Jars used but not submitted **-**

Field Sample Identification	Matrix*	Date/Time Sampled	# & type of bottles	Field Filtered & Preserved		Lab Filtration Required	Choose Total or Diss Metals	Choose Total or Diss Metals	Total Digest (Default Method)	Dissolved for well water, surface water	Dissolved for ground water	Mercury	Metals & Mercury	Metals Total Digest - for Ocean sediments (HNO3/HF/HClO4)	Mercury	Metals Soil	Hydrocarbons	
				RCAP-30	RCAP-MS													
1 SW-1	SW	22 Jan 15	1x 100, 50, 200	X	X							X						
2 SW-2A				X	X							X						
3 SW-4A				X	X							X						
4 SW-5				X	X							X						
5 SW-6A				X	X							X						
6 SW-9				X	X							X						
7 SW-1D				X	X							X						
8																		
9																		
10																		

RELINQUISHED BY: (Signature/Print)

<Original signed by>

A. Facy

23 Jan 15

Date

Time

RECEIVED BY: (Signature/Print)

<Original signed by>

Jae Poyt

Date

Time

White: Maxxam

Yellow : Mail

Pink: Client

ATL FCD 00149 / Revision 10

Your P.O. #: 20-019340
 Your Project #: 088664-05
 Site Location: ATLANTIC GOLD-BEAVER DAM
 Your C.O.C. #: B 100289

Attention:Jeff Parks

Conestoga-Rovers and Associates Ltd
 45 Akerley Blvd
 Dartmouth , NS
 B3B 1J7

Report Date: 2015/05/08
 Report #: R3419942
 Version: 1 - Final

CERTIFICATE OF ANALYSIS

MAXXAM JOB #: B579909

Received: 2015/05/01, 11:15

Sample Matrix: Water
 # Samples Received: 5

Analyses	Quantity	Date Extracted	Date Analyzed	Laboratory Method	Reference
Carbonate, Bicarbonate and Hydroxide	5	N/A	2015/05/06	N/A	SM 22 4500-CO2 D
Alkalinity	5	N/A	2015/05/05	ATL SOP 00013	EPA 310.2 R1974 m
Chloride	5	N/A	2015/05/06	ATL SOP 00014	SM 22 4500-Cl- E m
Colour	5	N/A	2015/05/06	ATL SOP 00020	SM 22 2120C m
Conductance - water	5	N/A	2015/05/05	ATL SOP 00004	SM 22 2510B m
Hardness (calculated as CaCO ₃)	5	N/A	2015/05/07	ATL SOP 00048	SM 22 2340 B
Mercury - Total (CVAA,LL)	4	2015/05/07	2015/05/07	ATL SOP 00026	EPA 245.1 R3 m
Metals Water Total MS (1)	5	2015/05/05	2015/05/06	ATL SOP 00058	EPA 6020A R1 m
Ion Balance (% Difference)	5	N/A	2015/05/07		Auto Calc.
Anion and Cation Sum	5	N/A	2015/05/07		Auto Calc.
Nitrogen Ammonia - water	5	N/A	2015/05/05	ATL SOP 00015	EPA 350.1 R2 m
Nitrogen - Nitrate + Nitrite	5	N/A	2015/05/07	ATL SOP 00016	USGS SOPINCF0452.2 m
Nitrogen - Nitrite	5	N/A	2015/05/05	ATL SOP 00017	SM 22 4500-NO2- B m
Nitrogen - Nitrate (as N)	5	N/A	2015/05/07	ATL SOP 00018	ASTM D3867
pH (2)	5	N/A	2015/05/05	ATL SOP 00003	SM 22 4500-H+ B m
Phosphorus - ortho	5	N/A	2015/05/06	ATL SOP 00021	EPA 365.2 m
Sat. pH and Langelier Index (@ 20C)	5	N/A	2015/05/07	ATL SOP 00049	Auto Calc.
Sat. pH and Langelier Index (@ 4C)	5	N/A	2015/05/07	ATL SOP 00049	Auto Calc.
Reactive Silica	5	N/A	2015/05/06	ATL SOP 00022	EPA 366.0 m
Sulphate	5	N/A	2015/05/06	ATL SOP 00023	EPA 375.4 R1978 m
Total Dissolved Solids (TDS calc)	5	N/A	2015/05/07		Auto Calc.
Organic carbon - Total (TOC) (3)	1	N/A	2015/05/06	ATL SOP 00037	SM 22 5310C m
Organic carbon - Total (TOC) (3)	4	N/A	2015/05/07	ATL SOP 00037	SM 22 5310C m
Turbidity	1	N/A	2015/05/06	ATL SOP 00011	EPA 180.1 R2 m
Turbidity	4	N/A	2015/05/08	ATL SOP 00011	EPA 180.1 R2 m

Reference Method suffix "m" indicates test methods incorporate validated modifications from specific reference methods to improve performance.

* RPDs calculated using raw data. The rounding of final results may result in the apparent difference.

(1) New RDLs in effect due to release of NS Contaminated Sites Regulations. Reduced RDL based on MDL study performance. Low level analytical run checks being implemented.

(2) The APHA Standard Method require pH to be analyzed within 15 minutes of sampling and therefore field analysis is required for compliance. All Laboratory pH analyses in this report are reported past the APHA Standard Method holding time.

(3) TOC / DOC present in the sample should be considered as non-purgeable TOC / DOC.

Your P.O. #: 20-019340
Your Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your C.O.C. #: B 100289

Attention:Jeff Parks

Conestoga-Rovers and Associates Ltd
45 Akerley Blvd
Dartmouth , NS
B3B 1J7

Report Date: 2015/05/08
Report #: R3419942
Version: 1 - Final

CERTIFICATE OF ANALYSIS

MAXXAM JOB #: B579909

Received: 2015/05/01, 11:15

Encryption Key <Original signed by>

Rachael Mansfield
08 May 2015 16:39:28 -03:00

Please direct all questions regarding this Certificate of Analysis to your Project Manager.

Michelle Hill, Project Manager

Email: M.Hill@maxxam.ca

Phone# (902)420-0203 Ex

Maxxam has procedures in place to guard against improper use of the electronic sign.

Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(L), signing the reports. For Service Group specific validation please refer to the Validation Signature Page.

Maxxam Job #: B579909
Report Date: 2015/05/08

Conestoga-Rovers and Associates Ltd
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340

RESULTS OF ANALYSES OF WATER

Maxxam ID		AEZ157		AEZ158	AEZ159			AEZ160		
Sampling Date		2015/04/29		2015/04/29	2015/04/29			2015/04/29		
COC Number		B 100289		B 100289	B 100289			B 100289		
	Units	SW-1	QC Batch	SW-2A	SW-4A	RDL	QC Batch	SW-5	RDL	QC Batch

Calculated Parameters

Anion Sum	me/L	0.0600	4006172	0.0500	0.0400	N/A	4006172	0.100	N/A	4006172
Bicarb. Alkalinity (calc. as CaCO ₃)	mg/L	<1.0	4006170	<1.0	<1.0	1.0	4006170	<1.0	1.0	4006170
Calculated TDS	mg/L	6.0	4006175	6.0	6.0	1.0	4006175	12	1.0	4006175
Carb. Alkalinity (calc. as CaCO ₃)	mg/L	<1.0	4006170	<1.0	<1.0	1.0	4006170	<1.0	1.0	4006170
Cation Sum	me/L	0.110	4006172	0.110	0.120	N/A	4006172	0.240	N/A	4006172
Hardness (CaCO ₃)	mg/L	1.6	4006001	1.4	1.6	1.0	4006001	7.3	1.0	4006001
Ion Balance (% Difference)	%	29.4	4006171	37.5	50.0	N/A	4006171	41.2	N/A	4006171
Langelier Index (@ 20C)	N/A	NC	4006173	NC	NC		4006173	NC		4006173
Langelier Index (@ 4C)	N/A	NC	4006174	NC	NC		4006174	NC		4006174
Nitrate (N)	mg/L	0.052	4005906	<0.050	<0.050	0.050	4005906	0.087	0.050	4005906
Saturation pH (@ 20C)	N/A	NC	4006173	NC	NC		4006173	NC		4006173
Saturation pH (@ 4C)	N/A	NC	4006174	NC	NC		4006174	NC		4006174

Inorganics

Total Alkalinity (Total as CaCO ₃)	mg/L	<5.0	4009444	<5.0	<5.0	5.0	4009444	<5.0	5.0	4009444
Dissolved Chloride (Cl)	mg/L	1.9	4009446	1.6	1.3	1.0	4009446	1.5	1.0	4009446
Colour	TCU	85	4009455	96	100	25	4009455	28	5.0	4009455
Nitrate + Nitrite	mg/L	0.052	4009464	<0.050	<0.050	0.050	4009464	0.087	0.050	4009464
Nitrite (N)	mg/L	<0.010	4009467	<0.010	<0.010	0.010	4009467	<0.010	0.010	4009467
Nitrogen (Ammonia Nitrogen)	mg/L	<0.050	4009585	<0.050	0.073	0.050	4009585	<0.050	0.050	4009585
Total Organic Carbon (C)	mg/L	6.3	4011581	5.5	5.5	0.50	4013585	3.5	0.50	4013585
Orthophosphate (P)	mg/L	<0.010	4009456	<0.010	<0.010	0.010	4009456	<0.010	0.010	4009456
pH	pH	5.19	4009555	5.08	5.14	N/A	4009555	6.14	N/A	4009711
Reactive Silica (SiO ₂)	mg/L	1.9	4009454	1.9	2.5	0.50	4009454	2.3	0.50	4009454
Dissolved Sulphate (SO ₄)	mg/L	<2.0	4009451	<2.0	<2.0	2.0	4009451	2.5	2.0	4009451
Turbidity	NTU	0.76	4015745	0.29	0.38	0.10	4015745	0.69	0.10	4012141
Conductivity	uS/cm	14	4009558	13	15	1.0	4009558	28	1.0	4009713

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

N/A = Not Applicable

Maxxam Job #: B579909
Report Date: 2015/05/08

Conestoga-Rovers and Associates Ltd
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340

RESULTS OF ANALYSES OF WATER

Maxxam ID		AEZ160			AEZ161		
Sampling Date		2015/04/29			2015/04/29		
COC Number		B 100289			B 100289		
	Units	SW-5 Lab-Dup	RDL	QC Batch	SW-9	RDL	QC Batch
Calculated Parameters							
Anion Sum	me/L		N/A	4006172	0.100	N/A	4006172
Bicarb. Alkalinity (calc. as CaCO ₃)	mg/L		1.0	4006170	<1.0	1.0	4006170
Calculated TDS	mg/L		1.0	4006175	9.0	1.0	4006175
Carb. Alkalinity (calc. as CaCO ₃)	mg/L		1.0	4006170	<1.0	1.0	4006170
Cation Sum	me/L		N/A	4006172	0.180	N/A	4006172
Hardness (CaCO ₃)	mg/L		1.0	4006001	2.8	1.0	4006001
Ion Balance (% Difference)	%		N/A	4006171	28.6	N/A	4006171
Langelier Index (@ 20C)	N/A			4006173	NC		4006173
Langelier Index (@ 4C)	N/A			4006174	NC		4006174
Nitrate (N)	mg/L		0.050	4005906	<0.050	0.050	4005906
Saturation pH (@ 20C)	N/A			4006173	NC		4006173
Saturation pH (@ 4C)	N/A			4006174	NC		4006174
Inorganics							
Total Alkalinity (Total as CaCO ₃)	mg/L		5.0	4009444	<5.0	5.0	4009444
Dissolved Chloride (Cl)	mg/L		1.0	4009446	3.4	1.0	4009446
Colour	TCU		5.0	4009455	82	25	4009455
Nitrate + Nitrite	mg/L		0.050	4009464	<0.050	0.050	4009464
Nitrite (N)	mg/L		0.010	4009467	<0.010	0.010	4009467
Nitrogen (Ammonia Nitrogen)	mg/L		0.050	4009585	0.082	0.050	4009585
Total Organic Carbon (C)	mg/L		0.50	4013585	6.1	0.50	4013585
Orthophosphate (P)	mg/L		0.010	4009456	<0.010	0.010	4009456
pH	pH	6.16	N/A	4009711	5.77	N/A	4009555
Reactive Silica (SiO ₂)	mg/L		0.50	4009454	1.6	0.50	4009454
Dissolved Sulphate (SO ₄)	mg/L		2.0	4009451	<2.0	2.0	4009451
Turbidity	NTU	0.76	0.10	4012141	1.0	0.10	4015745
Conductivity	uS/cm	27	1.0	4009713	19	1.0	4009558
RDL = Reportable Detection Limit							
QC Batch = Quality Control Batch							
Lab-Dup = Laboratory Initiated Duplicate							
N/A = Not Applicable							

Maxxam Job #: B579909
 Report Date: 2015/05/08

Conestoga-Rovers and Associates Ltd
 Client Project #: 088664-05
 Site Location: ATLANTIC GOLD-BEAVER DAM
 Your P.O. #: 20-019340

MERCURY BY COLD VAPOUR AA (WATER)

Maxxam ID		AEZ157	AEZ158	AEZ159	AEZ160		
Sampling Date		2015/04/29	2015/04/29	2015/04/29	2015/04/29		
COC Number		B 100289	B 100289	B 100289	B 100289		
	Units	SW-1	SW-2A	SW-4A	SW-5	RDL	QC Batch
Metals							
Total Mercury (Hg)	ug/L	<0.013	<0.013	<0.013	<0.013	0.013	4013354
RDL = Reportable Detection Limit							
QC Batch = Quality Control Batch							

Maxxam Job #: B579909
Report Date: 2015/05/08

Conestoga-Rovers and Associates Ltd
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340

ELEMENTS BY ICP/MS (WATER)

Maxxam ID		AEZ157	AEZ158	AEZ159	AEZ160	AEZ161		
Sampling Date		2015/04/29	2015/04/29	2015/04/29	2015/04/29	2015/04/29		
COC Number		B 100289						
	Units	SW-1	SW-2A	SW-4A	SW-5	SW-9	RDL	QC Batch
Metals								
Total Aluminum (Al)	ug/L	140	140	130	98	160	5.0	4007953
Total Antimony (Sb)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	4007953
Total Arsenic (As)	ug/L	<1.0	<1.0	1.1	15	<1.0	1.0	4007953
Total Barium (Ba)	ug/L	1.7	1.6	1.7	4.6	2.1	1.0	4007953
Total Beryllium (Be)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	4007953
Total Bismuth (Bi)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	4007953
Total Boron (B)	ug/L	<50	<50	<50	<50	<50	50	4007953
Total Cadmium (Cd)	ug/L	0.012	<0.010	0.012	0.018	0.014	0.010	4007953
Total Calcium (Ca)	ug/L	350	290	350	2200	640	100	4007953
Total Chromium (Cr)	ug/L	<1.0	1.2	<1.0	<1.0	<1.0	1.0	4007953
Total Cobalt (Co)	ug/L	<0.40	<0.40	<0.40	0.61	<0.40	0.40	4007953
Total Copper (Cu)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	4007953
Total Iron (Fe)	ug/L	240	260	160	560	220	50	4007953
Total Lead (Pb)	ug/L	<0.50	<0.50	<0.50	<0.50	<0.50	0.50	4007953
Total Magnesium (Mg)	ug/L	170	160	170	430	300	100	4007953
Total Manganese (Mn)	ug/L	27	25	20	200	36	2.0	4007953
Total Molybdenum (Mo)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	4007953
Total Nickel (Ni)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	4007953
Total Phosphorus (P)	ug/L	<100	<100	<100	<100	<100	100	4007953
Total Potassium (K)	ug/L	330	330	290	480	300	100	4007953
Total Selenium (Se)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	4007953
Total Silver (Ag)	ug/L	<0.10	<0.10	<0.10	<0.10	<0.10	0.10	4007953
Total Sodium (Na)	ug/L	1200	1200	1300	1400	2400	100	4007953
Total Strontium (Sr)	ug/L	2.9	3.0	2.8	11	2.8	2.0	4007953
Total Thallium (Tl)	ug/L	<0.10	<0.10	<0.10	<0.10	<0.10	0.10	4007953
Total Tin (Sn)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	4007953
Total Titanium (Ti)	ug/L	3.2	3.2	2.4	<2.0	3.1	2.0	4007953
Total Uranium (U)	ug/L	<0.10	<0.10	<0.10	<0.10	<0.10	0.10	4007953
Total Vanadium (V)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	4007953
Total Zinc (Zn)	ug/L	<5.0	<5.0	<5.0	5.4	<5.0	5.0	4007953
RDL = Reportable Detection Limit								
QC Batch = Quality Control Batch								

Maxxam Job #: B579909
Report Date: 2015/05/08

Conestoga-Rovers and Associates Ltd
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340

GENERAL COMMENTS

Each temperature is the average of up to three cooler temperatures taken at receipt

Package 1	1.7°C
-----------	-------

Sample AEZ157-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample AEZ158-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample AEZ159-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample AEZ160-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample AEZ161-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Results relate only to the items tested.

QUALITY ASSURANCE REPORT

Conestoga-Rovers and Associates Ltd

Client Project #: 088664-05

Site Location: ATLANTIC GOLD-BEAVER DAM

Your P.O. #: 20-019340

QC Batch	Parameter	Date	Matrix Spike		Spiked Blank		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	Units	Value (%)	QC Limits	% Recovery	QC Limits
4007953	Total Aluminum (Al)	2015/05/06	100	80 - 120	100	80 - 120	<5.0	ug/L	1.7 (1)	20		
4007953	Total Antimony (Sb)	2015/05/06	109	80 - 120	108	80 - 120	<1.0	ug/L	NC (1)	20		
4007953	Total Arsenic (As)	2015/05/06	98	80 - 120	99	80 - 120	<1.0	ug/L	NC (1)	20		
4007953	Total Barium (Ba)	2015/05/06	103	80 - 120	102	80 - 120	<1.0	ug/L	0.78 (1)	20		
4007953	Total Beryllium (Be)	2015/05/06	104	80 - 120	103	80 - 120	<1.0	ug/L	NC (1)	20		
4007953	Total Bismuth (Bi)	2015/05/06	107	80 - 120	105	80 - 120	<2.0	ug/L	NC (1)	20		
4007953	Total Boron (B)	2015/05/06	108	80 - 120	103	80 - 120	<50	ug/L	NC (1)	20		
4007953	Total Cadmium (Cd)	2015/05/06	103	80 - 120	102	80 - 120	<0.010	ug/L	NC (1)	20		
4007953	Total Calcium (Ca)	2015/05/06	98	80 - 120	100	80 - 120	<100	ug/L	1.1 (1)	20		
4007953	Total Chromium (Cr)	2015/05/06	97	80 - 120	98	80 - 120	<1.0	ug/L	NC (1)	20		
4007953	Total Cobalt (Co)	2015/05/06	97	80 - 120	98	80 - 120	<0.40	ug/L	NC (1)	20		
4007953	Total Copper (Cu)	2015/05/06	100	80 - 120	96	80 - 120	<2.0	ug/L	NC (1)	20		
4007953	Total Iron (Fe)	2015/05/06	102	80 - 120	104	80 - 120	<50	ug/L	NC (1)	20		
4007953	Total Lead (Pb)	2015/05/06	102	80 - 120	100	80 - 120	<0.50	ug/L	NC (1)	20		
4007953	Total Magnesium (Mg)	2015/05/06	102	80 - 120	103	80 - 120	<100	ug/L	2.4 (1)	20		
4007953	Total Manganese (Mn)	2015/05/06	103	80 - 120	103	80 - 120	<2.0	ug/L	NC (1)	20		
4007953	Total Molybdenum (Mo)	2015/05/06	103	80 - 120	102	80 - 120	<2.0	ug/L	NC (1)	20		
4007953	Total Nickel (Ni)	2015/05/06	97	80 - 120	100	80 - 120	<2.0	ug/L	NC (1)	20		
4007953	Total Phosphorus (P)	2015/05/06	107	80 - 120	106	80 - 120	<100	ug/L	NC (1)	20		
4007953	Total Potassium (K)	2015/05/06	105	80 - 120	105	80 - 120	<100	ug/L	10 (1)	20		
4007953	Total Selenium (Se)	2015/05/06	98	80 - 120	98	80 - 120	<1.0	ug/L	NC (1)	20		
4007953	Total Silver (Ag)	2015/05/06	105	80 - 120	105	80 - 120	<0.10	ug/L	NC (1)	20		
4007953	Total Sodium (Na)	2015/05/06	103	80 - 120	104	80 - 120	<100	ug/L	0.77 (1)	20		
4007953	Total Strontium (Sr)	2015/05/06	103	80 - 120	100	80 - 120	<2.0	ug/L	1.0 (1)	20		
4007953	Total Thallium (Tl)	2015/05/06	107	80 - 120	104	80 - 120	<0.10	ug/L	NC (1)	20		
4007953	Total Tin (Sn)	2015/05/06	107	80 - 120	109	80 - 120	<2.0	ug/L	NC (1)	20		
4007953	Total Titanium (Ti)	2015/05/06	100	80 - 120	101	80 - 120	<2.0	ug/L	NC (1)	20		
4007953	Total Uranium (U)	2015/05/06	108	80 - 120	106	80 - 120	<0.10	ug/L	NC (1)	20		
4007953	Total Vanadium (V)	2015/05/06	100	80 - 120	102	80 - 120	<2.0	ug/L	NC (1)	20		
4007953	Total Zinc (Zn)	2015/05/06	98	80 - 120	100	80 - 120	<5.0	ug/L	NC (1)	20		
4009444	Total Alkalinity (Total as CaCO ₃)	2015/05/05	98	80 - 120	101	80 - 120	<5.0	mg/L	NC (1)	25		
4009446	Dissolved Chloride (Cl)	2015/05/06	111	80 - 120	107	80 - 120	<1.0	mg/L	0.56 (1)	25	109	80 - 120

QUALITY ASSURANCE REPORT(CONT'D)

Conestoga-Rovers and Associates Ltd

Client Project #: 088664-05

Site Location: ATLANTIC GOLD-BEAVER DAM

Your P.O. #: 20-019340

QC Batch	Parameter	Date	Matrix Spike		Spiked Blank		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	Units	Value (%)	QC Limits	% Recovery	QC Limits
4009451	Dissolved Sulphate (SO4)	2015/05/06	85	80 - 120	91	80 - 120	<2.0	mg/L	NC (1)	25		
4009454	Reactive Silica (SiO2)	2015/05/06	NC	80 - 120	96	80 - 120	<0.50	mg/L	2.8 (1)	25		
4009455	Colour	2015/05/06			108	80 - 120	<5.0	TCU	NC (1)	25		
4009456	Orthophosphate (P)	2015/05/06	99	80 - 120	100	80 - 120	<0.010	mg/L	NC (1)	25		
4009464	Nitrate + Nitrite	2015/05/07	100	80 - 120	102	80 - 120	<0.050	mg/L	NC (1)	25		
4009467	Nitrite (N)	2015/05/05	101	80 - 120	100	80 - 120	<0.010	mg/L	NC (1)	25		
4009555	pH	2015/05/05							0.13 (1)	N/A	100	97 - 103
4009558	Conductivity	2015/05/05			107	80 - 120	1.8, RDL=1.0	uS/cm	0.0010 (1)	25		
4009585	Nitrogen (Ammonia Nitrogen)	2015/05/05	87	80 - 120	100	80 - 120	<0.050	mg/L	NC (1)	25		
4009711	pH	2015/05/05							0.33 (2)	N/A	100	97 - 103
4009713	Conductivity	2015/05/05			101	80 - 120	1.0, RDL=1.0	uS/cm	1.8 (2)	25		
4011581	Total Organic Carbon (C)	2015/05/06	105	80 - 120	103	80 - 120	<0.50	mg/L	NC (1)	20		
4012141	Turbidity	2015/05/06					<0.10	NTU	9.7 (2)	25	99	80 - 120
4013354	Total Mercury (Hg)	2015/05/07	101	80 - 120	97	80 - 120	<0.013	ug/L	NC (1)	20		
4013585	Total Organic Carbon (C)	2015/05/07	98	80 - 120	99	80 - 120	<0.50	mg/L	NC (1)	20		
4015745	Turbidity	2015/05/08					<0.10	NTU	NC (1)	25	103	80 - 120

N/A = Not Applicable

Duplicate: Paired analysis of a separate portion of the same sample. Used to evaluate the variance in the measurement.

Matrix Spike: A sample to which a known amount of the analyte of interest has been added. Used to evaluate sample matrix interference.

QC Standard: A sample of known concentration prepared by an external agency under stringent conditions. Used as an independent check of method accuracy.

Spiked Blank: A blank matrix sample to which a known amount of the analyte, usually from a second source, has been added. Used to evaluate method accuracy.

Method Blank: A blank matrix containing all reagents used in the analytical procedure. Used to identify laboratory contamination.

NC (Matrix Spike): The recovery in the matrix spike was not calculated. The relative difference between the concentration in the parent sample and the spiked amount was too small to permit a reliable recovery calculation (matrix spike concentration was less than 2x that of the native sample concentration).

NC (Duplicate RPD): The duplicate RPD was not calculated. The concentration in the sample and/or duplicate was too low to permit a reliable RPD calculation (one or both samples < 5x RDL).

(1) Duplicate Parent ID

(2) Duplicate Parent ID [AEZ160-01]

Maxxam Job #: B579909
Report Date: 2015/05/08

Conestoga-Rovers and Associates Ltd
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340

VALIDATION SIGNATURE PAGE

The analytical data and all QC contained in this report were reviewed and validated by the following individual(s).

<Original signed by>

Mike MacGillivray, Scientific Specialist (Inorganics)

Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(E), signing the reports. For Service Group specific validation please refer to the Validation Signature Page.



200 Bluewater Road, Suite 105, Bedford, Nova Scotia B4B 1G9
 49 Elizabeth Ave., St John's, NL A1A 1W9
 90 Esplanade Sydney, NS B1P 1A1
 www.maxxamanalytics.com E-mail: Clientservicesbedford@maxxamanalytics.com

MAXXAM Chain of Custody Record

COC #: B 100289

Page 1 of 1

This column for lab use only:

Client Code						
Maxxam Job #	B579909					
Cooler ID	Seal Present	Seal Intact	Temp 1	Temp 2	Temp 3	Average Temp
						102

INVOICE INFORMATION:

Company Name: CRA
 Contact Name: Jeff Parks
 Address: Dartmouth NS
 Postal Code B3B 1J7
 Email: j.parks@craworld.com
 Ph: 468-1248 Fax: 468-2207

REPORT INFORMATION (if differs from invoice):

Company Name:
 Contact Name:
 Address:
 Postal Code
 Email:
 Ph:

PO # 20-019340

Project # / Phase # 088664-05

Project Name / Site Location
 Atlantic Gold - Beaver Dam
 Quote 14 - 161KG

Site #

Task Order #

Sampled by AF + DN

TURNAROUND TIME

Standard

10 day

If RUSH Specify Date:

Pre-schedule rush work


Charge for # Jars used but not submitted -

Guideline Requirements / Detection Limits / Special Instructions

Integrity YES NO
 Labelled by *me*

Location / Bin #

Field Sample Identification	Matrix*	Date/Time Sampled	# & type of bottles	Field Filtered & Preserved	Lab Filtration Required	Choose Diss Metals	RCAP-MS Total Diss Metals	Total Digest (Default Method)	Metals Water	Metals Soil	Hydrocarbons	Mercury				
												Metals & Mercury Default Available Digest Method	Metals Total Digest - for Ocean sediments (HNO3/HF/HClO4)	Selenium (low level) Read for CCME Residential Parklands Agricultural Hot Water soluble Boron (required for CCME Agricultural)	RBCA Hydrocarbons (BTEX, C6-C32)	Hydrocarbons Soil (Portable) NS Fuel Oil Spill Low Level BTEX, C6-C32 NB Portable Water BTEX, VPH, Low level T.E.H.
1 SW-1	SW	29 Apr 15 50, 100, 200 ml	X		X	X			X							
2 SW-2A					X	X			X							
3 SW-4A					X	X			X							
4 SW-5					X	X			X							
5 SW-9					X	X						2pp				
6																
7																
8																2015 MAY 1 12:44
9																



B579909

RELINQUISHED BY: (Signature/Print)

<Original
signed by>

Afacey

Date

1 May 2015

RECEIVED BY: (Signature/Print)

<Original
signed by>

*Joe Royce
Lee Butt*

Date

15 MAY 11:15

Your P.O. #: 20-019340
 Your Project #: 088664-05
 Site Location: ATLANTIC GOLD-BEAVER DAM
 Your C.O.C. #: B 100296

Attention:Jeff Parks

Conestoga-Rovers and Associates Ltd
 45 Akerley Blvd
 Dartmouth , NS
 B3B 1J7

Report Date: 2015/06/05
 Report #: R3454128
 Version: 1 - Final

CERTIFICATE OF ANALYSIS

MAXXAM JOB #: B5A1423

Received: 2015/05/29, 08:37

Sample Matrix: Water
 # Samples Received: 8

Analyses	Quantity	Date Extracted	Date Analyzed	Laboratory Method	Reference
Carbonate, Bicarbonate and Hydroxide	8	N/A	2015/06/03	N/A	SM 22 4500-CO2 D
Alkalinity	8	N/A	2015/06/03	ATL SOP 00013	EPA 310.2 R1974 m
Chloride	8	N/A	2015/06/03	ATL SOP 00014	SM 22 4500-Cl- E m
Colour	8	N/A	2015/06/03	ATL SOP 00020	SM 22 2120C m
Conductance - water	8	N/A	2015/06/03	ATL SOP 00004	SM 22 2510B m
Hardness (calculated as CaCO ₃)	1	N/A	2015/06/03	ATL SOP 00048	SM 22 2340 B
Hardness (calculated as CaCO ₃)	7	N/A	2015/06/05	ATL SOP 00048	SM 22 2340 B
Mercury - Total (CVAA,LL)	8	2015/06/01	2015/06/02	ATL SOP 00026	EPA 245.1 R3 m
Metals Water Total MS	1	2015/06/02	2015/06/02	ATL SOP 00058	EPA 6020A R1 m
Metals Water Total MS	7	2015/06/03	2015/06/04	ATL SOP 00058	EPA 6020A R1 m
Ion Balance (% Difference)	8	N/A	2015/06/05		Auto Calc.
Anion and Cation Sum	1	N/A	2015/06/03		Auto Calc.
Anion and Cation Sum	7	N/A	2015/06/05		Auto Calc.
Nitrogen Ammonia - water	8	N/A	2015/06/02	ATL SOP 00015	EPA 350.1 R2 m
Nitrogen - Nitrate + Nitrite	8	N/A	2015/06/04	ATL SOP 00016	USGS SOPINCF0452.2 m
Nitrogen - Nitrite	8	N/A	2015/06/03	ATL SOP 00017	SM 22 4500-NO2- B m
Nitrogen - Nitrate (as N)	8	N/A	2015/06/05	ATL SOP 00018	ASTM D3867
pH (1)	8	N/A	2015/06/03	ATL SOP 00003	SM 22 4500-H+ B m
Phosphorus - ortho	8	N/A	2015/06/03	ATL SOP 00021	EPA 365.2 m
Sat. pH and Langelier Index (@ 20C)	1	N/A	2015/06/04	ATL SOP 00049	Auto Calc.
Sat. pH and Langelier Index (@ 20C)	7	N/A	2015/06/05	ATL SOP 00049	Auto Calc.
Sat. pH and Langelier Index (@ 4C)	1	N/A	2015/06/04	ATL SOP 00049	Auto Calc.
Sat. pH and Langelier Index (@ 4C)	7	N/A	2015/06/05	ATL SOP 00049	Auto Calc.
Reactive Silica	8	N/A	2015/06/03	ATL SOP 00022	EPA 366.0 m
Sulphate	8	N/A	2015/06/04	ATL SOP 00023	EPA 375.4 R1978 m
Total Dissolved Solids (TDS calc)	8	N/A	2015/06/05		Auto Calc.
Organic carbon - Total (TOC) (2)	8	N/A	2015/06/02	ATL SOP 00037	SM 22 5310C m
Turbidity	8	N/A	2015/06/03	ATL SOP 00011	EPA 180.1 R2 m

Reference Method suffix "m" indicates test methods incorporate validated modifications from specific reference methods to improve performance.

* RPDs calculated using raw data. The rounding of final results may result in the apparent difference.

Your P.O. #: 20-019340
Your Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your C.O.C. #: B 100296

Attention:Jeff Parks

Conestoga-Rovers and Associates Ltd
45 Akerley Blvd
Dartmouth , NS
B3B 1J7

Report Date: 2015/06/05
Report #: R3454128
Version: 1 - Final

CERTIFICATE OF ANALYSIS

MAXXAM JOB #: B5A1423

Received: 2015/05/29, 08:37

(1) The APHA Standard Method require pH to be analyzed within 15 minutes of sampling and therefore field analysis is required for compliance. All Laboratory pH analyses in this report are reported past the APHA Standard Method holding time.

(2) TOC / DOC present in the sample should be considered as non-purgeable TOC / DOC.

Encryption Key <Original signed by> Rachael Mansfield
05 Jun 2015 15:49:54 -03:00

Please direct all questions regarding this Certificate of Analysis to your Project Manager.

Michelle Hill, Project Manager

Email: M^Hill@maxxam.ca

Phone# (902)420-0203 Ext

=====

Maxxam has procedures in place to guard against improper use of the electronic signature device when signing the reports. For Service Group specific validation please refer to the Validation section.

Maxxam Job #: B5A1423
Report Date: 2015/06/05

Conestoga-Rovers and Associates Ltd
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340

RESULTS OF ANALYSES OF WATER

Maxxam ID		AIY460	AIY461	AIY462	AIY462		AIY463		
Sampling Date		2015/05/28	2015/05/28	2015/05/28	2015/05/28		2015/05/28		
COC Number		B 100296	B 100296	B 100296	B 100296		B 100296		
	Units	SW-1	SW-2A	SW-2AD Lab-Dup	QC Batch	SW-4A	RDL	QC Batch	

Calculated Parameters

Anion Sum	me/L	0.0900	0.0900	0.0900		4043516	0.110	N/A	4043516
Bicarb. Alkalinity (calc. as CaCO ₃)	mg/L	<1.0	<1.0	<1.0		4043514	<1.0	1.0	4043514
Calculated TDS	mg/L	8.0	7.0	7.0		4043520	9.0	1.0	4043520
Carb. Alkalinity (calc. as CaCO ₃)	mg/L	<1.0	<1.0	<1.0		4043514	<1.0	1.0	4043514
Cation Sum	me/L	0.160	0.140	0.140		4043516	0.180	N/A	4043516
Hardness (CaCO ₃)	mg/L	2.6	2.1	2.0		4043502	3.1	1.0	4043502
Ion Balance (% Difference)	%	28.0	21.7	21.7		4043515	24.1	N/A	4043515
Langelier Index (@ 20C)	N/A	NC	NC	NC		4043518	NC		4043518
Langelier Index (@ 4C)	N/A	NC	NC	NC		4043519	NC		4043519
Nitrate (N)	mg/L	<0.050	<0.050	<0.050		4042583	<0.050	0.050	4042583
Saturation pH (@ 20C)	N/A	NC	NC	NC		4043518	NC		4043518
Saturation pH (@ 4C)	N/A	NC	NC	NC		4043519	NC		4043519

Inorganics

Total Alkalinity (Total as CaCO ₃)	mg/L	<5.0	<5.0	<5.0	<5.0	4047788	<5.0	5.0	4047788
Dissolved Chloride (Cl)	mg/L	3.1	3.1	3.1	3.0	4047794	3.8	1.0	4047794
Colour	TCU	110	120	120	120	4047803	130	25	4047803
Nitrate + Nitrite	mg/L	<0.050	<0.050	<0.050	<0.050	4047812	<0.050	0.050	4047812
Nitrite (N)	mg/L	<0.010	<0.010	<0.010	<0.010	4047814	<0.010	0.010	4047814
Nitrogen (Ammonia Nitrogen)	mg/L	0.10	0.052	<0.050		4047272	0.092	0.050	4047276
Total Organic Carbon (C)	mg/L	7.5	7.9	8.1		4047061	9.7	0.50	4047063
Orthophosphate (P)	mg/L	<0.010	<0.010	<0.010	<0.010	4047807	<0.010	0.010	4047807
pH	pH	5.85	5.59	5.36		4048933	5.74	N/A	4048933
Reactive Silica (SiO ₂)	mg/L	1.1	1.1	1.1	1.1	4047800	1.5	0.50	4047800
Dissolved Sulphate (SO ₄)	mg/L	<2.0	<2.0	<2.0	<2.0	4047798	<2.0	2.0	4047798
Turbidity	NTU	1.1	1.5	1.4	1.3	4049776	1.4	0.10	4049776
Conductivity	uS/cm	16	16	15		4048936	18	1.0	4048936

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Lab-Dup = Laboratory Initiated Duplicate

N/A = Not Applicable

Maxxam Job #: B5A1423
Report Date: 2015/06/05

Conestoga-Rovers and Associates Ltd
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340

RESULTS OF ANALYSES OF WATER

Maxxam ID		AIY464			AIY465		AIY466	AIY466		
Sampling Date		2015/05/28			2015/05/28		2015/05/28	2015/05/28		
COC Number		B 100296			B 100296		B 100296	B 100296		
	Units	SW-5	RDL	QC Batch	SW-6A	QC Batch	SW-9	SW-9 Lab-Dup	RDL	QC Batch

Calculated Parameters

Anion Sum	me/L	0.360	N/A	4043516	0.0700	4043516	0.170		N/A	4043516
Bicarb. Alkalinity (calc. as CaCO3)	mg/L	7.8	1.0	4043514	<1.0	4043514	<1.0		1.0	4043514
Calculated TDS	mg/L	21	1.0	4043520	7.0	4043520	13		1.0	4043520
Carb. Alkalinity (calc. as CaCO3)	mg/L	<1.0	1.0	4043514	<1.0	4043514	<1.0		1.0	4043514
Cation Sum	me/L	0.350	N/A	4043516	0.140	4043516	0.260		N/A	4043516
Hardness (CaCO3)	mg/L	11	1.0	4043502	2.5	4043502	4.7		1.0	4043502
Ion Balance (% Difference)	%	1.41	N/A	4043515	33.3	4043515	20.9		N/A	4043515
Langelier Index (@ 20C)	N/A	-3.22		4043518	NC	4043518	NC			4043518
Langelier Index (@ 4C)	N/A	-3.48		4043519	NC	4043519	NC			4043519
Nitrate (N)	mg/L	<0.050	0.050	4042583	<0.050	4042583	<0.050		0.050	4043600
Saturation pH (@ 20C)	N/A	9.84		4043518	NC	4043518	NC			4043518
Saturation pH (@ 4C)	N/A	10.1		4043519	NC	4043519	NC			4043519

Inorganics

Total Alkalinity (Total as CaCO3)	mg/L	7.8	5.0	4047788	<5.0	4047788	<5.0		5.0	4047788
Dissolved Chloride (Cl)	mg/L	3.4	1.0	4047794	2.5	4047794	6.1		1.0	4047794
Colour	TCU	27	5.0	4047803	88	4047803	80		25	4047803
Nitrate + Nitrite	mg/L	<0.050	0.050	4047812	<0.050	4047812	<0.050		0.050	4047812
Nitrite (N)	mg/L	<0.010	0.010	4047814	<0.010	4047814	<0.010		0.010	4047814
Nitrogen (Ammonia Nitrogen)	mg/L	<0.050	0.050	4047276	<0.050	4047276	<0.050		0.050	4047276
Total Organic Carbon (C)	mg/L	3.6	0.50	4047063	7.3	4047063	6.7	6.8	0.50	4047063
Orthophosphate (P)	mg/L	0.011	0.010	4047807	<0.010	4047807	<0.010		0.010	4047807
pH	pH	6.62	N/A	4048933	5.76	4048933	6.17		N/A	4048933
Reactive Silica (SiO2)	mg/L	<0.50	0.50	4047800	1.1	4047800	1.5		0.50	4047800
Dissolved Sulphate (SO4)	mg/L	5.0	2.0	4047798	<2.0	4047798	<2.0		2.0	4047798
Turbidity	NTU	1.2	0.10	4049776	0.43	4049778	0.72		0.10	4049778
Conductivity	uS/cm	34	1.0	4048936	16	4048936	29		1.0	4048936

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Lab-Dup = Laboratory Initiated Duplicate

N/A = Not Applicable

Maxxam Job #: B5A1423
Report Date: 2015/06/05

Conestoga-Rovers and Associates Ltd
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340

RESULTS OF ANALYSES OF WATER

Maxxam ID		AIY467		
Sampling Date		2015/05/28		
COC Number		B 100296		
	Units	SW-10	RDL	QC Batch
Calculated Parameters				
Anion Sum	me/L	0.450	N/A	4043516
Bicarb. Alkalinity (calc. as CaCO ₃)	mg/L	6.8	1.0	4043514
Calculated TDS	mg/L	31	1.0	4043520
Carb. Alkalinity (calc. as CaCO ₃)	mg/L	<1.0	1.0	4043514
Cation Sum	me/L	0.430	N/A	4043516
Hardness (CaCO ₃)	mg/L	15	1.0	4043502
Ion Balance (% Difference)	%	2.27	N/A	4043515
Langelier Index (@ 20C)	N/A	-3.44		4043518
Langelier Index (@ 4C)	N/A	-3.69		4043519
Nitrate (N)	mg/L	0.074	0.050	4043600
Saturation pH (@ 20C)	N/A	9.78		4043518
Saturation pH (@ 4C)	N/A	10.0		4043519
Inorganics				
Total Alkalinity (Total as CaCO ₃)	mg/L	6.8	5.0	4047788
Dissolved Chloride (Cl)	mg/L	3.2	1.0	4047794
Colour	TCU	8.8	5.0	4047803
Nitrate + Nitrite	mg/L	0.074	0.050	4047812
Nitrite (N)	mg/L	<0.010	0.010	4047814
Nitrogen (Ammonia Nitrogen)	mg/L	<0.050	0.050	4047276
Total Organic Carbon (C)	mg/L	1.6	0.50	4047063
Orthophosphate (P)	mg/L	<0.010	0.010	4047807
pH	pH	6.34	N/A	4048933
Reactive Silica (SiO ₂)	mg/L	4.0	0.50	4047800
Dissolved Sulphate (SO ₄)	mg/L	11	2.0	4047798
Turbidity	NTU	0.79	0.10	4049778
Conductivity	uS/cm	46	1.0	4048936
RDL = Reportable Detection Limit				
QC Batch = Quality Control Batch				
N/A = Not Applicable				

Maxxam Job #: B5A1423
Report Date: 2015/06/05

Conestoga-Rovers and Associates Ltd
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340

MERCURY BY COLD VAPOUR AA (WATER)

Maxxam ID		AIY460	AIY460	AIY461	AIY462	AIY463	AIY464	AIY465		
Sampling Date		2015/05/28	2015/05/28	2015/05/28	2015/05/28	2015/05/28	2015/05/28	2015/05/28		
COC Number		B 100296	B 100296	B 100296	B 100296	B 100296	B 100296	B 100296		
	Units	SW-1	SW-1 Lab-Dup	SW-2A	SW-2AD	SW-4A	SW-5	SW-6A	RDL	QC Batch

Metals

Total Mercury (Hg)	ug/L	0.015	0.015	0.013	0.013	0.015	0.015	0.017	0.013	4045913
--------------------	------	-------	-------	-------	-------	-------	-------	-------	-------	---------

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Lab-Dup = Laboratory Initiated Duplicate

Maxxam ID		AIY466	AIY467		
Sampling Date		2015/05/28	2015/05/28		
COC Number		B 100296	B 100296		
	Units	SW-9	SW-10	RDL	QC Batch

Metals

Total Mercury (Hg)	ug/L	0.013	<0.013	0.013	4045913
--------------------	------	-------	--------	-------	---------

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Maxxam Job #: B5A1423
Report Date: 2015/06/05

Conestoga-Rovers and Associates Ltd
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340

ELEMENTS BY ICP/MS (WATER)

Maxxam ID		AIY460		AIY461	AIY462	AIY463	AIY464	AIY465		
Sampling Date		2015/05/28		2015/05/28	2015/05/28	2015/05/28	2015/05/28	2015/05/28		
COC Number		B 100296		B 100296						
	Units	SW-1	QC Batch	SW-2A	SW-2AD	SW-4A	SW-5	SW-6A	RDL	QC Batch
Metals										
Total Aluminum (Al)	ug/L	190	4045823	190	190	240	61	220	5.0	4047400
Total Antimony (Sb)	ug/L	<1.0	4045823	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	4047400
Total Arsenic (As)	ug/L	2.6	4045823	1.1	1.1	7.3	41	3.2	1.0	4047400
Total Barium (Ba)	ug/L	2.4	4045823	2.2	2.2	2.8	4.4	2.3	1.0	4047400
Total Beryllium (Be)	ug/L	<1.0	4045823	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	4047400
Total Bismuth (Bi)	ug/L	<2.0	4045823	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	4047400
Total Boron (B)	ug/L	<50	4045823	<50	<50	<50	<50	<50	50	4047400
Total Cadmium (Cd)	ug/L	<0.010	4045823	0.013	0.013	0.013	<0.010	<0.010	0.010	4047400
Total Calcium (Ca)	ug/L	630	4045823	470	460	780	3500	620	100	4047400
Total Chromium (Cr)	ug/L	3.0	4045823	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	4047400
Total Cobalt (Co)	ug/L	<0.40	4045823	<0.40	<0.40	0.42	<0.40	<0.40	0.40	4047400
Total Copper (Cu)	ug/L	<2.0	4045823	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	4047400
Total Iron (Fe)	ug/L	360	4045823	410	400	580	880	370	50	4047400
Total Lead (Pb)	ug/L	<0.50	4045823	<0.50	<0.50	<0.50	<0.50	<0.50	0.50	4047400
Total Magnesium (Mg)	ug/L	240	4045823	220	210	280	600	230	100	4047400
Total Manganese (Mn)	ug/L	31	4045823	27	27	37	65	29	2.0	4047400
Total Molybdenum (Mo)	ug/L	<2.0	4045823	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	4047400
Total Nickel (Ni)	ug/L	<2.0	4045823	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	4047400
Total Phosphorus (P)	ug/L	<100	4045823	<100	<100	<100	<100	<100	100	4047400
Total Potassium (K)	ug/L	340	4045823	290	290	280	670	280	100	4047400
Total Selenium (Se)	ug/L	<1.0	4045823	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	4047400
Total Silver (Ag)	ug/L	<0.10	4045823	<0.10	<0.10	<0.10	<0.10	<0.10	0.10	4047400
Total Sodium (Na)	ug/L	1800	4045823	1600	1600	1900	1700	1700	100	4047400
Total Strontium (Sr)	ug/L	4.6	4045823	4.1	3.9	5.1	18	4.4	2.0	4047400
Total Thallium (Tl)	ug/L	<0.10	4045823	<0.10	<0.10	<0.10	<0.10	<0.10	0.10	4047400
Total Tin (Sn)	ug/L	<2.0	4045823	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	4047400
Total Titanium (Ti)	ug/L	2.7	4045823	2.0	2.4	4.7	<2.0	2.8	2.0	4047400
Total Uranium (U)	ug/L	<0.10	4045823	<0.10	<0.10	<0.10	<0.10	<0.10	0.10	4047400
Total Vanadium (V)	ug/L	<2.0	4045823	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	4047400
Total Zinc (Zn)	ug/L	6.8	4045823	<5.0	<5.0	7.5	<5.0	5.7	5.0	4047400

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Maxxam Job #: B5A1423
Report Date: 2015/06/05

Conestoga-Rovers and Associates Ltd
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340

ELEMENTS BY ICP/MS (WATER)

Maxxam ID		AIY466	AIY467		
Sampling Date		2015/05/28	2015/05/28		
COC Number		B 100296	B 100296		
	Units	SW-9	SW-10	RDL	QC Batch
Metals					
Total Aluminum (Al)	ug/L	170	64	5.0	4047400
Total Antimony (Sb)	ug/L	<1.0	<1.0	1.0	4047400
Total Arsenic (As)	ug/L	<1.0	60	1.0	4047400
Total Barium (Ba)	ug/L	2.4	5.6	1.0	4047400
Total Beryllium (Be)	ug/L	<1.0	<1.0	1.0	4047400
Total Bismuth (Bi)	ug/L	<2.0	<2.0	2.0	4047400
Total Boron (B)	ug/L	<50	<50	50	4047400
Total Cadmium (Cd)	ug/L	<0.010	0.049	0.010	4047400
Total Calcium (Ca)	ug/L	1100	4800	100	4047400
Total Chromium (Cr)	ug/L	<1.0	<1.0	1.0	4047400
Total Cobalt (Co)	ug/L	<0.40	1.0	0.40	4047400
Total Copper (Cu)	ug/L	<2.0	3.9	2.0	4047400
Total Iron (Fe)	ug/L	210	740	50	4047400
Total Lead (Pb)	ug/L	<0.50	<0.50	0.50	4047400
Total Magnesium (Mg)	ug/L	480	680	100	4047400
Total Manganese (Mn)	ug/L	34	56	2.0	4047400
Total Molybdenum (Mo)	ug/L	<2.0	<2.0	2.0	4047400
Total Nickel (Ni)	ug/L	<2.0	7.1	2.0	4047400
Total Phosphorus (P)	ug/L	<100	<100	100	4047400
Total Potassium (K)	ug/L	270	740	100	4047400
Total Selenium (Se)	ug/L	<1.0	<1.0	1.0	4047400
Total Silver (Ag)	ug/L	<0.10	<0.10	0.10	4047400
Total Sodium (Na)	ug/L	3500	2000	100	4047400
Total Strontium (Sr)	ug/L	4.2	19	2.0	4047400
Total Thallium (Tl)	ug/L	<0.10	<0.10	0.10	4047400
Total Tin (Sn)	ug/L	<2.0	<2.0	2.0	4047400
Total Titanium (Ti)	ug/L	3.0	2.3	2.0	4047400
Total Uranium (U)	ug/L	<0.10	<0.10	0.10	4047400
Total Vanadium (V)	ug/L	<2.0	<2.0	2.0	4047400
Total Zinc (Zn)	ug/L	<5.0	16	5.0	4047400
RDL = Reportable Detection Limit					
QC Batch = Quality Control Batch					

Maxxam Job #: B5A1423
Report Date: 2015/06/05

Conestoga-Rovers and Associates Ltd
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340

GENERAL COMMENTS

Each temperature is the average of up to three cooler temperatures taken at receipt

Package 1	1.7°C
-----------	-------

Sample AIY460-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample AIY461-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample AIY462-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample AIY463-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample AIY465-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample AIY466-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Results relate only to the items tested.

Maxxam Job #: B5A1423
Report Date: 2015/06/05

QUALITY ASSURANCE REPORT

Conestoga-Rovers and Associates Ltd
Client Project #: 088664-05

Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340

QC Batch	Parameter	Date	Matrix Spike		Spiked Blank		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	Units	Value (%)	QC Limits	% Recovery	QC Limits
4045823	Total Aluminum (Al)	2015/06/02	111	80 - 120	108	80 - 120	<5.0	ug/L	NC (1)	20		
4045823	Total Antimony (Sb)	2015/06/02	114	80 - 120	105	80 - 120	<1.0	ug/L	NC (1)	20		
4045823	Total Arsenic (As)	2015/06/02	101	80 - 120	99	80 - 120	<1.0	ug/L	NC (1)	20		
4045823	Total Barium (Ba)	2015/06/02	NC	80 - 120	96	80 - 120	<1.0	ug/L	0.23 (1)	20		
4045823	Total Beryllium (Be)	2015/06/02	104	80 - 120	101	80 - 120	<1.0	ug/L	NC (1)	20		
4045823	Total Bismuth (Bi)	2015/06/02	100	80 - 120	104	80 - 120	<2.0	ug/L	NC (1)	20		
4045823	Total Boron (B)	2015/06/02	NC	80 - 120	118	80 - 120	<50	ug/L	NC (1)	20		
4045823	Total Cadmium (Cd)	2015/06/02	101	80 - 120	100	80 - 120	<0.010	ug/L	NC (1)	20		
4045823	Total Calcium (Ca)	2015/06/02	NC	80 - 120	103	80 - 120	<100	ug/L	1.7 (1)	20		
4045823	Total Chromium (Cr)	2015/06/02	98	80 - 120	98	80 - 120	<1.0	ug/L	NC (1)	20		
4045823	Total Cobalt (Co)	2015/06/02	96	80 - 120	99	80 - 120	<0.40	ug/L	NC (1)	20		
4045823	Total Copper (Cu)	2015/06/02	92	80 - 120	97	80 - 120	<2.0	ug/L	NC (1)	20		
4045823	Total Iron (Fe)	2015/06/02	103	80 - 120	105	80 - 120	<50	ug/L	NC (1)	20		
4045823	Total Lead (Pb)	2015/06/02	98	80 - 120	100	80 - 120	<0.50	ug/L	NC (1)	20		
4045823	Total Magnesium (Mg)	2015/06/02	NC	80 - 120	106	80 - 120	<100	ug/L	1.3 (1)	20		
4045823	Total Manganese (Mn)	2015/06/02	101	80 - 120	102	80 - 120	<2.0	ug/L	NC (1)	20		
4045823	Total Molybdenum (Mo)	2015/06/02	112	80 - 120	105	80 - 120	<2.0	ug/L	NC (1)	20		
4045823	Total Nickel (Ni)	2015/06/02	93	80 - 120	99	80 - 120	<2.0	ug/L	NC (1)	20		
4045823	Total Phosphorus (P)	2015/06/02	110	80 - 120	109	80 - 120	<100	ug/L	NC (1)	20		
4045823	Total Potassium (K)	2015/06/02	NC	80 - 120	107	80 - 120	<100	ug/L	2.4 (1)	20		
4045823	Total Selenium (Se)	2015/06/02	99	80 - 120	98	80 - 120	<1.0	ug/L	NC (1)	20		
4045823	Total Silver (Ag)	2015/06/02	103	80 - 120	102	80 - 120	<0.10	ug/L	NC (1)	20		
4045823	Total Sodium (Na)	2015/06/02	NC	80 - 120	109	80 - 120	<100	ug/L	1.8 (1)	20		
4045823	Total Strontium (Sr)	2015/06/02	NC	80 - 120	100	80 - 120	<2.0	ug/L	0.80 (1)	20		
4045823	Total Thallium (Tl)	2015/06/02	102	80 - 120	103	80 - 120	<0.10	ug/L	NC (1)	20		
4045823	Total Tin (Sn)	2015/06/02	109	80 - 120	102	80 - 120	<2.0	ug/L	NC (1)	20		
4045823	Total Titanium (Ti)	2015/06/02	104	80 - 120	99	80 - 120	<2.0	ug/L	NC (1)	20		
4045823	Total Uranium (U)	2015/06/02	106	80 - 120	103	80 - 120	<0.10	ug/L	2.4 (1)	20		
4045823	Total Vanadium (V)	2015/06/02	103	80 - 120	102	80 - 120	<2.0	ug/L	NC (1)	20		
4045823	Total Zinc (Zn)	2015/06/02	96	80 - 120	101	80 - 120	<5.0	ug/L	NC (1)	20		
4045913	Total Mercury (Hg)	2015/06/02	95 (2)	80 - 120	100	80 - 120	<0.013	ug/L	NC (3)	20		

Maxxam Job #: B5A1423
Report Date: 2015/06/05

QUALITY ASSURANCE REPORT(CONT'D)

Conestoga-Rovers and Associates Ltd
Client Project #: 088664-05

Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340

QC Batch	Parameter	Date	Matrix Spike		Spiked Blank		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	Units	Value (%)	QC Limits	% Recovery	QC Limits
4047061	Total Organic Carbon (C)	2015/06/02	102	80 - 120	101	80 - 120	<0.50	mg/L	2.3 (1)	20		
4047063	Total Organic Carbon (C)	2015/06/02	NC (4)	80 - 120	100	80 - 120	<0.50	mg/L	1.7 (5)	20		
4047272	Nitrogen (Ammonia Nitrogen)	2015/06/02	92	80 - 120	90	80 - 120	<0.050	mg/L	NC (1)	25		
4047276	Nitrogen (Ammonia Nitrogen)	2015/06/02	91	80 - 120	95	80 - 120	<0.050	mg/L	NC (1)	25		
4047400	Total Aluminum (Al)	2015/06/04	107	80 - 120	100	80 - 120	<5.0	ug/L				
4047400	Total Antimony (Sb)	2015/06/04	102	80 - 120	103	80 - 120	<1.0	ug/L				
4047400	Total Arsenic (As)	2015/06/04	96	80 - 120	97	80 - 120	<1.0	ug/L				
4047400	Total Barium (Ba)	2015/06/04	94	80 - 120	95	80 - 120	<1.0	ug/L				
4047400	Total Beryllium (Be)	2015/06/04	99	80 - 120	100	80 - 120	<1.0	ug/L				
4047400	Total Bismuth (Bi)	2015/06/04	100	80 - 120	102	80 - 120	<2.0	ug/L				
4047400	Total Boron (B)	2015/06/04	112	80 - 120	115	80 - 120	<50	ug/L				
4047400	Total Cadmium (Cd)	2015/06/04	97	80 - 120	99	80 - 120	<0.010	ug/L				
4047400	Total Calcium (Ca)	2015/06/04	NC	80 - 120	104	80 - 120	<100	ug/L	0.64 (1)	20		
4047400	Total Chromium (Cr)	2015/06/04	95	80 - 120	95	80 - 120	<1.0	ug/L				
4047400	Total Cobalt (Co)	2015/06/04	95	80 - 120	97	80 - 120	<0.40	ug/L				
4047400	Total Copper (Cu)	2015/06/04	93	80 - 120	96	80 - 120	<2.0	ug/L				
4047400	Total Iron (Fe)	2015/06/04	102	80 - 120	103	80 - 120	<50	ug/L				
4047400	Total Lead (Pb)	2015/06/04	94	80 - 120	97	80 - 120	<0.50	ug/L				
4047400	Total Magnesium (Mg)	2015/06/04	101	80 - 120	101	80 - 120	<100	ug/L	1.8 (1)	20		
4047400	Total Manganese (Mn)	2015/06/04	96	80 - 120	98	80 - 120	<2.0	ug/L				
4047400	Total Molybdenum (Mo)	2015/06/04	104	80 - 120	103	80 - 120	<2.0	ug/L				
4047400	Total Nickel (Ni)	2015/06/04	94	80 - 120	98	80 - 120	<2.0	ug/L				
4047400	Total Phosphorus (P)	2015/06/04	104	80 - 120	102	80 - 120	<100	ug/L				
4047400	Total Potassium (K)	2015/06/04	101	80 - 120	101	80 - 120	<100	ug/L				
4047400	Total Selenium (Se)	2015/06/04	97	80 - 120	98	80 - 120	<1.0	ug/L				
4047400	Total Silver (Ag)	2015/06/04	101	80 - 120	102	80 - 120	<0.10	ug/L				
4047400	Total Sodium (Na)	2015/06/04	NC	80 - 120	99	80 - 120	<100	ug/L				
4047400	Total Strontium (Sr)	2015/06/04	NC	80 - 120	98	80 - 120	<2.0	ug/L				
4047400	Total Thallium (Tl)	2015/06/04	101	80 - 120	102	80 - 120	<0.10	ug/L				
4047400	Total Tin (Sn)	2015/06/04	100	80 - 120	100	80 - 120	<2.0	ug/L				
4047400	Total Titanium (Ti)	2015/06/04	99	80 - 120	100	80 - 120	<2.0	ug/L				

Maxxam Job #: B5A1423
Report Date: 2015/06/05

QUALITY ASSURANCE REPORT(CONT'D)

Conestoga-Rovers and Associates Ltd
Client Project #: 088664-05

Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340

QC Batch	Parameter	Date	Matrix Spike		Spiked Blank		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	Units	Value (%)	QC Limits	% Recovery	QC Limits
4047400	Total Uranium (U)	2015/06/04	104	80 - 120	105	80 - 120	<0.10	ug/L				
4047400	Total Vanadium (V)	2015/06/04	97	80 - 120	99	80 - 120	<2.0	ug/L				
4047400	Total Zinc (Zn)	2015/06/04	96	80 - 120	97	80 - 120	<5.0	ug/L				
4047788	Total Alkalinity (Total as CaCO3)	2015/06/03	98 (6)	80 - 120	101	80 - 120	<5.0	mg/L	NC (7)	25		
4047794	Dissolved Chloride (Cl)	2015/06/03	104 (6)	80 - 120	100	80 - 120	<1.0	mg/L	NC (7)	25	109	80 - 120
4047798	Dissolved Sulphate (SO4)	2015/06/04	106 (6)	80 - 120	85	80 - 120	<2.0	mg/L	NC (7)	25		
4047800	Reactive Silica (SiO2)	2015/06/03	95 (6)	80 - 120	95	80 - 120	<0.50	mg/L	NC (7)	25		
4047803	Colour	2015/06/03			105	80 - 120	<5.0	TCU	NC (7)	25		
4047807	Orthophosphate (P)	2015/06/03	95 (6)	80 - 120	101	80 - 120	<0.010	mg/L	NC (7)	25		
4047812	Nitrate + Nitrite	2015/06/04	95 (6)	80 - 120	96	80 - 120	<0.050	mg/L	NC (7)	25		
4047814	Nitrite (N)	2015/06/03	88 (6)	80 - 120	103	80 - 120	<0.010	mg/L	NC (7)	25		
4048933	pH	2015/06/03							0.44 (1)	N/A	101	97 - 103
4048936	Conductivity	2015/06/03			101	80 - 120	<1.0	uS/cm	0.45 (1)	25		
4049776	Turbidity	2015/06/03					<0.10	NTU	8.8 (7)	25	104	80 - 120

Maxxam Job #: B5A1423
Report Date: 2015/06/05

QUALITY ASSURANCE REPORT(CONT'D)

Conestoga-Rovers and Associates Ltd

Client Project #: 088664-05

Site Location: ATLANTIC GOLD-BEAVER DAM

Your P.O. #: 20-019340

QC Batch	Parameter	Date	Matrix Spike		Spiked Blank		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	Units	Value (%)	QC Limits	% Recovery	QC Limits
4049778	Turbidity	2015/06/03					<0.10	NTU	1.6 (1)	25	105	80 - 120

N/A = Not Applicable

Duplicate: Paired analysis of a separate portion of the same sample. Used to evaluate the variance in the measurement.

Matrix Spike: A sample to which a known amount of the analyte of interest has been added. Used to evaluate sample matrix interference.

QC Standard: A sample of known concentration prepared by an external agency under stringent conditions. Used as an independent check of method accuracy.

Spiked Blank: A blank matrix sample to which a known amount of the analyte, usually from a second source, has been added. Used to evaluate method accuracy.

Method Blank: A blank matrix containing all reagents used in the analytical procedure. Used to identify laboratory contamination.

NC (Matrix Spike): The recovery in the matrix spike was not calculated. The relative difference between the concentration in the parent sample and the spiked amount was too small to permit a reliable recovery calculation (matrix spike concentration was less than 2x that of the native sample concentration).

NC (Duplicate RPD): The duplicate RPD was not calculated. The concentration in the sample and/or duplicate was too low to permit a reliable RPD calculation (one or both samples < 5x RDL).

(1) Duplicate Parent ID

(2) Matrix Spike Parent ID [AIY461-03]

(3) Duplicate Parent ID [AIY460-03]

(4) Matrix Spike Parent ID [AIY466-01]

(5) Duplicate Parent ID [AIY466-01]

(6) Matrix Spike Parent ID [AIY462-01]

(7) Duplicate Parent ID [AIY462-01]

Maxxam Job #: B5A1423
Report Date: 2015/06/05

Conestoga-Rovers and Associates Ltd
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340

VALIDATION SIGNATURE PAGE

The analytical data and all QC contained in this report were reviewed and validated by the following individual(s).

<Original signed by>

Kevin MacDonald, Inorganics Supervisor

<Original signed by>

Mike MacGillivray, Scientific Specialist (Inorganics)

Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(E), signing the reports. For Service Group specific validation please refer to the Validation Signature Page.



200 Bluewater Road, Suite 105, Bedford, Nova Scotia B4B 1G9 Tel: 902-420-0203 Fax: 902-420-8612 Toll Free: 1-800-565-7222
187 Elm Ave., St. John's, NL A1A 1W9 Tel: 709-754-0203 Fax: 709-754-8612 Toll Free: 1-888-492-7222
90 Espérance Sydney, NS B1P 1A1 Tel: 902-567-1255 Fax: 902-538-6504 Toll Free: 1-888-535-7777
www.maxxamalytics.com E-mail: [Clientservicesbedford@maxxamalytics.com](mailto:clientservicesbedford@maxxamalytics.com)

MAXXAM Chain of Custody Record

coc #: B 100296

Page _____ of _____

This column for lab use only:				INVOICE INFORMATION:				REPORT INFORMATION (if differs from invoice):				TURNAROUND TIME				
Client Code Maxxam Job # B5A154223 2015/03/12				Company Name: CRA Contact Name: Jeff Parks Address: Dartmouth, NS Postal Code B3B 1J1 Email: jparkscraworld.com Ph: 468-1248 Fax: 468-2207				Company Name: Contact Name: Address: Email: Ph:				PO # 20-019340 Project # / Phase # 0881664-05 Project Name / Site Location Atlantic Gold-Beaver Dam Quote 14-161KG Site # Task Order # Sampled by AF + ZJ		Standard <input checked="" type="checkbox"/>		
Cooler ID	Seal Present	Seal Intact	Temp 1	Temp 2	Temp 3	Average Temp								10 day <input type="checkbox"/>		
														If RUSH Specify Date:		
														Pre-schedule rush work		
														Charge for # Jars used but not submitted /		
Guideline Requirements / Detection Limits / Special Instructions																
Integrity		Integrity / Checklist by						Field Filtered & Preserved	Lab Filtration Required	RCAP-30	Choose Total or Diss Metals	Choose Total or Diss Metals	RCAP-MS	Total Digestion Method	Metals & Mercury	Hydrocarbons
YES	NO	N/A														
Labelled by		Location / Bin #														
*Specify Matrix: Surface/Salt/Ground/Tapwater/Sewage/Effluent/ Potable/NonPotable/Tissue/Soil/Sludge/Metal/Seawater																
Field Sample Identification				Matrix*	Date/Time Sampled	# & type of bottles	Field Filtered & Preserved	Lab Filtration Required	RCAP-30	Choose Total or Diss Metals	Choose Total or Diss Metals	RCAP-MS	Total Digestion Method	Metals & Mercury	Metals Soil	Hydrocarbons
1	SW-1	SW	28 May 15	3	X			X		X						
2	SW-2A				X			X		X						
3	SW-2AO				X			X		X						
4	SW-4A				X			X		X						
5	SW-5				X			X		X						
6	SW-6A				X			X		X						
7	SW-9				X			X		X						
8	SW-10				X			X		X						
9																
														2015 MAY 29 9:55		



B5A1423

THE MANHATTAN GMAT TEST

<Original *Zachary Jenkins* 5/29/15 8:35
signed

www.elsevier.com/locate/jimolmed

I RECEIVED BY: (Signature/Print) Date Time
<Original Jae Doyle

140-00-14

Mellon et al.

Page 8

AM-500-00149-1B

Your P.O. #: 20-019340
 Your Project #: 088664-05
 Site Location: ATLANTIC GOLD-BEAVER DAM
 Your C.O.C. #: 519518-01-01

Attention:Amanda Facey

GHD Limited
 45 Akerley Blvd
 Dartmouth , NS
 B3B 1J7

Report Date: 2015/07/13
 Report #: R3571678
 Version: 1 - Final

CERTIFICATE OF ANALYSIS

MAXXAM JOB #: B5C9254

Received: 2015/07/03, 16:20

Sample Matrix: Water
 # Samples Received: 8

Analyses	Quantity	Date Extracted	Date Analyzed	Laboratory Method	Reference
Carbonate, Bicarbonate and Hydroxide	8	N/A	2015/07/13	N/A	SM 22 4500-CO2 D
Alkalinity	8	N/A	2015/07/08	ATL SOP 00013	EPA 310.2 R1974 m
Chloride	8	N/A	2015/07/10	ATL SOP 00014	SM 22 4500-Cl- E m
Colour	8	N/A	2015/07/10	ATL SOP 00020	SM 22 2120C m
Conductance - water	8	N/A	2015/07/10	ATL SOP 00004	SM 22 2510B m
Hardness (calculated as CaCO ₃)	8	N/A	2015/07/09	ATL SOP 00048	SM 22 2340 B
Mercury - Total (CVAA,LL)	8	2015/07/07	2015/07/08	ATL SOP 00026	EPA 245.1 R3 m
Metals Water Total MS	6	2015/07/07	2015/07/08	ATL SOP 00058	EPA 6020A R1 m
Metals Water Total MS	2	2015/07/08	2015/07/09	ATL SOP 00058	EPA 6020A R1 m
Ion Balance (% Difference)	8	N/A	2015/07/13		Auto Calc.
Anion and Cation Sum	8	N/A	2015/07/13		Auto Calc.
Nitrogen Ammonia - water	8	N/A	2015/07/08	ATL SOP 00015	EPA 350.1 R2 m
Nitrogen - Nitrate + Nitrite	8	N/A	2015/07/09	ATL SOP 00016	USGS SOPINCF0452.2 m
Nitrogen - Nitrite	8	N/A	2015/07/10	ATL SOP 00017	SM 22 4500-NO2- B m
Nitrogen - Nitrate (as N)	8	N/A	2015/07/10	ATL SOP 00018	ASTM D3867
pH (1)	8	N/A	2015/07/10	ATL SOP 00003	SM 22 4500-H+ B m
Phosphorus - ortho	8	N/A	2015/07/10	ATL SOP 00021	EPA 365.2 m
Sat. pH and Langelier Index (@ 20C)	8	N/A	2015/07/13	ATL SOP 00049	Auto Calc.
Sat. pH and Langelier Index (@ 4C)	8	N/A	2015/07/13	ATL SOP 00049	Auto Calc.
Reactive Silica	8	N/A	2015/07/09	ATL SOP 00022	EPA 366.0 m
Sulphate	8	N/A	2015/07/10	ATL SOP 00023	EPA 375.4 R1978 m
Total Dissolved Solids (TDS calc)	8	N/A	2015/07/10		Auto Calc.
Organic carbon - Total (TOC) (2)	8	N/A	2015/07/08	ATL SOP 00037	SM 22 5310C m
Turbidity	8	N/A	2015/07/13	ATL SOP 00011	EPA 180.1 R2 m

Reference Method suffix "m" indicates test methods incorporate validated modifications from specific reference methods to improve performance.

* RPDs calculated using raw data. The rounding of final results may result in the apparent difference.

(1) The APHA Standard Method require pH to be analyzed within 15 minutes of sampling and therefore field analysis is required for compliance. All Laboratory pH analyses in this report are reported past the APHA Standard Method holding time.

(2) TOC / DOC present in the sample should be considered as non-purgeable TOC / DOC.

Your P.O. #: 20-019340
Your Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your C.O.C. #: 519518-01-01

Attention:Amanda Facey

GHD Limited
45 Akerley Blvd
Dartmouth , NS
B3B 1J7

Report Date: 2015/07/13
Report #: R3571678
Version: 1 - Final

CERTIFICATE OF ANALYSIS

MAXXAM JOB #: B5C9254

Received: 2015/07/03, 16:20

Encryption Key **<Original signed by>**

Rachael Mansfield
13 Jul 2015 15:19:30 -03:00

Please direct all questions regarding this Certificate of Analysis to your Project Manager.

Michelle Hill, Project Manager

Email: MHill@maxxam.ca

Phone# (902)420-0203 Ext:289

=====

Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(E), signing the reports. For Service Group specific validation please refer to the Validation Signature Page.

Maxxam Job #: B5C9254
Report Date: 2015/07/13

GHD Limited
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340
Sampler Initials: AF

RESULTS OF ANALYSES OF WATER

Maxxam ID		AOE400	AOE401		AOE402	AOE402		
Sampling Date		2015/06/30	2015/06/30		2015/06/30	2015/06/30		
COC Number		519518-01-01	519518-01-01		519518-01-01	519518-01-01		
	Units	SW-1	SW-2A	QC Batch	SW-4A	SW-4A Lab-Dup	RDL	QC Batch

Calculated Parameters

Anion Sum	me/L	0.0800	0.0800	4092060	0.0700		N/A	4092060
Bicarb. Alkalinity (calc. as CaCO ₃)	mg/L	<1.0	<1.0	4092057	<1.0		1.0	4092057
Calculated TDS	mg/L	9.0	8.0	4092063	8.0		1.0	4092063
Carb. Alkalinity (calc. as CaCO ₃)	mg/L	<1.0	<1.0	4092057	<1.0		1.0	4092057
Cation Sum	me/L	0.170	0.160	4092060	0.170		N/A	4092060
Hardness (CaCO ₃)	mg/L	2.9	2.6	4092058	3.0		1.0	4092058
Ion Balance (% Difference)	%	36.0	33.3	4092059	41.7		N/A	4092059
Langelier Index (@ 20C)	N/A	NC	NC	4092061	NC			4092061
Langelier Index (@ 4C)	N/A	NC	NC	4092062	NC			4092062
Nitrate (N)	mg/L	0.062	0.055	4092065	0.064		0.050	4092065
Saturation pH (@ 20C)	N/A	NC	NC	4092061	NC			4092061
Saturation pH (@ 4C)	N/A	NC	NC	4092062	NC			4092062

Inorganics

Total Alkalinity (Total as CaCO ₃)	mg/L	<5.0	<5.0	4096752	<5.0	<5.0	5.0	4096752
Dissolved Chloride (Cl)	mg/L	2.6	2.8	4096766	2.2	2.7	1.0	4096766
Colour	TCU	170	170	4096770	160	160	25	4096770
Nitrate + Nitrite	mg/L	0.062	0.055	4096777	0.064	0.077	0.050	4096777
Nitrite (N)	mg/L	<0.010	<0.010	4096781	<0.010	<0.010	0.010	4096781
Nitrogen (Ammonia Nitrogen)	mg/L	<0.050	<0.050	4096184	<0.050		0.050	4096184
Total Organic Carbon (C)	mg/L	12	12	4096103	12		0.50	4096104
Orthophosphate (P)	mg/L	<0.010	<0.010	4096771	<0.010	<0.010	0.010	4096771
pH	pH	6.00	5.29	4099822	5.42		N/A	4099822
Reactive Silica (SiO ₂)	mg/L	2.1	1.9	4096769	2.0	1.9	0.50	4096769
Dissolved Sulphate (SO ₄)	mg/L	<2.0	<2.0	4096767	<2.0	<2.0	2.0	4096767
Turbidity	NTU	1.2	0.99	4102538	1.3		0.10	4102538
Conductivity	uS/cm	17	17	4099826	17		1.0	4099826

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Lab-Dup = Laboratory Initiated Duplicate

Maxxam Job #: B5C9254
Report Date: 2015/07/13

GHD Limited
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340
Sampler Initials: AF

RESULTS OF ANALYSES OF WATER

Maxxam ID		AOE403		AOE404		AOE405		AOE406		
Sampling Date		2015/06/30		2015/06/30		2015/06/30		2015/06/30		
COC Number		519518-01-01		519518-01-01		519518-01-01		519518-01-01		
	Units	SW-5	RDL	SW-6A	QC Batch	SW-6AD	QC Batch	SW-9	RDL	QC Batch

Calculated Parameters										
Anion Sum	me/L	0.350	N/A	0.0700	4092060	0.0700	4092060	0.130	N/A	4092060
Bicarb. Alkalinity (calc. as CaCO3)	mg/L	9.3	1.0	<1.0	4092057	<1.0	4092057	<1.0	1.0	4092057
Calculated TDS	mg/L	21	1.0	7.0	4092063	7.0	4092063	13	1.0	4092063
Carb. Alkalinity (calc. as CaCO3)	mg/L	<1.0	1.0	<1.0	4092057	<1.0	4092057	<1.0	1.0	4092057
Cation Sum	me/L	0.350	N/A	0.170	4092060	0.160	4092060	0.310	N/A	4092060
Hardness (CaCO3)	mg/L	12	1.0	2.8	4092058	2.8	4092058	7.4	1.0	4092058
Ion Balance (% Difference)	%	0.00	N/A	41.7	4092059	39.1	4092059	40.9	N/A	4092059
Langelier Index (@ 20C)	N/A	-3.00		NC	4092061	NC	4092061	NC		4092061
Langelier Index (@ 4C)	N/A	-3.26		NC	4092062	NC	4092062	NC		4092062
Nitrate (N)	mg/L	0.063	0.050	0.053	4092065	0.059	4092065	<0.050	0.050	4092065
Saturation pH (@ 20C)	N/A	9.76		NC	4092061	NC	4092061	NC		4092061
Saturation pH (@ 4C)	N/A	10.0		NC	4092062	NC	4092062	NC		4092062
Inorganics										
Total Alkalinity (Total as CaCO3)	mg/L	9.3	5.0	<5.0	4096752	<5.0	4096782	<5.0	5.0	4096782
Dissolved Chloride (Cl)	mg/L	1.9	1.0	2.2	4096766	2.2	4096787	4.8	1.0	4096787
Colour	TCU	23	5.0	140	4096770	130	4096792	150	25	4096792
Nitrate + Nitrite	mg/L	0.063	0.050	0.053	4096777	0.059	4096794	<0.050	0.050	4096794
Nitrite (N)	mg/L	<0.010	0.010	<0.010	4096781	<0.010	4096799	<0.010	0.010	4096799
Nitrogen (Ammonia Nitrogen)	mg/L	0.052	0.050	0.22	4096184	<0.050	4096184	0.14	0.050	4096184
Total Organic Carbon (C)	mg/L	4.1	0.50	10	4096104	11	4096104	12	0.50	4096104
Orthophosphate (P)	mg/L	<0.010	0.010	<0.010	4096771	<0.010	4096793	<0.010	0.010	4096793
pH	pH	6.76	N/A	5.79	4099822	5.64	4099822	6.33	N/A	4099822
Reactive Silica (SiO2)	mg/L	0.92	0.50	1.3	4096769	1.2	4096789	2.2	0.50	4096789
Dissolved Sulphate (SO4)	mg/L	5.0	2.0	<2.0	4096767	<2.0	4096788	<2.0	2.0	4096788
Turbidity	NTU	0.83	0.10	0.65	4102538	1.1	4102538	0.99	0.10	4102542
Conductivity	uS/cm	35	1.0	16	4099826	16	4099826	29	1.0	4099826

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

N/A = Not Applicable

Maxxam Job #: B5C9254
Report Date: 2015/07/13

GHD Limited
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340
Sampler Initials: AF

RESULTS OF ANALYSES OF WATER

Maxxam ID		AOE407	AOE407		
Sampling Date		2015/06/30	2015/06/30		
COC Number		519518-01-01	519518-01-01		
	Units	SW-10	SW-10 Lab-Dup	RDL	QC Batch
Calculated Parameters					
Anion Sum	me/L	0.450		N/A	4092060
Bicarb. Alkalinity (calc. as CaCO ₃)	mg/L	8.0		1.0	4092057
Calculated TDS	mg/L	32		1.0	4092063
Carb. Alkalinity (calc. as CaCO ₃)	mg/L	<1.0		1.0	4092057
Cation Sum	me/L	0.450		N/A	4092060
Hardness (CaCO ₃)	mg/L	15		1.0	4092058
Ion Balance (% Difference)	%	0.00		N/A	4092059
Langelier Index (@ 20C)	N/A	-3.05			4092061
Langelier Index (@ 4C)	N/A	-3.31			4092062
Nitrate (N)	mg/L	0.060		0.050	4092065
Saturation pH (@ 20C)	N/A	9.70			4092061
Saturation pH (@ 4C)	N/A	9.96			4092062
Inorganics					
Total Alkalinity (Total as CaCO ₃)	mg/L	8.0		5.0	4096782
Dissolved Chloride (Cl)	mg/L	2.9		1.0	4096787
Colour	TCU	9.4		5.0	4096792
Nitrate + Nitrite	mg/L	0.060		0.050	4096794
Nitrite (N)	mg/L	<0.010		0.010	4096799
Nitrogen (Ammonia Nitrogen)	mg/L	<0.050		0.050	4096184
Total Organic Carbon (C)	mg/L	2.1		0.50	4096104
Orthophosphate (P)	mg/L	<0.010		0.010	4096793
pH	pH	6.65	6.72	N/A	4099822
Reactive Silica (SiO ₂)	mg/L	4.7		0.50	4096789
Dissolved Sulphate (SO ₄)	mg/L	9.6		2.0	4096788
Turbidity	NTU	1.0		0.10	4102542
Conductivity	uS/cm	46	46	1.0	4099826
RDL = Reportable Detection Limit QC Batch = Quality Control Batch Lab-Dup = Laboratory Initiated Duplicate N/A = Not Applicable					

Maxxam Job #: B5C9254
Report Date: 2015/07/13

GHD Limited
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340
Sampler Initials: AF

MERCURY BY COLD VAPOUR AA (WATER)

Maxxam ID		AOE400	AOE401		AOE402	AOE402	AOE403		
Sampling Date		2015/06/30	2015/06/30		2015/06/30	2015/06/30	2015/06/30		
COC Number		519518-01-01	519518-01-01		519518-01-01	519518-01-01	519518-01-01		
	Units	SW-1	SW-2A	QC Batch	SW-4A	SW-4A Lab-Dup	SW-5	RDL	QC Batch

Metals

Total Mercury (Hg)	ug/L	<0.013	<0.013	4094692	<0.013	<0.013	<0.013	0.013	4094727
--------------------	------	--------	--------	---------	--------	--------	--------	-------	---------

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Lab-Dup = Laboratory Initiated Duplicate

Maxxam ID		AOE404	AOE405	AOE406	AOE407			
Sampling Date		2015/06/30	2015/06/30	2015/06/30	2015/06/30			
COC Number		519518-01-01	519518-01-01	519518-01-01	519518-01-01			
	Units	SW-6A	SW-6AD	SW-9	SW-10	RDL	QC Batch	

Metals

Total Mercury (Hg)	ug/L	<0.013	<0.013	<0.013	<0.013	0.013	4094727
--------------------	------	--------	--------	--------	--------	-------	---------

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Maxxam Job #: B5C9254
Report Date: 2015/07/13

GHD Limited
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340
Sampler Initials: AF

ELEMENTS BY ICP/MS (WATER)

Maxxam ID		AOE400	AOE401	AOE402	AOE403	AOE404	AOE405		
Sampling Date		2015/06/30	2015/06/30	2015/06/30	2015/06/30	2015/06/30	2015/06/30		
COC Number		519518-01-01	519518-01-01	519518-01-01	519518-01-01	519518-01-01	519518-01-01		
	Units	SW-1	SW-2A	SW-4A	SW-5	SW-6A	SW-6AD	RDL	QC Batch

Metals

Total Aluminum (Al)	ug/L	280	280	300	45	290	300	5.0	4094135
Total Antimony (Sb)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	4094135
Total Arsenic (As)	ug/L	2.5	<1.0	5.4	32	3.0	3.1	1.0	4094135
Total Barium (Ba)	ug/L	3.0	3.0	2.8	3.6	2.6	2.7	1.0	4094135
Total Beryllium (Be)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	4094135
Total Bismuth (Bi)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	4094135
Total Boron (B)	ug/L	<50	<50	<50	<50	<50	<50	50	4094135
Total Cadmium (Cd)	ug/L	0.028	0.012	0.016	<0.010	0.016	0.015	0.010	4094135
Total Calcium (Ca)	ug/L	690	580	710	3600	670	670	100	4094135
Total Chromium (Cr)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	4094135
Total Cobalt (Co)	ug/L	<0.40	<0.40	<0.40	<0.40	<0.40	<0.40	0.40	4094135
Total Copper (Cu)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	4094135
Total Iron (Fe)	ug/L	580	590	650	530	550	560	50	4094135
Total Lead (Pb)	ug/L	0.54	0.55	0.52	<0.50	<0.50	<0.50	0.50	4094135
Total Magnesium (Mg)	ug/L	290	280	290	640	270	280	100	4094135
Total Manganese (Mn)	ug/L	37	35	32	50	33	34	2.0	4094135
Total Molybdenum (Mo)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	4094135
Total Nickel (Ni)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	4094135
Total Phosphorus (P)	ug/L	150	150	140	140	140	150	100	4094135
Total Potassium (K)	ug/L	170	160	140	580	190	190	100	4094135
Total Selenium (Se)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	4094135
Total Silver (Ag)	ug/L	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	0.10	4094135
Total Sodium (Na)	ug/L	1900	1900	1900	1800	1800	1800	100	4094135
Total Strontium (Sr)	ug/L	5.9	5.0	5.0	20	4.8	5.1	2.0	4094135
Total Thallium (Tl)	ug/L	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	0.10	4094135
Total Tin (Sn)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	4094135
Total Titanium (Ti)	ug/L	3.7	3.6	3.8	<2.0	3.4	3.9	2.0	4094135
Total Uranium (U)	ug/L	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	0.10	4094135
Total Vanadium (V)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	4094135
Total Zinc (Zn)	ug/L	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	5.0	4094135

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Maxxam Job #: B5C9254
Report Date: 2015/07/13

GHD Limited
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340
Sampler Initials: AF

ELEMENTS BY ICP/MS (WATER)

Maxxam ID		AOE406	AOE407		
Sampling Date		2015/06/30	2015/06/30		
COC Number		519518-01-01	519518-01-01		
	Units	SW-9	SW-10	RDL	QC Batch
Metals					
Total Aluminum (Al)	ug/L	280	39	5.0	4094792
Total Antimony (Sb)	ug/L	<1.0	<1.0	1.0	4094792
Total Arsenic (As)	ug/L	<1.0	130	1.0	4094792
Total Barium (Ba)	ug/L	3.3	5.4	1.0	4094792
Total Beryllium (Be)	ug/L	<1.0	<1.0	1.0	4094792
Total Bismuth (Bi)	ug/L	<2.0	<2.0	2.0	4094792
Total Boron (B)	ug/L	<50	<50	50	4094792
Total Cadmium (Cd)	ug/L	0.014	0.061	0.010	4094792
Total Calcium (Ca)	ug/L	1700	4900	100	4094792
Total Chromium (Cr)	ug/L	<1.0	<1.0	1.0	4094792
Total Cobalt (Co)	ug/L	<0.40	1.8	0.40	4094792
Total Copper (Cu)	ug/L	<2.0	3.0	2.0	4094792
Total Iron (Fe)	ug/L	440	1400	50	4094792
Total Lead (Pb)	ug/L	<0.50	<0.50	0.50	4094792
Total Magnesium (Mg)	ug/L	740	660	100	4094792
Total Manganese (Mn)	ug/L	57	110	2.0	4094792
Total Molybdenum (Mo)	ug/L	<2.0	<2.0	2.0	4094792
Total Nickel (Ni)	ug/L	<2.0	7.2	2.0	4094792
Total Phosphorus (P)	ug/L	150	140	100	4094792
Total Potassium (K)	ug/L	200	640	100	4094792
Total Selenium (Se)	ug/L	<1.0	<1.0	1.0	4094792
Total Silver (Ag)	ug/L	<0.10	<0.10	0.10	4094792
Total Sodium (Na)	ug/L	3100	1900	100	4094792
Total Strontium (Sr)	ug/L	5.9	19	2.0	4094792
Total Thallium (Tl)	ug/L	<0.10	<0.10	0.10	4094792
Total Tin (Sn)	ug/L	<2.0	<2.0	2.0	4094792
Total Titanium (Ti)	ug/L	3.1	<2.0	2.0	4094792
Total Uranium (U)	ug/L	<0.10	<0.10	0.10	4094792
Total Vanadium (V)	ug/L	<2.0	<2.0	2.0	4094792
Total Zinc (Zn)	ug/L	<5.0	13	5.0	4094792
RDL = Reportable Detection Limit					
QC Batch = Quality Control Batch					

Maxxam Job #: B5C9254

Report Date: 2015/07/13

GHD Limited

Client Project #: 088664-05

Site Location: ATLANTIC GOLD-BEAVER DAM

Your P.O. #: 20-019340

Sampler Initials: AF

GENERAL COMMENTS

Each temperature is the average of up to three cooler temperatures taken at receipt

Package 1	1.7°C
-----------	-------

Sample AOE400-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample AOE401-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample AOE402-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample AOE404-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample AOE405-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample AOE406-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Results relate only to the items tested.

Maxxam Job #: B5C9254
Report Date: 2015/07/13

QUALITY ASSURANCE REPORT

GHD Limited
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340
Sampler Initials: AF

QC Batch	Parameter	Date	Matrix Spike		Spiked Blank		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	Units	Value (%)	QC Limits	% Recovery	QC Limits
4094135	Total Aluminum (Al)	2015/07/08	102	80 - 120	104	80 - 120	<5.0	ug/L	NC (1)	20		
4094135	Total Antimony (Sb)	2015/07/08	106	80 - 120	102	80 - 120	<1.0	ug/L	NC (1)	20		
4094135	Total Arsenic (As)	2015/07/08	100	80 - 120	99	80 - 120	<1.0	ug/L	NC (1)	20		
4094135	Total Barium (Ba)	2015/07/08	99	80 - 120	98	80 - 120	<1.0	ug/L	NC (1)	20		
4094135	Total Beryllium (Be)	2015/07/08	99	80 - 120	99	80 - 120	<1.0	ug/L	NC (1)	20		
4094135	Total Bismuth (Bi)	2015/07/08	102	80 - 120	100	80 - 120	<2.0	ug/L	NC (1)	20		
4094135	Total Boron (B)	2015/07/08	108	80 - 120	109	80 - 120	<50	ug/L	NC (1)	20		
4094135	Total Cadmium (Cd)	2015/07/08	103	80 - 120	104	80 - 120	<0.010	ug/L	NC (1)	20		
4094135	Total Calcium (Ca)	2015/07/08	94	80 - 120	95	80 - 120	<100	ug/L	0.070 (1)	20		
4094135	Total Chromium (Cr)	2015/07/08	99	80 - 120	98	80 - 120	<1.0	ug/L	NC (1)	20		
4094135	Total Cobalt (Co)	2015/07/08	100	80 - 120	100	80 - 120	<0.40	ug/L	NC (1)	20		
4094135	Total Copper (Cu)	2015/07/08	98	80 - 120	99	80 - 120	<2.0	ug/L	0.31 (1)	20		
4094135	Total Iron (Fe)	2015/07/08	103	80 - 120	104	80 - 120	<50	ug/L	NC (1)	20		
4094135	Total Lead (Pb)	2015/07/08	102	80 - 120	101	80 - 120	<0.50	ug/L	NC (1)	20		
4094135	Total Magnesium (Mg)	2015/07/08	103	80 - 120	103	80 - 120	<100	ug/L	NC (1)	20		
4094135	Total Manganese (Mn)	2015/07/08	104	80 - 120	104	80 - 120	<2.0	ug/L	NC (1)	20		
4094135	Total Molybdenum (Mo)	2015/07/08	102	80 - 120	101	80 - 120	<2.0	ug/L	NC (1)	20		
4094135	Total Nickel (Ni)	2015/07/08	100	80 - 120	101	80 - 120	<2.0	ug/L	NC (1)	20		
4094135	Total Phosphorus (P)	2015/07/08	104	80 - 120	105	80 - 120	130, RDL=100	ug/L	NC (1)	20		
4094135	Total Potassium (K)	2015/07/08	97	80 - 120	99	80 - 120	<100	ug/L	NC (1)	20		
4094135	Total Selenium (Se)	2015/07/08	99	80 - 120	98	80 - 120	<1.0	ug/L	NC (1)	20		
4094135	Total Silver (Ag)	2015/07/08	107	80 - 120	103	80 - 120	<0.10	ug/L	NC (1)	20		
4094135	Total Sodium (Na)	2015/07/08	104	80 - 120	106	80 - 120	<100	ug/L	NC (1)	20		
4094135	Total Strontium (Sr)	2015/07/08	102	80 - 120	104	80 - 120	<2.0	ug/L	NC (1)	20		
4094135	Total Thallium (Tl)	2015/07/08	103	80 - 120	101	80 - 120	<0.10	ug/L	NC (1)	20		
4094135	Total Tin (Sn)	2015/07/08	104	80 - 120	102	80 - 120	<2.0	ug/L	NC (1)	20		
4094135	Total Titanium (Ti)	2015/07/08	104	80 - 120	104	80 - 120	<2.0	ug/L	NC (1)	20		
4094135	Total Uranium (U)	2015/07/08	110	80 - 120	108	80 - 120	<0.10	ug/L	NC (1)	20		
4094135	Total Vanadium (V)	2015/07/08	103	80 - 120	101	80 - 120	<2.0	ug/L	NC (1)	20		
4094135	Total Zinc (Zn)	2015/07/08	99	80 - 120	98	80 - 120	<5.0	ug/L	6.9 (1)	20		

Maxxam Job #: B5C9254
Report Date: 2015/07/13

QUALITY ASSURANCE REPORT(CONT'D)

GHD Limited
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340
Sampler Initials: AF

QC Batch	Parameter	Date	Matrix Spike		Spiked Blank		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	Units	Value (%)	QC Limits	% Recovery	QC Limits
4094692	Total Mercury (Hg)	2015/07/08	95	80 - 120	94	80 - 120	<0.013	ug/L	NC (1)	20		
4094727	Total Mercury (Hg)	2015/07/08	88 (2)	80 - 120	103	80 - 120	<0.013	ug/L	NC (3)	20		
4094792	Total Aluminum (Al)	2015/07/09	104	80 - 120	102	80 - 120	<5.0	ug/L	NC (1)	20		
4094792	Total Antimony (Sb)	2015/07/09	114	80 - 120	112	80 - 120	<1.0	ug/L	2.5 (1)	20		
4094792	Total Arsenic (As)	2015/07/09	100	80 - 120	98	80 - 120	<1.0	ug/L	NC (1)	20		
4094792	Total Barium (Ba)	2015/07/09	102	80 - 120	100	80 - 120	<1.0	ug/L	NC (1)	20		
4094792	Total Beryllium (Be)	2015/07/09	103	80 - 120	97	80 - 120	<1.0	ug/L	NC (1)	20		
4094792	Total Bismuth (Bi)	2015/07/09	106	80 - 120	107	80 - 120	<2.0	ug/L	NC (1)	20		
4094792	Total Boron (B)	2015/07/09	115	80 - 120	108	80 - 120	<50	ug/L	NC (1)	20		
4094792	Total Cadmium (Cd)	2015/07/09	105	80 - 120	98	80 - 120	<0.010	ug/L	NC (1)	20		
4094792	Total Calcium (Ca)	2015/07/09	97	80 - 120	97	80 - 120	<100	ug/L	NC (1)	20		
4094792	Total Chromium (Cr)	2015/07/09	96	80 - 120	95	80 - 120	<1.0	ug/L	NC (1)	20		
4094792	Total Cobalt (Co)	2015/07/09	96	80 - 120	96	80 - 120	<0.40	ug/L	NC (1)	20		
4094792	Total Copper (Cu)	2015/07/09	94	80 - 120	94	80 - 120	<2.0	ug/L	NC (1)	20		
4094792	Total Iron (Fe)	2015/07/09	102	80 - 120	102	80 - 120	<50	ug/L	NC (1)	20		
4094792	Total Lead (Pb)	2015/07/09	103	80 - 120	103	80 - 120	<0.50	ug/L	NC (1)	20		
4094792	Total Magnesium (Mg)	2015/07/09	102	80 - 120	103	80 - 120	<100	ug/L	NC (1)	20		
4094792	Total Manganese (Mn)	2015/07/09	100	80 - 120	101	80 - 120	<2.0	ug/L	NC (1)	20		
4094792	Total Molybdenum (Mo)	2015/07/09	108	80 - 120	107	80 - 120	<2.0	ug/L	NC (1)	20		
4094792	Total Nickel (Ni)	2015/07/09	96	80 - 120	95	80 - 120	<2.0	ug/L	NC (1)	20		
4094792	Total Phosphorus (P)	2015/07/09	108	80 - 120	108	80 - 120	140, RDL=100	ug/L	NC (1)	20		
4094792	Total Potassium (K)	2015/07/09	108	80 - 120	108	80 - 120	<100	ug/L	NC (1)	20		
4094792	Total Selenium (Se)	2015/07/09	99	80 - 120	99	80 - 120	<1.0	ug/L	NC (1)	20		
4094792	Total Silver (Ag)	2015/07/09	108	80 - 120	106	80 - 120	<0.10	ug/L	NC (1)	20		
4094792	Total Sodium (Na)	2015/07/09	96	80 - 120	99	80 - 120	<100	ug/L	0.87 (1)	20		
4094792	Total Strontium (Sr)	2015/07/09	106	80 - 120	103	80 - 120	<2.0	ug/L	NC (1)	20		
4094792	Total Thallium (Tl)	2015/07/09	106	80 - 120	106	80 - 120	<0.10	ug/L	NC (1)	20		
4094792	Total Tin (Sn)	2015/07/09	111	80 - 120	110	80 - 120	<2.0	ug/L	NC (1)	20		
4094792	Total Titanium (Ti)	2015/07/09	97	80 - 120	98	80 - 120	<2.0	ug/L	NC (1)	20		
4094792	Total Uranium (U)	2015/07/09	110	80 - 120	109	80 - 120	<0.10	ug/L	0.17 (1)	20		

Maxxam Job #: B5C9254
Report Date: 2015/07/13

QUALITY ASSURANCE REPORT(CONT'D)

GHD Limited
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340
Sampler Initials: AF

QC Batch	Parameter	Date	Matrix Spike		Spiked Blank		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	Units	Value (%)	QC Limits	% Recovery	QC Limits
4094792	Total Vanadium (V)	2015/07/09	97	80 - 120	96	80 - 120	<2.0	ug/L	NC (1)	20		
4094792	Total Zinc (Zn)	2015/07/09	96	80 - 120	97	80 - 120	<5.0	ug/L	NC (1)	20		
4096103	Total Organic Carbon (C)	2015/07/08	100	80 - 120	100	80 - 120	<0.50	mg/L	5.7 (1)	20		
4096104	Total Organic Carbon (C)	2015/07/08	108	80 - 120	98	80 - 120	<0.50	mg/L	NC (1)	20		
4096184	Nitrogen (Ammonia Nitrogen)	2015/07/08	96	80 - 120	109	80 - 120	0.076, RDL=0.050	mg/L	NC (1)	25		
4096752	Total Alkalinity (Total as CaCO3)	2015/07/08	101 (4)	80 - 120	101	80 - 120	<5.0	mg/L	NC (5)	25		
4096766	Dissolved Chloride (Cl)	2015/07/10	112 (4)	80 - 120	115	80 - 120	<1.0	mg/L	NC (5)	25	107	80 - 120
4096767	Dissolved Sulphate (SO4)	2015/07/10	105 (4)	80 - 120	100	80 - 120	<2.0	mg/L	NC (5)	25		
4096769	Reactive Silica (SiO2)	2015/07/09	95 (4)	80 - 120	105	80 - 120	<0.50	mg/L	NC (5)	25		
4096770	Colour	2015/07/10			110	80 - 120	<5.0	TCU	0.15 (5)	20		
4096771	Orthophosphate (P)	2015/07/10	94 (4)	80 - 120	99	80 - 120	<0.010	mg/L	NC (5)	25		
4096777	Nitrate + Nitrite	2015/07/09	99 (4)	80 - 120	109	80 - 120	<0.050	mg/L	NC (5)	25		
4096781	Nitrite (N)	2015/07/10	92 (4)	80 - 120	105	80 - 120	<0.010	mg/L	NC (5)	25		
4096782	Total Alkalinity (Total as CaCO3)	2015/07/08	NC	80 - 120	101	80 - 120	<5.0	mg/L	NC (1)	25		
4096787	Dissolved Chloride (Cl)	2015/07/10	115	80 - 120	110	80 - 120	<1.0	mg/L	NC (1)	25	101	80 - 120
4096788	Dissolved Sulphate (SO4)	2015/07/10	100	80 - 120	102	80 - 120	<2.0	mg/L	NC (1)	25		
4096789	Reactive Silica (SiO2)	2015/07/09	105	80 - 120	103	80 - 120	<0.50	mg/L	NC (1)	25		
4096792	Colour	2015/07/10			99	80 - 120	<5.0	TCU	NC (1)	20		
4096793	Orthophosphate (P)	2015/07/10	101	80 - 120	99	80 - 120	<0.010	mg/L	NC (1)	25		
4096794	Nitrate + Nitrite	2015/07/09	98	80 - 120	107	80 - 120	0.054, RDL=0.050	mg/L	NC (1)	25		
4096799	Nitrite (N)	2015/07/10	105	80 - 120	94	80 - 120	<0.010	mg/L	NC (1)	25		
4099822	pH	2015/07/10							1.0 (6)	N/A	100	97 - 103
4099826	Conductivity	2015/07/10			103	80 - 120	1.0, RDL=1.0	uS/cm	0 (6)	25		
4102538	Turbidity	2015/07/13					<0.10	NTU	NC (1)	25	91	80 - 120

Maxxam Job #: B5C9254
Report Date: 2015/07/13

QUALITY ASSURANCE REPORT(CONT'D)

GHD Limited
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340
Sampler Initials: AF

QC Batch	Parameter	Date	Matrix Spike		Spiked Blank		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	Units	Value (%)	QC Limits	% Recovery	QC Limits
4102542	Turbidity	2015/07/13					<0.10	NTU	6.1 (1)	25	95	80 - 120

N/A = Not Applicable

Duplicate: Paired analysis of a separate portion of the same sample. Used to evaluate the variance in the measurement.

Matrix Spike: A sample to which a known amount of the analyte of interest has been added. Used to evaluate sample matrix interference.

QC Standard: A sample of known concentration prepared by an external agency under stringent conditions. Used as an independent check of method accuracy.

Spiked Blank: A blank matrix sample to which a known amount of the analyte, usually from a second source, has been added. Used to evaluate method accuracy.

Method Blank: A blank matrix containing all reagents used in the analytical procedure. Used to identify laboratory contamination.

NC (Matrix Spike): The recovery in the matrix spike was not calculated. The relative difference between the concentration in the parent sample and the spiked amount was too small to permit a reliable recovery calculation (matrix spike concentration was less than 2x that of the native sample concentration).

NC (Duplicate RPD): The duplicate RPD was not calculated. The concentration in the sample and/or duplicate was too low to permit a reliable RPD calculation (one or both samples < 5x RDL).

(1) Duplicate Parent ID

(2) Matrix Spike Parent ID [AOE403-05]

(3) Duplicate Parent ID [AOE402-05]

(4) Matrix Spike Parent ID [AOE402-01]

(5) Duplicate Parent ID [AOE402-01]

(6) Duplicate Parent ID [AOE407-01]

Maxxam Job #: B5C9254
Report Date: 2015/07/13

GHD Limited
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340
Sampler Initials: AF

VALIDATION SIGNATURE PAGE

The analytical data and all QC contained in this report were reviewed and validated by the following individual(s).

<Original signed by>

Kevin MacDonald, Inorganics Supervisor

<Original signed by>

Mike MacGillivray, Scientific Specialist (Inorganics)

Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(E), signing the reports. For Service Group specific validation please refer to the Validation Signature Page.



Maxxam Analytics International Corporation o/a Maxxam Analytics
200 Bluelwater Road, Bedford, Nova Scotia Canada B4B 1G9 Tel:(902) 420-0203 Toll-Free:800-563-6266 Fax:(902) 420-8612 www.maxxam.ca

Chain Of Custody Record

Page 1 of 1

INVOICE TO:		Report Information				Project Information		Laboratory Use Only			
Company Name #16276 Conestoga-Rovers and Associates Ltd GHD	Contact Name Amanda Facey	Company Name	Address	Quotation # 14-1601KG	P.O. # 20-019340	Maxxam Job # B5C9254	Bottle Order # 519518				
Address 45 Akerley Blvd Dartmouth NS B3B 1J7	Phone (902) 468-1248	Phone	Fax	Project # 088664-05	Project Name Atlantic Gold - Beaver Dam	Chain Of Custody Record	Project Manager				
Phone (902) 468-2207	Email afacey@craworld.com amanda.facey@ghd.com	Email		Site #	Sampled By AF, ZJ	C#519518-01-01	Michelle Hill				
Ref:		Special Instructions		ANALYSIS REQUESTED (PLEASE BE SPECIFIC)				Turnaround Time (TAT) Required:			
								Please provide advance notice for rush projects Regular (Standard) TAT: <input checked="" type="checkbox"/> (will be applied if Rush TAT is not specified) Standard TAT = 5-7 Working days for most tests. Please note: Standard TAT for certain tests such as BOD and Dioxins/Furans are > 5 days - contact your Project Manager for details. Job Specific Rush TAT (if applies to entire submission) Date Required: <input type="text"/> Time Required: <input type="text"/>			
SAMPLES MUST BE KEPT COOL (< 10°C) FROM TIME OF SAMPLING UNTIL DELIVERY TO MAXXAM											
Sample Barcode Label	Sample (Location) Identification	Date Sampled	Time Sampled	Matrix	Field Filtered & Preserved	Lab Filtration Required	RCAp-MS Total Metals in Water	Mercury - Total (CVAA,LL)	# of Bottles	Comments / Hazards / Other Required Analysis	
1	SW-1	30 JUN 15		SW			X	X	5		
2	SW-2A						X	X			
3	SW-4A						X	X			
4	SW-5						X	X			
5	SW-6A						X	X			
6	SW-6AD						X	X			
7	SW-9						X	X			
8	SW-10						X	X		2015 JUL 3 12:25	
9										15 JUL 3 8:48	
10											
** RELINQUISHED BY: (Signature/Print)		Date: (YY/MM/DD)	Time	RECEIVED BY: (Signature/Print)		Date: (YY/MM/DD)	Time	# jars used and not submitted	Lab Use Only		
<Origin <i>A Facey</i>		15/07/03		<Original <i>Joe Doyle</i>					Time Sensitive <input type="checkbox"/>	Temperature (°C) on Receipt <i>1 2 2</i>	Custody Seal Intact on Cooler? <input type="checkbox"/> Yes <input type="checkbox"/> No
* IT IS THE RESPONSIBILITY OF THE RELINQUISHER TO ENSURE THE ACCURACY OF THE CHAIN OF CUSTODY RECORD. AN INCOMPLETE CHAIN OF CUSTODY MAY RESULT IN ANALYTICAL TAT DELAYS.										White: Maxxam <input type="checkbox"/> Yellow: Client <input type="checkbox"/>	

Maxxam Analytics International Corporation o/a Maxxam Analytics

Your P.O. #: 20-019340
 Your Project #: 088664-05
 Site Location: ATLANTIC GOLD-BEAVER DAM
 Your C.O.C. #: 523658-01-01

Attention:Amanda Facey

GHD Limited
 45 Akerley Blvd
 Dartmouth , NS
 B3B 1J7

Report Date: 2015/08/07
 Report #: R3620816
 Version: 1 - Final

CERTIFICATE OF ANALYSIS

MAXXAM JOB #: B5F0835

Received: 2015/07/30, 09:12

Sample Matrix: Water
 # Samples Received: 8

Analyses	Quantity	Date Extracted	Date Analyzed	Laboratory Method	Reference
Carbonate, Bicarbonate and Hydroxide	8	N/A	2015/08/07 N/A		SM 22 4500-CO2 D
Alkalinity	8	N/A	2015/08/06 ATL SOP 00013		EPA 310.2 R1974 m
Chloride	8	N/A	2015/08/07 ATL SOP 00014		SM 22 4500-Cl- E m
Colour	8	N/A	2015/08/06 ATL SOP 00020		SM 22 2120C m
Conductance - water	8	N/A	2015/08/06 ATL SOP 00004		SM 22 2510B m
Hardness (calculated as CaCO ₃)	8	N/A	2015/08/06 ATL SOP 00048		SM 22 2340 B
Mercury - Total (CVAA,LL)	7	2015/08/04	2015/08/04 ATL SOP 00026		EPA 245.1 R3 m
Mercury - Total (CVAA,LL)	1	2015/08/06	2015/08/06 ATL SOP 00026		EPA 245.1 R3 m
Metals Water Total MS	8	2015/08/05	2015/08/06 ATL SOP 00058		EPA 6020A R1 m
Ion Balance (% Difference)	8	N/A	2015/08/07		Auto Calc.
Anion and Cation Sum	8	N/A	2015/08/07		Auto Calc.
Nitrogen Ammonia - water	8	N/A	2015/08/05 ATL SOP 00015		EPA 350.1 R2 m
Nitrogen - Nitrate + Nitrite	8	N/A	2015/08/07 ATL SOP 00016		USGS SOPINCF0452.2 m
Nitrogen - Nitrite	8	N/A	2015/08/06 ATL SOP 00017		SM 22 4500-NO2- B m
Nitrogen - Nitrate (as N)	8	N/A	2015/08/07 ATL SOP 00018		ASTM D3867
pH (1)	8	N/A	2015/08/06 ATL SOP 00003		SM 22 4500-H+ B m
Phosphorus - ortho	8	N/A	2015/08/06 ATL SOP 00021		EPA 365.2 m
Sat. pH and Langelier Index (@ 20C)	8	N/A	2015/08/07 ATL SOP 00049		Auto Calc.
Sat. pH and Langelier Index (@ 4C)	8	N/A	2015/08/07 ATL SOP 00049		Auto Calc.
Reactive Silica	8	N/A	2015/08/06 ATL SOP 00022		EPA 366.0 m
Sulphate	8	N/A	2015/08/07 ATL SOP 00023		EPA 375.4 R1978 m
Total Dissolved Solids (TDS calc)	8	N/A	2015/08/07		Auto Calc.
Organic carbon - Total (TOC) (2)	8	N/A	2015/08/05 ATL SOP 00037		SM 22 5310C m
Turbidity	8	N/A	2015/08/07 ATL SOP 00011		EPA 180.1 R2 m

Reference Method suffix "m" indicates test methods incorporate validated modifications from specific reference methods to improve performance.

* RPDs calculated using raw data. The rounding of final results may result in the apparent difference.

(1) The APHA Standard Method require pH to be analyzed within 15 minutes of sampling and therefore field analysis is required for compliance. All Laboratory pH analyses in this report are reported past the APHA Standard Method holding time.

(2) TOC / DOC present in the sample should be considered as non-purgeable TOC / DOC.

Your P.O. #: 20-019340
Your Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your C.O.C. #: 523658-01-01

Attention:Amanda Facey

GHD Limited
45 Akerley Blvd
Dartmouth , NS
B3B 1J7

Report Date: 2015/08/07
Report #: R3620816
Version: 1 - Final

CERTIFICATE OF ANALYSIS

MAXXAM JOB #: B5F0835

Received: 2015/07/30, 09:12

Encryption Key **<Original signed by>**

Rachael Mansfield
07 Aug 2015 16:34:59 -03:00

Please direct all questions regarding this Certificate of Analysis to your Project Manager.

Michelle Hill, Project Manager

Email: MHill@maxxam.ca

Phone# (902)420-0203 Ext:289

=====

Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(E), signing the reports. For Service Group specific validation please refer to the Validation Signature Page.

Maxxam Job #: B5F0835
Report Date: 2015/08/07

GHD Limited
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340

RESULTS OF ANALYSES OF WATER

Maxxam ID		ASJ208	ASJ209	ASJ210		ASJ211		
Sampling Date		2015/07/29 14:15	2015/07/29 14:45	2015/07/29 15:27		2015/07/29 15:55		
COC Number		523658-01-01	523658-01-01	523658-01-01		523658-01-01		
	Units	SW-1	SW-2A	SW-4A	RDL	SW-5	RDL	QC Batch
Calculated Parameters								
Anion Sum	me/L	0.0800	0.0800	0.0700	N/A	0.360	N/A	4128401
Bicarb. Alkalinity (calc. as CaCO ₃)	mg/L	<1.0	<1.0	<1.0	1.0	11	1.0	4128398
Calculated TDS	mg/L	10	9.0	9.0	1.0	21	1.0	4127241
Carb. Alkalinity (calc. as CaCO ₃)	mg/L	<1.0	<1.0	<1.0	1.0	<1.0	1.0	4128398
Cation Sum	me/L	0.180	0.180	0.190	N/A	0.340	N/A	4128401
Hardness (CaCO ₃)	mg/L	3.3	2.9	3.6	1.0	12	1.0	4128399
Ion Balance (% Difference)	%	38.5	38.5	46.2	N/A	2.86	N/A	4128400
Langelier Index (@ 20C)	N/A	NC	NC	NC		-2.84		4127239
Langelier Index (@ 4C)	N/A	NC	NC	NC		-3.09		4127240
Nitrate (N)	mg/L	0.051	<0.050	<0.050	0.050	<0.050	0.050	4128388
Saturation pH (@ 20C)	N/A	NC	NC	NC		9.66		4127239
Saturation pH (@ 4C)	N/A	NC	NC	NC		9.92		4127240
Inorganics								
Total Alkalinity (Total as CaCO ₃)	mg/L	<5.0	<5.0	<5.0	5.0	11	5.0	4134526
Dissolved Chloride (Cl)	mg/L	2.8	2.8	2.6	1.0	1.7	1.0	4134529
Colour	TCU	160	180	170	25	24	5.0	4134542
Nitrate + Nitrite	mg/L	0.051	<0.050	<0.050	0.050	<0.050	0.050	4134544
Nitrite (N)	mg/L	<0.010	<0.010	<0.010	0.010	<0.010	0.010	4134547
Nitrogen (Ammonia Nitrogen)	mg/L	<0.050	<0.050	<0.050	0.050	<0.050	0.050	4134239
Total Organic Carbon (C)	mg/L	12	13	18	0.50	5.3	0.50	4133762
Orthophosphate (P)	mg/L	<0.010	<0.010	<0.010	0.010	<0.010	0.010	4134543
pH	pH	5.57	5.26	5.09	N/A	6.83	N/A	4135976
Reactive Silica (SiO ₂)	mg/L	2.6	2.6	2.3	0.50	0.77	0.50	4134540
Dissolved Sulphate (SO ₄)	mg/L	<2.0	<2.0	<2.0	2.0	4.5	2.0	4134539
Turbidity	NTU	1.1	0.97	0.81	0.10	0.91	0.10	4138515
Conductivity	uS/cm	18	19	19	1.0	32	1.0	4135978

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

N/A = Not Applicable

Maxxam Job #: B5F0835
Report Date: 2015/08/07

GHD Limited
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340

RESULTS OF ANALYSES OF WATER

Maxxam ID		ASJ212		ASJ213		ASJ214		ASJ215	
Sampling Date		2015/07/29 16:21		2015/07/29 16:48		2015/07/29 15:48		2015/07/29 16:48	
COC Number		523658-01-01		523658-01-01		523658-01-01		523658-01-01	
	Units	SW-6A	QC Batch	SW-9	RDL	SW-10	RDL	SW-9D	RDL QC Batch

Calculated Parameters

Anion Sum	me/L	0.0700	4128401	0.250	N/A	0.580	N/A	0.250	N/A	4128401
Bicarb. Alkalinity (calc. as CaCO3)	mg/L	<1.0	4128398	5.6	1.0	11	1.0	5.5	1.0	4128398
Calculated TDS	mg/L	8.0	4128391	18	1.0	39	1.0	18	1.0	4128391
Carb. Alkalinity (calc. as CaCO3)	mg/L	<1.0	4128398	<1.0	1.0	<1.0	1.0	<1.0	1.0	4128398
Cation Sum	me/L	0.170	4128401	0.330	N/A	0.510	N/A	0.340	N/A	4128401
Hardness (CaCO3)	mg/L	3.2	4128399	8.0	1.0	20	1.0	8.2	1.0	4128399
Ion Balance (% Difference)	%	41.7	4128400	13.8	N/A	6.42	N/A	15.3	N/A	4128400
Langelier Index (@ 20C)	N/A	NC	4128389	-3.90		-3.09		-3.83		4128389
Langelier Index (@ 4C)	N/A	NC	4128390	-4.16		-3.35		-4.08		4128390
Nitrate (N)	mg/L	<0.050	4128388	0.064	0.050	0.070	0.050	<0.050	0.050	4128388
Saturation pH (@ 20C)	N/A	NC	4128389	10.3		9.46		10.3		4128389
Saturation pH (@ 4C)	N/A	NC	4128390	10.5		9.71		10.5		4128390

Inorganics

Total Alkalinity (Total as CaCO3)	mg/L	<5.0	4134526	5.6	5.0	11	5.0	5.5	5.0	4134552
Dissolved Chloride (Cl)	mg/L	2.4	4134529	4.8	1.0	2.2	1.0	4.9	1.0	4134582
Colour	TCU	140	4134542	130	25	<5.0	5.0	130	25	4134598
Nitrate + Nitrite	mg/L	<0.050	4134544	0.064	0.050	0.070	0.050	<0.050	0.050	4134601
Nitrite (N)	mg/L	<0.010	4134547	<0.010	0.010	<0.010	0.010	<0.010	0.010	4134603
Nitrogen (Ammonia Nitrogen)	mg/L	<0.050	4134239	<0.050	0.050	<0.050	0.050	<0.050	0.050	4134239
Total Organic Carbon (C)	mg/L	13	4133762	12	0.50	1.8	0.50	12	0.50	4133762
Orthophosphate (P)	mg/L	<0.010	4134543	<0.010	0.010	0.012	0.010	<0.010	0.010	4134599
pH	pH	5.50	4135976	6.36	N/A	6.37	N/A	6.43	N/A	4135976
Reactive Silica (SiO2)	mg/L	1.6	4134540	2.7	0.50	6.0	0.50	2.6	0.50	4134596
Dissolved Sulphate (SO4)	mg/L	<2.0	4134539	<2.0	2.0	14	2.0	<2.0	2.0	4134594
Turbidity	NTU	0.49	4138515	1.0	0.10	<0.10	0.10	0.93	0.10	4138515
Conductivity	uS/cm	16	4135978	30	1.0	54	1.0	30	1.0	4135978

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

N/A = Not Applicable

Maxxam Job #: B5F0835
Report Date: 2015/08/07

GHD Limited
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340

MERCURY BY COLD VAPOUR AA (WATER)

Maxxam ID		ASJ208	ASJ209	ASJ210	ASJ211	ASJ212	ASJ213		
Sampling Date		2015/07/29 14:15	2015/07/29 14:45	2015/07/29 15:27	2015/07/29 15:55	2015/07/29 16:21	2015/07/29 16:48		
COC Number		523658-01-01	523658-01-01	523658-01-01	523658-01-01	523658-01-01	523658-01-01		
	Units	SW-1	SW-2A	SW-4A	SW-5	SW-6A	SW-9	RDL	QC Batch

Metals

Total Mercury (Hg)	ug/L	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	0.013	4133159
--------------------	------	--------	--------	--------	--------	--------	--------	-------	---------

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Maxxam ID		ASJ214		ASJ215				
Sampling Date		2015/07/29 15:48		2015/07/29 16:48				
COC Number		523658-01-01		523658-01-01				
	Units	SW-10	QC Batch	SW-9D	RDL	QC Batch		
Metals								
Total Mercury (Hg)	ug/L	<0.013	4133159	0.013	0.013	4136068		
RDL = Reportable Detection Limit								
QC Batch = Quality Control Batch								

Maxxam Job #: B5F0835
Report Date: 2015/08/07

GHD Limited
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340

ELEMENTS BY ICP/MS (WATER)

Maxxam ID		ASJ208	ASJ209	ASJ210	ASJ211	ASJ212	ASJ213	
Sampling Date		2015/07/29 14:15	2015/07/29 14:45	2015/07/29 15:27	2015/07/29 15:55	2015/07/29 16:21	2015/07/29 16:48	
COC Number		523658-01-01	523658-01-01	523658-01-01	523658-01-01	523658-01-01	523658-01-01	
	Units	SW-1	SW-2A	SW-4A	SW-5	SW-6A	SW-9	RDL QC Batch

Metals

Total Aluminum (Al)	ug/L	280	300	350	43	320	260	5.0	4133678
Total Antimony (Sb)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	4133678
Total Arsenic (As)	ug/L	3.7	1.5	5.6	20	2.8	<1.0	1.0	4133678
Total Barium (Ba)	ug/L	3.2	3.5	3.7	4.1	3.1	3.4	1.0	4133678
Total Beryllium (Be)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	4133678
Total Bismuth (Bi)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	4133678
Total Boron (B)	ug/L	<50	<50	<50	<50	<50	<50	50	4133678
Total Cadmium (Cd)	ug/L	0.014	0.017	0.014	<0.010	0.012	<0.010	0.010	4133678
Total Calcium (Ca)	ug/L	790	620	860	3800	770	1800	100	4133678
Total Chromium (Cr)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	4133678
Total Cobalt (Co)	ug/L	<0.40	<0.40	0.63	<0.40	<0.40	<0.40	0.40	4133678
Total Copper (Cu)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	4133678
Total Iron (Fe)	ug/L	750	820	840	610	750	490	50	4133678
Total Lead (Pb)	ug/L	<0.50	0.62	0.56	<0.50	<0.50	<0.50	0.50	4133678
Total Magnesium (Mg)	ug/L	310	330	360	720	310	830	100	4133678
Total Manganese (Mn)	ug/L	43	40	42	45	38	56	2.0	4133678
Total Molybdenum (Mo)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	4133678
Total Nickel (Ni)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	4133678
Total Phosphorus (P)	ug/L	170	170	150	170	160	160	100	4133678
Total Potassium (K)	ug/L	210	200	180	350	200	210	100	4133678
Total Selenium (Se)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	4133678
Total Silver (Ag)	ug/L	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	0.10	4133678
Total Sodium (Na)	ug/L	1900	1900	1700	1500	1700	3300	100	4133678
Total Strontium (Sr)	ug/L	6.3	6.3	6.4	25	5.5	6.5	2.0	4133678
Total Thallium (Tl)	ug/L	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	0.10	4133678
Total Tin (Sn)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	4133678
Total Titanium (Ti)	ug/L	3.7	4.6	3.8	<2.0	3.5	3.6	2.0	4133678
Total Uranium (U)	ug/L	<0.10	<0.10	<0.10	<0.10	<0.10	0.12	0.10	4133678
Total Vanadium (V)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	4133678
Total Zinc (Zn)	ug/L	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	5.0	4133678

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Maxxam Job #: B5F0835
Report Date: 2015/08/07

GHD Limited
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340

ELEMENTS BY ICP/MS (WATER)

Maxxam ID		ASJ214	ASJ215		
Sampling Date		2015/07/29 15:48	2015/07/29 16:48		
COC Number		523658-01-01	523658-01-01		
	Units	SW-10	SW-9D	RDL	QC Batch
Metals					
Total Aluminum (Al)	ug/L	28	270	5.0	4133678
Total Antimony (Sb)	ug/L	<1.0	<1.0	1.0	4133678
Total Arsenic (As)	ug/L	36	<1.0	1.0	4133678
Total Barium (Ba)	ug/L	7.3	3.3	1.0	4133678
Total Beryllium (Be)	ug/L	<1.0	<1.0	1.0	4133678
Total Bismuth (Bi)	ug/L	<2.0	<2.0	2.0	4133678
Total Boron (B)	ug/L	<50	<50	50	4133678
Total Cadmium (Cd)	ug/L	0.10	<0.010	0.010	4133678
Total Calcium (Ca)	ug/L	6400	1900	100	4133678
Total Chromium (Cr)	ug/L	<1.0	1.3	1.0	4133678
Total Cobalt (Co)	ug/L	1.4	<0.40	0.40	4133678
Total Copper (Cu)	ug/L	3.6	<2.0	2.0	4133678
Total Iron (Fe)	ug/L	78	510	50	4133678
Total Lead (Pb)	ug/L	<0.50	<0.50	0.50	4133678
Total Magnesium (Mg)	ug/L	900	840	100	4133678
Total Manganese (Mn)	ug/L	78	60	2.0	4133678
Total Molybdenum (Mo)	ug/L	<2.0	<2.0	2.0	4133678
Total Nickel (Ni)	ug/L	8.7	<2.0	2.0	4133678
Total Phosphorus (P)	ug/L	170	170	100	4133678
Total Potassium (K)	ug/L	790	240	100	4133678
Total Selenium (Se)	ug/L	<1.0	<1.0	1.0	4133678
Total Silver (Ag)	ug/L	<0.10	<0.10	0.10	4133678
Total Sodium (Na)	ug/L	2100	3500	100	4133678
Total Strontium (Sr)	ug/L	26	5.9	2.0	4133678
Total Thallium (Tl)	ug/L	<0.10	<0.10	0.10	4133678
Total Tin (Sn)	ug/L	<2.0	<2.0	2.0	4133678
Total Titanium (Ti)	ug/L	<2.0	4.9	2.0	4133678
Total Uranium (U)	ug/L	<0.10	0.13	0.10	4133678
Total Vanadium (V)	ug/L	<2.0	<2.0	2.0	4133678
Total Zinc (Zn)	ug/L	19	<5.0	5.0	4133678
RDL = Reportable Detection Limit					
QC Batch = Quality Control Batch					

Maxxam Job #: B5F0835
Report Date: 2015/08/07

GHD Limited
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340

GENERAL COMMENTS

Each temperature is the average of up to three cooler temperatures taken at receipt

Package 1	5.0°C
-----------	-------

Sample ASJ208-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample ASJ209-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample ASJ210-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample ASJ212-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample ASJ213-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample ASJ214-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample ASJ215-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Results relate only to the items tested.

Maxxam Job #: B5F0835
Report Date: 2015/08/07

QUALITY ASSURANCE REPORT

GHD Limited
Client Project #: 088664-05

Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340

QC Batch	Parameter	Date	Matrix Spike		Spiked Blank		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	Units	Value (%)	QC Limits	% Recovery	QC Limits
4133159	Total Mercury (Hg)	2015/08/05	113	80 - 120	105	80 - 120	<0.013	ug/L	NC (1)	20		
4133678	Total Aluminum (Al)	2015/08/07	102	80 - 120	103	80 - 120	<5.0	ug/L	NC (1)	20		
4133678	Total Antimony (Sb)	2015/08/07	105	80 - 120	103	80 - 120	<1.0	ug/L	NC (1)	20		
4133678	Total Arsenic (As)	2015/08/07	101	80 - 120	102	80 - 120	<1.0	ug/L	NC (1)	20		
4133678	Total Barium (Ba)	2015/08/07	100	80 - 120	100	80 - 120	<1.0	ug/L	NC (1)	20		
4133678	Total Beryllium (Be)	2015/08/07	102	80 - 120	102	80 - 120	<1.0	ug/L	NC (1)	20		
4133678	Total Bismuth (Bi)	2015/08/07	104	80 - 120	104	80 - 120	<2.0	ug/L	NC (1)	20		
4133678	Total Boron (B)	2015/08/07	105	80 - 120	105	80 - 120	<50	ug/L	NC (1)	20		
4133678	Total Cadmium (Cd)	2015/08/07	102	80 - 120	103	80 - 120	<0.010	ug/L	NC (1)	20		
4133678	Total Calcium (Ca)	2015/08/07	102	80 - 120	103	80 - 120	<100	ug/L	NC (1)	20		
4133678	Total Chromium (Cr)	2015/08/07	99	80 - 120	100	80 - 120	<1.0	ug/L	NC (1)	20		
4133678	Total Cobalt (Co)	2015/08/07	101	80 - 120	100	80 - 120	<0.40	ug/L	NC (1)	20		
4133678	Total Copper (Cu)	2015/08/07	NC	80 - 120	100	80 - 120	<2.0	ug/L	NC (1)	20		
4133678	Total Iron (Fe)	2015/08/07	105	80 - 120	106	80 - 120	<50	ug/L	NC (1)	20		
4133678	Total Lead (Pb)	2015/08/07	102	80 - 120	103	80 - 120	<0.50	ug/L	NC (1)	20		
4133678	Total Magnesium (Mg)	2015/08/07	105	80 - 120	106	80 - 120	<100	ug/L	NC (1)	20		
4133678	Total Manganese (Mn)	2015/08/07	102	80 - 120	103	80 - 120	<2.0	ug/L	NC (1)	20		
4133678	Total Molybdenum (Mo)	2015/08/07	106	80 - 120	106	80 - 120	<2.0	ug/L	NC (1)	20		
4133678	Total Nickel (Ni)	2015/08/07	100	80 - 120	101	80 - 120	<2.0	ug/L	NC (1)	20		
4133678	Total Phosphorus (P)	2015/08/07	105	80 - 120	106	80 - 120	150, RDL=100	ug/L	NC (1)	20		
4133678	Total Potassium (K)	2015/08/07	101	80 - 120	101	80 - 120	<100	ug/L	NC (1)	20		
4133678	Total Selenium (Se)	2015/08/07	101	80 - 120	100	80 - 120	<1.0	ug/L	NC (1)	20		
4133678	Total Silver (Ag)	2015/08/07	107	80 - 120	107	80 - 120	<0.10	ug/L	NC (1)	20		
4133678	Total Sodium (Na)	2015/08/07	103	80 - 120	104	80 - 120	<100	ug/L	1.7 (1)	20		
4133678	Total Strontium (Sr)	2015/08/07	103	80 - 120	104	80 - 120	<2.0	ug/L	NC (1)	20		
4133678	Total Thallium (Tl)	2015/08/07	101	80 - 120	102	80 - 120	<0.10	ug/L	NC (1)	20		
4133678	Total Tin (Sn)	2015/08/07	104	80 - 120	106	80 - 120	<2.0	ug/L	NC (1)	20		
4133678	Total Titanium (Ti)	2015/08/07	102	80 - 120	100	80 - 120	<2.0	ug/L	NC (1)	20		
4133678	Total Uranium (U)	2015/08/07	108	80 - 120	108	80 - 120	<0.10	ug/L	NC (1)	20		
4133678	Total Vanadium (V)	2015/08/07	102	80 - 120	103	80 - 120	<2.0	ug/L	NC (1)	20		
4133678	Total Zinc (Zn)	2015/08/07	100	80 - 120	101	80 - 120	<5.0	ug/L	NC (1)	20		

Maxxam Job #: B5F0835
Report Date: 2015/08/07

QUALITY ASSURANCE REPORT(CONT'D)

GHD Limited
Client Project #: 088664-05

Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340

QC Batch	Parameter	Date	Matrix Spike		Spiked Blank		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	Units	Value (%)	QC Limits	% Recovery	QC Limits
4133762	Total Organic Carbon (C)	2015/08/05	NC	80 - 120	103	80 - 120	<0.50	mg/L	1.3 (1)	20		
4134239	Nitrogen (Ammonia Nitrogen)	2015/08/05	87	80 - 120	93	80 - 120	<0.050	mg/L	NC (1)	20		
4134526	Total Alkalinity (Total as CaCO3)	2015/08/06	101	80 - 120	104	80 - 120	<5.0	mg/L	NC (1)	25		
4134529	Dissolved Chloride (Cl)	2015/08/07	NC	80 - 120	98	80 - 120	<1.0	mg/L	0.91 (1)	25	105	80 - 120
4134539	Dissolved Sulphate (SO4)	2015/08/07	115	80 - 120	104	80 - 120	<2.0	mg/L	NC (1)	25		
4134540	Reactive Silica (SiO2)	2015/08/06	97	80 - 120	99	80 - 120	<0.50	mg/L	1.7 (1)	25		
4134542	Colour	2015/08/06			95	80 - 120	<5.0	TCU	3.7 (1)	20		
4134543	Orthophosphate (P)	2015/08/06	102	80 - 120	99	80 - 120	<0.010	mg/L	NC (1)	25		
4134544	Nitrate + Nitrite	2015/08/07	99	80 - 120	100	80 - 120	<0.050	mg/L	NC (1)	25		
4134547	Nitrite (N)	2015/08/06	94	80 - 120	97	80 - 120	<0.010	mg/L	NC (1)	25		
4134552	Total Alkalinity (Total as CaCO3)	2015/08/06	104	80 - 120	107	80 - 120	<5.0	mg/L	NC (1)	25		
4134582	Dissolved Chloride (Cl)	2015/08/07	NC	80 - 120	108	80 - 120	<1.0	mg/L	5.1 (1)	25	101	80 - 120
4134594	Dissolved Sulphate (SO4)	2015/08/07	109	80 - 120	119	80 - 120	<2.0	mg/L	NC (1)	25		
4134596	Reactive Silica (SiO2)	2015/08/06	NC	80 - 120	97	80 - 120	<0.50	mg/L	8.2 (1)	25		
4134598	Colour	2015/08/06			96	80 - 120	<5.0	TCU	NC (1)	20		
4134599	Orthophosphate (P)	2015/08/06	95	80 - 120	98	80 - 120	<0.010	mg/L	NC (1)	25		
4134601	Nitrate + Nitrite	2015/08/07	95	80 - 120	97	80 - 120	<0.050	mg/L	NC (1)	25		
4134603	Nitrite (N)	2015/08/06	99	80 - 120	99	80 - 120	<0.010	mg/L	NC (1)	25		
4135976	pH	2015/08/06							0.66 (1)	N/A	101	97 - 103
4135978	Conductivity	2015/08/06			99	80 - 120	1.1, RDL=1.0	uS/cm	1.1 (1)	25		
4136068	Total Mercury (Hg)	2015/08/06	99	80 - 120	89	80 - 120	<0.013	ug/L	NC (1)	20		

Maxxam Job #: B5F0835
Report Date: 2015/08/07

QUALITY ASSURANCE REPORT(CONT'D)

GHD Limited
Client Project #: 088664-05

Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340

QC Batch	Parameter	Date	Matrix Spike		Spiked Blank		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	Units	Value (%)	QC Limits	% Recovery	QC Limits
4138515	Turbidity	2015/08/07					<0.10	NTU	NC (1)	25	102	80 - 120

N/A = Not Applicable

Duplicate: Paired analysis of a separate portion of the same sample. Used to evaluate the variance in the measurement.

Matrix Spike: A sample to which a known amount of the analyte of interest has been added. Used to evaluate sample matrix interference.

QC Standard: A sample of known concentration prepared by an external agency under stringent conditions. Used as an independent check of method accuracy.

Spiked Blank: A blank matrix sample to which a known amount of the analyte, usually from a second source, has been added. Used to evaluate method accuracy.

Method Blank: A blank matrix containing all reagents used in the analytical procedure. Used to identify laboratory contamination.

NC (Matrix Spike): The recovery in the matrix spike was not calculated. The relative difference between the concentration in the parent sample and the spiked amount was too small to permit a reliable recovery calculation (matrix spike concentration was less than 2x that of the native sample concentration).

NC (Duplicate RPD): The duplicate RPD was not calculated. The concentration in the sample and/or duplicate was too low to permit a reliable RPD calculation (one or both samples < 5x RDL).

(1) Duplicate Parent ID

Maxxam Job #: B5F0835
Report Date: 2015/08/07

GHD Limited
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340

VALIDATION SIGNATURE PAGE

The analytical data and all QC contained in this report were reviewed and validated by the following individual(s).

<Original signed by>

Kevin MacDonald, Inorganics Supervisor

Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(E), signing the reports. For Service Group specific validation please refer to the Validation Signature Page.



Maxxam Analytics International Corporation a/k/a Maxxam Analytics
200 Bluewater Road, Bedford, Nova Scotia Canada B4B 1G9 Tel.(902) 420-0203 Toll-Free 800-563-6265 Fax.(902) 420-8612 www.maxxam.ca

Chain Of Custody Record									
Page 1 of 1									
INVOICE TO:		Report Information			Project Information			Laboratory Use Only	
Company Name Contact Name Address Phone Email	#16276 GHD Limited Trina Jeffrey 45 Akerley Blvd Dartmouth NS B3B 1J7 (902) 468-1248 tjeffrey@craworld.com	Company Name Contact Name Address Phone Email	Amanda Facey amanda.facey@ghd.com, NationalEDDSsupport@maxxa	Quotation # P.O. # Project # Project Name Site # Sampled By	B46955 20-019340 088664-05 ATLANTIC GOLD - BEAVERDALE Dawn Negus / Zach Jewkes	Maxxam Job # Bottle Order #	BSF0835 523658	Chain Of Custody Record Project Manager	Michelle Hill C#523658-01-01
Regulatory Criteria:		Special Instructions			ANALYSIS REQUESTED (PLEASE BE SPECIFIC)				
** Specify Matrix: Surface/Ground/Tapwater/Sewage/Effluent/Seawater Potable/Nonpotable/Tissue/Soil/Sludge/Metal									
SAMPLES MUST BE KEPT COOL (< 10°C) FROM TIME OF SAMPLING UNTIL DELIVERY TO MAXXAM									
Sample Barcode Label	Sample (Location) Identification	Date Sampled	Time Sampled	Matrix	Field Filtered & Enveloped Lab Filtration Required	RCap-MS Total Metals in Water	Mercury - Total (CVA,LL)	# Bottles	Comments / Hazards / Other Required Analysis
1	SW-1	29/7/15	14:15	SW	X	X	X	5	
2	SW-2A	29/7/15	14:45	SW	X	X	X	5	
3	SW-4A	29/7/15	15:27	SW	X	X	X	5	
	SW-5	29/7/15	15:55	SW	X	X	X	5	
	SW-6A	29/7/15	16:21	SW	X	X	X	5	
	SW-9	29/7/15	16:48	SW	X	X	X	5	15 JUL 30 0:12:14
	SW-10	29/7/15	15:48	SW	X	X	X	5	
	SW-9D	29/7/15	16:48	SW	X	X	X	5	15 JUL 30 0:12
RELINQUISHED BY: (Signature/Print) <u>Dawn Negus</u> Date: (YY/MM/DD) <u>15/07/15</u> Time: <u>9:12</u> RECEIVED BY: (Signature/Print) <u>Sara Mason</u> Date: (YY/MM/DD) <u>15/07/15</u> Time: <u>9:12</u> # Jars used and not submitted: <u>0</u> Lab Use Only									
Time Sensitive: <input type="checkbox"/> Temperature (°C) on Receipt: <u>6 6 3</u> Custody Seal Intact on Cooler? <input type="checkbox"/> Yes <input type="checkbox"/> No									
* IT IS THE RESPONSIBILITY OF THE RELINQUISHER TO ENSURE THE ACCURACY OF THE CHAIN OF CUSTODY RECORD. AN INCOMPLETE CHAIN OF CUSTODY MAY RESULT IN ANALYTICAL TAT DELAYS.									



BSF0835

Maxxam Analytics International Corporation a/k/a Maxxam Analytics

Your P.O. #: 20-019340
 Your Project #: 088664-05
 Site Location: ATLANTIC GOLD-BEAVER DAM
 Your C.O.C. #: N/A

Attention:Dawn Negus

GHD Limited
 45 Akerley Blvd
 Dartmouth , NS
 B3B 1J7

Report Date: 2015/09/01
 Report #: R3647471
 Version: 1 - Final

CERTIFICATE OF ANALYSIS

MAXXAM JOB #: B5H0151

Received: 2015/08/25, 10:09

Sample Matrix: Water
 # Samples Received: 8

Analyses	Quantity	Date Extracted	Date Analyzed	Laboratory Method	Reference
Carbonate, Bicarbonate and Hydroxide	3	N/A	2015/08/28	N/A	SM 22 4500-CO2 D
Carbonate, Bicarbonate and Hydroxide	5	N/A	2015/08/31	N/A	SM 22 4500-CO2 D
Alkalinity	8	N/A	2015/08/31	ATL SOP 00013	EPA 310.2 R1974 m
Chloride	8	N/A	2015/09/01	ATL SOP 00014	SM 22 4500-Cl- E m
Colour	8	N/A	2015/08/31	ATL SOP 00020	SM 22 2120C m
Conductance - water	8	N/A	2015/08/28	ATL SOP 00004	SM 22 2510B m
Hardness (calculated as CaCO ₃)	8	N/A	2015/09/01	ATL SOP 00048	SM 22 2340 B
Mercury - Total (CVAA,LL)	8	2015/08/31	2015/08/31	ATL SOP 00026	EPA 245.1 R3 m
Metals Water Total MS	8	2015/08/28	2015/08/31	ATL SOP 00058	EPA 6020A R1 m
Ion Balance (% Difference)	8	N/A	2015/09/01		Auto Calc.
Anion and Cation Sum	8	N/A	2015/09/01		Auto Calc.
Nitrogen Ammonia - water	8	N/A	2015/08/31	ATL SOP 00015	EPA 350.1 R2 m
Nitrogen - Nitrate + Nitrite	8	N/A	2015/09/01	ATL SOP 00016	USGS SOPINCF0452.2 m
Nitrogen - Nitrite	8	N/A	2015/08/31	ATL SOP 00017	SM 22 4500-NO2- B m
Nitrogen - Nitrate (as N)	8	N/A	2015/09/01	ATL SOP 00018	ASTM D3867
pH (1)	8	N/A	2015/08/28	ATL SOP 00003	SM 22 4500-H+ B m
Phosphorus - ortho	8	N/A	2015/08/31	ATL SOP 00021	EPA 365.2 m
Sat. pH and Langelier Index (@ 20C)	8	N/A	2015/09/01	ATL SOP 00049	Auto Calc.
Sat. pH and Langelier Index (@ 4C)	8	N/A	2015/09/01	ATL SOP 00049	Auto Calc.
Reactive Silica	8	N/A	2015/09/01	ATL SOP 00022	EPA 366.0 m
Sulphate	8	N/A	2015/09/01	ATL SOP 00023	EPA 375.4 R1978 m
Total Dissolved Solids (TDS calc)	8	N/A	2015/09/01		Auto Calc.
Organic carbon - Total (TOC) (2)	8	N/A	2015/09/01	ATL SOP 00037	SM 22 5310C m
Turbidity	8	N/A	2015/08/28	ATL SOP 00011	EPA 180.1 R2 m

Reference Method suffix "m" indicates test methods incorporate validated modifications from specific reference methods to improve performance.

* RPDs calculated using raw data. The rounding of final results may result in the apparent difference.

(1) The APHA Standard Method require pH to be analyzed within 15 minutes of sampling and therefore field analysis is required for compliance. All Laboratory pH analyses in this report are reported past the APHA Standard Method holding time.

(2) TOC / DOC present in the sample should be considered as non-purgeable TOC / DOC.

Your P.O. #: 20-019340
Your Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your C.O.C. #: N/A

Attention:Dawn Negus

GHD Limited
45 Akerley Blvd
Dartmouth , NS
B3B 1J7

Report Date: 2015/09/01
Report #: R3647471
Version: 1 - Final

CERTIFICATE OF ANALYSIS

MAXXAM JOB #: B5H0151

Received: 2015/08/25, 10:09

Encryption Key *<Original signed hv>* Rachael Mansfield
 ✓ 01 Sep 2015 16:16:12 -03:00

Please direct all questions regarding this Certificate of Analysis to your Project Manager.

Michelle Hill, Project Manager

Email: MHill@maxxam.ca

Phone# (902)420-0203 Ext:289

=====

Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(E), signing the reports. For Service Group specific validation please refer to the Validation Signature Page.

Maxxam Job #: B5H0151
Report Date: 2015/09/01

GHD Limited
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340
Sampler Initials: DN

RESULTS OF ANALYSES OF WATER

Maxxam ID		AWD356	<th>AWD357</th> <th>AWD358</th> <td></td> <td></td> <th>AWD359</th> <td></td> <td></td>	AWD357	AWD358			AWD359			
Sampling Date		2015/08/24 14:04		2015/08/24 10:40	2015/08/24 11:30			2015/08/24 13:33			
COC Number		N/A		N/A	N/A			N/A			
	UNITS	SW-1	RDL	QC Batch	SW-2A	SW-4A	RDL	QC Batch	SW-5	RDL	QC Batch
Calculated Parameters											
Anion Sum	me/L	0.100	N/A	4164169	0.100	0.110	N/A	4164169	0.410	N/A	4164169
Bicarb. Alkalinity (calc. as CaCO ₃)	mg/L	<1.0	1.0	4164165	<1.0	<1.0	1.0	4164165	13	1.0	4164165
Calculated TDS	mg/L	12	1.0	4164173	12	12	1.0	4164173	25	1.0	4164173
Carb. Alkalinity (calc. as CaCO ₃)	mg/L	<1.0	1.0	4164165	<1.0	<1.0	1.0	4164165	<1.0	1.0	4164165
Cation Sum	me/L	0.230	N/A	4164169	0.220	0.230	N/A	4164169	0.420	N/A	4164169
Hardness (CaCO ₃)	mg/L	4.0	1.0	4164167	3.6	3.9	1.0	4164167	15	1.0	4164167
Ion Balance (% Difference)	%	39.4	N/A	4164168	37.5	35.3	N/A	4164168	1.20	N/A	4164168
Langelier Index (@ 20C)	N/A	NC		4164171	NC	NC		4164171	-2.55		4164171
Langelier Index (@ 4C)	N/A	NC		4164172	NC	NC		4164172	-2.80		4164172
Nitrate (N)	mg/L	<0.050	0.050	4164170	<0.050	<0.050	0.050	4164170	0.055	0.050	4164170
Saturation pH (@ 20C)	N/A	NC		4164171	NC	NC		4164171	9.50		4164171
Saturation pH (@ 4C)	N/A	NC		4164172	NC	NC		4164172	9.75		4164172
Inorganics											
Total Alkalinity (Total as CaCO ₃)	mg/L	<5.0	5.0	4168809	<5.0	<5.0	5.0	4168809	13	5.0	4168809
Dissolved Chloride (Cl)	mg/L	3.7	1.0	4168823	3.7	3.7	1.0	4168823	2.2	1.0	4168823
Colour	TCU	230	25	4168833	230	260	50	4168833	37	5.0	4168833
Nitrate + Nitrite	mg/L	<0.050	0.050	4168838	<0.050	<0.050	0.050	4168838	0.055	0.050	4168838
Nitrite (N)	mg/L	<0.010	0.010	4168842	<0.010	<0.010	0.010	4168842	<0.010	0.010	4168842
Nitrogen (Ammonia Nitrogen)	mg/L	<0.050	0.050	4169316	0.084	<0.050	0.050	4169316	<0.050	0.050	4169316
Total Organic Carbon (C)	mg/L	11 (1)	5.0	4172579	14 (1)	14 (1)	5.0	4172599	4.3	0.50	4172599
Orthophosphate (P)	mg/L	<0.010	0.010	4168837	<0.010	<0.010	0.010	4168837	0.011	0.010	4168837
pH	pH	5.59	N/A	4168309	5.16	4.93	N/A	4168309	6.95	N/A	4168375
Reactive Silica (SiO ₂)	mg/L	3.2	0.50	4168830	3.2	3.0	0.50	4168830	2.5	0.50	4168830
Dissolved Sulphate (SO ₄)	mg/L	<2.0	2.0	4168826	<2.0	<2.0	2.0	4168826	3.6	2.0	4168826
Turbidity	NTU	1.2	0.10	4168900	1.9	1.0	0.10	4168900	1.2	0.10	4168900
Conductivity	uS/cm	21	1.0	4168318	21	21	1.0	4168318	40	1.0	4168392
RDL = Reportable Detection Limit QC Batch = Quality Control Batch N/A = Not Applicable (1) Elevated reporting limit due to sample matrix.											

Maxxam Job #: B5H0151
Report Date: 2015/09/01

GHD Limited
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340
Sampler Initials: DN

RESULTS OF ANALYSES OF WATER

Maxxam ID		AWD360	AWD361		AWD362	AWD363		
Sampling Date		2015/08/24 12:27	2015/08/24 14:25		2015/08/24 13:52	2015/08/24 13:52		
COC Number		N/A	N/A		N/A	N/A		
	UNITS	SW-6A	SW-9	RDL	SW-10	SW-10D	RDL	QC Batch
Calculated Parameters								
Anion Sum	me/L	0.100	0.150	N/A	0.770	0.780	N/A	4164169
Bicarb. Alkalinity (calc. as CaCO3)	mg/L	<1.0	<1.0	1.0	25	25	1.0	4164165
Calculated TDS	mg/L	12	15	1.0	55	55	1.0	4164173
Carb. Alkalinity (calc. as CaCO3)	mg/L	<1.0	<1.0	1.0	<1.0	<1.0	1.0	4164165
Cation Sum	me/L	0.240	0.330	N/A	0.960	0.960	N/A	4164169
Hardness (CaCO3)	mg/L	4.4	7.5	1.0	30	30	1.0	4164167
Ion Balance (% Difference)	%	41.2	37.5	N/A	11.0	10.3	N/A	4164168
Langelier Index (@ 20C)	N/A	NC	NC		-2.67	-2.60		4164171
Langelier Index (@ 4C)	N/A	NC	NC		-2.92	-2.85		4164172
Nitrate (N)	mg/L	<0.050	<0.050	0.050	<0.050	<0.050	0.050	4164170
Saturation pH (@ 20C)	N/A	NC	NC		8.91	8.91		4164171
Saturation pH (@ 4C)	N/A	NC	NC		9.16	9.16		4164172
Inorganics								
Total Alkalinity (Total as CaCO3)	mg/L	<5.0	<5.0	5.0	25	25	5.0	4168809
Dissolved Chloride (Cl)	mg/L	3.5	5.4	1.0	2.9	3.1	1.0	4168823
Colour	TCU	220	180	25	100	110	25	4168833
Nitrate + Nitrite	mg/L	<0.050	<0.050	0.050	<0.050	<0.050	0.050	4168838
Nitrite (N)	mg/L	<0.010	<0.010	0.010	<0.010	<0.010	0.010	4168842
Nitrogen (Ammonia Nitrogen)	mg/L	<0.050	<0.050	0.050	0.10	0.19	0.050	4169316
Total Organic Carbon (C)	mg/L	12 (1)	11 (1)	5.0	7.6	7.4	0.50	4172599
Orthophosphate (P)	mg/L	<0.010	<0.010	0.010	0.064	0.064	0.010	4168837
pH	pH	5.37	6.05	N/A	6.24	6.31	N/A	4168354
Reactive Silica (SiO2)	mg/L	2.7	2.3	0.50	7.0	7.0	0.50	4168830
Dissolved Sulphate (SO4)	mg/L	<2.0	<2.0	2.0	8.8	8.9	2.0	4168826
Turbidity	NTU	0.54	0.82	0.10	10	8.3	0.10	4168900
Conductivity	uS/cm	20	29	1.0	75	76	1.0	4168347
RDL = Reportable Detection Limit								
QC Batch = Quality Control Batch								
N/A = Not Applicable								
(1) Elevated reporting limit due to sample matrix.								

Maxxam Job #: B5H0151
 Report Date: 2015/09/01

GHD Limited
 Client Project #: 088664-05
 Site Location: ATLANTIC GOLD-BEAVER DAM
 Your P.O. #: 20-019340
 Sampler Initials: DN

MERCURY BY COLD VAPOUR AA (WATER)

Maxxam ID		AWD356	AWD356	AWD357	AWD358	AWD359	AWD360	AWD361		
Sampling Date		2015/08/24 14:04	2015/08/24 14:04	2015/08/24 10:40	2015/08/24 11:30	2015/08/24 13:33	2015/08/24 12:27	2015/08/24 14:25		
COC Number		N/A	N/A	N/A	N/A	N/A	N/A	N/A		
	UNITS	SW-1 Lab-Dup		SW-2A	SW-4A	SW-5	SW-6A	SW-9	RDL	QC Batch

Metals

Total Mercury (Hg)	ug/L	0.032	0.035	0.035	0.028	0.027	0.035	0.032	0.013	4170872
--------------------	------	-------	-------	-------	-------	-------	-------	-------	-------	---------

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Lab-Dup = Laboratory Initiated Duplicate

Maxxam ID		AWD362	AWD363		
Sampling Date		2015/08/24 13:52	2015/08/24 13:52		
COC Number		N/A	N/A		
	UNITS	SW-10	SW-10D	RDL	QC Batch

Metals

Total Mercury (Hg)	ug/L	0.025	0.028	0.013	4170872
--------------------	------	-------	-------	-------	---------

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Maxxam Job #: B5H0151
Report Date: 2015/09/01

GHD Limited
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340
Sampler Initials: DN

ELEMENTS BY ICP/MS (WATER)

Maxxam ID		AWD356	AWD357	AWD358	AWD359	AWD360	AWD361	AWD362		
Sampling Date		2015/08/24 14:04	2015/08/24 10:40	2015/08/24 11:30	2015/08/24 13:33	2015/08/24 12:27	2015/08/24 14:25	2015/08/24 13:52		
COC Number		N/A								
	UNITS	SW-1	SW-2A	SW-4A	SW-5	SW-6A	SW-9	SW-10	RDL	QC Batch

Metals										
Total Aluminum (Al)	ug/L	390	400	390	52	470	320	220	5.0	4168208
Total Antimony (Sb)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	4168208
Total Arsenic (As)	ug/L	4.1	1.3	5.6	47	7.6	<1.0	380	1.0	4168208
Total Barium (Ba)	ug/L	4.2	4.6	3.4	4.5	3.8	4.2	7.1	1.0	4168208
Total Beryllium (Be)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	4168208
Total Bismuth (Bi)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	4168208
Total Boron (B)	ug/L	<50	<50	<50	<50	<50	<50	<50	50	4168208
Total Cadmium (Cd)	ug/L	0.036	0.022	0.021	<0.010	0.031	0.015	0.011	0.010	4168208
Total Calcium (Ca)	ug/L	900	770	930	4500	1000	1700	10000	100	4168208
Total Chromium (Cr)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	4168208
Total Cobalt (Co)	ug/L	0.57	0.53	0.48	<0.40	1.0	<0.40	2.2	0.40	4168208
Total Copper (Cu)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	4168208
Total Iron (Fe)	ug/L	1000	1000	1100	750	1500	580	6000	50	4168208
Total Lead (Pb)	ug/L	0.58	0.57	0.55	<0.50	<0.50	<0.50	1.1	0.50	4168208
Total Magnesium (Mg)	ug/L	420	420	370	870	430	810	1200	100	4168208
Total Manganese (Mn)	ug/L	65	58	51	97	100	76	290	2.0	4168208
Total Molybdenum (Mo)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	4168208
Total Nickel (Ni)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	6.2	2.0	4168208
Total Phosphorus (P)	ug/L	140	140	150	150	150	160	140	100	4168208
Total Potassium (K)	ug/L	190	170	200	450	240	180	1000	100	4168208
Total Selenium (Se)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	4168208
Total Silver (Ag)	ug/L	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	0.10	4168208
Total Sodium (Na)	ug/L	2400	2300	2200	2000	2200	3500	2500	100	4168208
Total Strontium (Sr)	ug/L	8.0	7.4	7.2	27	7.6	6.6	33	2.0	4168208
Total Thallium (Tl)	ug/L	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	0.10	4168208
Total Tin (Sn)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	4168208
Total Titanium (Ti)	ug/L	4.2	5.0	4.9	<2.0	4.3	4.3	2.8	2.0	4168208
Total Uranium (U)	ug/L	<0.10	<0.10	<0.10	<0.10	<0.10	0.11	0.21	0.10	4168208
Total Vanadium (V)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	4168208
Total Zinc (Zn)	ug/L	<5.0	<5.0	6.0	<5.0	<5.0	<5.0	<5.0	5.0	4168208

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Maxxam Job #: B5H0151
Report Date: 2015/09/01

GHD Limited
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340
Sampler Initials: DN

ELEMENTS BY ICP/MS (WATER)

Maxxam ID		AWD363		
Sampling Date		2015/08/24 13:52		
COC Number		N/A		
	UNITS	SW-10D	RDL	QC Batch
Metals				
Total Aluminum (Al)	ug/L	210	5.0	4168208
Total Antimony (Sb)	ug/L	<1.0	1.0	4168208
Total Arsenic (As)	ug/L	370	1.0	4168208
Total Barium (Ba)	ug/L	6.9	1.0	4168208
Total Beryllium (Be)	ug/L	<1.0	1.0	4168208
Total Bismuth (Bi)	ug/L	<2.0	2.0	4168208
Total Boron (B)	ug/L	<50	50	4168208
Total Cadmium (Cd)	ug/L	<0.010	0.010	4168208
Total Calcium (Ca)	ug/L	10000	100	4168208
Total Chromium (Cr)	ug/L	<1.0	1.0	4168208
Total Cobalt (Co)	ug/L	2.3	0.40	4168208
Total Copper (Cu)	ug/L	<2.0	2.0	4168208
Total Iron (Fe)	ug/L	5900	50	4168208
Total Lead (Pb)	ug/L	1.2	0.50	4168208
Total Magnesium (Mg)	ug/L	1200	100	4168208
Total Manganese (Mn)	ug/L	280	2.0	4168208
Total Molybdenum (Mo)	ug/L	<2.0	2.0	4168208
Total Nickel (Ni)	ug/L	6.1	2.0	4168208
Total Phosphorus (P)	ug/L	140	100	4168208
Total Potassium (K)	ug/L	1000	100	4168208
Total Selenium (Se)	ug/L	<1.0	1.0	4168208
Total Silver (Ag)	ug/L	<0.10	0.10	4168208
Total Sodium (Na)	ug/L	2400	100	4168208
Total Strontium (Sr)	ug/L	33	2.0	4168208
Total Thallium (Tl)	ug/L	<0.10	0.10	4168208
Total Tin (Sn)	ug/L	<2.0	2.0	4168208
Total Titanium (Ti)	ug/L	2.9	2.0	4168208
Total Uranium (U)	ug/L	0.20	0.10	4168208
Total Vanadium (V)	ug/L	<2.0	2.0	4168208
Total Zinc (Zn)	ug/L	<5.0	5.0	4168208
RDL = Reportable Detection Limit				
QC Batch = Quality Control Batch				

Maxxam Job #: B5H0151
Report Date: 2015/09/01

GHD Limited
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340
Sampler Initials: DN

GENERAL COMMENTS

Each temperature is the average of up to three cooler temperatures taken at receipt

Package 1	2.7°C
-----------	-------

Sample AWD356-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample AWD357-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample AWD358-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample AWD360-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample AWD361-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample AWD362-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample AWD363-01 : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Results relate only to the items tested.

Maxxam Job #: B5H0151
Report Date: 2015/09/01

QUALITY ASSURANCE REPORT

GHD Limited
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340
Sampler Initials: DN

QC Batch	Parameter	Date	Matrix Spike		SPIKED BLANK		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits	% Recovery	QC Limits
4168208	Total Aluminum (Al)	2015/08/29	105	80 - 120	104	80 - 120	<5.0	ug/L				
4168208	Total Antimony (Sb)	2015/08/29	106	80 - 120	100	80 - 120	<1.0	ug/L				
4168208	Total Arsenic (As)	2015/08/29	97	80 - 120	93	80 - 120	<1.0	ug/L				
4168208	Total Barium (Ba)	2015/08/29	101	80 - 120	98	80 - 120	<1.0	ug/L				
4168208	Total Beryllium (Be)	2015/08/29	102	80 - 120	97	80 - 120	<1.0	ug/L				
4168208	Total Bismuth (Bi)	2015/08/29	101	80 - 120	101	80 - 120	<2.0	ug/L				
4168208	Total Boron (B)	2015/08/29	102	80 - 120	96	80 - 120	<50	ug/L				
4168208	Total Cadmium (Cd)	2015/08/29	99	80 - 120	96	80 - 120	<0.010	ug/L				
4168208	Total Calcium (Ca)	2015/08/29	NC	80 - 120	102	80 - 120	<100	ug/L	2.4 (1)	20		
4168208	Total Chromium (Cr)	2015/08/29	97	80 - 120	94	80 - 120	<1.0	ug/L				
4168208	Total Cobalt (Co)	2015/08/29	95	80 - 120	93	80 - 120	<0.40	ug/L				
4168208	Total Copper (Cu)	2015/08/29	93	80 - 120	92	80 - 120	<2.0	ug/L	NC (1)	20		
4168208	Total Iron (Fe)	2015/08/29	NC	80 - 120	98	80 - 120	<50	ug/L	1.5 (1)	20		
4168208	Total Lead (Pb)	2015/08/29	100	80 - 120	98	80 - 120	<0.50	ug/L				
4168208	Total Magnesium (Mg)	2015/08/29	104	80 - 120	103	80 - 120	<100	ug/L	1.6 (1)	20		
4168208	Total Manganese (Mn)	2015/08/29	NC	80 - 120	99	80 - 120	<2.0	ug/L	0.54 (1)	20		
4168208	Total Molybdenum (Mo)	2015/08/29	105	80 - 120	99	80 - 120	<2.0	ug/L				
4168208	Total Nickel (Ni)	2015/08/29	95	80 - 120	94	80 - 120	<2.0	ug/L				
4168208	Total Phosphorus (P)	2015/08/29	104	80 - 120	103	80 - 120	160, RDL=100	ug/L				
4168208	Total Potassium (K)	2015/08/29	NC	80 - 120	104	80 - 120	<100	ug/L	2.6 (1)	20		
4168208	Total Selenium (Se)	2015/08/29	95	80 - 120	93	80 - 120	<1.0	ug/L				
4168208	Total Silver (Ag)	2015/08/29	100	80 - 120	96	80 - 120	<0.10	ug/L				
4168208	Total Sodium (Na)	2015/08/29	NC	80 - 120	102	80 - 120	<100	ug/L	1.9 (1)	20		
4168208	Total Strontium (Sr)	2015/08/29	NC	80 - 120	98	80 - 120	<2.0	ug/L				
4168208	Total Thallium (Tl)	2015/08/29	100	80 - 120	98	80 - 120	<0.10	ug/L				
4168208	Total Tin (Sn)	2015/08/29	104	80 - 120	99	80 - 120	<2.0	ug/L				
4168208	Total Titanium (Ti)	2015/08/29	105	80 - 120	101	80 - 120	<2.0	ug/L				
4168208	Total Uranium (U)	2015/08/29	111	80 - 120	106	80 - 120	<0.10	ug/L				
4168208	Total Vanadium (V)	2015/08/29	99	80 - 120	95	80 - 120	<2.0	ug/L				
4168208	Total Zinc (Zn)	2015/08/29	94	80 - 120	92	80 - 120	<5.0	ug/L	NC (1)	20		

Maxxam Job #: B5H0151
Report Date: 2015/09/01

QUALITY ASSURANCE REPORT(CONT'D)

GHD Limited
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340
Sampler Initials: DN

QC Batch	Parameter	Date	Matrix Spike		SPIKED BLANK		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits	% Recovery	QC Limits
4168309	pH	2015/08/28							1.3 (1)	N/A	99	97 - 103
4168318	Conductivity	2015/08/28			98	80 - 120	1.3, RDL=1.0	uS/cm	NC (1)	25		
4168347	Conductivity	2015/08/28			101	80 - 120	1.1, RDL=1.0	uS/cm	0.35 (1)	25		
4168354	pH	2015/08/28							0.66 (1)	N/A	100	97 - 103
4168375	pH	2015/08/28							0.42 (1)	N/A	100	97 - 103
4168392	Conductivity	2015/08/28			100	80 - 120	1.1, RDL=1.0	uS/cm	0.48 (1)	25		
4168809	Total Alkalinity (Total as CaCO3)	2015/08/31	106	80 - 120	103	80 - 120	<5.0	mg/L	NC (1)	25		
4168823	Dissolved Chloride (Cl)	2015/09/01	102	80 - 120	104	80 - 120	<1.0	mg/L	NC (1)	25	105	80 - 120
4168826	Dissolved Sulphate (SO4)	2015/09/01	107	80 - 120	100	80 - 120	<2.0	mg/L	NC (1)	25		
4168830	Reactive Silica (SiO2)	2015/09/01	100	80 - 120	99	80 - 120	<0.50	mg/L	NC (1)	25		
4168833	Colour	2015/08/31			102	80 - 120	<5.0	TCU	NC (1)	20		
4168837	Orthophosphate (P)	2015/08/31	98	80 - 120	97	80 - 120	<0.010	mg/L	NC (1)	25		
4168838	Nitrate + Nitrite	2015/09/01	98	80 - 120	98	80 - 120	<0.050	mg/L	NC (1)	25		
4168842	Nitrite (N)	2015/08/31	95	80 - 120	104	80 - 120	<0.010	mg/L	NC (1)	25		
4168900	Turbidity	2015/08/28					<0.10	NTU	0.33 (1)	25	102	80 - 120
4169316	Nitrogen (Ammonia Nitrogen)	2015/08/31	98	80 - 120	95	80 - 120	<0.050	mg/L	NC (1)	20		
4170872	Total Mercury (Hg)	2015/08/31	101 (2)	80 - 120	101	80 - 120	<0.013	ug/L	NC (3)	20		
4172579	Total Organic Carbon (C)	2015/09/01	91	80 - 120	101	80 - 120	<0.50	mg/L	NC (1)	20		

Maxxam Job #: B5H0151
Report Date: 2015/09/01

QUALITY ASSURANCE REPORT(CONT'D)

GHD Limited
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340
Sampler Initials: DN

QC Batch	Parameter	Date	Matrix Spike		SPIKED BLANK		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits	% Recovery	QC Limits
4172599	Total Organic Carbon (C)	2015/09/01	100	80 - 120	97	80 - 120	<0.50	mg/L	NC (1)	20		

N/A = Not Applicable

Duplicate: Paired analysis of a separate portion of the same sample. Used to evaluate the variance in the measurement.

Matrix Spike: A sample to which a known amount of the analyte of interest has been added. Used to evaluate sample matrix interference.

QC Standard: A sample of known concentration prepared by an external agency under stringent conditions. Used as an independent check of method accuracy.

Spiked Blank: A blank matrix sample to which a known amount of the analyte, usually from a second source, has been added. Used to evaluate method accuracy.

Method Blank: A blank matrix containing all reagents used in the analytical procedure. Used to identify laboratory contamination.

NC (Matrix Spike): The recovery in the matrix spike was not calculated. The relative difference between the concentration in the parent sample and the spiked amount was too small to permit a reliable recovery calculation (matrix spike concentration was less than 2x that of the native sample concentration).

NC (Duplicate RPD): The duplicate RPD was not calculated. The concentration in the sample and/or duplicate was too low to permit a reliable RPD calculation (one or both samples < 5x RDL).

(1) Duplicate Parent ID

(2) Matrix Spike Parent ID [AWD357-05]

(3) Duplicate Parent ID [AWD356-05]

Maxxam Job #: B5H0151
Report Date: 2015/09/01

GHD Limited
Client Project #: 088664-05
Site Location: ATLANTIC GOLD-BEAVER DAM
Your P.O. #: 20-019340
Sampler Initials: DN


VALIDATION SIGNATURE PAGE

The analytical data and all QC contained in this report were reviewed and validated by the following individual(s).

<Original signed by>

Mike MacGillivray, Scientific Specialist (Inorganics)

Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(E), signing the reports. For Service Group specific validation please refer to the Validation Signature Page.



Maxxam Analytics International Corporation o/a Maxxam Analytics
200 Bluewater Road, Bedford, Nova Scotia Canada B4B 1G9 Tel: (902) 420-0203 Toll-Free: 800-563-5256 Fax: (902) 420-8812 www.maxxam.ca

Chain Of Custody Record

Page 1 of 1

INVOICE TO:		Report Information				Project Information			Laboratory Use Only		
Company Name #16276 GHD Limited	Contact Name Dawn Negus	Company Name	Contact Name	Quotation # B37708	P.O. # 90-019340	Maxxam Job # B5H0151	Bottle Order # 526668				
Address 45 Akerley Blvd Dartmouth NS B3B 1J7	Address	Project # 088664-05	Project Name ATLANTIC GOLD - BEAVER DAM	Site #	Chain Of Custody Record	Project Manager					
Phone (902) 468-1248	Phone	Sampled By D. NEGUS / K. BAILIE	C#526668-01-01	Michelle Hill							
Email dnegus@craworld.com	Email										
Regulatory Criteria:		Special Instructions				ANALYSIS REQUESTED (PLEASE BE SPECIFIC)					
** Specify Matrix Surface/Ground/Tapwater/Sewage/Effluent/Seawater Potable/Nonpotable/Tissue/Soil/Studge/Metal											
SAMPLES MUST BE KEPT COOL (< 10°C) FROM TIME OF SAMPLING UNTIL DELIVERY TO MAXXAM											
	Sample Barcode Label B5H0151	Sample (Location) Identification SW-1	Date Sampled 24/8/15	Time Sampled 14:04	Matrix SW	Field Filtered & Preserved X	Lab Filtration Required X	Atlantic RCAP-MS Total Metals in Water X	Mercury - Total (CVAA,LL) X	Turnaround Time (TAT) Required: Please provide advance notice for rush projects Regular (Standard) TAT: (will be applied if Rush TAT is not specified) Standard TAT = 5-7 Working days for most tests. Please note: Standard TAT for certain tests such as BOD and Dioxins/Furans are > 5 days - contact your Project Manager for details.	
1		SW-2A	24/8/15	10:40	SW	X	X			5	
2		SW-4A	24/8/15	11:30	SW	X	X			5	
3		SW-5	24/8/15	13:33	SW	X	X			5	
4		SW-6A	24/8/15	12:27	SW	X	X			5	
5		SW-9	24/8/15	14:25	SW	X	X			5	
6		SW-10	24/8/15	13:52	SW	X	X			5	
7		SW-10 SW-10			SW	X	X			—	
8		SW-10.D	24/8/15	13:52	SW	X	X			5	
9										2015 AUG 25 11:30	
10											
** RELINQUISHED BY: (Signature/Print) <Original signed		Date: (YY/MM/DD) 15/25/08	Time 10:08	RECEIVED BY: (Signature/Print) <Original		Date: (YY/MM/DD) 15/25/08	Time 10:08	# Jars used and not submitted 0	Lab Use Only		
									Time Sensitive <input type="checkbox"/>	Temperature (°C) on Receipt 3 3 2	Custody Seal Intact on Cooler? <input type="checkbox"/> Yes <input type="checkbox"/> No
* IT IS THE RESPONSIBILITY OF THE RELINQUISHER TO ENSURE THE ACCURACY OF THE CHAIN OF CUSTODY RECORD. AN INCOMPLETE CHAIN OF CUSTODY MAY RESULT IN ANALYTICAL TAT DELAYS.											
White: Maxxam Yellow: Client											

Maxxam Analytics International Corporation o/a Maxxam Analytics

Your P.O. #: 73512044
 Your Project #: 088664-20
 Site Location: BEAVER DAM
 Your C.O.C. #: D34770

Attention: Jeff Parks

GHD Limited
 45 Akerley Blvd
 Dartmouth , NS
 CANADA B3B 1J7

Report Date: 2018/06/26
 Report #: R5266818
 Version: 1 - Final

CERTIFICATE OF ANALYSIS

MAXXAM JOB #: B8F1147

Received: 2018/06/19, 14:47

Sample Matrix: Water
 # Samples Received: 12

Analyses	Quantity	Date Extracted	Date Analyzed	Laboratory Method	Reference
Carbonate, Bicarbonate and Hydroxide	12	N/A	2018/06/22	N/A	SM 22 4500-CO2 D
Alkalinity	12	N/A	2018/06/25	ATL SOP 00013	EPA 310.2 R1974 m
Chloride	12	N/A	2018/06/22	ATL SOP 00014	SM 22 4500-Cl- E m
Colour	11	N/A	2018/06/22	ATL SOP 00020	SM 22 2120C m
Colour	1	N/A	2018/06/25	ATL SOP 00020	SM 22 2120C m
Conductance - water	12	N/A	2018/06/22	ATL SOP 00004	SM 23 2510B m
Hardness (calculated as CaCO3)	12	N/A	2018/06/22	ATL SOP 00048	SM 22 2340 B
Metals Water Diss. MS (as rec'd)	12	N/A	2018/06/22	ATL SOP 00058	EPA 6020A R1 m
Ion Balance (% Difference)	12	N/A	2018/06/26	N/A	Auto Calc.
Anion and Cation Sum	12	N/A	2018/06/22	N/A	Auto Calc.
Nitrogen Ammonia - water	12	N/A	2018/06/21	ATL SOP 00015	EPA 350.1 R2 m
Nitrogen - Nitrate + Nitrite	12	N/A	2018/06/25	ATL SOP 00016	USGS I-2547-11m
Nitrogen - Nitrite	12	N/A	2018/06/25	ATL SOP 00017	SM 23 4500-NO2- B m
Nitrogen - Nitrate (as N)	12	N/A	2018/06/26	ATL SOP 00018	ASTM D3867-16
pH (1)	12	N/A	2018/06/22	ATL SOP 00003	SM 23 4500-H+ B m
Phosphorus - ortho	12	N/A	2018/06/22	ATL SOP 00021	SM 23 4500-P E m
Sat. pH and Langelier Index (@ 20C)	12	N/A	2018/06/26	ATL SOP 00049	Auto Calc.
Sat. pH and Langelier Index (@ 4C)	12	N/A	2018/06/26	ATL SOP 00049	Auto Calc.
Reactive Silica	12	N/A	2018/06/25	ATL SOP 00022	EPA 366.0 m
Sulphate	12	N/A	2018/06/22	ATL SOP 00023	ASTM D516-16 m
Total Dissolved Solids (TDS calc)	12	N/A	2018/06/26	N/A	Auto Calc.
Organic carbon - Total (TOC) (2)	12	N/A	2018/06/22	ATL SOP 00203	SM 23 5310B m
Turbidity	12	N/A	2018/06/22	ATL SOP 00011	EPA 180.1 R2 m

Remarks:

Maxxam Analytics' laboratories are accredited to ISO/IEC 17025:2005 for specific parameters on scopes of accreditation. Unless otherwise noted, procedures used by Maxxam are based upon recognized Provincial, Federal or US method compendia such as CCME, MDDELCC, EPA, APHA.

All work recorded herein has been done in accordance with procedures and practices ordinarily exercised by professionals in Maxxam's profession using accepted testing methodologies, quality assurance and quality control procedures (except where otherwise agreed by the client and Maxxam in writing). All data is in statistical control and has met quality control and method performance criteria unless otherwise noted. All method blanks are reported; unless

Your P.O. #: 73512044
Your Project #: 088664-20
Site Location: BEAVER DAM
Your C.O.C. #: D34770

Attention: Jeff Parks

GHD Limited
45 Akerley Blvd
Dartmouth , NS
CANADA B3B 1J7

Report Date: 2018/06/26
Report #: R5266818
Version: 1 - Final

CERTIFICATE OF ANALYSIS

MAXXAM JOB #: B8F1147

Received: 2018/06/19, 14:47

indicated otherwise, associated sample data are not blank corrected.

Maxxam Analytics' liability is limited to the actual cost of the requested analyses, unless otherwise agreed in writing. There is no other warranty expressed or implied. Maxxam has been retained to provide analysis of samples provided by the Client using the testing methodology referenced in this report. Interpretation and use of test results are the sole responsibility of the Client and are not within the scope of services provided by Maxxam, unless otherwise agreed in writing.

Solid sample results, except biota, are based on dry weight unless otherwise indicated. Organic analyses are not recovery corrected except for isotope dilution methods.

Results relate to samples tested.

This Certificate shall not be reproduced except in full, without the written approval of the laboratory.

Reference Method suffix "m" indicates test methods incorporate validated modifications from specific reference methods to improve performance.

* RPDS calculated using raw data. The rounding of final results may result in the apparent difference.

(1) The APHA Standard Method require pH to be analyzed within 15 minutes of sampling and therefore field analysis is required for compliance. All Laboratory pH analyses in this report are reported past the APHA Standard Method holding time.

(2) TOC / DOC present in the sample should be considered as non-purgeable TOC / DOC.

<Original signed by>

Kavya Nair
Project Manager Assistant
26 Jun 2018 13:41:37

Encryption Key

Please direct all questions regarding this Certificate of Analysis to your Project Manager.

Heather Macumber, Senior Project Manager

Email: HMacumber@maxxam.ca

Phone# (902)420-0203 Ext:226

=====

Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(E), signing the reports. For Service Group specific validation please refer to the Validation Signature Page.



Maxxam Job #: B8F1147
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

RESULTS OF ANALYSES OF WATER

Maxxam ID		GZX294	GZX295	GZX296		GZX297			
Sampling Date		2018/06/19 10:29	2018/06/19 10:20	2018/06/19 10:16		2018/06/19 11:12			
COC Number		D34770	D34770	D34770		D34770			
	UNITS	MW-01A	MW-01B	MW-01C	QC Batch	MW-02A	RDL	QC Batch	MDL

Calculated Parameters

Anion Sum	me/L	0.560	1.56	1.35	5590385	0.330	N/A	5590385	N/A
Bicarb. Alkalinity (calc. as CaCO ₃)	mg/L	18	60	52	5590380	6.0	1.0	5590380	0.20
Calculated TDS	mg/L	37	91	79	5590389	21	1.0	5590389	0.20
Carb. Alkalinity (calc. as CaCO ₃)	mg/L	<1.0	<1.0	<1.0	5590380	<1.0	1.0	5590380	0.20
Cation Sum	me/L	0.510	1.47	1.26	5590385	0.260	N/A	5590385	N/A
Hardness (CaCO ₃)	mg/L	2.2	54	40	5590383	4.9	1.0	5590383	1.0
Ion Balance (% Difference)	%	4.67	2.97	3.45	5590384	11.9	N/A	5590384	N/A
Langelier Index (@ 20C)	N/A	-3.54	-0.512	-1.03	5590387	-4.58		5590387	
Langelier Index (@ 4C)	N/A	-3.79	-0.763	-1.28	5590388	-4.83		5590388	
Nitrate (N)	mg/L	<0.050	<0.050	<0.050	5590281	<0.050	0.050	5590281	N/A
Saturation pH (@ 20C)	N/A	10.3	8.29	8.50	5590387	10.4		5590387	
Saturation pH (@ 4C)	N/A	10.5	8.55	8.75	5590388	10.7		5590388	

Inorganics

Total Alkalinity (Total as CaCO ₃)	mg/L	18	61	52	5593768	6.0	5.0	5593768	N/A
Dissolved Chloride (Cl)	mg/L	4.8	4.4	4.7	5593775	5.4	1.0	5593775	N/A
Colour	TCU	<5.0	<5.0	6.5	5593779	<5.0	5.0	5593779	N/A
Nitrate + Nitrite (N)	mg/L	<0.050	<0.050	<0.050	5593781	<0.050	0.050	5593781	N/A
Nitrite (N)	mg/L	<0.010	<0.010	<0.010	5593783	<0.010	0.010	5593783	N/A
Nitrogen (Ammonia Nitrogen)	mg/L	<0.050	<0.050	<0.050	5592399	<0.050	0.050	5592423	N/A
Total Organic Carbon (C)	mg/L	1.3	2.6	1.9	5592255	1.2	0.50	5592255	N/A
Orthophosphate (P)	mg/L	<0.010	<0.010	<0.010	5593780	<0.010	0.010	5593780	N/A
pH	pH	6.75	7.78	7.47	5593693	5.83	N/A	5593691	N/A
Reactive Silica (SiO ₂)	mg/L	6.3	9.4	7.5	5593778	3.2	0.50	5593778	N/A
Dissolved Sulphate (SO ₄)	mg/L	3.0	11	8.7	5593777	2.6	2.0	5593777	N/A
Turbidity	NTU	29	7.1	17	5593709	22	0.10	5593708	0.10
Conductivity	uS/cm	54	140	120	5593694	34	1.0	5593692	N/A

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

N/A = Not Applicable



Maxxam Job #: B8F1147
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

RESULTS OF ANALYSES OF WATER

Maxxam ID		GZX298		GZX299				GZX299			
Sampling Date		2018/06/19 11:09		2018/06/19 09:47				2018/06/19 09:47			
COC Number		D34770		D34770				D34770			
	UNITS	MW-02B	QC Batch	MW-03A	RDL	QC Batch	MDL	MW-03A Lab-Dup	RDL	QC Batch	MDL
Calculated Parameters											
Anion Sum	me/L	0.480	5590385	0.280	N/A	5590385	N/A				
Bicarb. Alkalinity (calc. as CaCO3)	mg/L	17	5590380	6.2	1.0	5590380	0.20				
Calculated TDS	mg/L	40	5590389	20	1.0	5590389	0.20				
Carb. Alkalinity (calc. as CaCO3)	mg/L	<1.0	5590380	<1.0	1.0	5590380	0.20				
Cation Sum	me/L	0.440	5590385	0.260	N/A	5590385	N/A				
Hardness (CaCO3)	mg/L	10	5590383	5.9	1.0	5590383	1.0				
Ion Balance (% Difference)	%	4.35	5590384	3.70	N/A	5590384	N/A				
Langelier Index (@ 20C)	N/A	-3.20	5590387	-4.37		5590387					
Langelier Index (@ 4C)	N/A	-3.45	5590388	-4.63		5590388					
Nitrate (N)	mg/L	<0.050	5590281	0.31	0.050	5590281	N/A				
Saturation pH (@ 20C)	N/A	9.64	5590387	10.3		5590387					
Saturation pH (@ 4C)	N/A	9.89	5590388	10.6		5590388					
Inorganics											
Total Alkalinity (Total as CaCO3)	mg/L	17	5593768	6.2	5.0	5593768	N/A				
Dissolved Chloride (Cl)	mg/L	2.7	5593775	4.7	1.0	5593775	N/A				
Colour	TCU	<5.0	5593779	8.6	5.0	5593779	N/A				
Nitrate + Nitrite (N)	mg/L	<0.050	5593781	0.31	0.050	5593781	N/A				
Nitrite (N)	mg/L	<0.010	5593783	<0.010	0.010	5593783	N/A				
Nitrogen (Ammonia Nitrogen)	mg/L	<0.050	5592423	<0.050	0.050	5592423	N/A	<0.050	0.050	5592423	N/A
Total Organic Carbon (C)	mg/L	1.9	5593990	3.6	0.50	5592255	N/A	3.5	0.50	5592255	N/A
Orthophosphate (P)	mg/L	0.058	5593780	<0.010	0.010	5593780	N/A				
pH	pH	6.44	5593691	5.93	N/A	5593691	N/A				
Reactive Silica (SiO2)	mg/L	15	5593778	4.1	0.50	5593778	N/A				
Dissolved Sulphate (SO4)	mg/L	2.7	5593777	<2.0	2.0	5593777	N/A				
Turbidity	NTU	4.6	5593708	0.39	0.10	5593708	0.10				
Conductivity	uS/cm	46	5593692	32	1.0	5593692	N/A				
RDL = Reportable Detection Limit QC Batch = Quality Control Batch Lab-Dup = Laboratory Initiated Duplicate N/A = Not Applicable											



Maxxam Job #: B8F1147
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

RESULTS OF ANALYSES OF WATER

Maxxam ID		GZX300		GZX301	GZX302	GZX303			
Sampling Date		2018/06/19 09:52		2018/06/19 10:00	2018/06/19 10:42	2018/06/19 10:46			
COC Number		D34770		D34770	D34770	D34770			
	UNITS	MW-03B	QC Batch	MW-03C	MW-19A	MW-19B	RDL	QC Batch	MDL

Calculated Parameters

Anion Sum	me/L	0.980	5590385	1.87	0.210	1.49	N/A	5590385	N/A
Bicarb. Alkalinity (calc. as CaCO3)	mg/L	37	5590380	83	<1.0	60	1.0	5590380	0.20
Calculated TDS	mg/L	62	5590389	110	21	88	1.0	5590389	0.20
Carb. Alkalinity (calc. as CaCO3)	mg/L	<1.0	5590380	<1.0	<1.0	<1.0	1.0	5590380	0.20
Cation Sum	me/L	0.930	5590385	1.79	0.280	1.45	N/A	5590385	N/A
Hardness (CaCO3)	mg/L	35	5590383	67	5.4	59	1.0	5590383	1.0
Ion Balance (% Difference)	%	2.62	5590384	2.19	14.3	1.36	N/A	5590384	N/A
Langelier Index (@ 20C)	N/A	-2.01	5590387	-0.247	NC	-0.330		5590387	
Langelier Index (@ 4C)	N/A	-2.26	5590388	-0.498	NC	-0.581		5590388	
Nitrate (N)	mg/L	0.10	5590281	<0.050	0.25	0.066	0.050	5590281	N/A
Saturation pH (@ 20C)	N/A	8.67	5590387	8.06	NC	8.23		5590387	
Saturation pH (@ 4C)	N/A	8.93	5590388	8.31	NC	8.48		5590388	

Inorganics

Total Alkalinity (Total as CaCO3)	mg/L	37	5593768	84	<5.0	61	5.0	5593768	N/A
Dissolved Chloride (Cl)	mg/L	5.5	5593775	4.3	4.1	2.4	1.0	5593775	N/A
Colour	TCU	5.4	5593779	5.3	<5.0	<5.0	5.0	5593779	N/A
Nitrate + Nitrite (N)	mg/L	0.10	5593781	<0.050	0.25	0.066	0.050	5593781	N/A
Nitrite (N)	mg/L	<0.010	5593783	<0.010	<0.010	<0.010	0.010	5593783	N/A
Nitrogen (Ammonia Nitrogen)	mg/L	<0.050	5592423	<0.050	<0.050	<0.050	0.050	5592423	N/A
Total Organic Carbon (C)	mg/L	1.1	5593990	4.2	2.4	0.95	0.50	5592255	N/A
Orthophosphate (P)	mg/L	<0.010	5593780	<0.010	<0.010	<0.010	0.010	5593780	N/A
pH	pH	6.66	5593691	7.81	5.85	7.90	N/A	5593691	N/A
Reactive Silica (SiO2)	mg/L	10	5593778	9.6	5.9	8.9	0.50	5593778	N/A
Dissolved Sulphate (SO4)	mg/L	3.8	5593777	3.7	3.5	9.8	2.0	5593777	N/A
Turbidity	NTU	0.26	5593708	1.7	1.3	2.7	0.10	5593708	0.10
Conductivity	uS/cm	94	5593692	170	34	140	1.0	5593692	N/A

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

N/A = Not Applicable



Maxxam Job #: B8F1147
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

RESULTS OF ANALYSES OF WATER

Maxxam ID		GZX304			GZX304				GZX305				
Sampling Date		2018/06/19 10:53			2018/06/19 10:53				2018/06/19				
COC Number		D34770			D34770				D34770				
	UNITS	MW-19C	RDL	QC Batch	MDL	MW-19C Lab-Dup	RDL	QC Batch	MDL	MW-DUPC	RDL	QC Batch	MDL
Calculated Parameters													
Anion Sum	me/L	1.24	N/A	5590385	N/A					1.77	N/A	5590385	N/A
Bicarb. Alkalinity (calc. as CaCO ₃)	mg/L	37	1.0	5590380	0.20					77	1.0	5590380	0.20
Calculated TDS	mg/L	80	1.0	5590389	0.20					100	1.0	5590389	0.20
Carb. Alkalinity (calc. as CaCO ₃)	mg/L	<1.0	1.0	5590380	0.20					<1.0	1.0	5590380	0.20
Cation Sum	me/L	1.21	N/A	5590385	N/A					1.76	N/A	5590385	N/A
Hardness (CaCO ₃)	mg/L	36	1.0	5590383	1.0					66	1.0	5590383	1.0
Ion Balance (% Difference)	%	1.22	N/A	5590384	N/A					0.280	N/A	5590384	N/A
Langelier Index (@ 20C)	N/A	-1.53		5590387						-0.304		5590387	
Langelier Index (@ 4C)	N/A	-1.78		5590388						-0.556		5590388	
Nitrate (N)	mg/L	0.11	0.050	5590281	N/A					<0.050	0.050	5590281	N/A
Saturation pH (@ 20C)	N/A	8.68		5590387						8.10		5590387	
Saturation pH (@ 4C)	N/A	8.93		5590388						8.36		5590388	
Inorganics													
Total Alkalinity (Total as CaCO ₃)	mg/L	37	5.0	5593768	N/A					77	5.0	5589743	N/A
Dissolved Chloride (Cl)	mg/L	3.8	1.0	5593775	N/A					5.2	1.0	5589752	N/A
Colour	TCU	<5.0	5.0	5593779	N/A					<5.0	5.0	5597605	N/A
Nitrate + Nitrite (N)	mg/L	0.15	0.050	5593781	N/A					<0.050	0.050	5589765	N/A
Nitrite (N)	mg/L	0.041	0.010	5593783	N/A					<0.010	0.010	5589767	N/A
Nitrogen (Ammonia Nitrogen)	mg/L	<0.050	0.050	5592423	N/A					<0.050	0.050	5592423	N/A
Total Organic Carbon (C)	mg/L	2.1	0.50	5593990	N/A					4.3	0.50	5592255	N/A
Orthophosphate (P)	mg/L	<0.010	0.010	5593780	N/A					<0.010	0.010	5589762	N/A
pH	pH	7.15	N/A	5593695	N/A	7.20	N/A	5593695	N/A	7.80	N/A	5593691	N/A
Reactive Silica (SiO ₂)	mg/L	8.8	0.50	5593778	N/A					9.4	0.50	5589757	N/A
Dissolved Sulphate (SO ₄)	mg/L	18	2.0	5593777	N/A					3.9	2.0	5589755	N/A
Turbidity	NTU	7.0	0.10	5593709	0.10					1.5	0.10	5593709	0.10
Conductivity	uS/cm	130	1.0	5593696	N/A	130	1.0	5593696	N/A	170	1.0	5593692	N/A

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Lab-Dup = Laboratory Initiated Duplicate

N/A = Not Applicable



Maxxam Job #: B8F1147
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

RESULTS OF ANALYSES OF WATER

Maxxam ID		GZX305			
Sampling Date		2018/06/19			
COC Number		D34770			
	UNITS	MW-DUPC Lab-Dup	RDL	QC Batch	MDL
Inorganics					
Total Alkalinity (Total as CaCO3)	mg/L	84	5.0	5589743	N/A
Dissolved Chloride (Cl)	mg/L	5.8	1.0	5589752	N/A
Colour	TCU	<5.0	5.0	5597605	N/A
Nitrate + Nitrite (N)	mg/L	<0.050	0.050	5589765	N/A
Nitrite (N)	mg/L	<0.010	0.010	5589767	N/A
Orthophosphate (P)	mg/L	<0.010	0.010	5589762	N/A
Reactive Silica (SiO2)	mg/L	9.5	0.50	5589757	N/A
Dissolved Sulphate (SO4)	mg/L	3.9	2.0	5589755	N/A

RDL = Reportable Detection Limit
QC Batch = Quality Control Batch
Lab-Dup = Laboratory Initiated Duplicate
N/A = Not Applicable



Maxxam Job #: B8F1147
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

ELEMENTS BY ICP/MS (WATER)

Maxxam ID		GZX294	GZX295	GZX296	GZX297	GZX298	GZX299			
Sampling Date		2018/06/19 10:29	2018/06/19 10:20	2018/06/19 10:16	2018/06/19 11:12	2018/06/19 11:09	2018/06/19 09:47			
COC Number		D34770	D34770	D34770	D34770	D34770	D34770			
	UNITS	MW-01A	MW-01B	MW-01C	MW-02A	MW-02B	MW-03A	RDL	QC Batch	MDL

Metals

Dissolved Aluminum (Al)	ug/L	69	20	19	160	9.2	190	5.0	5592240	N/A
Dissolved Antimony (Sb)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	5592240	N/A
Dissolved Arsenic (As)	ug/L	<1.0	5.7	1.5	<1.0	2.1	<1.0	1.0	5592240	N/A
Dissolved Barium (Ba)	ug/L	1.3	4.0	7.3	9.3	4.2	7.2	1.0	5592240	N/A
Dissolved Beryllium (Be)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	5592240	N/A
Dissolved Bismuth (Bi)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	5592240	N/A
Dissolved Boron (B)	ug/L	<50	<50	<50	<50	<50	<50	50	5592240	N/A
Dissolved Cadmium (Cd)	ug/L	<0.010	<0.010	<0.010	0.025	0.60	0.030	0.010	5592240	N/A
Dissolved Calcium (Ca)	ug/L	560	18000	13000	1200	2700	1500	100	5592240	N/A
Dissolved Chromium (Cr)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	5592240	N/A
Dissolved Cobalt (Co)	ug/L	<0.40	<0.40	<0.40	1.8	<0.40	0.46	0.40	5592240	N/A
Dissolved Copper (Cu)	ug/L	<2.0	<2.0	<2.0	8.7	<2.0	<2.0	2.0	5592240	N/A
Dissolved Iron (Fe)	ug/L	<50	<50	<50	250	<50	<50	50	5592240	N/A
Dissolved Lead (Pb)	ug/L	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	0.50	5592240	N/A
Dissolved Magnesium (Mg)	ug/L	190	2200	1800	460	800	510	100	5592240	N/A
Dissolved Manganese (Mn)	ug/L	37	<2.0	140	150	22	50	2.0	5592240	N/A
Dissolved Molybdenum (Mo)	ug/L	<2.0	<2.0	2.1	<2.0	<2.0	<2.0	2.0	5592240	N/A
Dissolved Nickel (Ni)	ug/L	<2.0	<2.0	<2.0	7.8	2.1	3.5	2.0	5592240	N/A
Dissolved Phosphorus (P)	ug/L	<100	<100	<100	<100	<100	<100	100	5592240	N/A
Dissolved Potassium (K)	ug/L	1300	3100	3100	250	640	880	100	5592240	N/A
Dissolved Selenium (Se)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	5592240	N/A
Dissolved Silver (Ag)	ug/L	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	0.10	5592240	N/A
Dissolved Sodium (Na)	ug/L	9900	7100	8900	3400	5100	2700	100	5592240	N/A
Dissolved Strontium (Sr)	ug/L	6.0	69	77	6.0	20	11	2.0	5592240	N/A
Dissolved Thallium (Tl)	ug/L	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	0.10	5592240	N/A
Dissolved Tin (Sn)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	5592240	N/A
Dissolved Titanium (Ti)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	5592240	N/A
Dissolved Uranium (U)	ug/L	<0.10	0.90	0.63	<0.10	0.56	<0.10	0.10	5592240	N/A
Dissolved Vanadium (V)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	5592240	N/A
Dissolved Zinc (Zn)	ug/L	<5.0	<5.0	<5.0	12	91	<5.0	5.0	5592240	N/A

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

N/A = Not Applicable



Maxxam Job #: B8F1147
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

ELEMENTS BY ICP/MS (WATER)

Maxxam ID		GZX300	GZX301	GZX301	GZX302	GZX303	GZX304			
Sampling Date		2018/06/19 09:52	2018/06/19 10:00	2018/06/19 10:00	2018/06/19 10:42	2018/06/19 10:46	2018/06/19 10:53			
COC Number		D34770	D34770	D34770	D34770	D34770	D34770			
	UNITS	MW-03B	MW-03C	MW-03C Lab-Dup	MW-19A	MW-19B	MW-19C	RDL	QC Batch	MDL

Metals

Dissolved Aluminum (Al)	ug/L	<5.0	26	26	110	15	37	5.0	5592240	N/A	
Dissolved Antimony (Sb)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	5592240	N/A	
Dissolved Arsenic (As)	ug/L	<1.0	1.5	1.5	<1.0	8.5	3.0	1.0	5592240	N/A	
Dissolved Barium (Ba)	ug/L	3.9	8.6	8.6	7.4	10	7.3	1.0	5592240	N/A	
Dissolved Beryllium (Be)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	5592240	N/A	
Dissolved Bismuth (Bi)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	5592240	N/A	
Dissolved Boron (B)	ug/L	<50	<50	<50	<50	<50	<50	50	5592240	N/A	
Dissolved Cadmium (Cd)	ug/L	0.038	<0.010	<0.010	0.084	<0.010	0.010	0.010	5592240	N/A	
Dissolved Calcium (Ca)	ug/L	12000	23000	23000	1200	21000	12000	100	5592240	N/A	
Dissolved Chromium (Cr)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	5592240	N/A	
Dissolved Cobalt (Co)	ug/L	<0.40	<0.40	<0.40	1.2	<0.40	0.94	0.40	5592240	N/A	
Dissolved Copper (Cu)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	5592240	N/A	
Dissolved Iron (Fe)	ug/L	<50	<50	<50	<50	<50	<50	50	5592240	N/A	
Dissolved Lead (Pb)	ug/L	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	0.50	5592240	N/A	
Dissolved Magnesium (Mg)	ug/L	1100	2300	2300	600	1500	1200	100	5592240	N/A	
Dissolved Manganese (Mn)	ug/L	32	120	120	83	7.9	110	2.0	5592240	N/A	
Dissolved Molybdenum (Mo)	ug/L	<2.0	6.6	6.8	<2.0	15	18	2.0	5592240	N/A	
Dissolved Nickel (Ni)	ug/L	<2.0	<2.0	<2.0	2.4	<2.0	4.0	2.0	5592240	N/A	
Dissolved Phosphorus (P)	ug/L	<100	<100	<100	<100	<100	<100	100	5592240	N/A	
Dissolved Potassium (K)	ug/L	1700	4300	4400	800	1900	2100	100	5592240	N/A	
Dissolved Selenium (Se)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.0	5592240	N/A	
Dissolved Silver (Ag)	ug/L	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	0.10	5592240	N/A	
Dissolved Sodium (Na)	ug/L	4600	7700	7700	3400	5200	10000	100	5592240	N/A	
Dissolved Strontium (Sr)	ug/L	24	56	57	8.6	120	71	2.0	5592240	N/A	
Dissolved Thallium (Tl)	ug/L	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	0.10	5592240	N/A	
Dissolved Tin (Sn)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	5592240	N/A	
Dissolved Titanium (Ti)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	2.0	5592240	N/A	
Dissolved Uranium (U)	ug/L	0.25	1.6	1.6	<0.10	2.9	<0.10	0.10	5592240	N/A	
Dissolved Vanadium (V)	ug/L	<2.0	<2.0	<2.0	<2.0	3.1	<2.0	2.0	5592240	N/A	
Dissolved Zinc (Zn)	ug/L	<5.0	<5.0	<5.0	<5.0	9.9	<5.0	7.6	5.0	5592240	N/A

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Lab-Dup = Laboratory Initiated Duplicate

N/A = Not Applicable



Maxxam Job #: B8F1147
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

ELEMENTS BY ICP/MS (WATER)

Maxxam ID		GZX305			
Sampling Date		2018/06/19			
COC Number		D34770			
	UNITS	MW-DUPC	RDL	QC Batch	MDL
Metals					
Dissolved Aluminum (Al)	ug/L	30	5.0	5592240	N/A
Dissolved Antimony (Sb)	ug/L	<1.0	1.0	5592240	N/A
Dissolved Arsenic (As)	ug/L	1.7	1.0	5592240	N/A
Dissolved Barium (Ba)	ug/L	9.1	1.0	5592240	N/A
Dissolved Beryllium (Be)	ug/L	<1.0	1.0	5592240	N/A
Dissolved Bismuth (Bi)	ug/L	<2.0	2.0	5592240	N/A
Dissolved Boron (B)	ug/L	<50	50	5592240	N/A
Dissolved Cadmium (Cd)	ug/L	<0.010	0.010	5592240	N/A
Dissolved Calcium (Ca)	ug/L	23000	100	5592240	N/A
Dissolved Chromium (Cr)	ug/L	<1.0	1.0	5592240	N/A
Dissolved Cobalt (Co)	ug/L	<0.40	0.40	5592240	N/A
Dissolved Copper (Cu)	ug/L	<2.0	2.0	5592240	N/A
Dissolved Iron (Fe)	ug/L	<50	50	5592240	N/A
Dissolved Lead (Pb)	ug/L	<0.50	0.50	5592240	N/A
Dissolved Magnesium (Mg)	ug/L	2300	100	5592240	N/A
Dissolved Manganese (Mn)	ug/L	120	2.0	5592240	N/A
Dissolved Molybdenum (Mo)	ug/L	6.4	2.0	5592240	N/A
Dissolved Nickel (Ni)	ug/L	<2.0	2.0	5592240	N/A
Dissolved Phosphorus (P)	ug/L	<100	100	5592240	N/A
Dissolved Potassium (K)	ug/L	4300	100	5592240	N/A
Dissolved Selenium (Se)	ug/L	<1.0	1.0	5592240	N/A
Dissolved Silver (Ag)	ug/L	<0.10	0.10	5592240	N/A
Dissolved Sodium (Na)	ug/L	7700	100	5592240	N/A
Dissolved Strontium (Sr)	ug/L	56	2.0	5592240	N/A
Dissolved Thallium (Tl)	ug/L	<0.10	0.10	5592240	N/A
Dissolved Tin (Sn)	ug/L	3.8	2.0	5592240	N/A
Dissolved Titanium (Ti)	ug/L	<2.0	2.0	5592240	N/A
Dissolved Uranium (U)	ug/L	1.6	0.10	5592240	N/A
Dissolved Vanadium (V)	ug/L	<2.0	2.0	5592240	N/A
Dissolved Zinc (Zn)	ug/L	<5.0	5.0	5592240	N/A

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

N/A = Not Applicable



Maxxam Job #: B8F1147
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

TEST SUMMARY

Maxxam ID: GZX294
Sample ID: MW-01A
Matrix: Water

Collected: 2018/06/19
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Carbonate, Bicarbonate and Hydroxide	CALC	5590380	N/A	2018/06/22	Automated Statchk
Alkalinity	KONE	5593768	N/A	2018/06/25	Jacob Henley
Chloride	KONE	5593775	N/A	2018/06/22	Jacob Henley
Colour	KONE	5593779	N/A	2018/06/22	Jacob Henley
Conductance - water	AT	5593694	N/A	2018/06/22	Julia McGovern
Hardness (calculated as CaCO ₃)		5590383	N/A	2018/06/22	Automated Statchk
Metals Water Diss. MS (as rec'd)	CICP/MS	5592240	N/A	2018/06/22	Cassandra Hartery
Ion Balance (% Difference)	CALC	5590384	N/A	2018/06/26	Automated Statchk
Anion and Cation Sum	CALC	5590385	N/A	2018/06/22	Automated Statchk
Nitrogen Ammonia - water	KONE	5592399	N/A	2018/06/21	Jacob Henley
Nitrogen - Nitrate + Nitrite	KONE	5593781	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrite	KONE	5593783	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrate (as N)	CALC	5590281	N/A	2018/06/26	Automated Statchk
pH	AT	5593693	N/A	2018/06/22	Julia McGovern
Phosphorus - ortho	KONE	5593780	N/A	2018/06/22	Jacob Henley
Sat. pH and Langelier Index (@ 20C)	CALC	5590387	N/A	2018/06/26	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	5590388	N/A	2018/06/26	Automated Statchk
Reactive Silica	KONE	5593778	N/A	2018/06/25	Jacob Henley
Sulphate	KONE	5593777	N/A	2018/06/22	Jacob Henley
Total Dissolved Solids (TDS calc)	CALC	5590389	N/A	2018/06/26	Automated Statchk
Organic carbon - Total (TOC)	TOCV/NDIR	5592255	N/A	2018/06/22	Luke MacPherson
Turbidity	TURB	5593709	N/A	2018/06/22	Julia McGovern

Maxxam ID: GZX295
Sample ID: MW-01B
Matrix: Water

Collected: 2018/06/19
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Carbonate, Bicarbonate and Hydroxide	CALC	5590380	N/A	2018/06/22	Automated Statchk
Alkalinity	KONE	5593768	N/A	2018/06/25	Jacob Henley
Chloride	KONE	5593775	N/A	2018/06/22	Jacob Henley
Colour	KONE	5593779	N/A	2018/06/22	Jacob Henley
Conductance - water	AT	5593694	N/A	2018/06/22	Julia McGovern
Hardness (calculated as CaCO ₃)		5590383	N/A	2018/06/22	Automated Statchk
Metals Water Diss. MS (as rec'd)	CICP/MS	5592240	N/A	2018/06/22	Cassandra Hartery
Ion Balance (% Difference)	CALC	5590384	N/A	2018/06/26	Automated Statchk
Anion and Cation Sum	CALC	5590385	N/A	2018/06/22	Automated Statchk
Nitrogen Ammonia - water	KONE	5592399	N/A	2018/06/21	Jacob Henley
Nitrogen - Nitrate + Nitrite	KONE	5593781	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrite	KONE	5593783	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrate (as N)	CALC	5590281	N/A	2018/06/26	Automated Statchk
pH	AT	5593693	N/A	2018/06/22	Julia McGovern
Phosphorus - ortho	KONE	5593780	N/A	2018/06/22	Jacob Henley



Maxxam Job #: B8F1147
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

TEST SUMMARY

Maxxam ID: GZX295
Sample ID: MW-01B
Matrix: Water

Collected: 2018/06/19
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Sat. pH and Langelier Index (@ 20C)	CALC	5590387	N/A	2018/06/26	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	5590388	N/A	2018/06/26	Automated Statchk
Reactive Silica	KONE	5593778	N/A	2018/06/25	Jacob Henley
Sulphate	KONE	5593777	N/A	2018/06/22	Jacob Henley
Total Dissolved Solids (TDS calc)	CALC	5590389	N/A	2018/06/26	Automated Statchk
Organic carbon - Total (TOC)	TOCV/NDIR	5592255	N/A	2018/06/22	Luke MacPherson
Turbidity	TURB	5593709	N/A	2018/06/22	Julia McGovern

Maxxam ID: GZX296
Sample ID: MW-01C
Matrix: Water

Collected: 2018/06/19
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Carbonate, Bicarbonate and Hydroxide	CALC	5590380	N/A	2018/06/22	Automated Statchk
Alkalinity	KONE	5593768	N/A	2018/06/25	Jacob Henley
Chloride	KONE	5593775	N/A	2018/06/22	Jacob Henley
Colour	KONE	5593779	N/A	2018/06/22	Jacob Henley
Conductance - water	AT	5593694	N/A	2018/06/22	Julia McGovern
Hardness (calculated as CaCO ₃)		5590383	N/A	2018/06/22	Automated Statchk
Metals Water Diss. MS (as rec'd)	CICP/MS	5592240	N/A	2018/06/22	Cassandra Hartery
Ion Balance (% Difference)	CALC	5590384	N/A	2018/06/26	Automated Statchk
Anion and Cation Sum	CALC	5590385	N/A	2018/06/22	Automated Statchk
Nitrogen Ammonia - water	KONE	5592399	N/A	2018/06/21	Jacob Henley
Nitrogen - Nitrate + Nitrite	KONE	5593781	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrite	KONE	5593783	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrate (as N)	CALC	5590281	N/A	2018/06/26	Automated Statchk
pH	AT	5593693	N/A	2018/06/22	Julia McGovern
Phosphorus - ortho	KONE	5593780	N/A	2018/06/22	Jacob Henley
Sat. pH and Langelier Index (@ 20C)	CALC	5590387	N/A	2018/06/26	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	5590388	N/A	2018/06/26	Automated Statchk
Reactive Silica	KONE	5593778	N/A	2018/06/25	Jacob Henley
Sulphate	KONE	5593777	N/A	2018/06/22	Jacob Henley
Total Dissolved Solids (TDS calc)	CALC	5590389	N/A	2018/06/26	Automated Statchk
Organic carbon - Total (TOC)	TOCV/NDIR	5592255	N/A	2018/06/22	Luke MacPherson
Turbidity	TURB	5593709	N/A	2018/06/22	Julia McGovern

Maxxam ID: GZX297
Sample ID: MW-02A
Matrix: Water

Collected: 2018/06/19
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Carbonate, Bicarbonate and Hydroxide	CALC	5590380	N/A	2018/06/22	Automated Statchk
Alkalinity	KONE	5593768	N/A	2018/06/25	Jacob Henley



Maxxam Job #: B8F1147
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

TEST SUMMARY

Maxxam ID: GZX297
Sample ID: MW-02A
Matrix: Water

Collected: 2018/06/19
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Chloride	KONE	5593775	N/A	2018/06/22	Jacob Henley
Colour	KONE	5593779	N/A	2018/06/22	Jacob Henley
Conductance - water	AT	5593692	N/A	2018/06/22	Julia McGovern
Hardness (calculated as CaCO3)		5590383	N/A	2018/06/22	Automated Statchk
Metals Water Diss. MS (as rec'd)	CICP/MS	5592240	N/A	2018/06/22	Cassandra Hartery
Ion Balance (% Difference)	CALC	5590384	N/A	2018/06/26	Automated Statchk
Anion and Cation Sum	CALC	5590385	N/A	2018/06/22	Automated Statchk
Nitrogen Ammonia - water	KONE	5592423	N/A	2018/06/21	Jacob Henley
Nitrogen - Nitrate + Nitrite	KONE	5593781	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrite	KONE	5593783	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrate (as N)	CALC	5590281	N/A	2018/06/26	Automated Statchk
pH	AT	5593691	N/A	2018/06/22	Julia McGovern
Phosphorus - ortho	KONE	5593780	N/A	2018/06/22	Jacob Henley
Sat. pH and Langelier Index (@ 20C)	CALC	5590387	N/A	2018/06/26	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	5590388	N/A	2018/06/26	Automated Statchk
Reactive Silica	KONE	5593778	N/A	2018/06/25	Jacob Henley
Sulphate	KONE	5593777	N/A	2018/06/22	Jacob Henley
Total Dissolved Solids (TDS calc)	CALC	5590389	N/A	2018/06/26	Automated Statchk
Organic carbon - Total (TOC)	TOCV/NDIR	5592255	N/A	2018/06/22	Luke MacPherson
Turbidity	TURB	5593708	N/A	2018/06/22	Julia McGovern

Maxxam ID: GZX298
Sample ID: MW-02B
Matrix: Water

Collected: 2018/06/19
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Carbonate, Bicarbonate and Hydroxide	CALC	5590380	N/A	2018/06/22	Automated Statchk
Alkalinity	KONE	5593768	N/A	2018/06/25	Jacob Henley
Chloride	KONE	5593775	N/A	2018/06/22	Jacob Henley
Colour	KONE	5593779	N/A	2018/06/22	Jacob Henley
Conductance - water	AT	5593692	N/A	2018/06/22	Julia McGovern
Hardness (calculated as CaCO3)		5590383	N/A	2018/06/22	Automated Statchk
Metals Water Diss. MS (as rec'd)	CICP/MS	5592240	N/A	2018/06/22	Cassandra Hartery
Ion Balance (% Difference)	CALC	5590384	N/A	2018/06/26	Automated Statchk
Anion and Cation Sum	CALC	5590385	N/A	2018/06/22	Automated Statchk
Nitrogen Ammonia - water	KONE	5592423	N/A	2018/06/21	Jacob Henley
Nitrogen - Nitrate + Nitrite	KONE	5593781	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrite	KONE	5593783	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrate (as N)	CALC	5590281	N/A	2018/06/26	Automated Statchk
pH	AT	5593691	N/A	2018/06/22	Julia McGovern
Phosphorus - ortho	KONE	5593780	N/A	2018/06/22	Jacob Henley
Sat. pH and Langelier Index (@ 20C)	CALC	5590387	N/A	2018/06/26	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	5590388	N/A	2018/06/26	Automated Statchk



Maxxam Job #: B8F1147
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

TEST SUMMARY

Maxxam ID: GZX298
Sample ID: MW-02B
Matrix: Water

Collected: 2018/06/19
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Reactive Silica	KONE	5593778	N/A	2018/06/25	Jacob Henley
Sulphate	KONE	5593777	N/A	2018/06/22	Jacob Henley
Total Dissolved Solids (TDS calc)	CALC	5590389	N/A	2018/06/26	Automated Statchk
Organic carbon - Total (TOC)	TOCV/NDIR	5593990	N/A	2018/06/22	Luke MacPherson
Turbidity	TURB	5593708	N/A	2018/06/22	Julia McGovern

Maxxam ID: GZX299
Sample ID: MW-03A
Matrix: Water

Collected: 2018/06/19
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Carbonate, Bicarbonate and Hydroxide	CALC	5590380	N/A	2018/06/22	Automated Statchk
Alkalinity	KONE	5593768	N/A	2018/06/25	Jacob Henley
Chloride	KONE	5593775	N/A	2018/06/22	Jacob Henley
Colour	KONE	5593779	N/A	2018/06/22	Jacob Henley
Conductance - water	AT	5593692	N/A	2018/06/22	Julia McGovern
Hardness (calculated as CaCO ₃)		5590383	N/A	2018/06/22	Automated Statchk
Metals Water Diss. MS (as rec'd)	CICP/MS	5592240	N/A	2018/06/22	Cassandra Hartery
Ion Balance (% Difference)	CALC	5590384	N/A	2018/06/26	Automated Statchk
Anion and Cation Sum	CALC	5590385	N/A	2018/06/22	Automated Statchk
Nitrogen Ammonia - water	KONE	5592423	N/A	2018/06/21	Jacob Henley
Nitrogen - Nitrate + Nitrite	KONE	5593781	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrite	KONE	5593783	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrate (as N)	CALC	5590281	N/A	2018/06/26	Automated Statchk
pH	AT	5593691	N/A	2018/06/22	Julia McGovern
Phosphorus - ortho	KONE	5593780	N/A	2018/06/22	Jacob Henley
Sat. pH and Langlier Index (@ 20C)	CALC	5590387	N/A	2018/06/26	Automated Statchk
Sat. pH and Langlier Index (@ 4C)	CALC	5590388	N/A	2018/06/26	Automated Statchk
Reactive Silica	KONE	5593778	N/A	2018/06/25	Jacob Henley
Sulphate	KONE	5593777	N/A	2018/06/22	Jacob Henley
Total Dissolved Solids (TDS calc)	CALC	5590389	N/A	2018/06/26	Automated Statchk
Organic carbon - Total (TOC)	TOCV/NDIR	5592255	N/A	2018/06/22	Luke MacPherson
Turbidity	TURB	5593708	N/A	2018/06/22	Julia McGovern

Maxxam ID: GZX299 Dup
Sample ID: MW-03A
Matrix: Water

Collected: 2018/06/19
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Nitrogen Ammonia - water	KONE	5592423	N/A	2018/06/21	Jacob Henley
Organic carbon - Total (TOC)	TOCV/NDIR	5592255	N/A	2018/06/22	Luke MacPherson



Maxxam Job #: B8F1147
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

TEST SUMMARY

Maxxam ID: GZX300
Sample ID: MW-03B
Matrix: Water

Collected: 2018/06/19
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Carbonate, Bicarbonate and Hydroxide	CALC	5590380	N/A	2018/06/22	Automated Statchk
Alkalinity	KONE	5593768	N/A	2018/06/25	Jacob Henley
Chloride	KONE	5593775	N/A	2018/06/22	Jacob Henley
Colour	KONE	5593779	N/A	2018/06/22	Jacob Henley
Conductance - water	AT	5593692	N/A	2018/06/22	Julia McGovern
Hardness (calculated as CaCO ₃)		5590383	N/A	2018/06/22	Automated Statchk
Metals Water Diss. MS (as rec'd)	CICP/MS	5592240	N/A	2018/06/22	Cassandra Hartery
Ion Balance (% Difference)	CALC	5590384	N/A	2018/06/26	Automated Statchk
Anion and Cation Sum	CALC	5590385	N/A	2018/06/22	Automated Statchk
Nitrogen Ammonia - water	KONE	5592423	N/A	2018/06/21	Jacob Henley
Nitrogen - Nitrate + Nitrite	KONE	5593781	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrite	KONE	5593783	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrate (as N)	CALC	5590281	N/A	2018/06/26	Automated Statchk
pH	AT	5593691	N/A	2018/06/22	Julia McGovern
Phosphorus - ortho	KONE	5593780	N/A	2018/06/22	Jacob Henley
Sat. pH and Langelier Index (@ 20C)	CALC	5590387	N/A	2018/06/26	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	5590388	N/A	2018/06/26	Automated Statchk
Reactive Silica	KONE	5593778	N/A	2018/06/25	Jacob Henley
Sulphate	KONE	5593777	N/A	2018/06/22	Jacob Henley
Total Dissolved Solids (TDS calc)	CALC	5590389	N/A	2018/06/26	Automated Statchk
Organic carbon - Total (TOC)	TOCV/NDIR	5593990	N/A	2018/06/22	Luke MacPherson
Turbidity	TURB	5593708	N/A	2018/06/22	Julia McGovern

Maxxam ID: GZX301
Sample ID: MW-03C
Matrix: Water

Collected: 2018/06/19
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Carbonate, Bicarbonate and Hydroxide	CALC	5590380	N/A	2018/06/22	Automated Statchk
Alkalinity	KONE	5593768	N/A	2018/06/25	Jacob Henley
Chloride	KONE	5593775	N/A	2018/06/22	Jacob Henley
Colour	KONE	5593779	N/A	2018/06/22	Jacob Henley
Conductance - water	AT	5593692	N/A	2018/06/22	Julia McGovern
Hardness (calculated as CaCO ₃)		5590383	N/A	2018/06/22	Automated Statchk
Metals Water Diss. MS (as rec'd)	CICP/MS	5592240	N/A	2018/06/22	Cassandra Hartery
Ion Balance (% Difference)	CALC	5590384	N/A	2018/06/26	Automated Statchk
Anion and Cation Sum	CALC	5590385	N/A	2018/06/22	Automated Statchk
Nitrogen Ammonia - water	KONE	5592423	N/A	2018/06/21	Jacob Henley
Nitrogen - Nitrate + Nitrite	KONE	5593781	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrite	KONE	5593783	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrate (as N)	CALC	5590281	N/A	2018/06/26	Automated Statchk
pH	AT	5593691	N/A	2018/06/22	Julia McGovern
Phosphorus - ortho	KONE	5593780	N/A	2018/06/22	Jacob Henley



Maxxam Job #: B8F1147
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

TEST SUMMARY

Maxxam ID: GZX301
Sample ID: MW-03C
Matrix: Water

Collected: 2018/06/19
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Sat. pH and Langelier Index (@ 20C)	CALC	5590387	N/A	2018/06/26	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	5590388	N/A	2018/06/26	Automated Statchk
Reactive Silica	KONE	5593778	N/A	2018/06/25	Jacob Henley
Sulphate	KONE	5593777	N/A	2018/06/22	Jacob Henley
Total Dissolved Solids (TDS calc)	CALC	5590389	N/A	2018/06/26	Automated Statchk
Organic carbon - Total (TOC)	TOCV/NDIR	5592255	N/A	2018/06/22	Luke MacPherson
Turbidity	TURB	5593708	N/A	2018/06/22	Julia McGovern

Maxxam ID: GZX301 Dup
Sample ID: MW-03C
Matrix: Water

Collected: 2018/06/19
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Metals Water Diss. MS (as rec'd)	CICP/MS	5592240	N/A	2018/06/22	Cassandra Hartery

Maxxam ID: GZX302
Sample ID: MW-19A
Matrix: Water

Collected: 2018/06/19
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Carbonate, Bicarbonate and Hydroxide	CALC	5590380	N/A	2018/06/22	Automated Statchk
Alkalinity	KONE	5593768	N/A	2018/06/25	Jacob Henley
Chloride	KONE	5593775	N/A	2018/06/22	Jacob Henley
Colour	KONE	5593779	N/A	2018/06/22	Jacob Henley
Conductance - water	AT	5593692	N/A	2018/06/22	Julia McGovern
Hardness (calculated as CaCO3)		5590383	N/A	2018/06/22	Automated Statchk
Metals Water Diss. MS (as rec'd)	CICP/MS	5592240	N/A	2018/06/22	Cassandra Hartery
Ion Balance (% Difference)	CALC	5590384	N/A	2018/06/26	Automated Statchk
Anion and Cation Sum	CALC	5590385	N/A	2018/06/22	Automated Statchk
Nitrogen Ammonia - water	KONE	5592423	N/A	2018/06/21	Jacob Henley
Nitrogen - Nitrate + Nitrite	KONE	5593781	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrite	KONE	5593783	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrate (as N)	CALC	5590281	N/A	2018/06/26	Automated Statchk
pH	AT	5593691	N/A	2018/06/22	Julia McGovern
Phosphorus - ortho	KONE	5593780	N/A	2018/06/22	Jacob Henley
Sat. pH and Langelier Index (@ 20C)	CALC	5590387	N/A	2018/06/26	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	5590388	N/A	2018/06/26	Automated Statchk
Reactive Silica	KONE	5593778	N/A	2018/06/25	Jacob Henley
Sulphate	KONE	5593777	N/A	2018/06/22	Jacob Henley
Total Dissolved Solids (TDS calc)	CALC	5590389	N/A	2018/06/26	Automated Statchk
Organic carbon - Total (TOC)	TOCV/NDIR	5592255	N/A	2018/06/22	Luke MacPherson
Turbidity	TURB	5593708	N/A	2018/06/22	Julia McGovern



Maxxam Job #: B8F1147
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

TEST SUMMARY

Maxxam ID: GZX303
Sample ID: MW-19B
Matrix: Water

Collected: 2018/06/19
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Carbonate, Bicarbonate and Hydroxide	CALC	5590380	N/A	2018/06/22	Automated Statchk
Alkalinity	KONE	5593768	N/A	2018/06/25	Jacob Henley
Chloride	KONE	5593775	N/A	2018/06/22	Jacob Henley
Colour	KONE	5593779	N/A	2018/06/22	Jacob Henley
Conductance - water	AT	5593692	N/A	2018/06/22	Julia McGovern
Hardness (calculated as CaCO ₃)		5590383	N/A	2018/06/22	Automated Statchk
Metals Water Diss. MS (as rec'd)	CICP/MS	5592240	N/A	2018/06/22	Cassandra Hartery
Ion Balance (% Difference)	CALC	5590384	N/A	2018/06/26	Automated Statchk
Anion and Cation Sum	CALC	5590385	N/A	2018/06/22	Automated Statchk
Nitrogen Ammonia - water	KONE	5592423	N/A	2018/06/21	Jacob Henley
Nitrogen - Nitrate + Nitrite	KONE	5593781	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrite	KONE	5593783	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrate (as N)	CALC	5590281	N/A	2018/06/26	Automated Statchk
pH	AT	5593691	N/A	2018/06/22	Julia McGovern
Phosphorus - ortho	KONE	5593780	N/A	2018/06/22	Jacob Henley
Sat. pH and Langelier Index (@ 20C)	CALC	5590387	N/A	2018/06/26	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	5590388	N/A	2018/06/26	Automated Statchk
Reactive Silica	KONE	5593778	N/A	2018/06/25	Jacob Henley
Sulphate	KONE	5593777	N/A	2018/06/22	Jacob Henley
Total Dissolved Solids (TDS calc)	CALC	5590389	N/A	2018/06/26	Automated Statchk
Organic carbon - Total (TOC)	TOCV/NDIR	5592255	N/A	2018/06/22	Luke MacPherson
Turbidity	TURB	5593708	N/A	2018/06/22	Julia McGovern

Maxxam ID: GZX304
Sample ID: MW-19C
Matrix: Water

Collected: 2018/06/19
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Carbonate, Bicarbonate and Hydroxide	CALC	5590380	N/A	2018/06/22	Automated Statchk
Alkalinity	KONE	5593768	N/A	2018/06/25	Jacob Henley
Chloride	KONE	5593775	N/A	2018/06/22	Jacob Henley
Colour	KONE	5593779	N/A	2018/06/22	Jacob Henley
Conductance - water	AT	5593696	N/A	2018/06/22	Julia McGovern
Hardness (calculated as CaCO ₃)		5590383	N/A	2018/06/22	Automated Statchk
Metals Water Diss. MS (as rec'd)	CICP/MS	5592240	N/A	2018/06/22	Cassandra Hartery
Ion Balance (% Difference)	CALC	5590384	N/A	2018/06/26	Automated Statchk
Anion and Cation Sum	CALC	5590385	N/A	2018/06/22	Automated Statchk
Nitrogen Ammonia - water	KONE	5592423	N/A	2018/06/21	Jacob Henley
Nitrogen - Nitrate + Nitrite	KONE	5593781	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrite	KONE	5593783	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrate (as N)	CALC	5590281	N/A	2018/06/26	Automated Statchk
pH	AT	5593695	N/A	2018/06/22	Julia McGovern
Phosphorus - ortho	KONE	5593780	N/A	2018/06/22	Jacob Henley



Maxxam Job #: B8F1147
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

TEST SUMMARY

Maxxam ID: GZX304
Sample ID: MW-19C
Matrix: Water

Collected: 2018/06/19
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Sat. pH and Langelier Index (@ 20C)	CALC	5590387	N/A	2018/06/26	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	5590388	N/A	2018/06/26	Automated Statchk
Reactive Silica	KONE	5593778	N/A	2018/06/25	Jacob Henley
Sulphate	KONE	5593777	N/A	2018/06/22	Jacob Henley
Total Dissolved Solids (TDS calc)	CALC	5590389	N/A	2018/06/26	Automated Statchk
Organic carbon - Total (TOC)	TOCV/NDIR	5593990	N/A	2018/06/22	Luke MacPherson
Turbidity	TURB	5593709	N/A	2018/06/22	Julia McGovern

Maxxam ID: GZX304 Dup
Sample ID: MW-19C
Matrix: Water

Collected: 2018/06/19
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Conductance - water	AT	5593696	N/A	2018/06/22	Julia McGovern
pH	AT	5593695	N/A	2018/06/22	Julia McGovern

Maxxam ID: GZX305
Sample ID: MW-DUPC
Matrix: Water

Collected: 2018/06/19
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Carbonate, Bicarbonate and Hydroxide	CALC	5590380	N/A	2018/06/22	Automated Statchk
Alkalinity	KONE	5589743	N/A	2018/06/25	Jacob Henley
Chloride	KONE	5589752	N/A	2018/06/22	Jacob Henley
Colour	KONE	5597605	N/A	2018/06/25	Jacob Henley
Conductance - water	AT	5593692	N/A	2018/06/22	Julia McGovern
Hardness (calculated as CaCO ₃)		5590383	N/A	2018/06/22	Automated Statchk
Metals Water Diss. MS (as rec'd)	CICP/MS	5592240	N/A	2018/06/22	Cassandra Hartery
Ion Balance (% Difference)	CALC	5590384	N/A	2018/06/26	Automated Statchk
Anion and Cation Sum	CALC	5590385	N/A	2018/06/22	Automated Statchk
Nitrogen Ammonia - water	KONE	5592423	N/A	2018/06/21	Jacob Henley
Nitrogen - Nitrate + Nitrite	KONE	5589765	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrite	KONE	5589767	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrate (as N)	CALC	5590281	N/A	2018/06/26	Automated Statchk
pH	AT	5593691	N/A	2018/06/22	Julia McGovern
Phosphorus - ortho	KONE	5589762	N/A	2018/06/22	Jacob Henley
Sat. pH and Langelier Index (@ 20C)	CALC	5590387	N/A	2018/06/26	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	5590388	N/A	2018/06/26	Automated Statchk
Reactive Silica	KONE	5589757	N/A	2018/06/25	Jacob Henley
Sulphate	KONE	5589755	N/A	2018/06/22	Jacob Henley
Total Dissolved Solids (TDS calc)	CALC	5590389	N/A	2018/06/26	Automated Statchk
Organic carbon - Total (TOC)	TOCV/NDIR	5592255	N/A	2018/06/22	Luke MacPherson
Turbidity	TURB	5593709	N/A	2018/06/22	Julia McGovern



Maxxam Job #: B8F1147
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

TEST SUMMARY

Maxxam ID: GZX305 Dup
Sample ID: MW-DUPC
Matrix: Water

Collected: 2018/06/19
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Alkalinity	KONE	5589743	N/A	2018/06/25	Jacob Henley
Chloride	KONE	5589752	N/A	2018/06/22	Jacob Henley
Colour	KONE	5597605	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrate + Nitrite	KONE	5589765	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrite	KONE	5589767	N/A	2018/06/25	Jacob Henley
Phosphorus - ortho	KONE	5589762	N/A	2018/06/22	Jacob Henley
Reactive Silica	KONE	5589757	N/A	2018/06/25	Jacob Henley
Sulphate	KONE	5589755	N/A	2018/06/22	Jacob Henley



Maxxam Job #: B8F1147
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

GENERAL COMMENTS

Each temperature is the average of up to three cooler temperatures taken at receipt

Package 1	6.3°C
-----------	-------

Sample GZX297 [MW-02A] : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample GZX302 [MW-19A] : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Results relate only to the items tested.

Maxxam Job #: B8F1147
Report Date: 2018/06/26

QUALITY ASSURANCE REPORT

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

QC Batch	Parameter	Date	Matrix Spike		SPIKED BLANK		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits	% Recovery	QC Limits
5589743	Total Alkalinity (Total as CaCO ₃)	2018/06/25	NC	80 - 120	96	80 - 120	<5.0	mg/L	9.1	25		
5589752	Dissolved Chloride (Cl)	2018/06/22	100	80 - 120	103	80 - 120	<1.0	mg/L	10	25	102	80 - 120
5589755	Dissolved Sulphate (SO ₄)	2018/06/22	93	80 - 120	95	80 - 120	<2.0	mg/L	0.48	25		
5589757	Reactive Silica (SiO ₂)	2018/06/25	98	80 - 120	95	80 - 120	<0.50	mg/L	0.84	25		
5589762	Orthophosphate (P)	2018/06/22	87	80 - 120	94	80 - 120	<0.010	mg/L	NC	25		
5589765	Nitrate + Nitrite (N)	2018/06/25	96	80 - 120	98	80 - 120	<0.050	mg/L	NC	25		
5589767	Nitrite (N)	2018/06/25	92	80 - 120	96	80 - 120	<0.010	mg/L	NC	20		
5592240	Dissolved Aluminum (Al)	2018/06/22	97	80 - 120	98	80 - 120	<5.0	ug/L	1.7	20		
5592240	Dissolved Antimony (Sb)	2018/06/22	103	80 - 120	99	80 - 120	<1.0	ug/L	NC	20		
5592240	Dissolved Arsenic (As)	2018/06/22	96	80 - 120	96	80 - 120	<1.0	ug/L	3.9	20		
5592240	Dissolved Barium (Ba)	2018/06/22	104	80 - 120	105	80 - 120	<1.0	ug/L	0.23	20		
5592240	Dissolved Beryllium (Be)	2018/06/22	99	80 - 120	100	80 - 120	<1.0	ug/L	NC	20		
5592240	Dissolved Bismuth (Bi)	2018/06/22	101	80 - 120	104	80 - 120	<2.0	ug/L	NC	20		
5592240	Dissolved Boron (B)	2018/06/22	96	80 - 120	95	80 - 120	<50	ug/L	NC	20		
5592240	Dissolved Cadmium (Cd)	2018/06/22	103	80 - 120	104	80 - 120	<0.010	ug/L	NC	20		
5592240	Dissolved Calcium (Ca)	2018/06/22	99	80 - 120	105	80 - 120	<100	ug/L	1.0	20		
5592240	Dissolved Chromium (Cr)	2018/06/22	95	80 - 120	97	80 - 120	<1.0	ug/L	NC	20		
5592240	Dissolved Cobalt (Co)	2018/06/22	95	80 - 120	97	80 - 120	<0.40	ug/L	NC	20		
5592240	Dissolved Copper (Cu)	2018/06/22	91	80 - 120	93	80 - 120	<2.0	ug/L	NC	20		
5592240	Dissolved Iron (Fe)	2018/06/22	98	80 - 120	100	80 - 120	<50	ug/L	NC	20		
5592240	Dissolved Lead (Pb)	2018/06/22	98	80 - 120	100	80 - 120	<0.50	ug/L	NC	20		
5592240	Dissolved Magnesium (Mg)	2018/06/22	100	80 - 120	103	80 - 120	<100	ug/L	0.41	20		
5592240	Dissolved Manganese (Mn)	2018/06/22	NC	80 - 120	97	80 - 120	<2.0	ug/L	0.58	20		
5592240	Dissolved Molybdenum (Mo)	2018/06/22	103	80 - 120	103	80 - 120	<2.0	ug/L	3.7	20		
5592240	Dissolved Nickel (Ni)	2018/06/22	92	80 - 120	94	80 - 120	<2.0	ug/L	NC	20		
5592240	Dissolved Phosphorus (P)	2018/06/22	104	80 - 120	103	80 - 120	<100	ug/L	NC	20		
5592240	Dissolved Potassium (K)	2018/06/22	100	80 - 120	105	80 - 120	<100	ug/L	1.3	20		
5592240	Dissolved Selenium (Se)	2018/06/22	96	80 - 120	96	80 - 120	<1.0	ug/L	NC	20		
5592240	Dissolved Silver (Ag)	2018/06/22	92	80 - 120	99	80 - 120	<0.10	ug/L	NC	20		
5592240	Dissolved Sodium (Na)	2018/06/22	94	80 - 120	95	80 - 120	<100	ug/L	0.53	20		

Maxxam Job #: B8F1147
Report Date: 2018/06/26

QUALITY ASSURANCE REPORT(CONT'D)

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

QC Batch	Parameter	Date	Matrix Spike		SPIKED BLANK		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits	% Recovery	QC Limits
5592240	Dissolved Strontium (Sr)	2018/06/22	100	80 - 120	99	80 - 120	<2.0	ug/L	1.0	20		
5592240	Dissolved Thallium (Tl)	2018/06/22	103	80 - 120	104	80 - 120	<0.10	ug/L	NC	20		
5592240	Dissolved Tin (Sn)	2018/06/22	105	80 - 120	108	80 - 120	<2.0	ug/L	NC	20		
5592240	Dissolved Titanium (Ti)	2018/06/22	99	80 - 120	103	80 - 120	<2.0	ug/L	NC	20		
5592240	Dissolved Uranium (U)	2018/06/22	101	80 - 120	102	80 - 120	<0.10	ug/L	2.6	20		
5592240	Dissolved Vanadium (V)	2018/06/22	98	80 - 120	100	80 - 120	<2.0	ug/L	NC	20		
5592240	Dissolved Zinc (Zn)	2018/06/22	100	80 - 120	100	80 - 120	<5.0	ug/L	NC	20		
5592255	Total Organic Carbon (C)	2018/06/22	95	85 - 115	96	80 - 120	<0.50	mg/L	2.1	15		
5592399	Nitrogen (Ammonia Nitrogen)	2018/06/21	101	80 - 120	104	80 - 120	<0.050	mg/L	NC	20		
5592423	Nitrogen (Ammonia Nitrogen)	2018/06/21	103	80 - 120	100	80 - 120	<0.050	mg/L	NC	20		
5593691	pH	2018/06/22							0.74	N/A	101	97 - 103
5593692	Conductivity	2018/06/22			101	80 - 120	1.5, RDL=1.0	uS/cm	0.29	25		
5593693	pH	2018/06/22							0.48	N/A	100	97 - 103
5593694	Conductivity	2018/06/22			100	80 - 120	1.4, RDL=1.0	uS/cm	0.24	25		
5593695	pH	2018/06/22							0.76	N/A	100	97 - 103
5593696	Conductivity	2018/06/22			101	80 - 120	1.7, RDL=1.0	uS/cm	0.15	25		
5593708	Turbidity	2018/06/22			94	80 - 120	<0.10	NTU	2.4	20	97	80 - 120
5593709	Turbidity	2018/06/22			94	80 - 120	<0.10	NTU	9.5	20	96	80 - 120
5593768	Total Alkalinity (Total as CaCO3)	2018/06/25	90	80 - 120	95	80 - 120	<5.0	mg/L	2.2	25		
5593775	Dissolved Chloride (Cl)	2018/06/22	101	80 - 120	102	80 - 120	<1.0	mg/L	1.8	25	100	80 - 120
5593777	Dissolved Sulphate (SO4)	2018/06/22	97	80 - 120	93	80 - 120	<2.0	mg/L	0.015	25		
5593778	Reactive Silica (SiO2)	2018/06/25	NC	80 - 120	97	80 - 120	<0.50	mg/L	0.95	25		
5593779	Colour	2018/06/22			99	80 - 120	<5.0	TCU	NC	20		
5593780	Orthophosphate (P)	2018/06/22	92	80 - 120	94	80 - 120	<0.010	mg/L	NC	25		
5593781	Nitrate + Nitrite (N)	2018/06/25	95	80 - 120	97	80 - 120	<0.050	mg/L	0.94	25		
5593783	Nitrite (N)	2018/06/25	98	80 - 120	96	80 - 120	<0.010	mg/L	NC	20		
5593990	Total Organic Carbon (C)	2018/06/22	92	85 - 115	94	80 - 120	<0.50	mg/L	1.5	15		

Maxxam Job #: B8F1147
Report Date: 2018/06/26

QUALITY ASSURANCE REPORT(CONT'D)

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

QC Batch	Parameter	Date	Matrix Spike		SPIKED BLANK		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits	% Recovery	QC Limits
5597605	Colour	2018/06/25			96	80 - 120	<5.0	TCU	NC	20		

N/A = Not Applicable

Matrix Spike: A sample to which a known amount of the analyte of interest has been added. Used to evaluate sample matrix interference.

QC Standard: A sample of known concentration prepared by an external agency under stringent conditions. Used as an independent check of method accuracy.

Spiked Blank: A blank matrix sample to which a known amount of the analyte, usually from a second source, has been added. Used to evaluate method accuracy.

Method Blank: A blank matrix containing all reagents used in the analytical procedure. Used to identify laboratory contamination.

NC (Matrix Spike): The recovery in the matrix spike was not calculated. The relative difference between the concentration in the parent sample and the spike amount was too small to permit a reliable recovery calculation (matrix spike concentration was less than the native sample concentration)

NC (Duplicate RPD): The duplicate RPD was not calculated. The concentration in the sample and/or duplicate was too low to permit a reliable RPD calculation (absolute difference <= 2x RDL).



Maxxam Job #: B8F1147
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

VALIDATION SIGNATURE PAGE

The analytical data and all QC contained in this report were reviewed and validated by the following individual(s).

<Original signed by>

Mike MacGillivray, Scientific Specialist (Inorganics)

Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(E), signing the reports. For Service Group specific validation please refer to the Validation Signature Page.



200 Bluewater Road, Suite 105, Bedford, Nova Scotia B4B 1G9 Tel: 902-420-0203 Fax: 902-420-8612 Toll Free: 1-800-565-7227
49-55 Elizabeth Avenue, St John's, NL A1A 1W9 Tel: 709-754-0203 Fax: 709-754-8612 Toll Free: 1-888-942-5222
465 George Street, Unit G, Sydney, NS B1P 1K5 Tel: 902-567-1255 Fax: 902-539-6504 Toll Free: 1-888-533-7777

ATL FCD 00149 / 22

CHAIN OF CUSTODY RECORD

COC #: D34770 Page 1 of 2

Invoice Information		Report Information (if differs from invoice)		Project Information (where applicable)		Turnaround Time (TAT) Required				
Company Name: <u>GHD Ltd.</u>	Contact Name: <u>Trina Jeffrey</u>	Company Name: <u>JEFF PARKS</u>	Contact Name: <u>GHD</u>	Quotation #: <u>STANDING OFFER</u>	P.O. #: <u>73512044</u>	<input checked="" type="checkbox"/> Regular TAT (5 business days) Most				
Address: <u>45 Akerley Blvd.</u>	Address: <u>Dartmouth Postal Code: B3B 1J7</u>	Address: <u>45 Akerley Blvd.</u>	Address: <u>Dartmouth Postal Code: B3B 1J7</u>	Project #: <u>088664</u>	Site Location: <u>Beaver Dam</u>	PLEASE PROVIDE ADVANCE NOTICE FOR RUSH PROJECTS				
Phone: <u>902-468-1248</u> Fax:	Phone: <u>902-468-1248</u> Fax:	Site #:	Sampled By:	IF RUSH please specify date (Surcharges will be applied)						
Email: <u>trina.jeffrey@ghd.com</u>	Email: <u>jeffrey.parks@ghd.com</u>	D.N. / J.R. / R.H.		DATE REQUIRED:						
Laboratory Use Only				Analysis Requested						
CUSTODY SEAL	COOLER TEMPERATURES	COOLER TEMPERATURES					Regulatory Requirements (Specify)			
Present	Intact									
6										
8										
3										
COOLING MEDIA PRESENT Y / N										
SAMPLES MUST BE KEPT COOL (< 10 °C) FROM TIME OF SAMPLING UNTIL DELIVERY TO MAXXAM										
SAMPLE IDENTIFICATION		DATE SAMPLED (YYYY/MM/DD)	TIME SAMPLED (HH:MM)	MATRIX	# OF CONTAINERS SUBMITTED	FIELD FILTERED & PRESERVED	LAB FILTRATION REQUIRED	Metals (Water)	Metals (Soil)	Regulatory Requirements (Specify)
1 MW-01A		2018/06/19	10:29	H ₂ O	3 X	X	ICP-MS (Total Metals) Well / Surface water	Total Digest (Default Method) For well water & surface water	Mercury (ICP/ICPCE) TOTAL / DISSOLVED Metal Acid Extractable (Available) Digest Mercury Total Digest -for Ocean Sediments (INNO3/Hg/ICD4)	RBCA Hydrocarbons (BTEx, Cd-T-32) Hydrocarbons Soil (Porabile), NS Fuel Oil Spill Policy Low Level BTEx, Cd-T-32
2 MW-01B		2018/06/19	10:20	H ₂ O	3 X	X	ICP-MS (Dissolved Metals) Ground waters	Disolved (or ground water)	Mercury (ICP/ICPCE) TOTAL / DISSOLVED Metal Acid Extractable (Available) Digest Mercury (Low level by Cold Vapour AA)	CCME Hydrocarbons (C66-Hg/F1/INTEX, F2/F4) NB: Portable Water BTEx, VPH, Low level T-E-H PANs (Default for water/soil)
3 MW-01 C		2018/06/19	10:16	H ₂ O	3 X	X				PANs (FWAL/CCME Sediment)
4 MW-02 A		2018/06/19	11:12	H ₂ O	3 X	X				PCBs
5 MW-02 B		2018/06/19	11:09	H ₂ O	3 X	X				VOCs
6 MW-03 A		2018/06/19	9:47	H ₂ O	3 X	X				Total Coliform/E. coli (Present/Absence)
7 MW-03 B		2018/06/19	9:52	H ₂ O	3 X	X				Total Coliform/E. coli (Cont.)
8 MW-03 C		2018/06/19	10:00	H ₂ O	3 X	X				
9 MW-19 A		2018/06/19	10:42	H ₂ O	3 X	X				
10 MW-19 B		2018/06/19	10:46	H ₂ O	3 X	X				
RELINQUISHED BY: (Signature/Print)		DATE: (YYYY/MM/DD)	TIME: (HH:MM)	RECEIVED BY: (Signature/Print)		DATE: (YYYY/MM/DD)	TIME: (HH:MM)	MAXXAM JOB #		
<Original signed by>		2018/06/19	2:47	<Original signed by>		Jae Doyle		B8F1147		

Unless otherwise agreed to in writing, work submitted on this Chain of Custody is subject to Maxxam's standard Terms and Conditions. Signing of this Chain of Custody document is acknowledgment and acceptance of our terms which are available for viewing at www.maxxam.ca/terms.

White: Maxxam

Pink Client



200 Bluewater Road, Suite 105, Bedford, Nova Scotia B4B 1G9 Tel: 902-420-0203 Fax: 902-420-8612 Toll Free: 1-800-565-7227
 49-55 Elizabeth Avenue, St John's, NL A1A 1W9 Tel: 709-754-0203 Fax: 709-754-8812 Toll Free: 1-888-492-7227
 465 George Street, Unit G, Sydney, NS B1P 1K5 Tel: 902-567-1255 Fax: 902-539-6504 Toll Free: 1-888-535-7770

ATL FCD 00149 / 22

www.maxxam.ca

E-mail: customerservicebedford@maxxam.ca

CHAIN OF CUSTODY RECORD

COC #: D34772 Page 2 of 2

Invoice Information			Report Information (If differs from invoice)			Project Information (where applicable)			Turnaround Time (TAT) Required																																																																																																																										
Company Name: GHD Ltd.	Contact Name: Trina Jeffery	Address: 45 Akerley Blvd.	Company Name: GHD Ltd.	Contact Name: JEFF Parks	Address: 45 Akerley Blvd.	Quotation #: STANDING OFFER	P.O. #: 73512044	Project #: 088664	<input checked="" type="checkbox"/> Regular TAT (5 business days) Most analyses																																																																																																																										
Phone: 902-468-1248	Fax:	Postal Code: B3B 1J1	Dartmouth	Postal Code: B3B 1J1	Dartmouth	Site Location: Beaver Dam	Site #: B.D.N. / J.R. / R.H.	Sampled By:	PLEASE PROVIDE ADVANCE NOTICE FOR RUSH PROJECTS																																																																																																																										
Email: trina.jeffery@ghd.com			Phone: 902-468-1248	Fax:	Email: jeffrey.parks@ghd.com				IF RUSH please specify date (Surcharges will be applied)																																																																																																																										
Laboratory Use Only			Analysis Requested						DATE REQUIRED:																																																																																																																										
CUSTODY SEAL		COOLER TEMPERATURES		COOLER TEMPERATURES		<table border="1"> <thead> <tr> <th colspan="2"># OF CONTAINERS SUBMITTED</th> <th colspan="2">FIELD FILTERED & PRESERVED</th> <th colspan="2">LAB FILTRATION REQUIRED</th> <th colspan="2">RCAP-M5 (Dissolved Metals)</th> <th colspan="2">Ground waters</th> <th colspan="2">Metals (Water)</th> <th colspan="2">Metals (Soil)</th> <th colspan="2">Regulatory Requirements (Specify)</th> </tr> <tr> <th>Present</th> <th>Intact</th> <th></th> <th></th> <th></th> <th></th> <th>Total Digest (Default Method)</th> <th>For-well water & surface water</th> <th>Dissolved for ground water</th> <th>Dissolved (CIRCLE) TOTAL / DISSOLVED</th> <th>Methane & Mercury</th> <th>Methane & Mercury</th> <th>Metals Total Digest (for Ocean Sediments) (HNO3/HCl/HClO4)</th> <th>Metals Total Digest (for Ocean Sediments) (HNO3/HCl/HClO4)</th> <th>Hazardous Soluble Boron (required for CCR-E Agricultural / Landfill)</th> <th>RBCA Hydrocarbons (BTEX, O6-E32)</th> <th>Hydrocarbons Soil (Possible), NS Fuel Oil Spill Policy Low Level BTEX, O6-E32</th> <th>CCME Hydrocarbons (CWA5-PHC F3/BTEX, F2-F4)</th> <th>NB Portable Water (BTEX, VPH, Low level T.E.H)</th> <th>PAHs (Default for water/soil)</th> <th>PAHs (FWAL/CCME Sediment)</th> <th>PCBs</th> <th>VOCs</th> <th>Total Coliform/E. coli (Presence/Absence)</th> <th>Total Coliform/E. coli (Count)</th> <th>Hold - DO NOT ANALYZE</th> </tr> </thead> <tbody> <tr> <td>6</td> <td></td> </tr> <tr> <td>8</td> <td></td> </tr> <tr> <td>5</td> <td></td> </tr> </tbody> </table>						# OF CONTAINERS SUBMITTED		FIELD FILTERED & PRESERVED		LAB FILTRATION REQUIRED		RCAP-M5 (Dissolved Metals)		Ground waters		Metals (Water)		Metals (Soil)		Regulatory Requirements (Specify)		Present	Intact					Total Digest (Default Method)	For-well water & surface water	Dissolved for ground water	Dissolved (CIRCLE) TOTAL / DISSOLVED	Methane & Mercury	Methane & Mercury	Metals Total Digest (for Ocean Sediments) (HNO3/HCl/HClO4)	Metals Total Digest (for Ocean Sediments) (HNO3/HCl/HClO4)	Hazardous Soluble Boron (required for CCR-E Agricultural / Landfill)	RBCA Hydrocarbons (BTEX, O6-E32)	Hydrocarbons Soil (Possible), NS Fuel Oil Spill Policy Low Level BTEX, O6-E32	CCME Hydrocarbons (CWA5-PHC F3/BTEX, F2-F4)	NB Portable Water (BTEX, VPH, Low level T.E.H)	PAHs (Default for water/soil)	PAHs (FWAL/CCME Sediment)	PCBs	VOCs	Total Coliform/E. coli (Presence/Absence)	Total Coliform/E. coli (Count)	Hold - DO NOT ANALYZE	6																										8																										5																									
# OF CONTAINERS SUBMITTED		FIELD FILTERED & PRESERVED		LAB FILTRATION REQUIRED		RCAP-M5 (Dissolved Metals)		Ground waters		Metals (Water)		Metals (Soil)		Regulatory Requirements (Specify)																																																																																																																					
Present	Intact					Total Digest (Default Method)	For-well water & surface water	Dissolved for ground water	Dissolved (CIRCLE) TOTAL / DISSOLVED	Methane & Mercury	Methane & Mercury	Metals Total Digest (for Ocean Sediments) (HNO3/HCl/HClO4)	Metals Total Digest (for Ocean Sediments) (HNO3/HCl/HClO4)	Hazardous Soluble Boron (required for CCR-E Agricultural / Landfill)	RBCA Hydrocarbons (BTEX, O6-E32)	Hydrocarbons Soil (Possible), NS Fuel Oil Spill Policy Low Level BTEX, O6-E32	CCME Hydrocarbons (CWA5-PHC F3/BTEX, F2-F4)	NB Portable Water (BTEX, VPH, Low level T.E.H)	PAHs (Default for water/soil)	PAHs (FWAL/CCME Sediment)	PCBs	VOCs	Total Coliform/E. coli (Presence/Absence)	Total Coliform/E. coli (Count)	Hold - DO NOT ANALYZE																																																																																																										
6																																																																																																																																			
8																																																																																																																																			
5																																																																																																																																			
COOLING MEDIA PRESENT Y / N															COMMENTS																																																																																																																				
SAMPLES MUST BE KEPT COOL (< 10 °C) FROM TIME OF SAMPLING UNTIL DELIVERY TO MAXXAM															2018 JUN 19 15:24																																																																																																																				
SAMPLE IDENTIFICATION			DATE SAMPLED (YYYY/MM/DD)	TIME SAMPLED (HH:MM)	MATRIX	4 OF	FIELD FILTERED & PRESERVED	LAB FILTRATION REQUIRED	RCAP-M5 (Dissolved Metals)	Ground waters	Metals (Water)	Metals (Soil)	RBCA Hydrocarbons (BTEX, O6-E32)	Hydrocarbons Soil (Possible), NS Fuel Oil Spill Policy Low Level BTEX, O6-E32	CCME Hydrocarbons (CWA5-PHC F3/BTEX, F2-F4)	NB Portable Water (BTEX, VPH, Low level T.E.H)	PAHs (Default for water/soil)	PAHs (FWAL/CCME Sediment)	PCBs	VOCs	Total Coliform/E. coli (Presence/Absence)	Total Coliform/E. coli (Count)	Hold - DO NOT ANALYZE																																																																																																												
1. MW-19 C	2018/06/19	10:53	H ₂ O	3 X	X																																																																																																																														
2. MW-Dup C	2018/06/19	—	H ₂ O	3 X	X																																																																																																																														
3.																																																																																																																																			
4.																																																																																																																																			
5.																																																																																																																																			
6.																																																																																																																																			
7.																																																																																																																																			
8.																																																																																																																																			
9.																																																																																																																																			
10.																																																																																																																																			
RELINQUISHED BY: (Signature/Print)			DATE: (YYYY/MM/DD)	TIME: (HH:MM)	RECEIVED BY: (Signature/Print)			DATE: (YYYY/MM/DD)	TIME: (HH:MM)	MAXXAM JOB #																																																																																																																									
<Original signed by>			2018/06/19	2:47	<Original signed by>			<i>Joe Deyle</i>		B8F1147																																																																																																																									
Unless otherwise agreed to in writing, work submitted on this Chain of Custody is subject to Maxxam's standard Terms and Conditions. Signing of this Chain of Custody document is acknowledgment and acceptance of our terms which are available for viewing at www.maxxam.ca/terms .															18 JUN 19 14:47																																																																																																																				

White: Maxxam

Pink: Client

Your P.O. #: 73512044
 Your Project #: 088664-20
 Site Location: BEAVER DAM
 Your C.O.C. #: D34771

Attention: Jeff Parks

GHD Limited
 45 Akerley Blvd
 Dartmouth , NS
 CANADA B3B 1J7

Report Date: 2018/06/26
 Report #: R5266814
 Version: 1 - Final

CERTIFICATE OF ANALYSIS

MAXXAM JOB #: B8F0978

Received: 2018/06/19, 14:47

Sample Matrix: Water
 # Samples Received: 17

Analyses	Quantity	Date Extracted	Date Analyzed	Laboratory Method	Reference
Carbonate, Bicarbonate and Hydroxide	17	N/A	2018/06/22	N/A	SM 22 4500-CO2 D
Alkalinity	17	N/A	2018/06/25	ATL SOP 00013	EPA 310.2 R1974 m
Chloride	17	N/A	2018/06/22	ATL SOP 00014	SM 22 4500-Cl- E m
Colour	4	N/A	2018/06/22	ATL SOP 00020	SM 22 2120C m
Colour	13	N/A	2018/06/25	ATL SOP 00020	SM 22 2120C m
Conductance - water	17	N/A	2018/06/22	ATL SOP 00004	SM 23 2510B m
Hardness (calculated as CaCO3)	17	N/A	2018/06/22	ATL SOP 00048	SM 22 2340 B
Metals Water Diss. MS (as rec'd)	17	N/A	2018/06/22	ATL SOP 00058	EPA 6020A R1 m
Ion Balance (% Difference)	17	N/A	2018/06/26	N/A	Auto Calc.
Anion and Cation Sum	17	N/A	2018/06/22	N/A	Auto Calc.
Nitrogen Ammonia - water	17	N/A	2018/06/21	ATL SOP 00015	EPA 350.1 R2 m
Nitrogen - Nitrate + Nitrite	17	N/A	2018/06/25	ATL SOP 00016	USGS I-2547-11m
Nitrogen - Nitrite	17	N/A	2018/06/25	ATL SOP 00017	SM 23 4500-NO2- B m
Nitrogen - Nitrate (as N)	17	N/A	2018/06/26	ATL SOP 00018	ASTM D3867-16
pH (1)	17	N/A	2018/06/22	ATL SOP 00003	SM 23 4500-H+ B m
Phosphorus - ortho	17	N/A	2018/06/22	ATL SOP 00021	SM 23 4500-P E m
Sat. pH and Langelier Index (@ 20C)	17	N/A	2018/06/26	ATL SOP 00049	Auto Calc.
Sat. pH and Langelier Index (@ 4C)	17	N/A	2018/06/26	ATL SOP 00049	Auto Calc.
Reactive Silica	17	N/A	2018/06/25	ATL SOP 00022	EPA 366.0 m
Sulphate	17	N/A	2018/06/22	ATL SOP 00023	ASTM D516-16 m
Total Dissolved Solids (TDS calc)	17	N/A	2018/06/26	N/A	Auto Calc.
Organic carbon - Total (TOC) (2)	16	N/A	2018/06/22	ATL SOP 00203	SM 23 5310B m
Organic carbon - Total (TOC) (2)	1	N/A	2018/06/25	ATL SOP 00203	SM 23 5310B m
Turbidity	17	N/A	2018/06/22	ATL SOP 00011	EPA 180.1 R2 m

Remarks:

Maxxam Analytics' laboratories are accredited to ISO/IEC 17025:2005 for specific parameters on scopes of accreditation. Unless otherwise noted, procedures used by Maxxam are based upon recognized Provincial, Federal or US method compendia such as CCME, MDDELCC, EPA, APHA.

All work recorded herein has been done in accordance with procedures and practices ordinarily exercised by professionals in Maxxam's profession using accepted testing methodologies, quality assurance and quality control procedures (except where otherwise agreed by the client and Maxxam in writing). All

Your P.O. #: 73512044
Your Project #: 088664-20
Site Location: BEAVER DAM
Your C.O.C. #: D34771

Attention: Jeff Parks

GHD Limited
45 Akerley Blvd
Dartmouth , NS
CANADA B3B 1J7

Report Date: 2018/06/26
Report #: R5266814
Version: 1 - Final

CERTIFICATE OF ANALYSIS

MAXXAM JOB #: B8F0978

Received: 2018/06/19, 14:47

data is in statistical control and has met quality control and method performance criteria unless otherwise noted. All method blanks are reported; unless indicated otherwise, associated sample data are not blank corrected.

Maxxam Analytics' liability is limited to the actual cost of the requested analyses, unless otherwise agreed in writing. There is no other warranty expressed or implied. Maxxam has been retained to provide analysis of samples provided by the Client using the testing methodology referenced in this report. Interpretation and use of test results are the sole responsibility of the Client and are not within the scope of services provided by Maxxam, unless otherwise agreed in writing.

Solid sample results, except biota, are based on dry weight unless otherwise indicated. Organic analyses are not recovery corrected except for isotope dilution methods.

Results relate to samples tested.

This Certificate shall not be reproduced except in full, without the written approval of the laboratory.

Reference Method suffix "m" indicates test methods incorporate validated modifications from specific reference methods to improve performance.

* RPDs calculated using raw data. The rounding of final results may result in the apparent difference.

(1) The APHA Standard Method require pH to be analyzed within 15 minutes of sampling and therefore field analysis is required for compliance. All Laboratory pH analyses in this report are reported past the APHA Standard Method holding time.

(2) TOC / DOC present in the sample should be considered as non-purgeable TOC / DOC.

<Original signed by>

Kavya Nair
Project Manager Assistant
26 Jun 2018 13:38:53

Encryption Key

Please direct all questions regarding this Certificate of Analysis to your Project Manager.

Heather Macumber, Senior Project Manager

Email: HMacumber@maxxam.ca

Phone# (902)420-0203 Ext:226

=====

Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(E), signing the reports. For Service Group specific validation please refer to the Validation Signature Page.



Maxxam Job #: B8F0978
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

RESULTS OF ANALYSES OF WATER

Maxxam ID		GZW431			GZW431				GZW432				
Sampling Date		2018/06/18 11:26			2018/06/18 11:26				2018/06/18 11:37				
COC Number		D34771			D34771				D34771				
	UNITS	MW-12A	RDL	QC Batch	MDL	MW-12A Lab-Dup	RDL	QC Batch	MDL	MW-12B	RDL	QC Batch	MDL
Calculated Parameters													
Anion Sum	me/L	0.830	N/A	5589413	N/A					2.20	N/A	5589413	N/A
Bicarb. Alkalinity (calc. as CaCO3)	mg/L	33	1.0	5589410	0.20					80	1.0	5589410	0.20
Calculated TDS	mg/L	64	1.0	5589418	0.20					130	1.0	5589418	0.20
Carb. Alkalinity (calc. as CaCO3)	mg/L	<1.0	1.0	5589410	0.20					<1.0	1.0	5589410	0.20
Cation Sum	me/L	0.940	N/A	5589413	N/A					2.10	N/A	5589413	N/A
Hardness (CaCO3)	mg/L	31	1.0	5589411	1.0					70	1.0	5589411	1.0
Ion Balance (% Difference)	%	6.21	N/A	5589412	N/A					2.33	N/A	5589412	N/A
Langelier Index (@ 20C)	N/A	-2.42		5589415						-0.212		5589415	
Langelier Index (@ 4C)	N/A	-2.67		5589416						-0.462		5589416	
Nitrate (N)	mg/L	0.085	0.050	5590281	N/A					0.062	0.050	5590281	N/A
Saturation pH (@ 20C)	N/A	8.90		5589415						8.08		5589415	
Saturation pH (@ 4C)	N/A	9.15		5589416						8.33		5589416	
Inorganics													
Total Alkalinity (Total as CaCO3)	mg/L	33	5.0	5593768	N/A	33	5.0	5593768	N/A	81	5.0	5589743	N/A
Dissolved Chloride (Cl)	mg/L	2.4	1.0	5593775	N/A	2.4	1.0	5593775	N/A	4.6	1.0	5589752	N/A
Colour	TCU	<5.0	5.0	5593779	N/A	<5.0	5.0	5593779	N/A	<5.0	5.0	5597605	N/A
Nitrate + Nitrite (N)	mg/L	0.085	0.050	5593781	N/A	0.086	0.050	5593781	N/A	0.062	0.050	5589765	N/A
Nitrite (N)	mg/L	<0.010	0.010	5593783	N/A	<0.010	0.010	5593783	N/A	<0.010	0.010	5589767	N/A
Nitrogen (Ammonia Nitrogen)	mg/L	<0.050	0.050	5592399	N/A	<0.050	0.050	5592399	N/A	<0.050	0.050	5592399	N/A
Total Organic Carbon (C)	mg/L	<0.50	0.50	5592255	N/A					1.0	0.50	5592255	N/A
Orthophosphate (P)	mg/L	<0.010	0.010	5593780	N/A	<0.010	0.010	5593780	N/A	0.016	0.010	5589762	N/A
pH	pH	6.48	N/A	5593693	N/A	6.45	N/A	5593693	N/A	7.86	N/A	5593691	N/A
Reactive Silica (SiO2)	mg/L	17	0.50	5593778	N/A	17	0.50	5593778	N/A	10	0.50	5589757	N/A
Dissolved Sulphate (SO4)	mg/L	4.0	2.0	5593777	N/A	4.0	2.0	5593777	N/A	21	2.0	5589755	N/A
Turbidity	NTU	41	0.10	5593708	0.10	40	0.10	5593708	0.10	11	0.10	5593709	0.10
Conductivity	uS/cm	80	1.0	5593694	N/A	80	1.0	5593694	N/A	200	1.0	5593692	N/A

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Lab-Dup = Laboratory Initiated Duplicate

N/A = Not Applicable



Maxxam Job #: B8F0978
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

RESULTS OF ANALYSES OF WATER

Maxxam ID		GZW433			GZW434			GZW435			
Sampling Date		2018/06/18 11:58			2018/06/18 12:07			2018/06/18 12:15			
COC Number		D34771			D34771			D34771			
	UNITS	MW-09A	RDL	QC Batch	MW-09B	RDL	QC Batch	MW-09D	RDL	QC Batch	MDL

Calculated Parameters

Anion Sum	me/L	0.340	N/A	5589413	2.46	N/A	5589413	2.97	N/A	5589413	N/A
Bicarb. Alkalinity (calc. as CaCO3)	mg/L	9.2	1.0	5589410	71	1.0	5589410	65	1.0	5589410	0.20
Calculated TDS	mg/L	30	1.0	5589418	150	1.0	5589418	190	1.0	5589418	0.20
Carb. Alkalinity (calc. as CaCO3)	mg/L	<1.0	1.0	5589410	<1.0	1.0	5589410	<1.0	1.0	5589410	0.20
Cation Sum	me/L	0.630	N/A	5589413	2.37	N/A	5589413	2.89	N/A	5589413	N/A
Hardness (CaCO3)	mg/L	25	1.0	5589411	72	1.0	5589411	93	1.0	5589411	1.0
Ion Balance (% Difference)	%	29.9	N/A	5589412	1.86	N/A	5589412	1.37	N/A	5589412	N/A
Langelier Index (@ 20C)	N/A	-3.07		5589415	-0.174		5589415	-0.547		5589415	
Langelier Index (@ 4C)	N/A	-3.32		5589416	-0.424		5589416	-0.798		5589416	
Nitrate (N)	mg/L	<0.050	0.050	5590281	<0.050	0.050	5590281	<0.050	0.050	5590281	N/A
Saturation pH (@ 20C)	N/A	9.37		5589415	8.11		5589415	8.09		5589415	
Saturation pH (@ 4C)	N/A	9.62		5589416	8.36		5589416	8.34		5589416	

Inorganics

Total Alkalinity (Total as CaCO3)	mg/L	9.2	5.0	5589743	72	5.0	5589743	65	5.0	5589743	N/A
Dissolved Chloride (Cl)	mg/L	3.5	1.0	5589752	5.1	1.0	5589752	8.6	1.0	5589752	N/A
Colour	TCU	<5.0	5.0	5597605	<5.0	5.0	5597605	<5.0	5.0	5597605	N/A
Nitrate + Nitrite (N)	mg/L	<0.050	0.050	5589765	<0.050	0.050	5589765	<0.050	0.050	5589765	N/A
Nitrite (N)	mg/L	<0.010	0.010	5589767	<0.010	0.010	5589767	<0.010	0.010	5589767	N/A
Nitrogen (Ammonia Nitrogen)	mg/L	<0.050	0.050	5592399	<0.050	0.050	5592399	<0.050	0.050	5592399	N/A
Total Organic Carbon (C)	mg/L	0.59	0.50	5592255	2.5	0.50	5592255	9.1 (1)	5.0	5593990	N/A
Orthophosphate (P)	mg/L	<0.010	0.010	5589762	0.027	0.010	5589762	0.012	0.010	5589762	N/A
pH	pH	6.30	N/A	5593693	7.94	N/A	5593691	7.54	N/A	5593691	N/A
Reactive Silica (SiO2)	mg/L	5.1	0.50	5589757	9.3	0.50	5589757	12	0.50	5589757	N/A
Dissolved Sulphate (SO4)	mg/L	2.9	2.0	5589755	42 (1)	10	5589755	68 (1)	10	5589755	N/A
Turbidity	NTU	0.29	0.10	5593709	6.1	0.10	5593709	2.4	0.10	5593708	0.10
Conductivity	uS/cm	30	1.0	5593694	230	1.0	5593692	300	1.0	5593692	N/A

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

N/A = Not Applicable

(1) Elevated reporting limit due to sample matrix.



Maxxam Job #: B8F0978
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

RESULTS OF ANALYSES OF WATER

Maxxam ID		GZW436	GZW437		GZW438		GZW439			
Sampling Date		2018/06/18 12:50	2018/06/18 12:58		2018/06/18 15:10		2018/06/18 15:16			
COC Number		D34771	D34771		D34771		D34771			
	UNITS	MW-04A	MW-04B	QC Batch	MW-21A	QC Batch	MW-21B	RDL	QC Batch	MDL
Calculated Parameters										
Anion Sum	me/L	0.440	1.16	5590385	0.250	5590385	0.580	N/A	5590385	N/A
Bicarb. Alkalinity (calc. as CaCO3)	mg/L	11	41	5590380	6.5	5590380	21	1.0	5590380	0.20
Calculated TDS	mg/L	32	71	5590389	20	5590389	40	1.0	5590389	0.20
Carb. Alkalinity (calc. as CaCO3)	mg/L	<1.0	<1.0	5590380	<1.0	5590380	<1.0	1.0	5590380	0.20
Cation Sum	me/L	0.510	1.08	5590385	0.240	5590385	0.550	N/A	5590385	N/A
Hardness (CaCO3)	mg/L	17	44	5590383	7.0	5590383	18	1.0	5590383	1.0
Ion Balance (% Difference)	%	7.37	3.57	5590384	2.04	5590384	2.65	N/A	5590384	N/A
Langelier Index (@ 20C)	N/A	-3.26	-1.26	5590387	-4.65	5590387	-2.94		5590387	
Langelier Index (@ 4C)	N/A	-3.51	-1.51	5590388	-4.90	5590388	-3.19		5590388	
Nitrate (N)	mg/L	<0.050	<0.050	5590281	0.48	5590281	0.35	0.050	5590281	N/A
Saturation pH (@ 20C)	N/A	9.58	8.54	5590387	10.3	5590387	9.30		5590387	
Saturation pH (@ 4C)	N/A	9.83	8.79	5590388	10.5	5590388	9.56		5590388	
Inorganics										
Total Alkalinity (Total as CaCO3)	mg/L	11	41	5589743	6.5	5589743	21	5.0	5589743	N/A
Dissolved Chloride (Cl)	mg/L	6.4	4.9	5589752	3.1	5589752	3.1	1.0	5589752	N/A
Colour	TCU	<5.0	<5.0	5597605	8.0	5597605	<5.0	5.0	5597605	N/A
Nitrate + Nitrite (N)	mg/L	<0.050	<0.050	5589765	0.48	5589765	0.35	0.050	5589765	N/A
Nitrite (N)	mg/L	<0.010	<0.010	5589767	<0.010	5589767	<0.010	0.010	5589767	N/A
Nitrogen (Ammonia Nitrogen)	mg/L	<0.050	<0.050	5592399	<0.050	5592399	<0.050	0.050	5592399	N/A
Total Organic Carbon (C)	mg/L	0.73	1.1	5592255	2.1	5593990	1.0	0.50	5593990	N/A
Orthophosphate (P)	mg/L	<0.010	<0.010	5589762	<0.010	5589762	0.018	0.010	5589762	N/A
pH	pH	6.32	7.28	5593693	5.64	5593693	6.37	N/A	5593697	N/A
Reactive Silica (SiO2)	mg/L	6.4	9.6	5589757	5.6	5589757	8.9	0.50	5589757	N/A
Dissolved Sulphate (SO4)	mg/L	2.3	9.6	5589755	<2.0	5589755	2.2	2.0	5589755	N/A
Turbidity	NTU	0.79	5.9	5593709	1.1	5593709	23	0.10	5593709	0.10
Conductivity	uS/cm	41	110	5593694	33	5593694	61	1.0	5593698	N/A
RDL = Reportable Detection Limit QC Batch = Quality Control Batch N/A = Not Applicable										



Maxxam Job #: B8F0978
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

RESULTS OF ANALYSES OF WATER

Maxxam ID		GZW439				GZW440		GZW441			
Sampling Date		2018/06/18 15:16				2018/06/18 15:28		2018/06/18 13:36			
COC Number		D34771				D34771		D34771			
	UNITS	MW-21B Lab-Dup	RDL	QC Batch	MDL	MW-21C	QC Batch	MW-16A	RDL	QC Batch	MDL
Calculated Parameters											
Anion Sum	me/L					1.67	5590385	1.80	N/A	5590385	N/A
Bicarb. Alkalinity (calc. as CaCO3)	mg/L					54	5590380	79	1.0	5590380	0.20
Calculated TDS	mg/L					110	5590389	100	1.0	5590389	0.20
Carb. Alkalinity (calc. as CaCO3)	mg/L					<1.0	5590380	<1.0	1.0	5590380	0.20
Cation Sum	me/L					1.56	5590385	1.72	N/A	5590385	N/A
Hardness (CaCO3)	mg/L					38	5590383	66	1.0	5590383	1.0
Ion Balance (% Difference)	%					3.41	5590384	2.27	N/A	5590384	N/A
Langelier Index (@ 20C)	N/A					-1.93	5590387	-0.291		5590387	
Langelier Index (@ 4C)	N/A					-2.18	5590388	-0.542		5590388	
Nitrate (N)	mg/L					0.14	5590281	0.092	0.050	5590281	N/A
Saturation pH (@ 20C)	N/A					8.63	5590387	8.08		5590387	
Saturation pH (@ 4C)	N/A					8.88	5590388	8.33		5590388	
Inorganics											
Total Alkalinity (Total as CaCO3)	mg/L					54	5589743	79	5.0	5589743	N/A
Dissolved Chloride (Cl)	mg/L					5.2	5589752	4.0	1.0	5589752	N/A
Colour	TCU					<5.0	5597605	<5.0	5.0	5597605	N/A
Nitrate + Nitrite (N)	mg/L					0.14	5589765	0.092	0.050	5589765	N/A
Nitrite (N)	mg/L					<0.010	5589767	<0.010	0.010	5589767	N/A
Nitrogen (Ammonia Nitrogen)	mg/L					<0.050	5592399	<0.050	0.050	5592399	N/A
Total Organic Carbon (C)	mg/L					4.2	5593990	0.60	0.50	5596952	N/A
Orthophosphate (P)	mg/L					<0.010	5589762	<0.010	0.010	5589762	N/A
pH	pH	6.39	N/A	5593697	N/A	6.70	5593693	7.79	N/A	5593695	N/A
Reactive Silica (SiO2)	mg/L					15	5589757	11	0.50	5589757	N/A
Dissolved Sulphate (SO4)	mg/L					21	5589755	4.5	2.0	5589755	N/A
Turbidity	NTU					7.6	5593711	3.0	0.10	5593711	0.10
Conductivity	uS/cm	60	1.0	5593698	N/A	160	5593694	160	1.0	5593696	N/A

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Lab-Dup = Laboratory Initiated Duplicate

N/A = Not Applicable



Maxxam Job #: B8F0978
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

RESULTS OF ANALYSES OF WATER

Maxxam ID		GZW442		GZW443		GZW444		GZW445			
Sampling Date		2018/06/18 13:40		2018/06/18 14:11		2018/06/18 14:19		2018/06/18 14:25			
COC Number		D34771		D34771		D34771		D34771			
Calculated Parameters											
Anion Sum	me/L	1.43	5590385	0.510	5590385	0.300	5590385	0.420	N/A	5590385	N/A
Bicarb. Alkalinity (calc. as CaCO ₃)	mg/L	59	5590380	15	5590380	8.3	5590380	14	1.0	5590380	0.20
Calculated TDS	mg/L	84	5590389	34	5590389	25	5590389	32	1.0	5590389	0.20
Carb. Alkalinity (calc. as CaCO ₃)	mg/L	<1.0	5590380	<1.0	5590380	<1.0	5590380	<1.0	1.0	5590380	0.20
Cation Sum	me/L	1.34	5590385	0.470	5590385	0.260	5590385	0.390	N/A	5590385	N/A
Hardness (CaCO ₃)	mg/L	55	5590383	15	5590383	6.6	5590383	12	1.0	5590383	1.0
Ion Balance (% Difference)	%	3.25	5590384	4.08	5590384	7.14	5590384	3.70	N/A	5590384	N/A
Langelier Index (@ 20C)	N/A	-0.510	5590387	-3.14	5590387	-4.06	5590387	-3.07		5590387	
Langelier Index (@ 4C)	N/A	-0.761	5590388	-3.40	5590388	-4.31	5590388	-3.33		5590388	
Nitrate (N)	mg/L	0.14	5590281	<0.050	5590281	<0.050	5590281	<0.050	0.050	5590281	N/A
Saturation pH (@ 20C)	N/A	8.27	5590387	9.42	5590387	10.2	5590387	9.59		5590387	
Saturation pH (@ 4C)	N/A	8.52	5590388	9.67	5590388	10.4	5590388	9.84		5590388	
Inorganics											
Total Alkalinity (Total as CaCO ₃)	mg/L	59	5589743	15	5589743	8.3	5593768	14	5.0	5593768	N/A
Dissolved Chloride (Cl)	mg/L	4.1	5589752	5.2	5589752	2.9	5593775	2.9	1.0	5593775	N/A
Colour	TCU	<5.0	5597605	<5.0	5597605	<5.0	5597513	<5.0	5.0	5593779	N/A
Nitrate + Nitrite (N)	mg/L	0.14	5589765	<0.050	5589765	<0.050	5593781	<0.050	0.050	5593781	N/A
Nitrite (N)	mg/L	<0.010	5589767	<0.010	5589767	<0.010	5593783	<0.010	0.010	5593783	N/A
Nitrogen (Ammonia Nitrogen)	mg/L	<0.050	5592399	<0.050	5592399	<0.050	5592399	<0.050	0.050	5592399	N/A
Total Organic Carbon (C)	mg/L	<0.50	5593990	0.59	5593990	0.56	5593990	<0.50	0.50	5593990	N/A
Orthophosphate (P)	mg/L	<0.010	5589762	<0.010	5589762	0.014	5593780	<0.010	0.010	5593780	N/A
pH	pH	7.76	5593693	6.28	5593693	6.10	5593693	6.51	N/A	5593691	N/A
Reactive Silica (SiO ₂)	mg/L	10	5589757	6.9	5589757	8.6	5593778	10	0.50	5593778	N/A
Dissolved Sulphate (SO ₄)	mg/L	6.0	5589755	2.6	5589755	2.7	5593777	2.9	2.0	5593777	N/A
Turbidity	NTU	0.68	5593709	1.6	5593711	0.49	5593711	0.74	0.10	5593709	0.10
Conductivity	uS/cm	130	5593694	46	5593694	29	5593694	40	1.0	5593692	N/A
RDL = Reportable Detection Limit QC Batch = Quality Control Batch N/A = Not Applicable											



Maxxam Job #: B8F0978
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

RESULTS OF ANALYSES OF WATER

Maxxam ID		GZW446		GZW447			GZW447				
Sampling Date		2018/06/18		2018/06/18			2018/06/18				
COC Number		D34771		D34771			D34771				
	UNITS	MW-DUPA	QC Batch	MW-DUPB	RDL	QC Batch	MDL	MW-DUPB Lab-Dup	RDL	QC Batch	MDL
Calculated Parameters											
Anion Sum	me/L	0.320	5590385	0.300	N/A	5590385	N/A				
Bicarb. Alkalinity (calc. as CaCO3)	mg/L	8.8	5590380	7.4	1.0	5590380	0.20				
Calculated TDS	mg/L	29	5590389	25	1.0	5590389	0.20				
Carb. Alkalinity (calc. as CaCO3)	mg/L	<1.0	5590380	<1.0	1.0	5590380	0.20				
Cation Sum	me/L	0.630	5590385	0.260	N/A	5590385	N/A				
Hardness (CaCO3)	mg/L	25	5590383	6.7	1.0	5590383	1.0				
Ion Balance (% Difference)	%	32.6	5590384	7.14	N/A	5590384	N/A				
Langelier Index (@ 20C)	N/A	-2.95	5590387	-4.08		5590387					
Langelier Index (@ 4C)	N/A	-3.20	5590388	-4.33		5590388					
Nitrate (N)	mg/L	<0.050	5590281	<0.050	0.050	5590281	N/A				
Saturation pH (@ 20C)	N/A	9.39	5590387	10.2		5590387					
Saturation pH (@ 4C)	N/A	9.64	5590388	10.4		5590388					
Inorganics											
Total Alkalinity (Total as CaCO3)	mg/L	8.8	5593768	7.4	5.0	5593768	N/A				
Dissolved Chloride (Cl)	mg/L	2.9	5593775	3.3	1.0	5593775	N/A				
Colour	TCU	<5.0	5593779	5.3	5.0	5593779	N/A				
Nitrate + Nitrite (N)	mg/L	<0.050	5593781	<0.050	0.050	5593781	N/A				
Nitrite (N)	mg/L	0.021	5593783	<0.010	0.010	5593783	N/A				
Nitrogen (Ammonia Nitrogen)	mg/L	<0.050	5592399	<0.050	0.050	5592399	N/A				
Total Organic Carbon (C)	mg/L	0.61	5593990	0.51	0.50	5592255	N/A				
Orthophosphate (P)	mg/L	<0.010	5593780	0.017	0.010	5593780	N/A				
pH	pH	6.44	5593691	6.12	N/A	5593693	N/A				
Reactive Silica (SiO2)	mg/L	5.1	5593778	9.1	0.50	5593778	N/A				
Dissolved Sulphate (SO4)	mg/L	2.9	5593777	2.6	2.0	5593777	N/A				
Turbidity	NTU	0.33	5593708	0.90	0.10	5593709	0.10	0.99	0.10	5593709	0.10
Conductivity	uS/cm	31	5593692	29	1.0	5593694	N/A				

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Lab-Dup = Laboratory Initiated Duplicate

N/A = Not Applicable



Maxxam Job #: B8F0978
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

ELEMENTS BY ICP/MS (WATER)

Maxxam ID		GZW431	GZW432	GZW433	GZW434	GZW435		GZW436			
Sampling Date		2018/06/18 11:26	2018/06/18 11:37	2018/06/18 11:58	2018/06/18 12:07	2018/06/18 12:15		2018/06/18 12:50			
COC Number		D34771	D34771	D34771	D34771	D34771		D34771			
	UNITS	MW-12A	MW-12B	MW-09A	MW-09B	MW-09D	QC Batch	MW-04A	RDL	QC Batch	MDL

Metals											
Dissolved Aluminum (Al)	ug/L	5.0	5.5	<5.0	61	8.9	5592239	6.0	5.0	5593914	N/A
Dissolved Antimony (Sb)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	5592239	<1.0	1.0	5593914	N/A
Dissolved Arsenic (As)	ug/L	<1.0	44	1.0	120	140	5592239	<1.0	1.0	5593914	N/A
Dissolved Barium (Ba)	ug/L	6.7	10	6.1	12	8.9	5592239	4.1	1.0	5593914	N/A
Dissolved Beryllium (Be)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	5592239	<1.0	1.0	5593914	N/A
Dissolved Bismuth (Bi)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	5592239	<2.0	2.0	5593914	N/A
Dissolved Boron (B)	ug/L	<50	<50	<50	<50	<50	5592239	<50	50	5593914	N/A
Dissolved Cadmium (Cd)	ug/L	0.027	<0.010	0.030	<0.010	<0.010	5592239	0.011	0.010	5593914	N/A
Dissolved Calcium (Ca)	ug/L	7900	24000	9100	25000	30000	5592239	4800	100	5593914	N/A
Dissolved Chromium (Cr)	ug/L	<1.0	2.3	<1.0	<1.0	<1.0	5592239	<1.0	1.0	5593914	N/A
Dissolved Cobalt (Co)	ug/L	2.6	<0.40	1.2	<0.40	<0.40	5592239	0.87	0.40	5593914	N/A
Dissolved Copper (Cu)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	5592239	<2.0	2.0	5593914	N/A
Dissolved Iron (Fe)	ug/L	220	<50	<50	<50	<50	5592239	<50	50	5593914	N/A
Dissolved Lead (Pb)	ug/L	<0.50	<0.50	<0.50	<0.50	<0.50	5592239	<0.50	0.50	5593914	N/A
Dissolved Magnesium (Mg)	ug/L	2700	2500	640	2300	4100	5592239	1200	100	5593914	N/A
Dissolved Manganese (Mn)	ug/L	1300	230	110	11	46	5592239	69	2.0	5593914	N/A
Dissolved Molybdenum (Mo)	ug/L	<2.0	19	<2.0	9.2	10	5592239	<2.0	2.0	5593914	N/A
Dissolved Nickel (Ni)	ug/L	2.5	<2.0	3.3	<2.0	<2.0	5592239	5.4	2.0	5593914	N/A
Dissolved Phosphorus (P)	ug/L	<100	<100	<100	<100	<100	5592239	<100	100	5593914	N/A
Dissolved Potassium (K)	ug/L	2300	1600	720	1700	1200	5592239	1100	100	5593914	N/A
Dissolved Selenium (Se)	ug/L	<1.0	<1.0	<1.0	<1.0	<1.0	5592239	<1.0	1.0	5593914	N/A
Dissolved Silver (Ag)	ug/L	<0.10	<0.10	<0.10	<0.10	<0.10	5592239	<0.10	0.10	5593914	N/A
Dissolved Sodium (Na)	ug/L	6000	15000	2400	20000	23000	5592239	3300	100	5593914	N/A
Dissolved Strontium (Sr)	ug/L	53	80	14	340	680	5592239	25	2.0	5593914	N/A
Dissolved Thallium (Tl)	ug/L	<0.10	<0.10	<0.10	<0.10	<0.10	5592239	<0.10	0.10	5593914	N/A
Dissolved Tin (Sn)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	5592239	<2.0	2.0	5593914	N/A
Dissolved Titanium (Ti)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	5592239	<2.0	2.0	5593914	N/A
Dissolved Uranium (U)	ug/L	<0.10	2.0	<0.10	6.6	3.7	5592239	<0.10	0.10	5593914	N/A
Dissolved Vanadium (V)	ug/L	<2.0	<2.0	<2.0	<2.0	<2.0	5592239	<2.0	2.0	5593914	N/A
Dissolved Zinc (Zn)	ug/L	<5.0	<5.0	<5.0	<5.0	<5.0	5592239	<5.0	5.0	5593914	N/A

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

N/A = Not Applicable



Maxxam Job #: B8F0978
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

ELEMENTS BY ICP/MS (WATER)

Maxxam ID		GZW436		GZW437		GZW438		GZW439			
Sampling Date		2018/06/18 12:50		2018/06/18 12:58		2018/06/18 15:10		2018/06/18 15:16			
COC Number		D34771		D34771		D34771		D34771			
	UNITS	MW-04A Lab-Dup	QC Batch	MW-04B	QC Batch	MW-21A	QC Batch	MW-21B	RDL	QC Batch	MDL
Metals											
Dissolved Aluminum (Al)	ug/L	5.8	5593914	9.0	5592239	430	5593914	16	5.0	5592239	N/A
Dissolved Antimony (Sb)	ug/L	<1.0	5593914	<1.0	5592239	<1.0	5593914	<1.0	1.0	5592239	N/A
Dissolved Arsenic (As)	ug/L	<1.0	5593914	<1.0	5592239	<1.0	5593914	<1.0	1.0	5592239	N/A
Dissolved Barium (Ba)	ug/L	4.1	5593914	4.0	5592239	15	5593914	3.5	1.0	5592239	N/A
Dissolved Beryllium (Be)	ug/L	<1.0	5593914	<1.0	5592239	<1.0	5593914	<1.0	1.0	5592239	N/A
Dissolved Bismuth (Bi)	ug/L	<2.0	5593914	<2.0	5592239	<2.0	5593914	<2.0	2.0	5592239	N/A
Dissolved Boron (B)	ug/L	<50	5593914	<50	5592239	<50	5593914	<50	50	5592239	N/A
Dissolved Cadmium (Cd)	ug/L	0.010	5593914	<0.010	5592239	0.049	5593914	0.015	0.010	5592239	N/A
Dissolved Calcium (Ca)	ug/L	4800	5593914	15000	5592239	1500	5593914	4700	100	5592239	N/A
Dissolved Chromium (Cr)	ug/L	<1.0	5593914	<1.0	5592239	<1.0	5593914	<1.0	1.0	5592239	N/A
Dissolved Cobalt (Co)	ug/L	0.84	5593914	<0.40	5592239	3.7	5593914	<0.40	0.40	5592239	N/A
Dissolved Copper (Cu)	ug/L	<2.0	5593914	<2.0	5592239	<2.0	5593914	<2.0	2.0	5592239	N/A
Dissolved Iron (Fe)	ug/L	<50	5593914	<50	5592239	65	5593914	<50	50	5592239	N/A
Dissolved Lead (Pb)	ug/L	<0.50	5593914	<0.50	5592239	<0.50	5593914	<0.50	0.50	5592239	N/A
Dissolved Magnesium (Mg)	ug/L	1200	5593914	1600	5592239	780	5593914	1500	100	5592239	N/A
Dissolved Manganese (Mn)	ug/L	70	5593914	55	5592239	650	5593914	110	2.0	5592239	N/A
Dissolved Molybdenum (Mo)	ug/L	<2.0	5593914	<2.0	5592239	<2.0	5593914	<2.0	2.0	5592239	N/A
Dissolved Nickel (Ni)	ug/L	5.4	5593914	<2.0	5592239	2.8	5593914	<2.0	2.0	5592239	N/A
Dissolved Phosphorus (P)	ug/L	<100	5593914	<100	5592239	<100	5593914	<100	100	5592239	N/A
Dissolved Potassium (K)	ug/L	1100	5593914	1300	5592239	850	5593914	1200	100	5592239	N/A
Dissolved Selenium (Se)	ug/L	<1.0	5593914	<1.0	5592239	<1.0	5593914	<1.0	1.0	5592239	N/A
Dissolved Silver (Ag)	ug/L	<0.10	5593914	<0.10	5592239	<0.10	5593914	<0.10	0.10	5592239	N/A
Dissolved Sodium (Na)	ug/L	3200	5593914	4100	5592239	1800	5593914	3700	100	5592239	N/A
Dissolved Strontium (Sr)	ug/L	24	5593914	84	5592239	15	5593914	33	2.0	5592239	N/A
Dissolved Thallium (Tl)	ug/L	<0.10	5593914	<0.10	5592239	<0.10	5593914	<0.10	0.10	5592239	N/A
Dissolved Tin (Sn)	ug/L	<2.0	5593914	<2.0	5592239	<2.0	5593914	<2.0	2.0	5592239	N/A
Dissolved Titanium (Ti)	ug/L	<2.0	5593914	<2.0	5592239	<2.0	5593914	<2.0	2.0	5592239	N/A
Dissolved Uranium (U)	ug/L	<0.10	5593914	<0.10	5592239	0.10	5593914	<0.10	0.10	5592239	N/A
Dissolved Vanadium (V)	ug/L	<2.0	5593914	<2.0	5592239	<2.0	5593914	<2.0	2.0	5592239	N/A
Dissolved Zinc (Zn)	ug/L	<5.0	5593914	<5.0	5592239	<5.0	5593914	<5.0	5.0	5592239	N/A

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Lab-Dup = Laboratory Initiated Duplicate

N/A = Not Applicable



Maxxam Job #: B8F0978
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

ELEMENTS BY ICP/MS (WATER)

Maxxam ID		GZW440		GZW441		GZW442	GZW443			
Sampling Date		2018/06/18 15:28		2018/06/18 13:36		2018/06/18 13:40	2018/06/18 14:11			
COC Number		D34771		D34771		D34771	D34771			
	UNITS	MW-21C	QC Batch	MW-16A	QC Batch	MW-16B	MW-17A	RDL	QC Batch	MDL
Metals										
Dissolved Aluminum (Al)	ug/L	7.5	5592239	<5.0	5593914	11	6.4	5.0	5592239	N/A
Dissolved Antimony (Sb)	ug/L	<1.0	5592239	<1.0	5593914	<1.0	<1.0	1.0	5592239	N/A
Dissolved Arsenic (As)	ug/L	<1.0	5592239	1.5	5593914	8.6	<1.0	1.0	5592239	N/A
Dissolved Barium (Ba)	ug/L	9.7	5592239	3.5	5593914	4.6	10	1.0	5592239	N/A
Dissolved Beryllium (Be)	ug/L	<1.0	5592239	<1.0	5593914	<1.0	<1.0	1.0	5592239	N/A
Dissolved Bismuth (Bi)	ug/L	<2.0	5592239	<2.0	5593914	<2.0	<2.0	2.0	5592239	N/A
Dissolved Boron (B)	ug/L	<50	5592239	<50	5593914	<50	<50	50	5592239	N/A
Dissolved Cadmium (Cd)	ug/L	0.019	5592239	0.021	5593914	<0.010	0.039	0.010	5592239	N/A
Dissolved Calcium (Ca)	ug/L	9700	5592239	23000	5593914	20000	4900	100	5592239	N/A
Dissolved Chromium (Cr)	ug/L	<1.0	5592239	<1.0	5593914	<1.0	<1.0	1.0	5592239	N/A
Dissolved Cobalt (Co)	ug/L	0.51	5592239	2.1	5593914	<0.40	3.0	0.40	5592239	N/A
Dissolved Copper (Cu)	ug/L	<2.0	5592239	<2.0	5593914	<2.0	3.7	2.0	5592239	N/A
Dissolved Iron (Fe)	ug/L	<50	5592239	<50	5593914	<50	<50	50	5592239	N/A
Dissolved Lead (Pb)	ug/L	<0.50	5592239	<0.50	5593914	<0.50	<0.50	0.50	5592239	N/A
Dissolved Magnesium (Mg)	ug/L	3200	5592239	1900	5593914	1400	790	100	5592239	N/A
Dissolved Manganese (Mn)	ug/L	180	5592239	690	5593914	6.3	240	2.0	5592239	N/A
Dissolved Molybdenum (Mo)	ug/L	2.6	5592239	<2.0	5593914	<2.0	<2.0	2.0	5592239	N/A
Dissolved Nickel (Ni)	ug/L	<2.0	5592239	<2.0	5593914	<2.0	8.5	2.0	5592239	N/A
Dissolved Phosphorus (P)	ug/L	<100	5592239	<100	5593914	<100	<100	100	5592239	N/A
Dissolved Potassium (K)	ug/L	2100	5592239	550	5593914	1700	670	100	5592239	N/A
Dissolved Selenium (Se)	ug/L	<1.0	5592239	<1.0	5593914	<1.0	<1.0	1.0	5592239	N/A
Dissolved Silver (Ag)	ug/L	<0.10	5592239	<0.10	5593914	<0.10	<0.10	0.10	5592239	N/A
Dissolved Sodium (Na)	ug/L	17000	5592239	8700	5593914	4600	3400	100	5592239	N/A
Dissolved Strontium (Sr)	ug/L	85	5592239	77	5593914	74	32	2.0	5592239	N/A
Dissolved Thallium (Tl)	ug/L	<0.10	5592239	<0.10	5593914	<0.10	<0.10	0.10	5592239	N/A
Dissolved Tin (Sn)	ug/L	<2.0	5592239	<2.0	5593914	<2.0	<2.0	2.0	5592239	N/A
Dissolved Titanium (Ti)	ug/L	<2.0	5592239	<2.0	5593914	<2.0	<2.0	2.0	5592239	N/A
Dissolved Uranium (U)	ug/L	0.29	5592239	2.4	5593914	2.6	<0.10	0.10	5592239	N/A
Dissolved Vanadium (V)	ug/L	<2.0	5592239	<2.0	5593914	<2.0	<2.0	2.0	5592239	N/A
Dissolved Zinc (Zn)	ug/L	6.5	5592239	<5.0	5593914	<5.0	12	5.0	5592239	N/A

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

N/A = Not Applicable



Maxxam Job #: B8F0978
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

ELEMENTS BY ICP/MS (WATER)

Maxxam ID		GZW444		GZW445		GZW446		GZW447			
Sampling Date		2018/06/18 14:19		2018/06/18 14:25		2018/06/18		2018/06/18			
COC Number		D34771		D34771		D34771		D34771			
	UNITS	MW-17B	QC Batch	MW-17C	QC Batch	MW-DUPA	QC Batch	MW-DUPB	RDL	QC Batch	MDL

Metals

Dissolved Aluminum (Al)	ug/L	12	5593914	<5.0	5592239	81	5593914	11	5.0	5592240	N/A
Dissolved Antimony (Sb)	ug/L	<1.0	5593914	<1.0	5592239	<1.0	5593914	<1.0	1.0	5592240	N/A
Dissolved Arsenic (As)	ug/L	<1.0	5593914	1.2	5592239	<1.0	5593914	<1.0	1.0	5592240	N/A
Dissolved Barium (Ba)	ug/L	3.0	5593914	2.4	5592239	5.7	5593914	2.9	1.0	5592240	N/A
Dissolved Beryllium (Be)	ug/L	<1.0	5593914	<1.0	5592239	<1.0	5593914	<1.0	1.0	5592240	N/A
Dissolved Bismuth (Bi)	ug/L	<2.0	5593914	<2.0	5592239	<2.0	5593914	<2.0	2.0	5592240	N/A
Dissolved Boron (B)	ug/L	<50	5593914	<50	5592239	<50	5593914	<50	50	5592240	N/A
Dissolved Cadmium (Cd)	ug/L	0.033	5593914	<0.010	5592239	0.026	5593914	0.037	0.010	5592240	N/A
Dissolved Calcium (Ca)	ug/L	1600	5593914	3600	5592239	9000	5593914	1600	100	5592240	N/A
Dissolved Chromium (Cr)	ug/L	<1.0	5593914	<1.0	5592239	<1.0	5593914	<1.0	1.0	5592240	N/A
Dissolved Cobalt (Co)	ug/L	<0.40	5593914	<0.40	5592239	1.3	5593914	<0.40	0.40	5592240	N/A
Dissolved Copper (Cu)	ug/L	<2.0	5593914	<2.0	5592239	<2.0	5593914	<2.0	2.0	5592240	N/A
Dissolved Iron (Fe)	ug/L	<50	5593914	<50	5592239	<50	5593914	<50	50	5592240	N/A
Dissolved Lead (Pb)	ug/L	<0.50	5593914	<0.50	5592239	<0.50	5593914	<0.50	0.50	5592240	N/A
Dissolved Magnesium (Mg)	ug/L	630	5593914	670	5592239	640	5593914	630	100	5592240	N/A
Dissolved Manganese (Mn)	ug/L	200	5593914	20	5592239	110	5593914	200	2.0	5592240	N/A
Dissolved Molybdenum (Mo)	ug/L	<2.0	5593914	<2.0	5592239	<2.0	5593914	<2.0	2.0	5592240	N/A
Dissolved Nickel (Ni)	ug/L	<2.0	5593914	<2.0	5592239	3.6	5593914	<2.0	2.0	5592240	N/A
Dissolved Phosphorus (P)	ug/L	<100	5593914	<100	5592239	<100	5593914	<100	100	5592240	N/A
Dissolved Potassium (K)	ug/L	410	5593914	440	5592239	670	5593914	410	100	5592240	N/A
Dissolved Selenium (Se)	ug/L	<1.0	5593914	<1.0	5592239	<1.0	5593914	<1.0	1.0	5592240	N/A
Dissolved Silver (Ag)	ug/L	<0.10	5593914	<0.10	5592239	<0.10	5593914	<0.10	0.10	5592240	N/A
Dissolved Sodium (Na)	ug/L	2800	5593914	3200	5592239	2500	5593914	2700	100	5592240	N/A
Dissolved Strontium (Sr)	ug/L	19	5593914	18	5592239	14	5593914	18	2.0	5592240	N/A
Dissolved Thallium (Tl)	ug/L	<0.10	5593914	<0.10	5592239	<0.10	5593914	<0.10	0.10	5592240	N/A
Dissolved Tin (Sn)	ug/L	<2.0	5593914	<2.0	5592239	<2.0	5593914	<2.0	2.0	5592240	N/A
Dissolved Titanium (Ti)	ug/L	<2.0	5593914	<2.0	5592239	<2.0	5593914	<2.0	2.0	5592240	N/A
Dissolved Uranium (U)	ug/L	<0.10	5593914	<0.10	5592239	<0.10	5593914	<0.10	0.10	5592240	N/A
Dissolved Vanadium (V)	ug/L	<2.0	5593914	<2.0	5592239	<2.0	5593914	<2.0	2.0	5592240	N/A
Dissolved Zinc (Zn)	ug/L	<5.0	5593914	<5.0	5592239	<5.0	5593914	<5.0	5.0	5592240	N/A

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

N/A = Not Applicable



Maxxam Job #: B8F0978
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

TEST SUMMARY

Maxxam ID: GZW431
Sample ID: MW-12A
Matrix: Water

Collected: 2018/06/18
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Carbonate, Bicarbonate and Hydroxide	CALC	5589410	N/A	2018/06/22	Automated Statchk
Alkalinity	KONE	5593768	N/A	2018/06/25	Jacob Henley
Chloride	KONE	5593775	N/A	2018/06/22	Jacob Henley
Colour	KONE	5593779	N/A	2018/06/22	Jacob Henley
Conductance - water	AT	5593694	N/A	2018/06/22	Julia McGovern
Hardness (calculated as CaCO ₃)		5589411	N/A	2018/06/22	Automated Statchk
Metals Water Diss. MS (as rec'd)	CICP/MS	5592239	N/A	2018/06/22	Bryon Angevine
Ion Balance (% Difference)	CALC	5589412	N/A	2018/06/26	Automated Statchk
Anion and Cation Sum	CALC	5589413	N/A	2018/06/22	Automated Statchk
Nitrogen Ammonia - water	KONE	5592399	N/A	2018/06/21	Jacob Henley
Nitrogen - Nitrate + Nitrite	KONE	5593781	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrite	KONE	5593783	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrate (as N)	CALC	5590281	N/A	2018/06/26	Automated Statchk
pH	AT	5593693	N/A	2018/06/22	Julia McGovern
Phosphorus - ortho	KONE	5593780	N/A	2018/06/22	Jacob Henley
Sat. pH and Langelier Index (@ 20C)	CALC	5589415	N/A	2018/06/26	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	5589416	N/A	2018/06/26	Automated Statchk
Reactive Silica	KONE	5593778	N/A	2018/06/25	Jacob Henley
Sulphate	KONE	5593777	N/A	2018/06/22	Jacob Henley
Total Dissolved Solids (TDS calc)	CALC	5589418	N/A	2018/06/26	Automated Statchk
Organic carbon - Total (TOC)	TOCV/NDIR	5592255	N/A	2018/06/22	Luke MacPherson
Turbidity	TURB	5593708	N/A	2018/06/22	Julia McGovern

Maxxam ID: GZW431 Dup
Sample ID: MW-12A
Matrix: Water

Collected: 2018/06/18
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Alkalinity	KONE	5593768	N/A	2018/06/25	Jacob Henley
Chloride	KONE	5593775	N/A	2018/06/22	Jacob Henley
Colour	KONE	5593779	N/A	2018/06/22	Jacob Henley
Conductance - water	AT	5593694	N/A	2018/06/22	Julia McGovern
Nitrogen Ammonia - water	KONE	5592399	N/A	2018/06/21	Jacob Henley
Nitrogen - Nitrate + Nitrite	KONE	5593781	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrite	KONE	5593783	N/A	2018/06/25	Jacob Henley
pH	AT	5593693	N/A	2018/06/22	Julia McGovern
Phosphorus - ortho	KONE	5593780	N/A	2018/06/22	Jacob Henley
Reactive Silica	KONE	5593778	N/A	2018/06/25	Jacob Henley
Sulphate	KONE	5593777	N/A	2018/06/22	Jacob Henley
Turbidity	TURB	5593708	N/A	2018/06/22	Julia McGovern



Maxxam Job #: B8F0978
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

TEST SUMMARY

Maxxam ID: GZW432
Sample ID: MW-12B
Matrix: Water

Collected: 2018/06/18
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Carbonate, Bicarbonate and Hydroxide	CALC	5589410	N/A	2018/06/22	Automated Statchk
Alkalinity	KONE	5589743	N/A	2018/06/25	Jacob Henley
Chloride	KONE	5589752	N/A	2018/06/22	Jacob Henley
Colour	KONE	5597605	N/A	2018/06/25	Jacob Henley
Conductance - water	AT	5593692	N/A	2018/06/22	Julia McGovern
Hardness (calculated as CaCO ₃)		5589411	N/A	2018/06/22	Automated Statchk
Metals Water Diss. MS (as rec'd)	CICP/MS	5592239	N/A	2018/06/22	Bryon Angevine
Ion Balance (% Difference)	CALC	5589412	N/A	2018/06/26	Automated Statchk
Anion and Cation Sum	CALC	5589413	N/A	2018/06/22	Automated Statchk
Nitrogen Ammonia - water	KONE	5592399	N/A	2018/06/21	Jacob Henley
Nitrogen - Nitrate + Nitrite	KONE	5589765	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrite	KONE	5589767	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrate (as N)	CALC	5590281	N/A	2018/06/26	Automated Statchk
pH	AT	5593691	N/A	2018/06/22	Julia McGovern
Phosphorus - ortho	KONE	5589762	N/A	2018/06/22	Jacob Henley
Sat. pH and Langelier Index (@ 20C)	CALC	5589415	N/A	2018/06/26	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	5589416	N/A	2018/06/26	Automated Statchk
Reactive Silica	KONE	5589757	N/A	2018/06/25	Jacob Henley
Sulphate	KONE	5589755	N/A	2018/06/22	Jacob Henley
Total Dissolved Solids (TDS calc)	CALC	5589418	N/A	2018/06/26	Automated Statchk
Organic carbon - Total (TOC)	TOCV/NDIR	5592255	N/A	2018/06/22	Luke MacPherson
Turbidity	TURB	5593709	N/A	2018/06/22	Julia McGovern

Maxxam ID: GZW433
Sample ID: MW-09A
Matrix: Water

Collected: 2018/06/18
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Carbonate, Bicarbonate and Hydroxide	CALC	5589410	N/A	2018/06/22	Automated Statchk
Alkalinity	KONE	5589743	N/A	2018/06/25	Jacob Henley
Chloride	KONE	5589752	N/A	2018/06/22	Jacob Henley
Colour	KONE	5597605	N/A	2018/06/25	Jacob Henley
Conductance - water	AT	5593694	N/A	2018/06/22	Julia McGovern
Hardness (calculated as CaCO ₃)		5589411	N/A	2018/06/22	Automated Statchk
Metals Water Diss. MS (as rec'd)	CICP/MS	5592239	N/A	2018/06/22	Bryon Angevine
Ion Balance (% Difference)	CALC	5589412	N/A	2018/06/26	Automated Statchk
Anion and Cation Sum	CALC	5589413	N/A	2018/06/22	Automated Statchk
Nitrogen Ammonia - water	KONE	5592399	N/A	2018/06/21	Jacob Henley
Nitrogen - Nitrate + Nitrite	KONE	5589765	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrite	KONE	5589767	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrate (as N)	CALC	5590281	N/A	2018/06/26	Automated Statchk
pH	AT	5593693	N/A	2018/06/22	Julia McGovern
Phosphorus - ortho	KONE	5589762	N/A	2018/06/22	Jacob Henley



Maxxam Job #: B8F0978
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

TEST SUMMARY

Maxxam ID: GZW433
Sample ID: MW-09A
Matrix: Water

Collected: 2018/06/18
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Sat. pH and Langelier Index (@ 20C)	CALC	5589415	N/A	2018/06/26	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	5589416	N/A	2018/06/26	Automated Statchk
Reactive Silica	KONE	5589757	N/A	2018/06/25	Jacob Henley
Sulphate	KONE	5589755	N/A	2018/06/22	Jacob Henley
Total Dissolved Solids (TDS calc)	CALC	5589418	N/A	2018/06/26	Automated Statchk
Organic carbon - Total (TOC)	TOCV/NDIR	5592255	N/A	2018/06/22	Luke MacPherson
Turbidity	TURB	5593709	N/A	2018/06/22	Julia McGovern

Maxxam ID: GZW434
Sample ID: MW-09B
Matrix: Water

Collected: 2018/06/18
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Carbonate, Bicarbonate and Hydroxide	CALC	5589410	N/A	2018/06/22	Automated Statchk
Alkalinity	KONE	5589743	N/A	2018/06/25	Jacob Henley
Chloride	KONE	5589752	N/A	2018/06/22	Jacob Henley
Colour	KONE	5597605	N/A	2018/06/25	Jacob Henley
Conductance - water	AT	5593692	N/A	2018/06/22	Julia McGovern
Hardness (calculated as CaCO ₃)		5589411	N/A	2018/06/22	Automated Statchk
Metals Water Diss. MS (as rec'd)	CICP/MS	5592239	N/A	2018/06/22	Bryon Angevine
Ion Balance (% Difference)	CALC	5589412	N/A	2018/06/26	Automated Statchk
Anion and Cation Sum	CALC	5589413	N/A	2018/06/22	Automated Statchk
Nitrogen Ammonia - water	KONE	5592399	N/A	2018/06/21	Jacob Henley
Nitrogen - Nitrate + Nitrite	KONE	5589765	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrite	KONE	5589767	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrate (as N)	CALC	5590281	N/A	2018/06/26	Automated Statchk
pH	AT	5593691	N/A	2018/06/22	Julia McGovern
Phosphorus - ortho	KONE	5589762	N/A	2018/06/22	Jacob Henley
Sat. pH and Langelier Index (@ 20C)	CALC	5589415	N/A	2018/06/26	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	5589416	N/A	2018/06/26	Automated Statchk
Reactive Silica	KONE	5589757	N/A	2018/06/25	Jacob Henley
Sulphate	KONE	5589755	N/A	2018/06/22	Jacob Henley
Total Dissolved Solids (TDS calc)	CALC	5589418	N/A	2018/06/26	Automated Statchk
Organic carbon - Total (TOC)	TOCV/NDIR	5592255	N/A	2018/06/22	Luke MacPherson
Turbidity	TURB	5593709	N/A	2018/06/22	Julia McGovern

Maxxam ID: GZW435
Sample ID: MW-09D
Matrix: Water

Collected: 2018/06/18
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Carbonate, Bicarbonate and Hydroxide	CALC	5589410	N/A	2018/06/22	Automated Statchk
Alkalinity	KONE	5589743	N/A	2018/06/25	Jacob Henley



Maxxam Job #: B8F0978
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

TEST SUMMARY

Maxxam ID: GZW435
Sample ID: MW-09D
Matrix: Water

Collected: 2018/06/18
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Chloride	KONE	5589752	N/A	2018/06/22	Jacob Henley
Colour	KONE	5597605	N/A	2018/06/25	Jacob Henley
Conductance - water	AT	5593692	N/A	2018/06/22	Julia McGovern
Hardness (calculated as CaCO3)		5589411	N/A	2018/06/22	Automated Statchk
Metals Water Diss. MS (as rec'd)	CICP/MS	5592239	N/A	2018/06/22	Bryon Angevine
Ion Balance (% Difference)	CALC	5589412	N/A	2018/06/26	Automated Statchk
Anion and Cation Sum	CALC	5589413	N/A	2018/06/22	Automated Statchk
Nitrogen Ammonia - water	KONE	5592399	N/A	2018/06/21	Jacob Henley
Nitrogen - Nitrate + Nitrite	KONE	5589765	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrite	KONE	5589767	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrate (as N)	CALC	5590281	N/A	2018/06/26	Automated Statchk
pH	AT	5593691	N/A	2018/06/22	Julia McGovern
Phosphorus - ortho	KONE	5589762	N/A	2018/06/22	Jacob Henley
Sat. pH and Langelier Index (@ 20C)	CALC	5589415	N/A	2018/06/26	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	5589416	N/A	2018/06/26	Automated Statchk
Reactive Silica	KONE	5589757	N/A	2018/06/25	Jacob Henley
Sulphate	KONE	5589755	N/A	2018/06/22	Jacob Henley
Total Dissolved Solids (TDS calc)	CALC	5589418	N/A	2018/06/26	Automated Statchk
Organic carbon - Total (TOC)	TOCV/NDIR	5593990	N/A	2018/06/22	Luke MacPherson
Turbidity	TURB	5593708	N/A	2018/06/22	Julia McGovern

Maxxam ID: GZW436
Sample ID: MW-04A
Matrix: Water

Collected: 2018/06/18
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Carbonate, Bicarbonate and Hydroxide	CALC	5590380	N/A	2018/06/22	Automated Statchk
Alkalinity	KONE	5589743	N/A	2018/06/25	Jacob Henley
Chloride	KONE	5589752	N/A	2018/06/22	Jacob Henley
Colour	KONE	5597605	N/A	2018/06/25	Jacob Henley
Conductance - water	AT	5593694	N/A	2018/06/22	Julia McGovern
Hardness (calculated as CaCO3)		5590383	N/A	2018/06/22	Automated Statchk
Metals Water Diss. MS (as rec'd)	CICP/MS	5593914	N/A	2018/06/22	Bryon Angevine
Ion Balance (% Difference)	CALC	5590384	N/A	2018/06/26	Automated Statchk
Anion and Cation Sum	CALC	5590385	N/A	2018/06/22	Automated Statchk
Nitrogen Ammonia - water	KONE	5592399	N/A	2018/06/21	Jacob Henley
Nitrogen - Nitrate + Nitrite	KONE	5589765	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrite	KONE	5589767	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrate (as N)	CALC	5590281	N/A	2018/06/26	Automated Statchk
pH	AT	5593693	N/A	2018/06/22	Julia McGovern
Phosphorus - ortho	KONE	5589762	N/A	2018/06/22	Jacob Henley
Sat. pH and Langelier Index (@ 20C)	CALC	5590387	N/A	2018/06/26	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	5590388	N/A	2018/06/26	Automated Statchk



Maxxam Job #: B8F0978
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

TEST SUMMARY

Maxxam ID: GZW436
Sample ID: MW-04A
Matrix: Water

Collected: 2018/06/18
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Reactive Silica	KONE	5589757	N/A	2018/06/25	Jacob Henley
Sulphate	KONE	5589755	N/A	2018/06/22	Jacob Henley
Total Dissolved Solids (TDS calc)	CALC	5590389	N/A	2018/06/26	Automated Statchk
Organic carbon - Total (TOC)	TOCV/NDIR	5592255	N/A	2018/06/22	Luke MacPherson
Turbidity	TURB	5593709	N/A	2018/06/22	Julia McGovern

Maxxam ID: GZW436 Dup
Sample ID: MW-04A
Matrix: Water

Collected: 2018/06/18
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Metals Water Diss. MS (as rec'd)	CICP/MS	5593914	N/A	2018/06/22	Bryon Angevine

Maxxam ID: GZW437
Sample ID: MW-04B
Matrix: Water

Collected: 2018/06/18
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Carbonate, Bicarbonate and Hydroxide	CALC	5590380	N/A	2018/06/22	Automated Statchk
Alkalinity	KONE	5589743	N/A	2018/06/25	Jacob Henley
Chloride	KONE	5589752	N/A	2018/06/22	Jacob Henley
Colour	KONE	5597605	N/A	2018/06/25	Jacob Henley
Conductance - water	AT	5593694	N/A	2018/06/22	Julia McGovern
Hardness (calculated as CaCO ₃)		5590383	N/A	2018/06/22	Automated Statchk
Metals Water Diss. MS (as rec'd)	CICP/MS	5592239	N/A	2018/06/22	Bryon Angevine
Ion Balance (% Difference)	CALC	5590384	N/A	2018/06/26	Automated Statchk
Anion and Cation Sum	CALC	5590385	N/A	2018/06/22	Automated Statchk
Nitrogen Ammonia - water	KONE	5592399	N/A	2018/06/21	Jacob Henley
Nitrogen - Nitrate + Nitrite	KONE	5589765	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrite	KONE	5589767	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrate (as N)	CALC	5590281	N/A	2018/06/26	Automated Statchk
pH	AT	5593693	N/A	2018/06/22	Julia McGovern
Phosphorus - ortho	KONE	5589762	N/A	2018/06/22	Jacob Henley
Sat. pH and Langlier Index (@ 20C)	CALC	5590387	N/A	2018/06/26	Automated Statchk
Sat. pH and Langlier Index (@ 4C)	CALC	5590388	N/A	2018/06/26	Automated Statchk
Reactive Silica	KONE	5589757	N/A	2018/06/25	Jacob Henley
Sulphate	KONE	5589755	N/A	2018/06/22	Jacob Henley
Total Dissolved Solids (TDS calc)	CALC	5590389	N/A	2018/06/26	Automated Statchk
Organic carbon - Total (TOC)	TOCV/NDIR	5592255	N/A	2018/06/22	Luke MacPherson
Turbidity	TURB	5593709	N/A	2018/06/22	Julia McGovern



Maxxam Job #: B8F0978
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

TEST SUMMARY

Maxxam ID: GZW438
Sample ID: MW-21A
Matrix: Water

Collected: 2018/06/18
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Carbonate, Bicarbonate and Hydroxide	CALC	5590380	N/A	2018/06/22	Automated Statchk
Alkalinity	KONE	5589743	N/A	2018/06/25	Jacob Henley
Chloride	KONE	5589752	N/A	2018/06/22	Jacob Henley
Colour	KONE	5597605	N/A	2018/06/25	Jacob Henley
Conductance - water	AT	5593694	N/A	2018/06/22	Julia McGovern
Hardness (calculated as CaCO ₃)		5590383	N/A	2018/06/22	Automated Statchk
Metals Water Diss. MS (as rec'd)	CICP/MS	5593914	N/A	2018/06/22	Bryon Angevine
Ion Balance (% Difference)	CALC	5590384	N/A	2018/06/26	Automated Statchk
Anion and Cation Sum	CALC	5590385	N/A	2018/06/22	Automated Statchk
Nitrogen Ammonia - water	KONE	5592399	N/A	2018/06/21	Jacob Henley
Nitrogen - Nitrate + Nitrite	KONE	5589765	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrite	KONE	5589767	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrate (as N)	CALC	5590281	N/A	2018/06/26	Automated Statchk
pH	AT	5593693	N/A	2018/06/22	Julia McGovern
Phosphorus - ortho	KONE	5589762	N/A	2018/06/22	Jacob Henley
Sat. pH and Langelier Index (@ 20C)	CALC	5590387	N/A	2018/06/26	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	5590388	N/A	2018/06/26	Automated Statchk
Reactive Silica	KONE	5589757	N/A	2018/06/25	Jacob Henley
Sulphate	KONE	5589755	N/A	2018/06/22	Jacob Henley
Total Dissolved Solids (TDS calc)	CALC	5590389	N/A	2018/06/26	Automated Statchk
Organic carbon - Total (TOC)	TOCV/NDIR	5593990	N/A	2018/06/22	Luke MacPherson
Turbidity	TURB	5593709	N/A	2018/06/22	Julia McGovern

Maxxam ID: GZW439
Sample ID: MW-21B
Matrix: Water

Collected: 2018/06/18
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Carbonate, Bicarbonate and Hydroxide	CALC	5590380	N/A	2018/06/22	Automated Statchk
Alkalinity	KONE	5589743	N/A	2018/06/25	Jacob Henley
Chloride	KONE	5589752	N/A	2018/06/22	Jacob Henley
Colour	KONE	5597605	N/A	2018/06/25	Jacob Henley
Conductance - water	AT	5593698	N/A	2018/06/22	Julia McGovern
Hardness (calculated as CaCO ₃)		5590383	N/A	2018/06/22	Automated Statchk
Metals Water Diss. MS (as rec'd)	CICP/MS	5592239	N/A	2018/06/22	Bryon Angevine
Ion Balance (% Difference)	CALC	5590384	N/A	2018/06/26	Automated Statchk
Anion and Cation Sum	CALC	5590385	N/A	2018/06/22	Automated Statchk
Nitrogen Ammonia - water	KONE	5592399	N/A	2018/06/21	Jacob Henley
Nitrogen - Nitrate + Nitrite	KONE	5589765	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrite	KONE	5589767	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrate (as N)	CALC	5590281	N/A	2018/06/26	Automated Statchk
pH	AT	5593697	N/A	2018/06/22	Julia McGovern
Phosphorus - ortho	KONE	5589762	N/A	2018/06/22	Jacob Henley



Maxxam Job #: B8F0978
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

TEST SUMMARY

Maxxam ID: GZW439
Sample ID: MW-21B
Matrix: Water

Collected: 2018/06/18
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Sat. pH and Langelier Index (@ 20C)	CALC	5590387	N/A	2018/06/26	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	5590388	N/A	2018/06/26	Automated Statchk
Reactive Silica	KONE	5589757	N/A	2018/06/25	Jacob Henley
Sulphate	KONE	5589755	N/A	2018/06/22	Jacob Henley
Total Dissolved Solids (TDS calc)	CALC	5590389	N/A	2018/06/26	Automated Statchk
Organic carbon - Total (TOC)	TOCV/NDIR	5593990	N/A	2018/06/22	Luke MacPherson
Turbidity	TURB	5593709	N/A	2018/06/22	Julia McGovern

Maxxam ID: GZW439 Dup
Sample ID: MW-21B
Matrix: Water

Collected: 2018/06/18
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Conductance - water	AT	5593698	N/A	2018/06/22	Julia McGovern
pH	AT	5593697	N/A	2018/06/22	Julia McGovern

Maxxam ID: GZW440
Sample ID: MW-21C
Matrix: Water

Collected: 2018/06/18
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Carbonate, Bicarbonate and Hydroxide	CALC	5590380	N/A	2018/06/22	Automated Statchk
Alkalinity	KONE	5589743	N/A	2018/06/25	Jacob Henley
Chloride	KONE	5589752	N/A	2018/06/22	Jacob Henley
Colour	KONE	5597605	N/A	2018/06/25	Jacob Henley
Conductance - water	AT	5593694	N/A	2018/06/22	Julia McGovern
Hardness (calculated as CaCO ₃)		5590383	N/A	2018/06/22	Automated Statchk
Metals Water Diss. MS (as rec'd)	CICP/MS	5592239	N/A	2018/06/22	Bryon Angevine
Ion Balance (% Difference)	CALC	5590384	N/A	2018/06/26	Automated Statchk
Anion and Cation Sum	CALC	5590385	N/A	2018/06/22	Automated Statchk
Nitrogen Ammonia - water	KONE	5592399	N/A	2018/06/21	Jacob Henley
Nitrogen - Nitrate + Nitrite	KONE	5589765	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrite	KONE	5589767	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrate (as N)	CALC	5590281	N/A	2018/06/26	Automated Statchk
pH	AT	5593693	N/A	2018/06/22	Julia McGovern
Phosphorus - ortho	KONE	5589762	N/A	2018/06/22	Jacob Henley
Sat. pH and Langelier Index (@ 20C)	CALC	5590387	N/A	2018/06/26	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	5590388	N/A	2018/06/26	Automated Statchk
Reactive Silica	KONE	5589757	N/A	2018/06/25	Jacob Henley
Sulphate	KONE	5589755	N/A	2018/06/22	Jacob Henley
Total Dissolved Solids (TDS calc)	CALC	5590389	N/A	2018/06/26	Automated Statchk
Organic carbon - Total (TOC)	TOCV/NDIR	5593990	N/A	2018/06/22	Luke MacPherson
Turbidity	TURB	5593711	N/A	2018/06/22	Julia McGovern



Maxxam Job #: B8F0978
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

TEST SUMMARY

Maxxam ID: GZW441
Sample ID: MW-16A
Matrix: Water

Collected: 2018/06/18
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Carbonate, Bicarbonate and Hydroxide	CALC	5590380	N/A	2018/06/22	Automated Statchk
Alkalinity	KONE	5589743	N/A	2018/06/25	Jacob Henley
Chloride	KONE	5589752	N/A	2018/06/22	Jacob Henley
Colour	KONE	5597605	N/A	2018/06/25	Jacob Henley
Conductance - water	AT	5593696	N/A	2018/06/22	Julia McGovern
Hardness (calculated as CaCO ₃)		5590383	N/A	2018/06/22	Automated Statchk
Metals Water Diss. MS (as rec'd)	CICP/MS	5593914	N/A	2018/06/22	Bryon Angevine
Ion Balance (% Difference)	CALC	5590384	N/A	2018/06/26	Automated Statchk
Anion and Cation Sum	CALC	5590385	N/A	2018/06/22	Automated Statchk
Nitrogen Ammonia - water	KONE	5592399	N/A	2018/06/21	Jacob Henley
Nitrogen - Nitrate + Nitrite	KONE	5589765	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrite	KONE	5589767	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrate (as N)	CALC	5590281	N/A	2018/06/26	Automated Statchk
pH	AT	5593695	N/A	2018/06/22	Julia McGovern
Phosphorus - ortho	KONE	5589762	N/A	2018/06/22	Jacob Henley
Sat. pH and Langelier Index (@ 20C)	CALC	5590387	N/A	2018/06/26	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	5590388	N/A	2018/06/26	Automated Statchk
Reactive Silica	KONE	5589757	N/A	2018/06/25	Jacob Henley
Sulphate	KONE	5589755	N/A	2018/06/22	Jacob Henley
Total Dissolved Solids (TDS calc)	CALC	5590389	N/A	2018/06/26	Automated Statchk
Organic carbon - Total (TOC)	TOCV/NDIR	5596952	N/A	2018/06/25	Luke MacPherson
Turbidity	TURB	5593711	N/A	2018/06/22	Julia McGovern

Maxxam ID: GZW442
Sample ID: MW-16B
Matrix: Water

Collected: 2018/06/18
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Carbonate, Bicarbonate and Hydroxide	CALC	5590380	N/A	2018/06/22	Automated Statchk
Alkalinity	KONE	5589743	N/A	2018/06/25	Jacob Henley
Chloride	KONE	5589752	N/A	2018/06/22	Jacob Henley
Colour	KONE	5597605	N/A	2018/06/25	Jacob Henley
Conductance - water	AT	5593694	N/A	2018/06/22	Julia McGovern
Hardness (calculated as CaCO ₃)		5590383	N/A	2018/06/22	Automated Statchk
Metals Water Diss. MS (as rec'd)	CICP/MS	5592239	N/A	2018/06/22	Bryon Angevine
Ion Balance (% Difference)	CALC	5590384	N/A	2018/06/26	Automated Statchk
Anion and Cation Sum	CALC	5590385	N/A	2018/06/22	Automated Statchk
Nitrogen Ammonia - water	KONE	5592399	N/A	2018/06/21	Jacob Henley
Nitrogen - Nitrate + Nitrite	KONE	5589765	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrite	KONE	5589767	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrate (as N)	CALC	5590281	N/A	2018/06/26	Automated Statchk
pH	AT	5593693	N/A	2018/06/22	Julia McGovern
Phosphorus - ortho	KONE	5589762	N/A	2018/06/22	Jacob Henley



Maxxam Job #: B8F0978
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

TEST SUMMARY

Maxxam ID: GZW442
Sample ID: MW-16B
Matrix: Water

Collected: 2018/06/18
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Sat. pH and Langelier Index (@ 20C)	CALC	5590387	N/A	2018/06/26	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	5590388	N/A	2018/06/26	Automated Statchk
Reactive Silica	KONE	5589757	N/A	2018/06/25	Jacob Henley
Sulphate	KONE	5589755	N/A	2018/06/22	Jacob Henley
Total Dissolved Solids (TDS calc)	CALC	5590389	N/A	2018/06/26	Automated Statchk
Organic carbon - Total (TOC)	TOCV/NDIR	5593990	N/A	2018/06/22	Luke MacPherson
Turbidity	TURB	5593709	N/A	2018/06/22	Julia McGovern

Maxxam ID: GZW443
Sample ID: MW-17A
Matrix: Water

Collected: 2018/06/18
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Carbonate, Bicarbonate and Hydroxide	CALC	5590380	N/A	2018/06/22	Automated Statchk
Alkalinity	KONE	5589743	N/A	2018/06/25	Jacob Henley
Chloride	KONE	5589752	N/A	2018/06/22	Jacob Henley
Colour	KONE	5597605	N/A	2018/06/25	Jacob Henley
Conductance - water	AT	5593694	N/A	2018/06/22	Julia McGovern
Hardness (calculated as CaCO ₃)		5590383	N/A	2018/06/22	Automated Statchk
Metals Water Diss. MS (as rec'd)	CICP/MS	5592239	N/A	2018/06/22	Bryon Angevine
Ion Balance (% Difference)	CALC	5590384	N/A	2018/06/26	Automated Statchk
Anion and Cation Sum	CALC	5590385	N/A	2018/06/22	Automated Statchk
Nitrogen Ammonia - water	KONE	5592399	N/A	2018/06/21	Jacob Henley
Nitrogen - Nitrate + Nitrite	KONE	5589765	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrite	KONE	5589767	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrate (as N)	CALC	5590281	N/A	2018/06/26	Automated Statchk
pH	AT	5593693	N/A	2018/06/22	Julia McGovern
Phosphorus - ortho	KONE	5589762	N/A	2018/06/22	Jacob Henley
Sat. pH and Langelier Index (@ 20C)	CALC	5590387	N/A	2018/06/26	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	5590388	N/A	2018/06/26	Automated Statchk
Reactive Silica	KONE	5589757	N/A	2018/06/25	Jacob Henley
Sulphate	KONE	5589755	N/A	2018/06/22	Jacob Henley
Total Dissolved Solids (TDS calc)	CALC	5590389	N/A	2018/06/26	Automated Statchk
Organic carbon - Total (TOC)	TOCV/NDIR	5593990	N/A	2018/06/22	Luke MacPherson
Turbidity	TURB	5593711	N/A	2018/06/22	Julia McGovern

Maxxam ID: GZW444
Sample ID: MW-17B
Matrix: Water

Collected: 2018/06/18
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Carbonate, Bicarbonate and Hydroxide	CALC	5590380	N/A	2018/06/22	Automated Statchk
Alkalinity	KONE	5593768	N/A	2018/06/25	Jacob Henley



Maxxam Job #: B8F0978
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

TEST SUMMARY

Maxxam ID: GZW444
Sample ID: MW-17B
Matrix: Water

Collected: 2018/06/18
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Chloride	KONE	5593775	N/A	2018/06/22	Jacob Henley
Colour	KONE	5597513	N/A	2018/06/25	Jacob Henley
Conductance - water	AT	5593694	N/A	2018/06/22	Julia McGovern
Hardness (calculated as CaCO ₃)		5590383	N/A	2018/06/22	Automated Statchk
Metals Water Diss. MS (as rec'd)	CICP/MS	5593914	N/A	2018/06/22	Bryon Angevine
Ion Balance (% Difference)	CALC	5590384	N/A	2018/06/26	Automated Statchk
Anion and Cation Sum	CALC	5590385	N/A	2018/06/22	Automated Statchk
Nitrogen Ammonia - water	KONE	5592399	N/A	2018/06/21	Jacob Henley
Nitrogen - Nitrate + Nitrite	KONE	5593781	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrite	KONE	5593783	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrate (as N)	CALC	5590281	N/A	2018/06/26	Automated Statchk
pH	AT	5593693	N/A	2018/06/22	Julia McGovern
Phosphorus - ortho	KONE	5593780	N/A	2018/06/22	Jacob Henley
Sat. pH and Langelier Index (@ 20C)	CALC	5590387	N/A	2018/06/26	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	5590388	N/A	2018/06/26	Automated Statchk
Reactive Silica	KONE	5593778	N/A	2018/06/25	Jacob Henley
Sulphate	KONE	5593777	N/A	2018/06/22	Jacob Henley
Total Dissolved Solids (TDS calc)	CALC	5590389	N/A	2018/06/26	Automated Statchk
Organic carbon - Total (TOC)	TOCV/NDIR	5593990	N/A	2018/06/22	Luke MacPherson
Turbidity	TURB	5593711	N/A	2018/06/22	Julia McGovern

Maxxam ID: GZW445
Sample ID: MW-17C
Matrix: Water

Collected: 2018/06/18
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Carbonate, Bicarbonate and Hydroxide	CALC	5590380	N/A	2018/06/22	Automated Statchk
Alkalinity	KONE	5593768	N/A	2018/06/25	Jacob Henley
Chloride	KONE	5593775	N/A	2018/06/22	Jacob Henley
Colour	KONE	5593779	N/A	2018/06/22	Jacob Henley
Conductance - water	AT	5593692	N/A	2018/06/22	Julia McGovern
Hardness (calculated as CaCO ₃)		5590383	N/A	2018/06/22	Automated Statchk
Metals Water Diss. MS (as rec'd)	CICP/MS	5592239	N/A	2018/06/22	Bryon Angevine
Ion Balance (% Difference)	CALC	5590384	N/A	2018/06/26	Automated Statchk
Anion and Cation Sum	CALC	5590385	N/A	2018/06/22	Automated Statchk
Nitrogen Ammonia - water	KONE	5592399	N/A	2018/06/21	Jacob Henley
Nitrogen - Nitrate + Nitrite	KONE	5593781	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrite	KONE	5593783	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrate (as N)	CALC	5590281	N/A	2018/06/26	Automated Statchk
pH	AT	5593691	N/A	2018/06/22	Julia McGovern
Phosphorus - ortho	KONE	5593780	N/A	2018/06/22	Jacob Henley
Sat. pH and Langelier Index (@ 20C)	CALC	5590387	N/A	2018/06/26	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	5590388	N/A	2018/06/26	Automated Statchk



Maxxam Job #: B8F0978
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

TEST SUMMARY

Maxxam ID: GZW445
Sample ID: MW-17C
Matrix: Water

Collected: 2018/06/18
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Reactive Silica	KONE	5593778	N/A	2018/06/25	Jacob Henley
Sulphate	KONE	5593777	N/A	2018/06/22	Jacob Henley
Total Dissolved Solids (TDS calc)	CALC	5590389	N/A	2018/06/26	Automated Statchk
Organic carbon - Total (TOC)	TOCV/NDIR	5593990	N/A	2018/06/22	Luke MacPherson
Turbidity	TURB	5593709	N/A	2018/06/22	Julia McGovern

Maxxam ID: GZW446
Sample ID: MW-DUPA
Matrix: Water

Collected: 2018/06/18
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Carbonate, Bicarbonate and Hydroxide	CALC	5590380	N/A	2018/06/22	Automated Statchk
Alkalinity	KONE	5593768	N/A	2018/06/25	Jacob Henley
Chloride	KONE	5593775	N/A	2018/06/22	Jacob Henley
Colour	KONE	5593779	N/A	2018/06/22	Jacob Henley
Conductance - water	AT	5593692	N/A	2018/06/22	Julia McGovern
Hardness (calculated as CaCO ₃)		5590383	N/A	2018/06/22	Automated Statchk
Metals Water Diss. MS (as rec'd)	CICP/MS	5593914	N/A	2018/06/22	Bryon Angevine
Ion Balance (% Difference)	CALC	5590384	N/A	2018/06/26	Automated Statchk
Anion and Cation Sum	CALC	5590385	N/A	2018/06/22	Automated Statchk
Nitrogen Ammonia - water	KONE	5592399	N/A	2018/06/21	Jacob Henley
Nitrogen - Nitrate + Nitrite	KONE	5593781	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrite	KONE	5593783	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrate (as N)	CALC	5590281	N/A	2018/06/26	Automated Statchk
pH	AT	5593691	N/A	2018/06/22	Julia McGovern
Phosphorus - ortho	KONE	5593780	N/A	2018/06/22	Jacob Henley
Sat. pH and Langlier Index (@ 20C)	CALC	5590387	N/A	2018/06/26	Automated Statchk
Sat. pH and Langlier Index (@ 4C)	CALC	5590388	N/A	2018/06/26	Automated Statchk
Reactive Silica	KONE	5593778	N/A	2018/06/25	Jacob Henley
Sulphate	KONE	5593777	N/A	2018/06/22	Jacob Henley
Total Dissolved Solids (TDS calc)	CALC	5590389	N/A	2018/06/26	Automated Statchk
Organic carbon - Total (TOC)	TOCV/NDIR	5593990	N/A	2018/06/22	Luke MacPherson
Turbidity	TURB	5593708	N/A	2018/06/22	Julia McGovern

Maxxam ID: GZW447
Sample ID: MW-DUPB
Matrix: Water

Collected: 2018/06/18
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Carbonate, Bicarbonate and Hydroxide	CALC	5590380	N/A	2018/06/22	Automated Statchk
Alkalinity	KONE	5593768	N/A	2018/06/25	Jacob Henley
Chloride	KONE	5593775	N/A	2018/06/22	Jacob Henley
Colour	KONE	5593779	N/A	2018/06/22	Jacob Henley



Maxxam Job #: B8F0978
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

TEST SUMMARY

Maxxam ID: GZW447
Sample ID: MW-DUPB
Matrix: Water

Collected: 2018/06/18
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Conductance - water	AT	5593694	N/A	2018/06/22	Julia McGovern
Hardness (calculated as CaCO3)		5590383	N/A	2018/06/22	Automated Statchk
Metals Water Diss. MS (as rec'd)	CICP/MS	5592240	N/A	2018/06/22	Cassandra Hartery
Ion Balance (% Difference)	CALC	5590384	N/A	2018/06/26	Automated Statchk
Anion and Cation Sum	CALC	5590385	N/A	2018/06/22	Automated Statchk
Nitrogen Ammonia - water	KONE	5592399	N/A	2018/06/21	Jacob Henley
Nitrogen - Nitrate + Nitrite	KONE	5593781	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrite	KONE	5593783	N/A	2018/06/25	Jacob Henley
Nitrogen - Nitrate (as N)	CALC	5590281	N/A	2018/06/26	Automated Statchk
pH	AT	5593693	N/A	2018/06/22	Julia McGovern
Phosphorus - ortho	KONE	5593780	N/A	2018/06/22	Jacob Henley
Sat. pH and Langlier Index (@ 20C)	CALC	5590387	N/A	2018/06/26	Automated Statchk
Sat. pH and Langlier Index (@ 4C)	CALC	5590388	N/A	2018/06/26	Automated Statchk
Reactive Silica	KONE	5593778	N/A	2018/06/25	Jacob Henley
Sulphate	KONE	5593777	N/A	2018/06/22	Jacob Henley
Total Dissolved Solids (TDS calc)	CALC	5590389	N/A	2018/06/26	Automated Statchk
Organic carbon - Total (TOC)	TOCV/NDIR	5592255	N/A	2018/06/22	Luke MacPherson
Turbidity	TURB	5593709	N/A	2018/06/22	Julia McGovern

Maxxam ID: GZW447 Dup
Sample ID: MW-DUPB
Matrix: Water

Collected: 2018/06/18
Shipped:
Received: 2018/06/19

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Turbidity	TURB	5593709	N/A	2018/06/22	Julia McGovern



Maxxam Job #: B8F0978
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

GENERAL COMMENTS

Each temperature is the average of up to three cooler temperatures taken at receipt

Package 1	6.3°C
Package 2	5.3°C

Sample GZW431 [MW-12A] : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample GZW433 [MW-09A] : RCAP Ion Balance acceptable. Low ionic strength sample.

Sample GZW436 [MW-04A] : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample GZW444 [MW-17B] : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample GZW446 [MW-DUPA] : RCAP Ion Balance acceptable. Low ionic strength sample.

Sample GZW447 [MW-DUPB] : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Results relate only to the items tested.

Maxxam Job #: B8F0978
Report Date: 2018/06/26

QUALITY ASSURANCE REPORT

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

QC Batch	Parameter	Date	Matrix Spike		SPIKED BLANK		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits	% Recovery	QC Limits
5589743	Total Alkalinity (Total as CaCO ₃)	2018/06/25	NC	80 - 120	96	80 - 120	<5.0	mg/L	9.1	25		
5589752	Dissolved Chloride (Cl)	2018/06/22	100	80 - 120	103	80 - 120	<1.0	mg/L	10	25	102	80 - 120
5589755	Dissolved Sulphate (SO ₄)	2018/06/22	93	80 - 120	95	80 - 120	<2.0	mg/L	0.48	25		
5589757	Reactive Silica (SiO ₂)	2018/06/25	98	80 - 120	95	80 - 120	<0.50	mg/L	0.84	25		
5589762	Orthophosphate (P)	2018/06/22	87	80 - 120	94	80 - 120	<0.010	mg/L	NC	25		
5589765	Nitrate + Nitrite (N)	2018/06/25	96	80 - 120	98	80 - 120	<0.050	mg/L	NC	25		
5589767	Nitrite (N)	2018/06/25	92	80 - 120	96	80 - 120	<0.010	mg/L	NC	20		
5592239	Dissolved Aluminum (Al)	2018/06/22	100	80 - 120	98	80 - 120	<5.0	ug/L	NC	20		
5592239	Dissolved Antimony (Sb)	2018/06/22	103	80 - 120	98	80 - 120	<1.0	ug/L	NC	20		
5592239	Dissolved Arsenic (As)	2018/06/22	97	80 - 120	95	80 - 120	<1.0	ug/L	NC	20		
5592239	Dissolved Barium (Ba)	2018/06/22	101	80 - 120	101	80 - 120	<1.0	ug/L	0.13	20		
5592239	Dissolved Beryllium (Be)	2018/06/22	101	80 - 120	100	80 - 120	<1.0	ug/L	NC	20		
5592239	Dissolved Bismuth (Bi)	2018/06/22	98	80 - 120	103	80 - 120	<2.0	ug/L	NC	20		
5592239	Dissolved Boron (B)	2018/06/22	99	80 - 120	94	80 - 120	<50	ug/L	NC	20		
5592239	Dissolved Cadmium (Cd)	2018/06/22	102	80 - 120	101	80 - 120	<0.010	ug/L	NC	20		
5592239	Dissolved Calcium (Ca)	2018/06/22	NC	80 - 120	102	80 - 120	<100	ug/L	0.11	20		
5592239	Dissolved Chromium (Cr)	2018/06/22	96	80 - 120	95	80 - 120	<1.0	ug/L	NC	20		
5592239	Dissolved Cobalt (Co)	2018/06/22	94	80 - 120	95	80 - 120	<0.40	ug/L	NC	20		
5592239	Dissolved Copper (Cu)	2018/06/22	90	80 - 120	93	80 - 120	<2.0	ug/L	NC	20		
5592239	Dissolved Iron (Fe)	2018/06/22	99	80 - 120	98	80 - 120	<50	ug/L	NC	20		
5592239	Dissolved Lead (Pb)	2018/06/22	97	80 - 120	98	80 - 120	<0.50	ug/L	NC	20		
5592239	Dissolved Magnesium (Mg)	2018/06/22	NC	80 - 120	101	80 - 120	<100	ug/L	0.36	20		
5592239	Dissolved Manganese (Mn)	2018/06/22	95	80 - 120	96	80 - 120	<2.0	ug/L	NC	20		
5592239	Dissolved Molybdenum (Mo)	2018/06/22	106	80 - 120	102	80 - 120	<2.0	ug/L	NC	20		
5592239	Dissolved Nickel (Ni)	2018/06/22	92	80 - 120	95	80 - 120	<2.0	ug/L	NC	20		
5592239	Dissolved Phosphorus (P)	2018/06/22	104	80 - 120	102	80 - 120	<100	ug/L	NC	20		
5592239	Dissolved Potassium (K)	2018/06/22	102	80 - 120	103	80 - 120	<100	ug/L	1.3	20		
5592239	Dissolved Selenium (Se)	2018/06/22	96	80 - 120	95	80 - 120	<1.0	ug/L	NC	20		
5592239	Dissolved Silver (Ag)	2018/06/22	99	80 - 120	98	80 - 120	<0.10	ug/L	NC	20		
5592239	Dissolved Sodium (Na)	2018/06/22	94	80 - 120	96	80 - 120	<100	ug/L	0.37	20		

Maxxam Job #: B8F0978
Report Date: 2018/06/26

QUALITY ASSURANCE REPORT(CONT'D)

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

QC Batch	Parameter	Date	Matrix Spike		SPIKED BLANK		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits	% Recovery	QC Limits
5592239	Dissolved Strontium (Sr)	2018/06/22	NC	80 - 120	97	80 - 120	<2.0	ug/L	0.60	20		
5592239	Dissolved Thallium (Tl)	2018/06/22	101	80 - 120	101	80 - 120	<0.10	ug/L	NC	20		
5592239	Dissolved Tin (Sn)	2018/06/22	108	80 - 120	107	80 - 120	<2.0	ug/L	NC	20		
5592239	Dissolved Titanium (Ti)	2018/06/22	100	80 - 120	99	80 - 120	<2.0	ug/L	NC	20		
5592239	Dissolved Uranium (U)	2018/06/22	101	80 - 120	99	80 - 120	<0.10	ug/L	0.48	20		
5592239	Dissolved Vanadium (V)	2018/06/22	99	80 - 120	98	80 - 120	<2.0	ug/L	NC	20		
5592239	Dissolved Zinc (Zn)	2018/06/22	97	80 - 120	99	80 - 120	<5.0	ug/L	NC	20		
5592240	Dissolved Aluminum (Al)	2018/06/22	97	80 - 120	98	80 - 120	<5.0	ug/L	1.7	20		
5592240	Dissolved Antimony (Sb)	2018/06/22	103	80 - 120	99	80 - 120	<1.0	ug/L	NC	20		
5592240	Dissolved Arsenic (As)	2018/06/22	96	80 - 120	96	80 - 120	<1.0	ug/L	3.9	20		
5592240	Dissolved Barium (Ba)	2018/06/22	104	80 - 120	105	80 - 120	<1.0	ug/L	0.23	20		
5592240	Dissolved Beryllium (Be)	2018/06/22	99	80 - 120	100	80 - 120	<1.0	ug/L	NC	20		
5592240	Dissolved Bismuth (Bi)	2018/06/22	101	80 - 120	104	80 - 120	<2.0	ug/L	NC	20		
5592240	Dissolved Boron (B)	2018/06/22	96	80 - 120	95	80 - 120	<50	ug/L	NC	20		
5592240	Dissolved Cadmium (Cd)	2018/06/22	103	80 - 120	104	80 - 120	<0.010	ug/L	NC	20		
5592240	Dissolved Calcium (Ca)	2018/06/22	99	80 - 120	105	80 - 120	<100	ug/L	1.0	20		
5592240	Dissolved Chromium (Cr)	2018/06/22	95	80 - 120	97	80 - 120	<1.0	ug/L	NC	20		
5592240	Dissolved Cobalt (Co)	2018/06/22	95	80 - 120	97	80 - 120	<0.40	ug/L	NC	20		
5592240	Dissolved Copper (Cu)	2018/06/22	91	80 - 120	93	80 - 120	<2.0	ug/L	NC	20		
5592240	Dissolved Iron (Fe)	2018/06/22	98	80 - 120	100	80 - 120	<50	ug/L	NC	20		
5592240	Dissolved Lead (Pb)	2018/06/22	98	80 - 120	100	80 - 120	<0.50	ug/L	NC	20		
5592240	Dissolved Magnesium (Mg)	2018/06/22	100	80 - 120	103	80 - 120	<100	ug/L	0.41	20		
5592240	Dissolved Manganese (Mn)	2018/06/22	NC	80 - 120	97	80 - 120	<2.0	ug/L	0.58	20		
5592240	Dissolved Molybdenum (Mo)	2018/06/22	103	80 - 120	103	80 - 120	<2.0	ug/L	3.7	20		
5592240	Dissolved Nickel (Ni)	2018/06/22	92	80 - 120	94	80 - 120	<2.0	ug/L	NC	20		
5592240	Dissolved Phosphorus (P)	2018/06/22	104	80 - 120	103	80 - 120	<100	ug/L	NC	20		
5592240	Dissolved Potassium (K)	2018/06/22	100	80 - 120	105	80 - 120	<100	ug/L	1.3	20		
5592240	Dissolved Selenium (Se)	2018/06/22	96	80 - 120	96	80 - 120	<1.0	ug/L	NC	20		
5592240	Dissolved Silver (Ag)	2018/06/22	92	80 - 120	99	80 - 120	<0.10	ug/L	NC	20		
5592240	Dissolved Sodium (Na)	2018/06/22	94	80 - 120	95	80 - 120	<100	ug/L	0.53	20		

Maxxam Job #: B8F0978
Report Date: 2018/06/26

QUALITY ASSURANCE REPORT(CONT'D)

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

QC Batch	Parameter	Date	Matrix Spike		SPIKED BLANK		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits	% Recovery	QC Limits
5592240	Dissolved Strontium (Sr)	2018/06/22	100	80 - 120	99	80 - 120	<2.0	ug/L	1.0	20		
5592240	Dissolved Thallium (Tl)	2018/06/22	103	80 - 120	104	80 - 120	<0.10	ug/L	NC	20		
5592240	Dissolved Tin (Sn)	2018/06/22	105	80 - 120	108	80 - 120	<2.0	ug/L	NC	20		
5592240	Dissolved Titanium (Ti)	2018/06/22	99	80 - 120	103	80 - 120	<2.0	ug/L	NC	20		
5592240	Dissolved Uranium (U)	2018/06/22	101	80 - 120	102	80 - 120	<0.10	ug/L	2.6	20		
5592240	Dissolved Vanadium (V)	2018/06/22	98	80 - 120	100	80 - 120	<2.0	ug/L	NC	20		
5592240	Dissolved Zinc (Zn)	2018/06/22	100	80 - 120	100	80 - 120	<5.0	ug/L	NC	20		
5592255	Total Organic Carbon (C)	2018/06/22	95	85 - 115	96	80 - 120	<0.50	mg/L	2.1	15		
5592399	Nitrogen (Ammonia Nitrogen)	2018/06/21	101	80 - 120	104	80 - 120	<0.050	mg/L	NC	20		
5593691	pH	2018/06/22							0.74	N/A	101	97 - 103
5593692	Conductivity	2018/06/22			101	80 - 120	1.5, RDL=1.0	uS/cm	0.29	25		
5593693	pH	2018/06/22							0.48	N/A	100	97 - 103
5593694	Conductivity	2018/06/22			100	80 - 120	1.4, RDL=1.0	uS/cm	0.24	25		
5593695	pH	2018/06/22							0.76	N/A	100	97 - 103
5593696	Conductivity	2018/06/22			101	80 - 120	1.7, RDL=1.0	uS/cm	0.15	25		
5593697	pH	2018/06/22							0.39	N/A	101	97 - 103
5593698	Conductivity	2018/06/22			101	80 - 120	1.8, RDL=1.0	uS/cm	1.9	25		
5593708	Turbidity	2018/06/22			94	80 - 120	<0.10	NTU	2.4	20	97	80 - 120
5593709	Turbidity	2018/06/22			94	80 - 120	<0.10	NTU	9.5	20	96	80 - 120
5593711	Turbidity	2018/06/22			92	80 - 120	<0.10	NTU	4.5	20	96	80 - 120
5593768	Total Alkalinity (Total as CaCO3)	2018/06/25	90	80 - 120	95	80 - 120	<5.0	mg/L	2.2	25		
5593775	Dissolved Chloride (Cl)	2018/06/22	101	80 - 120	102	80 - 120	<1.0	mg/L	1.8	25	100	80 - 120
5593777	Dissolved Sulphate (SO4)	2018/06/22	97	80 - 120	93	80 - 120	<2.0	mg/L	0.015	25		
5593778	Reactive Silica (SiO2)	2018/06/25	NC	80 - 120	97	80 - 120	<0.50	mg/L	0.95	25		
5593779	Colour	2018/06/22			99	80 - 120	<5.0	TCU	NC	20		
5593780	Orthophosphate (P)	2018/06/22	92	80 - 120	94	80 - 120	<0.010	mg/L	NC	25		
5593781	Nitrate + Nitrite (N)	2018/06/25	95	80 - 120	97	80 - 120	<0.050	mg/L	0.94	25		
5593783	Nitrite (N)	2018/06/25	98	80 - 120	96	80 - 120	<0.010	mg/L	NC	20		
5593914	Dissolved Aluminum (Al)	2018/06/22	100	80 - 120	99	80 - 120	<5.0	ug/L	3.1	20		
5593914	Dissolved Antimony (Sb)	2018/06/22	94	80 - 120	92	80 - 120	<1.0	ug/L	NC	20		

Maxxam Job #: B8F0978
Report Date: 2018/06/26

QUALITY ASSURANCE REPORT(CONT'D)

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

QC Batch	Parameter	Date	Matrix Spike		SPIKED BLANK		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits	% Recovery	QC Limits
5593914	Dissolved Arsenic (As)	2018/06/22	95	80 - 120	95	80 - 120	<1.0	ug/L	NC	20		
5593914	Dissolved Barium (Ba)	2018/06/22	95	80 - 120	95	80 - 120	<1.0	ug/L	0.55	20		
5593914	Dissolved Beryllium (Be)	2018/06/22	94	80 - 120	96	80 - 120	<1.0	ug/L	NC	20		
5593914	Dissolved Bismuth (Bi)	2018/06/22	101	80 - 120	99	80 - 120	<2.0	ug/L	NC	20		
5593914	Dissolved Boron (B)	2018/06/22	93	80 - 120	93	80 - 120	<50	ug/L	NC	20		
5593914	Dissolved Cadmium (Cd)	2018/06/22	95	80 - 120	98	80 - 120	<0.010	ug/L	0.74	20		
5593914	Dissolved Calcium (Ca)	2018/06/22	98	80 - 120	99	80 - 120	<100	ug/L	0.17	20		
5593914	Dissolved Chromium (Cr)	2018/06/22	92	80 - 120	93	80 - 120	<1.0	ug/L	NC	20		
5593914	Dissolved Cobalt (Co)	2018/06/22	95	80 - 120	96	80 - 120	<0.40	ug/L	3.5	20		
5593914	Dissolved Copper (Cu)	2018/06/22	94	80 - 120	96	80 - 120	<2.0	ug/L	NC	20		
5593914	Dissolved Iron (Fe)	2018/06/22	97	80 - 120	98	80 - 120	<50	ug/L	NC	20		
5593914	Dissolved Lead (Pb)	2018/06/22	97	80 - 120	97	80 - 120	<0.50	ug/L	NC	20		
5593914	Dissolved Magnesium (Mg)	2018/06/22	97	80 - 120	98	80 - 120	<100	ug/L	0.76	20		
5593914	Dissolved Manganese (Mn)	2018/06/22	96	80 - 120	99	80 - 120	<2.0	ug/L	2.1	20		
5593914	Dissolved Molybdenum (Mo)	2018/06/22	100	80 - 120	98	80 - 120	<2.0	ug/L	NC	20		
5593914	Dissolved Nickel (Ni)	2018/06/22	94	80 - 120	96	80 - 120	<2.0	ug/L	0.38	20		
5593914	Dissolved Phosphorus (P)	2018/06/22	102	80 - 120	103	80 - 120	<100	ug/L	NC	20		
5593914	Dissolved Potassium (K)	2018/06/22	100	80 - 120	101	80 - 120	<100	ug/L	0.065	20		
5593914	Dissolved Selenium (Se)	2018/06/22	95	80 - 120	95	80 - 120	<1.0	ug/L	NC	20		
5593914	Dissolved Silver (Ag)	2018/06/22	95	80 - 120	95	80 - 120	<0.10	ug/L	NC	20		
5593914	Dissolved Sodium (Na)	2018/06/22	93	80 - 120	95	80 - 120	<100	ug/L	0.99	20		
5593914	Dissolved Strontium (Sr)	2018/06/22	97	80 - 120	97	80 - 120	<2.0	ug/L	0.61	20		
5593914	Dissolved Thallium (Tl)	2018/06/22	101	80 - 120	100	80 - 120	<0.10	ug/L	NC	20		
5593914	Dissolved Tin (Sn)	2018/06/22	103	80 - 120	98	80 - 120	<2.0	ug/L	NC	20		
5593914	Dissolved Titanium (Ti)	2018/06/22	101	80 - 120	98	80 - 120	<2.0	ug/L	NC	20		
5593914	Dissolved Uranium (U)	2018/06/22	100	80 - 120	99	80 - 120	<0.10	ug/L	NC	20		
5593914	Dissolved Vanadium (V)	2018/06/22	94	80 - 120	96	80 - 120	<2.0	ug/L	NC	20		
5593914	Dissolved Zinc (Zn)	2018/06/22	100	80 - 120	101	80 - 120	<5.0	ug/L	NC	20		
5593990	Total Organic Carbon (C)	2018/06/22	92	85 - 115	94	80 - 120	<0.50	mg/L	1.5	15		
5596952	Total Organic Carbon (C)	2018/06/25	105	85 - 115	106	80 - 120	<0.50	mg/L	5.4	15		

Maxxam Job #: B8F0978
Report Date: 2018/06/26

QUALITY ASSURANCE REPORT(CONT'D)

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

QC Batch	Parameter	Date	Matrix Spike		SPIKED BLANK		Method Blank		RPD		QC Standard	
			% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits	% Recovery	QC Limits
5597513	Colour	2018/06/25			98	80 - 120	<5.0	TCU	NC	20		
5597605	Colour	2018/06/25			96	80 - 120	<5.0	TCU	NC	20		

N/A = Not Applicable

Matrix Spike: A sample to which a known amount of the analyte of interest has been added. Used to evaluate sample matrix interference.

QC Standard: A sample of known concentration prepared by an external agency under stringent conditions. Used as an independent check of method accuracy.

Spiked Blank: A blank matrix sample to which a known amount of the analyte, usually from a second source, has been added. Used to evaluate method accuracy.

Method Blank: A blank matrix containing all reagents used in the analytical procedure. Used to identify laboratory contamination.

NC (Matrix Spike): The recovery in the matrix spike was not calculated. The relative difference between the concentration in the parent sample and the spike amount was too small to permit a reliable recovery calculation (matrix spike concentration was less than the native sample concentration)

NC (Duplicate RPD): The duplicate RPD was not calculated. The concentration in the sample and/or duplicate was too low to permit a reliable RPD calculation (absolute difference <= 2x RDL).



Maxxam Job #: B8F0978
Report Date: 2018/06/26

GHD Limited
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 73512044
Sampler Initials: DN

VALIDATION SIGNATURE PAGE

The analytical data and all QC contained in this report were reviewed and validated by the following individual(s).

<Original signed by>

Eric Dearman, Scientific Specialist

<Original signed by>

Mike MacGillivray, Scientific Specialist (Inorganics)

Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(E), signing the reports. For Service Group specific validation please refer to the Validation Signature Page.



200 Bluewater Road, Suite 105, Bedford, Nova Scotia B4B 1G9 Tel: 902-420-0203 Fax: 902-420-8612 Toll Free: 1-800-565-7227
 49-55 Elizabeth Avenue, St John's, NL A1A 1W9 Tel: 709-754-0203 Fax: 709-754-8612 Toll Free: 1-888-492-7227
 465 George Street, Unit G, Sydney, NS B1P 1K5 Tel: 902-567-1255 Fax: 902-539-6504 Toll Free: 1-888-535-7770
www.maxxam.ca E-mail: customerservicebedford@maxxam.ca

ATL FCD 00149 / 22

CHAIN OF CUSTODY RECORD

COC #: D34771 Page 1 of 2

Invoice Information		Report Information (If differs from invoice)		Project Information (where applicable)		Turnaround Time (TAT) Required		
Company Name: <u>GHD LTD</u>	Contact Name: <u>JEFFREY, TRINA</u>	Company Name: <u>JEFF PARKS</u>	Contact Name: <u>JEFF PARKS</u>	Quotation #: <u>STANDING OFFER</u>	P.O. #: <u>73512044</u>	<input checked="" type="checkbox"/> Regular TAT (5 business days) Most analyses		
Address: <u>45 AKERLEY BLVD</u>	Address: <u>DARTMOUTH</u>	Postal Code: <u>B3B 1J7</u>	Postal Code: <u></u>	Project #: <u>0881064</u>	Site Location: <u>BEAVER DAM</u>	PLEASE PROVIDE ADVANCE NOTICE FOR RUSH PROJECTS		
Phone: <u>902-468-1248</u>	Phone: <u></u>	Fax: <u></u>	Email: <u>jeffrey.parks@ghd.com</u>	Site #: <u>D.N./J.R./R.H.</u>	Sampled By: <u></u>	IF RUSH please specify date (Surcharges will be applied)		
Laboratory Use Only				Analysis Requested				
CUSTODY SEAL	COOLER TEMPERATURES	COOLER TEMPERATURES		Metals (Water)	Metals (Soil)	Regulatory Requirements (Specify)		
Present	Intact			ICAP-MS (Dissolved Metals) Ground waters				
		6	4	Total Dissolved Metals (Default Method) for (solid) water & surface water				
		6	5	Dissolved (CIRCLE) TOTAL / DISSOLVED				
		7	7	Mercury (CIRCLE) TOTAL / DISSOLVED				
COOLING MEDIA PRESENT Y / N				Metals & Mercury				
SAMPLES MUST BE KEPT COOL (< 10 °C) FROM TIME OF SAMPLING UNTIL DELIVERY TO MAXXAM				Metals Total Digest for Ocean sediments (HNO3/HF/HClO4)				
SAMPLE IDENTIFICATION		DATE SAMPLED (YYYY/MM/DD)	TIME SAMPLED (HH:MM)	MATRIX	Mercury Low level by Cold Vapour AA			
1	MW-12A	18/06/18	11:26	GW	RBCA Hydrocarbons (ITEX, CCE-C32), Hydrocarbons, Soil (Portable), NS Fuel Oil Spill Policy			
2	MW-12B	18/06/18	11:31	GW	Ions (Solid) ITEX, OCS-CH2, CCME Hydrocarbons (CM5-SPHC 1/1/BTEX, F2-F4), NB Portable Water BTEX, VPH, Low level T.E.H.			
3	MW-09A	18/06/18	11:58	GW	PAHs (Default; for water/oil)			
4	MW-09B	18/06/18	12:07	GW	PCBs			
5	MW-09D	18/06/18	12:15	GW	VOCs			
6	MW-04A	18/06/18	12:50	GW	Total Coliform/E.Coli (Presence/Absence)			
7	MW-04B	18/06/18	12:58	GW	Total Coliform/E.Coli (Count)			
8	MW-21A	18/06/18	15:10	GW	HOLD: DO NOT ANALYZE			
9	MW-21B	18/06/18	15:16	GW	COMMENTS			
10	MW-21C	18/06/18	15:28	GW	2018 JUN 19 15:24			
RELINQUISHED BY: (Signature/Print)		DATE: (YYYY/MM/DD)	TIME: (HH:MM)	RECEIVED BY: (Signature/Print)	DATE: (YYYY/MM/DD)	TIME: (HH:MM)	MAXXAM JOB #	
<Original signed by>		2018/06/19	2:46	<Original signed by> <u>Jeff Parks</u>			<u>B8F09178</u>	
Unless otherwise agreed to in writing, work submitted on this Chain of Custody is subject to Maxxam's standard Terms and Conditions. Signing of this Chain of Custody document is acknowledgment and acceptance of our terms which are available for viewing at www.maxxam.ca/terms .								

White: Maxxam

Pink: Client



200 Bluewater Road, Suite 105, Bedford, Nova Scotia B4B 1G9 Tel: 902-420-0203 Fax: 902-420-8612 Toll Free: 1-800-555-7227
 49-55 Elizabeth Avenue, St John's, NL A1A 1W9 Tel: 709-754-0203 Fax: 709-754-8612 Toll Free: 1-888-492-7227
 465 George Street, Unit G, Sydney, NS B1P 1K5 Tel: 902-567-1255 Fax: 902-539-6504 Toll Free: 1-888-535-7770

ATL FCD 00149 / 22

www.maxxam.ca

E-mail: customerservicebedford@maxxam.ca

CHAIN OF CUSTODY RECORD

COC #: D34773 Page 2 of 2

Invoice Information		Report Information (if differs from invoice)		Project Information (where applicable)		Turnaround Time (TAT) Required		
Company Name: GHD LTD	Contact Name: TRINA JEFFREY	Company Name: JEFFREY PARKS	Contact Name: JEFFREY PARKS	Quotation #: STANDING OFFER	P.O. #: 73512044	<input checked="" type="checkbox"/> Regular TAT (5 business days) Most		
Address: 45 AKERLEY BLVD	Address: DARTMOUTH Postal Code: B3B 1J7	Address: PO BOX 220	Postal Code: FAX:	Project #: 088664	Site Location: BEAVER DAM	<input checked="" type="checkbox"/> PLEASE PROVIDE ADVANCE NOTICE FOR RUSH PROJECTS		
Phone: 902-468-1248	Phone: 902-468-220	Phone: _____	Fax: _____	Site #: DN/JR/RH	Sampled By: _____	IF RUSH please specify date (Surcharges will be applied)		
Email: trina.jeffrey@ghd.com	Email: jeffrey.parks@ghd.com	DATE REQUIRED:						
Laboratory Use Only				Analysis Requested				
CUSTODY SEAL		COOLER TEMPERATURES		COOLER TEMPERATURES				
Present	Intact	6	4	5	7			
COOLING MEDIA PRESENT Y / N								
SAMPLES MUST BE KEPT COOL (< 10 °C) FROM TIME OF SAMPLING UNTIL DELIVERY TO MAXXAM								
SAMPLE IDENTIFICATION		DATE SAMPLED (YYYY/MM/DD)	TIME SAMPLED (HH:MM)	MATRIX	RCAP-MIS (Dissolved Metals) Ground waters	Metals (Water)	Metals (Soil)	Regulatory Requirements (Specify)
1	MW-16 A	18/06/18	13:36	GW	4 X	X	Total Digest (Default Method) for well water & surface water	
2	MW-16 B	18/06/18	13:40	GW	4 X	X	Disolved for ground water	
3	MW-17 A	18/06/18	14:11	GW	4 X	X	Mercury (ICP/ICP TOTAL) / DISSOLVED	
4	MW-17 B	18/06/18	14:19	GW	4 X	X	Metals & Mercury Digest Acid Extractable (Available) Digest	
5	MW-17 C	18/06/18	14:25	GW	4 X	X	Metals Total Digest + for Ocean sediments (HNO3/HCl/HClO4)	
6	MW-DUP A	18/06/18	-	GW	4 X	X	Mercury low level by Cath Vapour AA	
7	MW-DUP B	18/06/18	-	GW	4 X	X	Hot Water Soluble Boron (required for CCMF Agricultural/ Landfill)	
8								
9								
10								
RELINQUISHED BY: (Signature/Print)		DATE: (YYYY/MM/DD)	TIME: (HH:MM)	RECEIVED BY: (Signature/Print)		DATE: (YYYY/MM/DD)	TIME: (HH:MM)	MAXXAM JOB #
<Original signed by>		2018/06/19	2:46	<Original signed>		<i>Jae Day/k</i>		<i>B8F0978</i>
<i>18 JUN 19 15:24</i>								<i>B8F0978 k/d</i>
Unless otherwise agreed to in writing, work submitted on this Chain of Custody is subject to Maxxam's standard Terms and Conditions. Signing of this Chain of Custody document is acknowledgment and acceptance of our terms which are available for viewing at www.maxxam.ca/terms .								

White: Maxxam

Pink: Client

Your P.O. #: 3151
 Your Project #: 088664-20
 Site Location: BEAVER DAM
 Your C.O.C. #: D34774

Attention: James Millard

Atlantic Mining NS Corp
 6749 Moose River Rd
 Middle Musquodoboit, NS
 CANADA B0N 1X0

Report Date: 2018/07/09
 Report #: R5286935
 Version: 1 - Final

CERTIFICATE OF ANALYSIS

MAXXAM JOB #: B8G1148

Received: 2018/06/28, 10:31

Sample Matrix: Water
 # Samples Received: 22

Analyses	Quantity	Date Extracted	Date Analyzed	Laboratory Method	Reference
Carbonate, Bicarbonate and Hydroxide	22	N/A	2018/07/04	N/A	SM 22 4500-CO2 D
Alkalinity	1	N/A	2018/07/04	ATL SOP 00013	EPA 310.2 R1974 m
Alkalinity	8	N/A	2018/07/05	ATL SOP 00013	EPA 310.2 R1974 m
Alkalinity	13	N/A	2018/07/06	ATL SOP 00013	EPA 310.2 R1974 m
Chloride	1	N/A	2018/07/05	ATL SOP 00014	SM 23 4500-Cl- E m
Chloride	21	N/A	2018/07/06	ATL SOP 00014	SM 23 4500-Cl- E m
Colour	1	N/A	2018/07/06	ATL SOP 00020	SM 22 2120C m
Colour	21	N/A	2018/07/09	ATL SOP 00020	SM 22 2120C m
Conductance - water	22	N/A	2018/07/04	ATL SOP 00004	SM 23 2510B m
Hardness (calculated as CaCO ₃)	8	N/A	2018/07/05	ATL SOP 00048	SM 22 2340 B
Hardness (calculated as CaCO ₃)	14	N/A	2018/07/06	ATL SOP 00048	SM 22 2340 B
Metals Water Diss. MS (as rec'd)	8	N/A	2018/07/05	ATL SOP 00058	EPA 6020A R1 m
Metals Water Diss. MS (as rec'd)	14	N/A	2018/07/06	ATL SOP 00058	EPA 6020A R1 m
Ion Balance (% Difference)	1	N/A	2018/07/06	N/A	Auto Calc.
Ion Balance (% Difference)	21	N/A	2018/07/09	N/A	Auto Calc.
Anion and Cation Sum	8	N/A	2018/07/05	N/A	Auto Calc.
Anion and Cation Sum	14	N/A	2018/07/06	N/A	Auto Calc.
Nitrogen Ammonia - water	21	N/A	2018/07/05	ATL SOP 00015	EPA 350.1 R2 m
Nitrogen Ammonia - water	1	N/A	2018/07/06	ATL SOP 00015	EPA 350.1 R2 m
Nitrogen - Nitrate + Nitrite	1	N/A	2018/07/05	ATL SOP 00016	USGS I-2547-11m
Nitrogen - Nitrate + Nitrite	21	N/A	2018/07/09	ATL SOP 00016	USGS I-2547-11m
Nitrogen - Nitrite	22	N/A	2018/07/05	ATL SOP 00017	SM 23 4500-NO2- B m
Nitrogen - Nitrate (as N)	1	N/A	2018/07/06	ATL SOP 00018	ASTM D3867-16
Nitrogen - Nitrate (as N)	21	N/A	2018/07/09	ATL SOP 00018	ASTM D3867-16
pH (1)	22	N/A	2018/07/04	ATL SOP 00003	SM 23 4500-H+ B m
Phosphorus - ortho	1	N/A	2018/07/05	ATL SOP 00021	SM 23 4500-P E m
Phosphorus - ortho	21	N/A	2018/07/06	ATL SOP 00021	SM 23 4500-P E m
Sat. pH and Langelier Index (@ 20C)	1	N/A	2018/07/06	ATL SOP 00049	Auto Calc.
Sat. pH and Langelier Index (@ 20C)	21	N/A	2018/07/09	ATL SOP 00049	Auto Calc.
Sat. pH and Langelier Index (@ 4C)	1	N/A	2018/07/06	ATL SOP 00049	Auto Calc.

Your P.O. #: 3151
 Your Project #: 088664-20
 Site Location: BEAVER DAM
 Your C.O.C. #: D34774

Attention: James Millard

Atlantic Mining NS Corp
 6749 Moose River Rd
 Middle Musquodoboit, NS
 CANADA B0N 1X0

Report Date: 2018/07/09
 Report #: R5286935
 Version: 1 - Final

CERTIFICATE OF ANALYSIS

MAXXAM JOB #: B8G1148

Received: 2018/06/28, 10:31

Sample Matrix: Water
 # Samples Received: 22

Analyses	Quantity	Date Extracted	Date Analyzed	Laboratory Method	Reference
Sat. pH and Langelier Index (@ 4C)	21	N/A	2018/07/09	ATL SOP 00049	Auto Calc.
Reactive Silica	14	N/A	2018/07/05	ATL SOP 00022	EPA 366.0 m
Reactive Silica	8	N/A	2018/07/06	ATL SOP 00022	EPA 366.0 m
Sulphate	1	N/A	2018/07/04	ATL SOP 00023	ASTM D516-16 m
Sulphate	21	N/A	2018/07/06	ATL SOP 00023	ASTM D516-16 m
Total Dissolved Solids (TDS calc)	1	N/A	2018/07/06	N/A	Auto Calc.
Total Dissolved Solids (TDS calc)	21	N/A	2018/07/09	N/A	Auto Calc.
Organic carbon - Total (TOC) (2)	8	N/A	2018/07/04	ATL SOP 00203	SM 23 5310B m
Organic carbon - Total (TOC) (2)	14	N/A	2018/07/05	ATL SOP 00203	SM 23 5310B m
Turbidity	22	N/A	2018/07/05	ATL SOP 00011	EPA 180.1 R2 m

Remarks:

Maxxam Analytics' laboratories are accredited to ISO/IEC 17025:2005 for specific parameters on scopes of accreditation. Unless otherwise noted, procedures used by Maxxam are based upon recognized Provincial, Federal or US method compendia such as CCME, MDDELCC, EPA, APHA.

All work recorded herein has been done in accordance with procedures and practices ordinarily exercised by professionals in Maxxam's profession using accepted testing methodologies, quality assurance and quality control procedures (except where otherwise agreed by the client and Maxxam in writing). All data is in statistical control and has met quality control and method performance criteria unless otherwise noted. All method blanks are reported; unless indicated otherwise, associated sample data are not blank corrected.

Maxxam Analytics' liability is limited to the actual cost of the requested analyses, unless otherwise agreed in writing. There is no other warranty expressed or implied. Maxxam has been retained to provide analysis of samples provided by the Client using the testing methodology referenced in this report. Interpretation and use of test results are the sole responsibility of the Client and are not within the scope of services provided by Maxxam, unless otherwise agreed in writing.

Solid sample results, except biota, are based on dry weight unless otherwise indicated. Organic analyses are not recovery corrected except for isotope dilution methods.

Results relate to samples tested.

This Certificate shall not be reproduced except in full, without the written approval of the laboratory.

Reference Method suffix "m" indicates test methods incorporate validated modifications from specific reference methods to improve performance.

* RPDs calculated using raw data. The rounding of final results may result in the apparent difference.

(1) The APHA Standard Method require pH to be analyzed within 15 minutes of sampling and therefore field analysis is required for compliance. All Laboratory pH analyses in this report are reported past the APHA Standard Method holding time.

(2) TOC / DOC present in the sample should be considered as non-purgeable TOC / DOC.

Your P.O. #: 3151
Your Project #: 088664-20
Site Location: BEAVER DAM
Your C.O.C. #: D34774

Attention: James Millard

Atlantic Mining NS Corp
6749 Moose River Rd
Middle Musquodoboit, NS
CANADA B0N 1X0

Report Date: 2018/07/09
Report #: R5286935
Version: 1 - Final

CERTIFICATE OF ANALYSIS

MAXXAM JOB #: B8G1148

Received: 2018/06/28, 10:31

Encryption Key



Maxxam
09 Jul 2018 17:20:08

Please direct all questions regarding this Certificate of Analysis to your Project Manager.

Maryann Comeau, Project Manager

Email: MComeau@maxxam.ca

Phone# (902) 420-0203

=====

This report has been generated and distributed using a secure automated process.

Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(E), signing the reports. For Service Group specific validation please refer to the Validation Signature Page.



Maxxam Job #: B8G1148
Report Date: 2018/07/09

Atlantic Mining NS Corp
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 3151
Sampler Initials: RH

RESULTS OF ANALYSES OF WATER

Maxxam ID		HCC205	HCC206	HCC207		HCC207		HCC208		HCC209	
Sampling Date		2018/06/27 10:49	2018/06/27 10:57	2018/06/27 11:03		2018/06/27 11:03		2018/06/27 11:19		2018/06/27 11:23	
COC Number		D34774	D34774	D34774		D34774		D34774		D34774	
	UNITS	MW-05A	MW-05B	MW-05D	RDL	MW-05D Lab-Dup	RDL	MW-07A	RDL	MW-07B	RDL
Calculated Parameters											
Anion Sum	me/L	0.410	0.990	1.73	N/A			2.47	N/A	7.02	N/A
Bicarb. Alkalinity (calc. as CaCO3)	mg/L	11	37	66	1.0			100	1.0	320	1.0
Calculated TDS	mg/L	27	60	100	1.0			150	1.0	380	1.0
Carb. Alkalinity (calc. as CaCO3)	mg/L	ND	ND	ND	1.0			ND	1.0	2.2	1.0
Cation Sum	me/L	0.370	0.900	1.61	N/A			2.53	N/A	6.68	N/A
Hardness (CaCO3)	mg/L	10	27	56	1.0			93	1.0	290	1.0
Ion Balance (% Difference)	%	5.13	4.76	3.59	N/A			1.20	N/A	2.48	N/A
Langelier Index (@ 20C)	N/A	-3.37	-1.33	-0.134				-0.988		0.935	
Langelier Index (@ 4C)	N/A	-3.62	-1.58	-0.385				-1.24		0.686	
Nitrate (N)	mg/L	0.051	0.061	ND	0.050			ND	0.050	ND	0.050
Saturation pH (@ 20C)	N/A	9.80	8.80	8.26				7.93		6.93	
Saturation pH (@ 4C)	N/A	10.1	9.05	8.51				8.18		7.18	
Inorganics											
Total Alkalinity (Total as CaCO3)	mg/L	11	37	66	5.0			100	10	320	25
Dissolved Chloride (Cl-)	mg/L	4.5	4.0	4.7	1.0			4.4	1.0	6.7	1.0
Colour	TCU	ND	ND	ND	5.0			8.0	5.0	ND	5.0
Nitrate + Nitrite (N)	mg/L	0.051	0.061	ND	0.050			ND	0.050	ND	0.050
Nitrite (N)	mg/L	ND	ND	ND	0.010			ND	0.010	ND	0.010
Nitrogen (Ammonia Nitrogen)	mg/L	ND	ND	ND	0.050	ND	0.050	ND	0.050	0.060	0.050
Total Organic Carbon (C)	mg/L	1.5	2.0	1.3	0.50			1.1	0.50	3.2	0.50
Orthophosphate (P)	mg/L	ND	ND	ND	0.010			ND	0.010	0.013	0.010
pH	pH	6.43	7.47	8.13	N/A			6.94	N/A	7.86	N/A
Reactive Silica (SiO2)	mg/L	5.1	8.2	12	0.50			21	0.50	24	0.50
Dissolved Sulphate (SO4)	mg/L	3.0	6.6	13	2.0			13	2.0	19	2.0
Turbidity	NTU	1.5	11	2.2	0.10			30	0.10	4.6	0.10
Conductivity	uS/cm	44	100	170	1.0			240	1.0	620	1.0

RDL = Reportable Detection Limit

Lab-Dup = Laboratory Initiated Duplicate

N/A = Not Applicable

ND = Not detected



Maxxam Job #: B8G1148
Report Date: 2018/07/09

Atlantic Mining NS Corp
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 3151
Sampler Initials: RH

RESULTS OF ANALYSES OF WATER

Maxxam ID		HCC210		HCC211	HCC212	HCC213	HCC214		HCC215	
Sampling Date		2018/06/27 11:28		2018/06/27 11:49	2018/06/27 11:54	2018/06/27 11:45	2018/06/27 12:42		2018/06/27 12:51	
COC Number		D34774		D34774	D34774	D34774	D34774		D34774	
	UNITS	MW-07D	RDL	MW-11A	MW-11B	MW-11C	MW-14A	RDL	MW-14B	RDL

Calculated Parameters

Anion Sum	me/L	2.59	N/A	0.300	1.87	2.02	0.740	N/A	5.07	N/A
Bicarb. Alkalinity (calc. as CaCO ₃)	mg/L	110	1.0	5.5	78	68	27	1.0	91	1.0
Calculated TDS	mg/L	150	1.0	21	100	120	53	1.0	320	1.0
Carb. Alkalinity (calc. as CaCO ₃)	mg/L	1.1	1.0	ND	ND	ND	ND	1.0	1.3	1.0
Cation Sum	me/L	2.75	N/A	0.280	1.71	1.91	0.670	N/A	4.58	N/A
Hardness (CaCO ₃)	mg/L	120	1.0	8.0	71	76	18	1.0	46	1.0
Ion Balance (% Difference)	%	3.00	N/A	3.45	4.47	2.80	4.96	N/A	5.08	N/A
Langelier Index (@ 20C)	N/A	0.288		-4.04	0.0690	-0.283	-2.64		-0.123	
Langelier Index (@ 4C)	N/A	0.0380		-4.29	-0.182	-0.534	-2.89		-0.371	
Nitrate (N)	mg/L	ND	0.050	0.059	0.19	0.066	0.11	0.050	ND	0.050
Saturation pH (@ 20C)	N/A	7.77		10.2	8.05	8.10	9.19		8.29	
Saturation pH (@ 4C)	N/A	8.02		10.4	8.30	8.35	9.44		8.54	

Inorganics

Total Alkalinity (Total as CaCO ₃)	mg/L	110 (1)	25	5.5	79	69	27	5.0	92	5.0
Dissolved Chloride (Cl ⁻)	mg/L	6.9	1.0	4.8	3.5	4.4	3.6	1.0	13	1.0
Colour	TCU	ND	5.0	ND	ND	ND	ND	5.0	ND	5.0
Nitrate + Nitrite (N)	mg/L	ND	0.050	0.059	0.19	0.066	0.11	0.050	ND	0.050
Nitrite (N)	mg/L	ND	0.010	ND	ND	ND	ND	0.010	ND	0.010
Nitrogen (Ammonia Nitrogen)	mg/L	ND	0.050	ND	ND	ND	ND	0.050	ND	0.050
Total Organic Carbon (C)	mg/L	2.2	0.50	1.3	0.65	1.7	0.62	0.50	14	0.50
Orthophosphate (P)	mg/L	0.035	0.010	ND	0.018	0.021	0.012	0.010	ND	0.010
pH	pH	8.05	N/A	6.12	8.11	7.82	6.56	N/A	8.17	N/A
Reactive Silica (SiO ₂)	mg/L	15	0.50	3.8	8.7	8.8	14	0.50	8.9	0.50
Dissolved Sulphate (SO ₄)	mg/L	12	2.0	2.6	8.2	25	4.3	2.0	140	10
Turbidity	NTU	9.5	0.10	0.80	10	6.8	61	0.10	37	0.10
Conductivity	uS/cm	280	1.0	35	170	200	74	1.0	540	1.0

RDL = Reportable Detection Limit

N/A = Not Applicable

ND = Not detected

(1) Elevated reporting limit due to sample matrix.



Maxxam Job #: B8G1148
Report Date: 2018/07/09

Atlantic Mining NS Corp
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 3151
Sampler Initials: RH

RESULTS OF ANALYSES OF WATER

Maxxam ID		HCC216	HCC217	HCC218		HCC218		HCC219	HCC220	
Sampling Date		2018/06/27 13:01	2018/06/27 12:18	2018/06/27 12:22		2018/06/27 12:22		2018/06/27 12:27	2018/06/26 13:28	
COC Number		D34774	D34774	D34774		D34774		D34774	D34774	
	UNITS	MW-14C	MW-18A	MW-18B	RDL	MW-18B Lab-Dup	RDL	MW-18C	MW-20A	RDL

Calculated Parameters

Anion Sum	me/L	1.80	0.310	1.34	N/A			2.02	0.360	N/A
Bicarb. Alkalinity (calc. as CaCO3)	mg/L	72	5.5	45	1.0			52	7.9	1.0
Calculated TDS	mg/L	100	23	84	1.0			130	26	1.0
Carb. Alkalinity (calc. as CaCO3)	mg/L	1.3	ND	ND	1.0			ND	ND	1.0
Cation Sum	me/L	1.60	0.270	1.23	N/A			1.89	0.310	N/A
Hardness (CaCO3)	mg/L	29	6.8	41	1.0			45	7.6	1.0
Ion Balance (% Difference)	%	5.88	6.90	4.28	N/A			3.32	7.46	N/A
Langelier Index (@ 20C)	N/A	-0.227	-4.17	-0.820				-0.636	-4.03	
Langelier Index (@ 4C)	N/A	-0.478	-4.42	-1.07				-0.886	-4.28	
Nitrate (N)	mg/L	0.052	0.062	ND	0.050			ND	0.21	0.050
Saturation pH (@ 20C)	N/A	8.52	10.3	8.52				8.44	10.1	
Saturation pH (@ 4C)	N/A	8.77	10.6	8.77				8.69	10.4	

Inorganics

Total Alkalinity (Total as CaCO3)	mg/L	74	5.5	45	5.0	46	5.0	52	7.9	5.0
Dissolved Chloride (Cl-)	mg/L	3.9	3.8	3.5	1.0	3.3	1.0	5.3	4.8	1.0
Colour	TCU	ND	ND	ND	5.0	ND	5.0	ND	5.5	5.0
Nitrate + Nitrite (N)	mg/L	0.052	0.062	ND	0.050	0.050	0.050	ND	0.21	0.050
Nitrite (N)	mg/L	ND	ND	ND	0.010	ND	0.010	ND	ND	0.010
Nitrogen (Ammonia Nitrogen)	mg/L	ND	ND	ND	0.050			ND	ND	0.050
Total Organic Carbon (C)	mg/L	1.5	1.7	1.4	0.50			5.8	1.3	0.50
Orthophosphate (P)	mg/L	ND	ND	0.054	0.010	0.051	0.010	ND	ND	0.010
pH	pH	8.29	6.18	7.70	N/A	7.83	N/A	7.81	6.08	N/A
Reactive Silica (SiO2)	mg/L	10	5.3	11	0.50	11	0.50	11	6.7	0.50
Dissolved Sulphate (SO4)	mg/L	11	4.3	17	2.0	16	2.0	40	2.3	2.0
Turbidity	NTU	33	1.1	20	0.10	19	0.10	18	4.9	0.10
Conductivity	uS/cm	170	35	130	1.0	130	1.0	210	38	1.0

RDL = Reportable Detection Limit

Lab-Dup = Laboratory Initiated Duplicate

N/A = Not Applicable

ND = Not detected



Maxxam Job #: B8G1148
Report Date: 2018/07/09

Atlantic Mining NS Corp
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 3151
Sampler Initials: RH

RESULTS OF ANALYSES OF WATER

Maxxam ID		HCC221	HCC222	HCC223	HCC224	HCC225		HCC226	
Sampling Date		2018/06/26 13:36	2018/06/26 12:58	2018/06/26 13:03	2018/06/26 13:09	2018/06/27 13:20		2018/06/27 13:25	
COC Number		D34774	D34774	D34774	D34774	D34774		D34774	
	UNITS	MW-20B	MW-22A	MW-22B	MW-22C	DUP4	RDL	DUP5	RDL

Calculated Parameters

Anion Sum	me/L	2.12	0.300	1.56	2.24	0.420	N/A	5.04	N/A
Bicarb. Alkalinity (calc. as CaCO3)	mg/L	90	5.8	59	94	11	1.0	94	1.0
Calculated TDS	mg/L	120	23	94	130	28	1.0	310	1.0
Carb. Alkalinity (calc. as CaCO3)	mg/L	ND	ND	ND	1.0	ND	1.0	1.5	1.0
Cation Sum	me/L	1.95	0.260	1.38	2.00	0.380	N/A	4.50	N/A
Hardness (CaCO3)	mg/L	72	5.5	48	52	10	1.0	45	1.0
Ion Balance (% Difference)	%	4.18	7.14	6.12	5.66	5.00	N/A	5.66	N/A
Langelier Index (@ 20C)	N/A	-0.0410	-4.11	-0.786	-0.0890	-3.46		-0.0470	
Langelier Index (@ 4C)	N/A	-0.291	-4.36	-1.04	-0.340	-3.71		-0.297	
Nitrate (N)	mg/L	ND	0.093	ND	ND	ND	0.050	ND	0.050
Saturation pH (@ 20C)	N/A	8.07	10.5	8.41	8.16	9.79		8.29	
Saturation pH (@ 4C)	N/A	8.32	10.7	8.66	8.41	10.0		8.54	

Inorganics

Total Alkalinity (Total as CaCO3)	mg/L	91	5.8	60	95	11	5.0	95	5.0
Dissolved Chloride (Cl-)	mg/L	3.6	4.0	4.2	4.2	4.8	1.0	13	1.0
Colour	TCU	ND	ND	ND	ND	ND	5.0	5.7	5.0
Nitrate + Nitrite (N)	mg/L	ND	0.093	ND	ND	ND	0.050	ND	0.050
Nitrite (N)	mg/L	ND	ND	ND	ND	ND	0.010	ND	0.010
Nitrogen (Ammonia Nitrogen)	mg/L	0.054	ND	ND	ND	ND	0.050	ND	0.050
Total Organic Carbon (C)	mg/L	0.84	1.0	1.8	1.6	1.5	0.50	14	0.50
Orthophosphate (P)	mg/L	ND	ND	ND	ND	ND	0.010	ND	0.010
pH	pH	8.02	6.38	7.63	8.07	6.33	N/A	8.24	N/A
Reactive Silica (SiO2)	mg/L	12	6.5	14	12	5.2	0.50	9.0	0.50
Dissolved Sulphate (SO4)	mg/L	9.8	3.3	12	10	3.0	2.0	130	10
Turbidity	NTU	4.7	2.2	1.8	6.8	0.77	0.10	37	0.10
Conductivity	uS/cm	200	33	150	210	43	1.0	540	1.0

RDL = Reportable Detection Limit

N/A = Not Applicable

ND = Not detected



Maxxam Job #: B8G1148
Report Date: 2018/07/09

Atlantic Mining NS Corp
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 3151
Sampler Initials: RH

ELEMENTS BY ICP/MS (WATER)

Maxxam ID		HCC205	HCC206	HCC206	HCC207	HCC208	HCC209	HCC210	HCC211	
Sampling Date		2018/06/27 10:49	2018/06/27 10:57	2018/06/27 10:57	2018/06/27 11:03	2018/06/27 11:19	2018/06/27 11:23	2018/06/27 11:28	2018/06/27 11:49	
COC Number		D34774								
	UNITS	MW-05A	MW-05B	MW-05B Lab-Dup	MW-05D	MW-07A	MW-07B	MW-07D	MW-11A	RDL
Metals										
Dissolved Aluminum (Al)	ug/L	8.3	10	9.9	29	ND	5.7	10	31	5.0
Dissolved Antimony (Sb)	ug/L	ND	1.0							
Dissolved Arsenic (As)	ug/L	ND	1.0	1.0	ND	12	39	170	ND	1.0
Dissolved Barium (Ba)	ug/L	5.9	5.8	5.9	3.4	11	13	5.5	6.9	1.0
Dissolved Beryllium (Be)	ug/L	ND	1.0							
Dissolved Bismuth (Bi)	ug/L	ND	2.0							
Dissolved Boron (B)	ug/L	ND	50							
Dissolved Cadmium (Cd)	ug/L	0.031	0.018	0.014	ND	ND	ND	ND	0.024	0.010
Dissolved Calcium (Ca)	ug/L	2900	9000	8900	18000	27000	100000	38000	2400	100
Dissolved Chromium (Cr)	ug/L	ND	ND	ND	ND	6.2	ND	ND	ND	1.0
Dissolved Cobalt (Co)	ug/L	2.2	1.3	1.4	ND	0.55	ND	ND	1.0	0.40
Dissolved Copper (Cu)	ug/L	4.7	4.8	4.7	ND	ND	ND	ND	ND	2.0
Dissolved Iron (Fe)	ug/L	ND	100	91	ND	5100	ND	ND	ND	50
Dissolved Lead (Pb)	ug/L	ND	0.50							
Dissolved Magnesium (Mg)	ug/L	770	1200	1100	2400	6400	8600	5400	470	100
Dissolved Manganese (Mn)	ug/L	110	130	130	20	530	970	44	76	2.0
Dissolved Molybdenum (Mo)	ug/L	ND	4.2	4.2	ND	ND	ND	ND	ND	2.0
Dissolved Nickel (Ni)	ug/L	8.8	3.9	3.8	ND	2.4	ND	ND	2.8	2.0
Dissolved Phosphorus (P)	ug/L	ND	100							
Dissolved Potassium (K)	ug/L	990	1400	1400	980	1800	3600	1200	590	100
Dissolved Selenium (Se)	ug/L	ND	1.0							
Dissolved Silver (Ag)	ug/L	ND	0.10							
Dissolved Sodium (Na)	ug/L	3300	7200	7200	11000	10000	18000	9200	2400	100
Dissolved Strontium (Sr)	ug/L	14	34	33	160	140	340	310	17	2.0
Dissolved Thallium (Tl)	ug/L	ND	0.10							
Dissolved Tin (Sn)	ug/L	3.5	ND	2.0						
Dissolved Titanium (Ti)	ug/L	ND	2.0							
Dissolved Uranium (U)	ug/L	ND	0.14	0.14	0.35	0.11	2.3	0.73	ND	0.10
Dissolved Vanadium (V)	ug/L	ND	2.0							
Dissolved Zinc (Zn)	ug/L	30	8.7	9.7	ND	9.5	ND	ND	12	5.0

RDL = Reportable Detection Limit

Lab-Dup = Laboratory Initiated Duplicate

ND = Not detected



Maxxam Job #: B8G1148
Report Date: 2018/07/09

Atlantic Mining NS Corp
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 3151
Sampler Initials: RH

ELEMENTS BY ICP/MS (WATER)

Maxxam ID		HCC212	HCC213	HCC214	HCC215	HCC216	HCC217	HCC218	HCC219	
Sampling Date		2018/06/27 11:54	2018/06/27 11:45	2018/06/27 12:42	2018/06/27 12:51	2018/06/27 13:01	2018/06/27 12:18	2018/06/27 12:22	2018/06/27 12:27	
COC Number		D34774								
	UNITS	MW-11B	MW-11C	MW-14A	MW-14B	MW-14C	MW-18A	MW-18B	MW-18C	RDL

Metals										
Dissolved Aluminum (Al)	ug/L	14	18	ND	ND	6.5	23	13	16	5.0
Dissolved Antimony (Sb)	ug/L	ND	ND	ND	1.6	ND	ND	ND	ND	1.0
Dissolved Arsenic (As)	ug/L	60	78	4.9	7.7	1.6	40	230	57	1.0
Dissolved Barium (Ba)	ug/L	7.8	11	3.2	5.9	13	5.7	4.1	6.4	1.0
Dissolved Beryllium (Be)	ug/L	ND	1.0							
Dissolved Bismuth (Bi)	ug/L	ND	2.0							
Dissolved Boron (B)	ug/L	ND	ND	ND	84	120	ND	ND	ND	50
Dissolved Cadmium (Cd)	ug/L	ND	ND	0.014	ND	ND	0.028	ND	ND	0.010
Dissolved Calcium (Ca)	ug/L	25000	26000	4900	15000	9300	1600	15000	16000	100
Dissolved Chromium (Cr)	ug/L	ND	1.0							
Dissolved Cobalt (Co)	ug/L	ND	0.44	1.6	ND	ND	2.2	ND	ND	0.40
Dissolved Copper (Cu)	ug/L	ND	ND	ND	ND	ND	5.1	ND	ND	2.0
Dissolved Iron (Fe)	ug/L	ND	50							
Dissolved Lead (Pb)	ug/L	ND	0.50							
Dissolved Magnesium (Mg)	ug/L	1800	2400	1300	2200	1400	710	1200	1400	100
Dissolved Manganese (Mn)	ug/L	35	56	190	11	ND	53	3.1	13	2.0
Dissolved Molybdenum (Mo)	ug/L	ND	2.6	ND	15	ND	ND	4.9	4.1	2.0
Dissolved Nickel (Ni)	ug/L	ND	ND	4.2	ND	ND	6.3	ND	ND	2.0
Dissolved Phosphorus (P)	ug/L	ND	100							
Dissolved Potassium (K)	ug/L	1600	1100	1300	1400	660	790	1500	1600	100
Dissolved Selenium (Se)	ug/L	ND	1.0							
Dissolved Silver (Ag)	ug/L	ND	0.10							
Dissolved Sodium (Na)	ug/L	5800	8500	6700	83000	23000	2500	8400	22000	100
Dissolved Strontium (Sr)	ug/L	86	190	38	330	270	13	85	180	2.0
Dissolved Thallium (Tl)	ug/L	ND	0.10							
Dissolved Tin (Sn)	ug/L	ND	2.0							
Dissolved Titanium (Ti)	ug/L	ND	2.0							
Dissolved Uranium (U)	ug/L	0.91	3.3	ND	4.7	0.53	ND	1.1	1.8	0.10
Dissolved Vanadium (V)	ug/L	ND	2.0							
Dissolved Zinc (Zn)	ug/L	ND	10	8.1	ND	ND	19	ND	ND	5.0

RDL = Reportable Detection Limit

ND = Not detected



Maxxam Job #: B8G1148
Report Date: 2018/07/09

Atlantic Mining NS Corp
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 3151
Sampler Initials: RH

ELEMENTS BY ICP/MS (WATER)

Maxxam ID		HCC220	HCC221	HCC222	HCC223	HCC224	HCC225	HCC226	
Sampling Date		2018/06/26 13:28	2018/06/26 13:36	2018/06/26 12:58	2018/06/26 13:03	2018/06/26 13:09	2018/06/27 13:20	2018/06/27 13:25	
COC Number		D34774							
	UNITS	MW-20A	MW-20B	MW-22A	MW-22B	MW-22C	DUP4	DUP5	RDL

Metals

Dissolved Aluminum (Al)	ug/L	38	62	22	23	12	8.8	ND	5.0
Dissolved Antimony (Sb)	ug/L	ND	ND	ND	ND	ND	ND	1.6	1.0
Dissolved Arsenic (As)	ug/L	ND	7.0	ND	1.5	5.4	ND	7.6	1.0
Dissolved Barium (Ba)	ug/L	4.8	11	5.0	3.6	4.7	5.7	5.7	1.0
Dissolved Beryllium (Be)	ug/L	ND	1.0						
Dissolved Bismuth (Bi)	ug/L	ND	2.0						
Dissolved Boron (B)	ug/L	ND	ND	ND	ND	ND	ND	78	50
Dissolved Cadmium (Cd)	ug/L	0.035	0.011	0.016	ND	ND	0.031	ND	0.010
Dissolved Calcium (Ca)	ug/L	1900	22000	1000	14000	17000	2900	15000	100
Dissolved Chromium (Cr)	ug/L	ND	1.0						
Dissolved Cobalt (Co)	ug/L	2.8	ND	1.8	0.43	ND	2.1	ND	0.40
Dissolved Copper (Cu)	ug/L	3.0	ND	9.4	ND	ND	5.0	ND	2.0
Dissolved Iron (Fe)	ug/L	ND	50						
Dissolved Lead (Pb)	ug/L	ND	0.50						
Dissolved Magnesium (Mg)	ug/L	680	4500	700	3000	2500	760	2100	100
Dissolved Manganese (Mn)	ug/L	150	100	160	190	15	110	11	2.0
Dissolved Molybdenum (Mo)	ug/L	ND	7.0	ND	ND	3.3	ND	15	2.0
Dissolved Nickel (Ni)	ug/L	6.8	ND	8.1	ND	ND	8.4	ND	2.0
Dissolved Phosphorus (P)	ug/L	ND	100						
Dissolved Potassium (K)	ug/L	610	1600	810	1600	1100	1000	1400	100
Dissolved Selenium (Se)	ug/L	ND	1.0						
Dissolved Silver (Ag)	ug/L	ND	0.10						
Dissolved Sodium (Na)	ug/L	3200	10000	3000	8900	21000	3300	82000	100
Dissolved Strontium (Sr)	ug/L	19	270	15	81	280	15	330	2.0
Dissolved Thallium (Tl)	ug/L	ND	0.10						
Dissolved Tin (Sn)	ug/L	ND	2.1	ND	ND	ND	2.5	ND	2.0
Dissolved Titanium (Ti)	ug/L	ND	2.0						
Dissolved Uranium (U)	ug/L	ND	0.86	ND	0.26	0.52	ND	4.7	0.10
Dissolved Vanadium (V)	ug/L	ND	2.0						
Dissolved Zinc (Zn)	ug/L	10	ND	16	5.2	ND	35	ND	5.0

RDL = Reportable Detection Limit

ND = Not detected



Maxxam Job #: B8G1148
Report Date: 2018/07/09

Atlantic Mining NS Corp
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 3151
Sampler Initials: RH

GENERAL COMMENTS

Each temperature is the average of up to three cooler temperatures taken at receipt

Package 1	4.3°C
Package 2	3.0°C

Sample HCC205 [MW-05A] : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample HCC215 [MW-14B] : Poor RCAP Ion Balance due to sample matrix.

Sample HCC216 [MW-14C] : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample HCC217 [MW-18A] : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample HCC220 [MW-20A] : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample HCC222 [MW-22A] : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample HCC223 [MW-22B] : RCAP Ion Balance acceptable. Anion/cation agreement within 0.2 meq/L.

Sample HCC224 [MW-22C] : Poor RCAP Ion Balance due to sample matrix.

Sample HCC226 [DUP5] : Poor RCAP Ion Balance due to sample matrix.

Results relate only to the items tested.



Maxxam Job #: B8G1148
Report Date: 2018/07/09

Atlantic Mining NS Corp
Client Project #: 088664-20
Site Location: BEAVER DAM
Your P.O. #: 3151
Sampler Initials: RH

VALIDATION SIGNATURE PAGE

The analytical data and all QC contained in this report were reviewed and validated by the following individual(s).

<Original signed by>

Mike MacGillivray, Scientific Specialist (Inorganics)

Maxxam has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per section 5.10.2 of ISO/IEC 17025:2005(E), signing the reports. For Service Group specific validation please refer to the Validation Signature Page.



ATLANTIC GOLD

Appendix F.4

Groundwater Quality Data

Table 5: Groundwater Quality Data
Beaver Dam Mine Project
Marinette, Nova Scotia

Sample	Criteria			MW-01									MW-02									MW-03									
	CCME FWAL	MDMER	Tier 1 EQS	MW-01A			MW-01B			MW-01C			MW-02A			MW-02B			MW-03A			MW-03B			MW-03C						
				19-Jun-18	12-Sep-18	29-Nov-18	29-Nov-18 Field DUP4	19-Jun-18	12-Sep-18	29-Nov-18	19-Jun-18	12-Sep-18	29-Nov-18	19-Jun-18	19-Jun-18 Field DUP 3	12-Sep-18															
Sample Date																															
Calculated Parameters	Units																														
Anion Sum	me/L				0.560	0.460	0.500	1.56	1.50	1.58	1.35	0.930	0.950	0.330	0.280	0.360	0.480	0.480	0.520	0.520	0.280	0.420	0.370	0.980	1.05	1.03	1.87	1.77	1.97		
Bicarb. Alkalinity (calc. as CaCO ₃)	mg/L				18	14	15	60	58	61	52	34	33	6.0	6.2	7.0	17	16	18	18	6.2	9.9	11	37	39	40	83	77	86		
Calculated TDS	mg/L				37	34	33	91	89	92	79	57	58	21	25	23	40	41	48	46	20	31	27	62	65	63	110	100	110		
Carb. Alkalinity (calc. as CaCO ₃)	mg/L				<1.0	ND	<1.0	<1.0	<1.0	<1.0	ND	<1.0	<1.0	<1.0	ND	<1.0	<1.0	ND	<1.0	ND											
Cation Sum	me/L				0.510	0.440	0.440	1.47	1.46	1.48	1.26	0.940	0.880	0.260	0.270	0.310	0.440	0.450	0.730	0.620	0.260	0.390	0.350	0.930	0.970	0.960	1.79	1.76	1.91		
Hardness (CaCO ₃)	mg/L				2.2	7.4	11	54	58	60	40	33	27	4.9	5.6	6.6	10	9.6	13	12	5.9	9.5	4.9	35	36	37	67	66	75		
Ion Balance (% Difference)	%				4.67	2.22	6.38	2.97	1.35	3.27	3.45	0.530	3.83	11.9	1.82	7.46	4.35	3.23	16.8	8.77	3.70	3.70	2.78	2.62	3.96	3.52	2.19	0.280	1.55		
Langelier Index (@ 20°C)	N/A				-3.54	-3.14	-3.07	-0.512	-0.286	-0.411	-1.03	-1.41	-1.93	-4.58	-4.24	-3.86	-3.20	-2.94	-2.77	-2.81	-4.37	-3.65	-3.92	-2.01	-1.67	-1.93	-0.247	-0.304	-0.0900		
Langelier Index (@ 4°C)	N/A				-3.79	-3.39	-3.32	-0.763	-0.537	-0.663	-1.28	-1.66	-2.18	-4.83	-4.50	-4.11	-3.45	-3.19	-3.03	-3.06	-4.63	-3.91	-4.18	-2.26	-1.92	-2.18	-0.498	-0.556	-0.341		
Nitrate (N)	mg/L	2.935			<0.050	0.065	<0.050	<0.050	ND	<0.050	<0.050	ND	<0.050	<0.050	ND	<0.050	<0.050	0.052	<0.050	<0.050	0.31	0.44	0.68	0.10	0.11	0.091	<0.050	<0.050	0.074		
Saturation pH (@ 20°C)	N/A				10.3	9.9	9.66	8.29	8.28	8.24	8.50	8.75	8.84	10.4	10.2	9.64	9.70	9.47	9.49	10.3	9.87	10.2	8.67	8.63	8.61	8.06	8.10	8.00			
Saturation pH (@ 4°C)	N/A				10.5	10.1	9.92	8.55	8.53	8.49	8.75	9.00	9.09	10.7	10.6	10.4	9.89	9.95	9.72	9.75	10.6	10.1	10.4	8.93	8.89	8.86	8.31	8.36	8.25		
Inorganics																															
Total Alkalinity (Total as CaCO ₃)	mg/L				18	14	15	61	59	62	52	34	33	6.0	6.2	7.0	17	16	18	18	6.2	9.9	11	37	39	40	84	77	87		
Dissolved Chloride (Cl)	mg/L				4.8	4.0	5.3	4.4	4.1	4.3	5.1	5.1	5.4	3.3	5.8	2.7	3.3	3.1	3.0	4.7	4.9	3.7	5.5	6.3	5.4	5.2	5.1				
Colour	TCU				<5.0	ND	<5.0	<5.0	ND	<5.0	6.5	ND	<5.0	<5.0	ND	<5.0	<5.0	<5.0	ND	8.6	ND	6.0	5.4	ND	<5.0	5.3	<5.0	ND			
Nitrate + Nitrite (N)	mg/L				<0.050	0.065	<0.050	<0.050	ND	<0.050	<0.050	ND	<0.050	<0.050	ND	<0.050	<0.050	0.052	<0.050	<0.050	0.31	0.44	0.68	0.10	0.11	0.091	<0.050	<0.050	0.074		
Nitrite (N)	mg/L	0.06			<0.010	ND	<0.010	<0.010	ND	<0.010	<0.010	ND	<0.010	<0.010	ND	<0.010	<0.010	ND	<0.010	<0.010											
Nitrogen (Ammonia Nitrogen)	mg/L	Varies(1)			<0.050	ND	<0.050	<0.050	ND	<0.050	<0.050	ND	<0.050	<0.050	ND	<0.050	<0.050	ND	<0.050	<0.050											
Total Organic Carbon (C)	mg/L				1.3	ND (1)	<0.50	2.6	ND	<0.50	1.9	2.9	1.3	1.2	ND	0.72	1.9	ND	0.56	0.57	3.6	2.3	2.6	1.1	0.88	<0.50	4.2	4.3	1.7		
Orthophosphate (P)	mg/L				<0.010	ND	<0.010	<0.010	0.058	0.068	0.065	0.066	<0.010	ND	<0.010	<0.010	<0.010	<0.010	<0.010	ND	<0.010	<0.010									
pH	pH	6.5-9	6-9.5		6.75	6.74	6.60	7.78	8.00	7.83	7.47	7.34	6.91	5.83	6.12	6.31	6.44	6.76	6.69	6.69	5.93	6.21	6.23	6.66	6.97	6.68	7.81	7.80	7.91		
Reactive Silica (SiO ₂)	mg/L				6.3	8.4	6.3	9.4	10	10	7.5	7.1	6.8	3.2	9.2	4.1	15	15	15	15											

Table 5: Groundwater Quality Data
Beaver Dam Mine Project
Marinette, Nova Scotia

Sample	
Sample Date	29-Nov-18
Calculated Parameters	Units
Anion Sum	me/L
Bicarb. Alkalinity (calc. as CaCO ₃)	mg/L
Calculated TDS	mg/L
Carb. Alkalinity (calc. as CaCO ₃)	mg/L
Cation Sum	me/L
Hardness (CaCO ₃)	mg/L
Ion Balance (% Difference)	%
Langelier Index (@ 20C)	N/A
Langelier Index (@ 4C)	N/A
Nitrate (N)	mg/L
Saturation pH (@ 20C)	N/A
Saturation pH (@ 4C)	N/A
Inorganics	
Total Alkalinity (Total as CaCO ₃)	mg/L
Dissolved Chloride (Cl)	mg/L
Colour	TCU
Nitrate + Nitrite (N)	mg/L
Nitrite (N)	mg/L
Nitrogen (Ammonia Nitrogen)	mg/L
Total Organic Carbon (C)	mg/L
Orthophosphate (P)	mg/L
pH	pH
Reactive Silica (SiO ₂)	mg/L
Dissolved Sulphate (SO ₄)	mg/L
Turbidity	NTU
Conductivity	uS/cm
Metals	
Dissolved Aluminum (Al)	ug/L
Dissolved Antimony (Sb)	ug/L
Dissolved Arsenic (As)	ug/L
Dissolved Barium (Ba)	ug/L
Dissolved Beryllium (Be)	ug/L
Dissolved Bismuth (Bi)	ug/L
Dissolved Boron (B)	ug/L
Dissolved Cadmium (Cd)	ug/L
Dissolved Calcium (Ca)	ug/L
Dissolved Chromium (Cr)	ug/L
Dissolved Cobalt (Co)	ug/L
Dissolved Copper (Cu)	ug/L
Dissolved Iron (Fe)	ug/L
Dissolved Lead (Pb)	ug/L
Dissolved Magnesium (Mg)	ug/L
Dissolved Manganese (Mn)	ug/L
Dissolved Molybdenum (Mo)	ug/L
Dissolved Nickel (Ni)	ug/L
Dissolved Phosphorus (P)	ug/L
Dissolved Potassium (K)	ug/L
Dissolved Selenium (Se)	ug/L
Dissolved Silver (Ag)	ug/L
Dissolved Sodium (Na)	ug/L
Dissolved Strontium (Sr)	ug/L
Dissolved Thallium (Tl)	ug/L
Dissolved Tin (Sn)	ug/L
Dissolved Titanium (Ti)	ug/L
Dissolved Uranium (U)	ug/L
Dissolved Vanadium (V)	ug/L
Dissolved Zinc (Zn)	ug/L
Notes	
CCME FAL - Canadian Council of Ministers of the Environment V (provided for reference)	
MDMER - Federal Metal and Diamond Mining Effluent Regulation a grab sample (provided for reference)	
Tier 1 EGQS - Nova Scotia Environment Tier 1 Environmental Quality Agricultural/Residential	
(1) Ammonia guideline dependent on temperature and pH, e.g., i pH = 6.0 to 0.02 mg/L at pH = 10 (see CCME Fact Sheet).	
- denotes not analyzed	
NC = not calculated	

Table 5: Groundwater Quality Data
Beaver Dam Mine Project
Marinette, Nova Scotia

Sample	MW-04										MW-05										MW-07											
	MW-04A			MW-04B							MW-05A			MW-05B				MW-05D			MW-07A			MW-07B			MW-07D					
	18-Jun-18	12-Sep-18	29-Nov-18	18-Jun-18	12-Sep-18	12-Sep-18 Field DUP 3	29-Nov-18	27-Jun-18	27-Jun-18 Field DUP 4	12-Sep-18	29-Nov-18	27-Jun-18	12-Sep-18	12-Sep-18 Field DUP 2	29-Nov-18	27-Jun-18	12-Sep-18	29-Nov-18														
Sample Date	18-Jun-18	12-Sep-18	29-Nov-18	18-Jun-18	12-Sep-18	12-Sep-18 Field DUP 3	29-Nov-18	27-Jun-18	27-Jun-18 Field DUP 4	12-Sep-18	29-Nov-18	27-Jun-18	12-Sep-18	12-Sep-18 Field DUP 2	29-Nov-18	27-Jun-18	12-Sep-18	29-Nov-18														
Calculated Parameters	Units																															
Anion Sum	me/L	0.440	0.420	0.340	1.16	1.03	0.390	1.01	0.41	0.420	0.450	0.350	0.990	1.84	1.78	1.29	1.73	1.70	1.75	2.47	2.46	2.50	7.02	6.93	6.81	2.59	2.91	2.91	3.03			
Bicarb. Alkalinity (calc. as CaCO3)	mg/L	11	9.8	6.4	41	36	11	36	11	11	15	8.8	37	73	72	50	66	66	66	100	100	110	320	310	310	110	120	120	120			
Calculated TDS	mg/L	32	31	24	71	67	30	63	27	28	30	24	60	100	100	80	100	100	100	150	150	150	380	370	360	150	170	180				
Carb. Alkalinity (calc. as CaCO3)	mg/L	<1.0	ND	<1.0	<1.0	ND	ND	<1.0	<1.0	<1.0	ND	<1.0	<1.0	ND	<1.0	<1.0	ND	<1.0	<1.0	ND	<1.0	2.2	2.0	2.4	1.1	1.3	1.2					
Cation Sum	me/L	0.510	0.390	0.300	1.08	1.06	0.330	0.940	0.37	0.380	0.390	0.290	0.900	1.03	1.04	1.20	1.61	1.58	1.61	2.53	2.70	2.58	6.68	6.50	6.32	2.75	2.86	2.93				
Hardness (CaCO3)	mg/L	17	11	7.2	44	41	8.0	37	10	10	11	8.2	27	34	35	40	56	56	56	93	100	99	290	280	270	120	110	120				
Ion Balance (% Difference)	%	7.37	3.70	6.25	3.57	1.44	8.33	3.59	5.13	5.00	7.14	9.38	4.76	28.2	26.2	3.61	3.59	3.66	4.17	1.20	4.65	1.57	2.48	3.20	3.73	3.00	0.870	1.68				
Langelier Index (@ 20C)	N/A	-3.26	-3.27	-4.15	-1.26	-1.22	-3.78	-1.41	-3.37	-3.46	-3.35	-3.86	-1.33	-0.614	-0.780	-1.08	-0.134	-0.184	-0.292	-0.988	-0.642	-0.919	0.935	0.874	0.947	0.288	0.346	0.292				
Langelier Index (@ 4C)	N/A	-3.51	-3.53	-4.40	-1.51	-1.47	-4.03	-1.66	-3.62	-3.71	-3.60	-4.12	-1.58	-0.865	-1.03	-1.34	-0.385	-0.435	-0.543	-1.24	-0.892	-1.17	0.686	0.625	0.698	0.0380	0.0960	0.0420				
Nitrate (N)	mg/L	<0.050	0.060	<0.050	0.054	0.28	0.065	0.051	<0.050	ND	<0.050	0.061	ND	ND	<0.050	<0.050	ND	<0.050	<0.050	ND	<0.050	<0.050	ND	<0.050	ND	<0.050	ND	<0.050	ND	<0.050		
Saturation pH (@ 20C)	N/A	9.58	9.80	10.2	8.54	8.62	9.97	8.67	9.8	9.79	9.64	9.98	8.80	8.42	8.50	8.26	8.26	8.26	8.26	7.93	7.90	7.89	6.93	6.96	7.77	7.73	7.72	7.72				
Saturation pH (@ 4C)	N/A	9.83	10.1	10.4	8.79	8.88	10.2	8.92	10.1	10.0	9.89	10.2	9.05	8.68	8.67	8.75	8.51	8.51	8.51	8.18	8.15	8.14	7.18	7.21	7.21	8.02	7.98	7.97				
Inorganics																																
Total Alkalinity (Total as CaCO3)	mg/L	11	9.9	6.4	41	36	11	36	11	11	15	8.8	37	74	72	50	66	66	66	100	100	110	320	310	310	110	120	120				
Dissolved Chloride (Cl)	mg/L	6.4	5.0	5.8	4.9	4.5	3.7	4.2	4.5	4.8	3.1	4.0	3.9	3.5	3.8	4.7	4.6	5.0	4.4	4.5	4.0	6.7	6.2	6.9	6.5	7.5						
Colour	TCU	<5.0	ND	<5.0	<5.0	ND	ND	<5.0	<5.0	<5.0	ND	<5.0	<5.0	ND	ND	<5.0	<5.0	ND	<5.0	8.0	70	49	<5.0	ND	<5.0	<5.0	ND	<5.0				
Nitrate + Nitrite (N)	mg/L	<0.050	0.060	<0.050	0.054	0.28	0.065	0.051	<0.050	ND	<0.050	0.061	ND	ND	<0.050	<0.050	ND	<0.050	<0.050	ND	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050			
Nitrite (N)	mg/L	<0.010	ND	<0.010	<0.010	ND	ND	<0.010	<0.010	<0.010	ND	<0.010	<0.010	ND	ND	<0.010	<0.010	ND	<0.010	<0.010	ND	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010			
Nitrogen (Ammonia Nitrogen)	mg/L	<0.050	ND	<0.050	<0.050	ND	ND	<0.050	<0.050	<0.050	ND	<0.050	<0.050	ND	ND	<0.050	<0.050	ND	<0.050	<0.050	ND	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050			
Total Organic Carbon (C)	mg/L	0.73	ND	<0.50	1.1	1.6	ND	0.82	1.5	1.5	0.61	0.64	2.0	7.6	8.0	2.0	1.3	ND	0.78	1.1	0.72	0.75	3.2	3.4	2.4	2.2	3.3	3.6				
Orthophosphate (P)	mg/L	<0.010	ND	<0.010	<0.010	ND	0.010	<0.010	<0.010	<0.010	ND	<0.010	<0.010	ND	ND	<0.01																

Table 5: Groundwater Quality Data
Beaver Dam Mine Project
Marinette, Nova Scotia

Sample	MW-09												MW-11												MW-12					
	MW-09A				MW-09B				MW-09D				MW-11A			MW-11B			MW-11C			MW-12A			MW-12B					
Sample Date	18-Jun-18	18-Jun-18 Field DUP 1	12-Sep-18	29-Nov-18	18-Jun-18	12-Sep-18	29-Nov-18	18-Jun-18	12-Sep-18	29-Nov-18	29-Nov-18 Field DUP5	27-Jun-18	12-Sep-18	29-Nov-18	27-Jun-18	12-Sep-18	29-Nov-18	27-Jun-18	21-Sep-18 Field Dup 5	29-Nov-18	18-Jun-18	12-Sep-18	29-Nov-18	18-Jun-18	12-Sep-18	29-Nov-18				
Calculated Parameters	Units																													
Anion Sum	me/L	0.340	0.320	0.930	0.420	2.46	2.75	2.46	2.97	4.21	3.31	3.20	0.300	0.340	0.320	1.87	1.06	1.76	2.02	2.02	2.12	2.02	0.83	0.880	1.05	2.20	2.21	2.28		
Bicarb. Alkalinity (calc. as CaCO3)	mg/L	9.2	8.8	37	12	71	74	76	65	79	70	69	5.5	8.3	6.9	78	47	75	68	71	76	70	33	36	42	80	83	85		
Calculated TDS	mg/L	30	29	56	28	150	170	140	190	260	200	200	21	23	22	100	63	97	120	120	120	120	64	62	72	130	130	130		
Carb. Alkalinity (calc. as CaCO3)	mg/L	<1.0	<1.0	ND	<1.0	<1.0	ND	<1.0	<1.0	<1.0	<1.0	<1.0	ND	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	ND	<1.0	<1.0	<1.0	ND	<1.0		
Cation Sum	me/L	0.630	0.630	0.870	0.360	2.37	2.53	2.24	2.89	4.01	3.02	3.04	0.280	0.290	0.290	1.71	1.15	1.61	1.91	1.89	1.88	1.82	0.94	0.770	0.940	2.10	2.06	2.11		
Hardness (CaCO3)	mg/L	25	25	36	12	72	66	78	93	120	110	110	8.0	7.8	8.2	71	24	65	76	71	73	31	24	31	70	70	71			
Ion Balance (% Difference)	%	29.9	32.6	3.33	7.69	1.86	4.17	4.68	1.37	2.43	4.58	2.56	3.45	7.94	4.92	4.47	4.07	4.45	2.80	3.32	6.00	5.21	6.21	6.67	5.53	2.33	3.51	3.87		
Langelier Index (@ 20°C)	N/A	-3.07	-2.95	-1.79	-3.15	-0.174	-0.0840	-0.296	-0.547	-0.0610	-0.186	-0.240	-4.04	-3.63	-3.81	0.0690	-1.41	-0.198	-0.283	-0.250	-0.307	-0.211	-2.42	-2.50	-2.16	-0.212	-0.155	-0.220		
Langelier Index (@ 4°C)	N/A	-3.32	-3.20	-2.04	-3.40	-0.424	-0.335	-0.546	-0.798	-0.311	-0.436	-0.490	-4.29	-3.88	-4.07	-0.182	-1.66	-0.449	-0.534	-0.501	-0.557	-0.461	-2.67	-2.75	-2.41	-0.462	-0.405	-0.471		
Nitrate (N)	mg/L	<0.050	<0.050	0.051	0.059	<0.050	ND	<0.050	<0.050	ND	<0.050	<0.050	0.059	ND	<0.050	0.19	ND	0.079	0.066	0.089	0.077	0.053	0.085	0.17	0.16	0.062	ND	<0.050		
Saturation pH (@ 20°C)	N/A	9.37	9.39	8.64	9.60	8.11	8.13	8.04	8.09	7.90	8.00	8.01	10.2	10.0	10.0	8.05	8.75	8.10	8.10	8.08	8.10	8.9	8.95	8.78	8.08	8.07	8.05			
Saturation pH (@ 4°C)	N/A	9.62	9.64	8.89	9.85	8.36	8.38	8.29	8.34	8.15	8.25	8.26	10.4	10.3	10.3	8.30	9.00	8.35	8.35	8.33	8.35	9.15	9.21	9.03	8.33	8.32	8.30			
Inorganics																														
Total Alkalinity (Total as CaCO3)	mg/L	9.2	8.8	37	12	72	75	77	65	80	70	69	5.5	8.3	6.9	79	47	75	69	72	77	71	33	36	42	81	83	85		
Dissolved Chloride (Cl)	mg/L	3.5	2.9	3.3	3.9	5.1	4.6	4.2	8.6	11	8.9	8.9	4.8	3.9	4.6	3.5	4.1	3.9	4.4	3.7	3.8	4.2	2.4	2.8	3.4	4.6	3.3	3.8		
Colour	TCU	<5.0	<5.0	ND	<5.0	<5.0	ND	<5.0	<5.0	ND	<5.0	<5.0	<5.0	ND	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0		
Nitrate + Nitrite (N)	mg/L	<0.050	<0.050	0.051	0.059	<0.050	ND	<0.050	<0.050	ND	<0.050	<0.050	0.059	ND	<0.050	0.19	ND	0.079	0.066	0.089	0.077	0.053	0.085	0.17	0.16	0.062	ND	<0.050		
Nitrite (N)	mg/L	<0.010	0.021	ND	<0.010	0.010	ND	<0.010	<0.010	ND	<0.010	<0.010	<0.010	ND	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010		
Nitrogen (Ammonia Nitrogen)	mg/L	<0.050	<0.050	ND	<0.050	<0.050	ND	<0.050	<0.050	ND	<0.050	<0.050	<0.050	ND	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050	<0.050		
Total Organic Carbon (C)	mg/L	0.59	0.61	ND	<0.50	2.5	5.4	2.9	9.1	17	10	10	0.60	0.71	0.65	9.0	<5.0 (1)	1.7	0.91	0.95	0.99	<0.50	ND	<0.50	1.0	ND	<0.50			
Orthophosphate (P)	mg/L	<0.010	<0.010	ND	<0.010	0.027	0.016	0.022	0.012	0.013	0.015	0.015	<0.010	ND	<0.010	0.018	ND	<0.010	0.021	0.019	0.018	0.018	<0.010	ND	<0.010	0.016	0.013	<0.010		
pH	pH	6.30	6.44	6.85	6.45	7.94	8.05	7.75	7.54	7.84	7.82	7.77	6.12	6.37	6.23	8.11	7.34	7.91	7.82	7.85	7.77	7.89	6.48	6.46	6.61	7.86	7.91	7.83		
Reactive Silica (SiO2)	mg/L	5.1	5.1	8.6	6.1	9.3	9.0	9.3	12	11	12	12	3.8	5.2	4.5	8.7	4.6	8.5	8.8	9.0	8.9	9.1	17	17	18	10	11			

Table 5: Groundwater Quality Data
Beaver Dam Mine Project
Marinette, Nova Scotia

Sample		MW-14												MW-16												MW-17											
		MW-14A				MW-14B				MW-14C				MW-16A				MW-16B				MW-17A				MW-17B				MW-17C							
Sample Date		27-Jun-18	12-Sep-18	29-Nov-18	27-Jun-18	27-Jun-18 Field DUP 5	12-Sep-18	29-Nov-18	27-Jun-18	12-Sep-18	29-Nov-18	29-Nov-18 Field DUP2	18-Jun-18	12-Sep-18	29-Nov-18	29-Nov-18 Field DUP1	18-Jun-18	12-Sep-18	29-Nov-18																		
Calculated Parameters	Units																																				
Anion Sum	me/L	0.740	0.670	0.820	5.07	5.04	4.00	2.43	1.80	1.73	1.78	1.76	1.80	1.38	1.02	1.03	1.43	1.41	1.44	0.510	0.640	0.400	0.300	0.300	0.330	0.340	0.420	0.450	0.450	0.450	0.450						
Bicarb. Alkalinity (calc. as CaCO ₃)	mg/L	27	25	31	91	94	84	72	71	72	72	72	79	60	43	42	59	59	59	15	23	11	8.3	7.4	9.3	8.3	14	15	14								
Calculated TDS	mg/L	53	52	58	320	310	240	140	100	100	100	100	100	100	78	62	64	84	82	84	34	42	28	25	26	28	32	35	34								
Carb. Alkalinity (calc. as CaCO ₃)	mg/L	<1.0	ND	<1.0	1.3	1.5	1.1	1.0	1.3	ND	<1.0	<1.0	<1.0	<1.0	ND	<1.0	<1.0	ND	<1.0	<1.0	ND	<1.0	<1.0	ND	<1.0	<1.0	ND	<1.0	<1.0	ND	<1.0						
Cation Sum	me/L	0.670	0.620	0.750	4.58	4.50	3.58	2.24	1.60	1.57	1.60	1.63	1.72	1.25	1.00	1.08	1.34	1.30	1.34	0.470	0.540	0.350	0.260	0.260	0.250	0.290	0.390	0.400	0.410								
Hardness (CaCO ₃)	mg/L	18	14	16	46	45	54	53	29	32	33	34	66	46	21	23	55	54	55	15	18	10	6.6	6.7	6.1	7.1	12	12	12								
Ion Balance (% Difference)	%	4.96	3.88	4.46	5.08	5.66	5.54	4.07	5.88	4.85	5.33	3.83	2.27	4.94	0.990	2.37	3.25	4.06	3.60	4.08	8.47	6.67	7.14	7.14	13.8	7.94	3.70	5.88	4.65								
Langelier Index (@ 20°C)	N/A	-2.64	-2.58	-2.47	-0.123	-0.0470	-0.106	-0.112	-0.227	-0.406	-0.579	-0.465	-0.291	-1.07	-1.89	-1.92	-0.510	-0.249	-0.488	-3.14	-2.47	-3.58	-4.06	-4.08	-3.80	-3.88	-3.07	-2.93	-3.13								
Langelier Index (@ 4°C)	N/A	-2.89	-2.83	-2.73	-0.371	-0.297	-0.356	-0.363	-0.478	-0.657	-0.830	-0.716	-0.542	-1.33	-2.14	-2.17	-0.761	-0.501	-0.740	-3.40	-2.72	-3.83	-4.31	-4.33	-4.06	-4.14	-3.33	-3.18	-3.38								
Nitrate (N)	mg/L	0.11	0.084	0.10	<0.050	<0.050	ND	<0.050	0.052	ND	<0.050	<0.050	0.092	ND	0.075	0.054	0.14	0.13	0.16	<0.050	ND	<0.050	<0.050														
Saturation pH (@ 20°C)	N/A	9.19	9.31	9.17	8.29	8.29	8.20	8.22	8.52	8.48	8.47	8.46	8.08	8.34	8.83	8.79	8.27	9.42	9.17	9.76	10.2	10.2	10.1	10.1	9.59	9.57	9.60										
Saturation pH (@ 4°C)	N/A	9.44	9.57	9.42	8.54	8.54	8.45	8.47	8.77	8.73	8.72	8.72	8.33	8.59	9.08	9.05	8.52	8.52	8.52	9.67	9.42	10.0	10.4	10.4	10.4	10.4	9.84	9.82	9.85								
Inorganics																																					
Total Alkalinity (Total as CaCO ₃)	mg/L	27	25	31	92	95	95	85	74	72	73	72	79	60	43	42	59	60	60	15	23	11	8.3	7.4	9.3	8.3	14	15	14								
Dissolved Chloride (Cl)	mg/L	3.6	3.2	3.7	13	13	8.5	5.0	3.9	3.0	3.9	3.6	4.0	3.2	3.4	3.9	4.1	3.3	4.0	5.2	4.3	4.6	2.9	3.3	2.9	4.4	2.7	4.0									
Colour	TCU	<5.0	ND	<5.0	<5.0	5.7	ND	<5.0	<5.0	ND	<5.0	<5.0	<5.0	ND	<5.0	<5.0	ND	<5.0	<5.0	ND	<5.0	<5.0	ND	<5.0	<5.0	ND	<5.0	<5.0	ND	<5.0							
Nitrate + Nitrite (N)	mg/L	0.11	0.084	0.10	<0.050	<0.050	ND	<0.050	0.052	ND	<0.050	<0.050	0.092	ND	0.075	0.054	0.14	0.13	0.16	<0.050	ND	<0.050	<0.050														
Nitrite (N)	mg/L	<0.010	ND	<0.010	<0.010	<0.010	ND	<0.010	<0.010	ND	<0.010	<0.010	<0.010	ND	<0.010	<0.010	ND	<0.010	<0.010	ND	<0.010	<0.010	ND	<0.010	<0.010	ND	<0.010	<0.010	ND	<0.010	<0.010						
Nitrogen (Ammonia Nitrogen)	mg/L	<0.050	ND	<0.050	<0.050	<0.050	ND	<0.050	<0.050	ND	<0.050	<0.050	0.050	ND	0.075	0.065	<0.050	ND	<0.050	<0.050																	
Total Organic Carbon (C)	mg/L	0.62	ND	<5.0 (1)	14	14	6.6	1.3	1.5	0.53	0.61	<0.50	0.60	1.5	2.3	<5.0 (1)	<0.50	ND	<0.50	0.59	ND	0.55	0.56	0.51	ND	0.63	<0.50	ND	1.2								
Orthophosphate (P)	mg/L	0.012	0.018	0.01																																	

Table 5: Groundwater Quality Data
Beaver Dam Mine Project
Marinette, Nova Scotia

Sample	Sample Date	MW-18												MW-19												MW-20																							
		MW-18A						MW-18B						MW-18C						MW-19A						MW-19B						MW-19C						MW-20A						MW-20B					
		27-Jun-18	12-Sep-18	12-Sep-18 Field DUP 1	29-Nov-18	27-Jun-18	12-Sep-18	29-Nov-18	27-Jun-18	12-Sep-18	29-Nov-18	19-Jun-18	12-Sep-18	29-Nov-18	19-Jun-18	12-Sep-18	29-Nov-18	19-Jun-18	12-Sep-18	29-Nov-18	26-Jun-18	12-Sep-18	12-Sep-18 Field DUP 4	29-Nov-18	26-Jun-18	12-Sep-18	29-Nov-18	26-Jun-18	12-Sep-18	29-Nov-18	26-Jun-18	12-Sep-18	29-Nov-18																
Calculated Parameters	Units																																																
Anion Sum	me/L	0.310	0.320	0.330	0.290	1.34	1.39	1.33	2.02	2.52	2.19	0.210	0.240	0.280	1.49	1.65	1.61	1.24	1.30	1.30	0.360	0.410	1.11	0.270	2.12	2.23	2.04																						
Bicarb. Alkalinity (calc. as CaCO ₃)	mg/L	5.5	6.8	7.3	5.0	45	50	49	52	56	57	<1.0	5.3	6.0	60	67	65	37	39	46	7.9	12	41	5.3	90	96	87																						
Calculated TDS	mg/L	23	24	24	21	84	86	82	130	160	140	21	18	21	88	94	93	80	83	79	26	31	68	19	120	120	100																						
Carb. Alkalinity (calc. as CaCO ₃)	mg/L	<1.0	ND	ND	<1.0	<1.0	ND	<1.0	<1.0	ND	<1.0	<1.0	ND	<1.0	<1.0	ND	<1.0	<1.0	ND	<1.0	ND	<1.0	ND	<1.0	ND	<1.0	ND	<1.0																					
Cation Sum	me/L	0.270	0.290	0.270	0.230	1.23	1.25	1.26	1.89	2.33	2.00	0.280	0.180	0.240	1.45	1.49	1.50	1.21	1.22	1.17	0.310	0.330	1.01	0.220	1.95	1.96	1.33																						
Hardness (CaCO ₃)	mg/L	6.8	7.6	7.3	5.6	41	30	42	45	58	56	5.4	4.1	4.9	59	60	63	36	36	41	7.6	8.1	40	3.4	72	74	48																						
Ion Balance (% Difference)	%	6.90	4.92	10.0	11.5	4.28	5.30	2.70	3.32	3.92	4.53	14.3	14.3	7.69	1.36	5.10	3.54	1.22	3.17	5.26	7.46	10.8	4.72	10.2	4.18	6.44	21.1																						
Langelier Index (@ 20°C)	N/A	-4.17	-3.82	-3.86	-4.42	-0.820	-0.564	-0.618	-0.636	-0.465	-0.497	NC	-4.53	-4.47	-0.330	-0.255	-0.439	-1.53	-1.39	-1.19	-4.03	-3.63	-1.40	-4.76	-0.0410	-0.0810	-0.315																						
Langelier Index (@ 4°C)	N/A	-4.42	-4.07	-4.11	-4.68	-1.07	-0.815	-0.869	-0.886	-0.715	-0.748	NC	-4.78	-4.72	-0.581	-0.506	-0.690	-1.78	-1.64	-1.44	-4.28	-3.88	-1.66	-5.01	-0.291	-0.332	-0.566																						
Nitrate (N)	mg/L	0.062	ND	ND	0.076	<0.050	ND	<0.050	<0.050	ND	<0.050	0.25	0.15	0.16	0.066	ND	<0.050	0.11	0.052	0.090	0.21	0.27	ND	0.25	<0.050	ND	0.052																						
Saturation pH (@ 20°C)	N/A	10.3	10.2	10.1	10.4	8.52	8.61	8.47	8.44	8.32	8.32	NC	10.6	10.4	8.23	8.18	8.17	8.68	8.64	8.51	9.93	8.57	10.1	8.07	8.03	8.26																							
Saturation pH (@ 4°C)	N/A	10.6	10.4	10.4	10.7	8.77	8.86	8.72	8.69	8.57	8.57	NC	10.8	10.7	8.48	8.43	8.43	8.93	8.89	8.76	10.4	10.2	8.83	10.9	8.32	8.28	8.51																						
Inorganics																																																	
Total Alkalinity (Total as CaCO ₃)	mg/L	5.5	6.8	7.3	5.0	45	50	49	52	56	57	<5.0	5.3	6.0	61	68	65	37	39	46	7.9	12	41	5.3	91	97	87																						
Dissolved Chloride (Cl)	mg/L	3.8	3.5	3.7	4.3	3.5	2.7	2.9	5.3	5.7	5.2	4.1	2.9	3.4	2.4	2.6	2.9	3.8	3.3	3.5	4.8	3.6	3.7	3.4	3.6	3.1	3.2																						
Colour	TCU	<5.0	ND	ND	<5.0	<5.0	ND	<5.0	<5.0	ND	<5.0	<5.0	ND	<5.0	ND	<5.0	<5.0	ND	<5.0	ND	<5.0	ND	<5.0	ND	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0														
Nitrate + Nitrite (N)	mg/L	0.062	ND	ND	0.076	<0.050	ND	<0.050	<0.050	ND	<0.050	0.25	0.15	0.16	0.066	ND	<0.050	0.15	0.063	0.090	0.21	0.27	ND	0.25	<0.050	ND	0.052																						
Nitrite (N)	mg/L	<0.10	ND	ND	<0.10	<0.10	ND	<0.10	<0.10	ND	<0.10	<1.0	ND	<1.0	<0.10	ND	<1.0	<0.10	ND	<1.0	ND	<1.0	ND	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0															
Nitrogen (Ammonia Nitrogen)	mg/L	<0.050	ND	ND	<0.050	<0.050	ND	<0.050	<0.050	ND	<0.050	<0.050	ND	<0.050	<0.050	ND	<0.050	<0.050	ND	<0.050	ND	<0.050	ND	<0.050	ND	<0.050	ND	<0.050	ND	<0.050	ND	<0.050																	
Total Organic Carbon (C)	mg/L	1.7	ND	ND	0.55	1.4																																											

Table 5: Groundwater Quality Data
Beaver Dam Mine Project
Marinette, Nova Scotia

Sample	Sample Date	MW-21												MW-22											
		MW-21A				MW-21B				MW-21C				MW-22A				MW-22B				MW-22C			
		18-Jun-18	12-Sep-18	29-Nov-18	29-Nov-18 Field DUP3	18-Jun-18	12-Sep-18	29-Nov-18	18-Jun-18	12-Sep-18	29-Nov-18	26-Jun-18	12-Sep-18	29-Nov-18											
Calculated Parameters	Units																								
Anion Sum	me/L	0.250	0.420	0.490	0.430	0.580	0.690	0.490	1.67	1.69	1.61	0.300	0.390	0.400	1.56	0.850	1.00	2.24	2.13	2.14					
Bicarb. Alkalinity (calc. as CaCO ₃)	mg/L	6.5	13	17	15	21	26	17	54	61	58	5.8	11	6.2	59	31	35	94	95	94					
Calculated TDS	mg/L	20	31	33	31	40	46	34	110	110	100	23	31	28	94	59	65	130	120	120					
Carb. Alkalinity (calc. as CaCO ₃)	mg/L	<1.0	ND	<1.0	<1.0	<1.0	ND	<1.0	<1.0	ND	<1.0	<1.0	ND	<1.0	<1.0	ND	<1.0	1.0	ND	1.3					
Cation Sum	me/L	0.240	0.370	0.400	0.400	0.550	0.620	0.450	1.56	1.52	1.48	0.260	0.330	0.340	1.38	0.790	0.920	2.00	1.90	1.99					
Hardness (CaCO ₃)	mg/L	7.0	7.5	10	9.8	18	20	15	38	43	45	5.5	7.4	4.2	48	14	21	52	56	59					
Ion Balance (% Difference)	%	2.04	6.33	10.1	3.61	2.65	5.34	4.26	3.41	5.30	4.21	7.14	8.33	8.11	6.12	3.66	4.17	5.66	5.71	3.63					
Langelier Index (@ 20C)	N/A	-4.65	-4.08	-3.72	-3.78	-2.94	-2.91	-3.30	-1.93	-1.55	-1.59	-4.11	-3.83	-4.71	-0.786	-2.36	-2.15	-0.0890	-0.106	0.0590					
Langelier Index (@ 4C)	N/A	-4.90	-4.34	-3.97	-4.03	-3.19	-3.16	-3.56	-2.18	-1.81	-1.84	-4.36	-4.08	-4.96	-1.04	-2.62	-2.40	-0.340	-0.357	-0.192					
Nitrate (N)	mg/L	0.48	0.67	0.37	0.38	0.35	0.53	0.28	0.14	0.17	0.26	0.093	0.059	<0.050	<0.050	ND	0.050	<0.050	ND	<0.050					
Saturation pH (@ 20C)	N/A	10.3	9.94	9.66	9.72	9.30	9.13	9.50	8.63	8.56	8.58	10.5	10.0	10.6	8.41	9.23	9.00	8.16	8.13	8.11					
Saturation pH (@ 4C)	N/A	10.5	10.2	9.91	9.97	9.56	9.38	9.75	8.88	8.81	8.83	10.7	10.3	10.9	8.66	9.48	9.25	8.41	8.38	8.36					
Inorganics																									
Total Alkalinity (Total as CaCO ₃)	mg/L	6.5	13	17	15	21	26	17	54	61	58	5.8	11	6.2	60	31	35	95	96	95					
Dissolved Chloride (Cl)	mg/L	3.1	2.6	3.0	2.3	3.1	2.6	2.9	5.2	4.5	4.7	4.0	3.5	6.1	4.2	3.7	5.5	4.2	3.2	3.9					
Colour	TCU	8.0	5.6	<5.0	<5.0	<5.0	ND	<5.0	<5.0	ND	<5.0	ND	<5.0	ND	<5.0	<5.0	ND	<5.0	<5.0	ND	<5.0				
Nitrate + Nitrite (N)	mg/L	0.48	0.67	0.37	0.38	0.35	0.53	0.28	0.14	0.18	0.28	0.093	0.059	<0.050	<0.050	ND	0.050	<0.050	ND	<0.050					
Nitrite (N)	mg/L	<0.010	ND	<0.010	<0.010	<0.010	ND	<0.010	0.010	0.010	0.019	<0.010	ND	<0.010	<0.010	ND	<0.010	<0.010	ND	<0.010					
Nitrogen (Ammonia Nitrogen)	mg/L	<0.050	ND	<0.050	<0.050	<0.050	ND	<0.050	<0.050	ND	<0.050	<0.050	ND	<0.050	<0.050	ND	<0.050	<0.050	ND	<0.050					
Total Organic Carbon (C)	mg/L	2.1	2.0	2.4	2.3	1.0	1.3	2.1	4.2	2.5	2.3	1.0	0.93	1.4	1.8	2.6	2.8	1.6	0.93	0.86					
Orthophosphate (P)	mg/L	<0.010	ND	<0.010	<0.010	0.018	0.020	0.017	<0.010	ND	<0.010														
pH	pH	5.64	5.86	5.94	5.94	6.37	6.22	6.19	6.70	7.01	7.00	6.38	6.20	5.92	7.63	6.86	6.85	8.07	8.02	8.17					
Reactive Silica (SiO ₂)	mg/L	5.6	6.8	7.0	7.0	8.9	10	7.9	15	19	19	6.5	10	5.7	14	13	11	12	12	12					
Dissolved Sulphate (SO ₄)	mg/L	<2.0	2.3	2.1	2.2	2.2	2.7	2.1	21	16	14	3.3	3.3	5.0	12	5.6	7.2	10	6.1	6.3					
Turbidity	NTU	1.1	1.7	9.9	32	23	17	17	7.6	1.8	3.0	2.2	2.7	2.6	1.8	2.3	17	6.8	1.0	1.9					
Conductivity	uS/cm	33	48	49	48	61	71	50	160	170	150	33	41	45	150	89	98	210	200	200					
Metals																									
Dissolved Aluminum (Al)	ug/L	430	390	160	180	16	26	49	7.5	ND	<5.0	22	19	170	23	8.6	13	12	7.6	13					
Dissolved Antimony (Sb)	ug/L	<1.0	ND	<1.0	<1.0	<1.0	ND	<1.0	<1.0	ND	<1.0	<1.0	ND	<1.0	<1.0	ND	<1.0	<1.0	ND	<1.0					
Dissolved Arsenic (As)	ug/L	<1.0	ND	<1.0	<1.0	<1.0	ND	<1.0	<1.0	ND	<1.0	<1.0	ND	<1.0	1.5	1.2	<1.0	5.4	5.0	4.8					
Dissolved Barium (Ba)	ug/L	15	19	14	14	3.5	5.8	3.4	9.7	8.2	8.1	5.0	5.3	10	3.6	3.9	7.6	4.7	2.9	2.7					
Dissolved Beryllium (Be)	ug/L	<1.0	ND	<1.0	<1.0	<1.0	ND	<1.0																	